


ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
CONSTRUCTION PLANS FOR STATE HIGHWAY

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		1	61
				2 CLEAR LAKE STR. & APPRS. (S)				



VICINITY MAP


CLEAR LAKE STR. & APPRS. (S)

MISSISSIPPI COUNTY


ROUTE 148 SECTION 1

JOB 100723

FED. AID PROJ. BRN-0047 (45)




ARK. HWY. DIST. NO. 10



BRIDGE CONSTRUCTION DATA

STA. 104+98.45 BRIDGE END
BRIDGE NO. 07225
117'-0" INTEGRAL UNIT
(36', 45', 36')
30' CLEAR ROADWAY BRIDGE
118'-1 1/4" BRIDGE LENGTH
STA. 106+16.55 BRIDGE END

STA. 101+00.01
BEGIN JOB 100723
LOG MILE 1.82



STA. 111+99.99
END JOB 100723
LOG MILE 1.61

• DESIGN TRAFFIC DATA •

DESIGN YEAR	-----	2031
2011 ADT	-----	600
2031 ADT	-----	700
2031 DHV	-----	77
DIRECTIONAL DISTRIBUTION	-----	60%
TRUCKS	-----	7%
DESIGN SPEED	-----	55 MPH

BEGIN PROJECT
LAT. = N 35°51'47"
LONG. = W 89°50'31"

MID-POINT OF PROJECT
LAT. = N 35°51'47"
LONG. = W 89°50'17"

END PROJECT
LAT. = N 35°51'47"
LONG. = W 89°50'19"

GROSS LENGTH OF PROJECT	1099.98	FEET	OR	0.208	MILES
NET " " ROADWAY	981.88	"	"	0.186	"
NET " " BRIDGES	118.10	"	"	0.022	"
NET " " PROJECT	1099.98	"	"	0.208	"

P.E. 100723
NON-PART.



APPROVED



7/22/11
DEPUTY DIRECTOR
AND CHIEF ENGINEER

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 100723	2	61

2 INDEX OF SHEETS, GOVERNING SPECIFICATIONS AND GENERAL NOTES



7-25-11

INDEX OF SHEETS

SHEET NO.		BRIDGE NO.	DRWG NO.	DATE
1	TITLE SHEET			
2	INDEX OF SHEETS, GOVERNING SPECIFICATIONS, AND GENERAL NOTES			
3-4	TYPICAL SECTIONS OF IMPROVEMENT			
5	SPECIAL DETAILS			
6-7	TEMPORARY EROSION CONTROL DETAILS			
8-11	MAINTENANCE OF TRAFFIC DETAILS			
12-15	QUANTITY SHEETS	07225	52154	
16	SCHEDULE OF BRIDGE QUANTITIES			
17	SUMMARY OF QUANTITIES AND REVISIONS			
18-19	SURVEY CONTROL DETAILS			
20-21	PLAN AND PROFILE SHEETS			
22	LAYOUT OF BRIDGE OVER DITCH NO. 6 - SHEET 1 OF 2	07225	52155	
23	LAYOUT OF BRIDGE OVER DITCH NO. 6 - SHEET 2 OF 2	07225	52156	
24	DETAILS OF END BENTS	07225	52157	
25	DETAILS OF INTERMEDIATE BENTS	07225	52158	
26	DETAILS OF CONCRETE FILLED STEEL SHELL PILES AND PILE ENCASEMENTS	07225	52159	
27	DETAILS OF 117" INTEGRAL W-BEAM UNIT - SHEET 1 OF 7	07225	52160	
28	DETAILS OF 117" INTEGRAL W-BEAM UNIT - SHEET 2 OF 7	07225	52161	
29	DETAILS OF 117" INTEGRAL W-BEAM UNIT - SHEET 3 OF 7	07225	52162	
30	DETAILS OF 117" INTEGRAL W-BEAM UNIT - SHEET 4 OF 7	07225	52163	
31	DETAILS OF 117" INTEGRAL W-BEAM UNIT - SHEET 5 OF 7	07225	52164	
32	DETAILS OF 117" INTEGRAL W-BEAM UNIT - SHEET 6 OF 7	07225	52165	
33	DETAILS OF 117" INTEGRAL W-BEAM UNIT - SHEET 7 OF 7	07225	52166	
34	DETAILS OF TYPE SPECIAL APPROACH SLABS	07225	52167	
35	EMBANKMENT CONSTRUCTION AND BACKFILL AT BRIDGE ENDS	1888A		4-10-03
36	DETAILS FOR DUMPED RIPRAP AND FILTER BLANKET AND DETAILS FOR COMPUTING EXCAVATION FOR STRUCTURES	1891F		4-10-03
37	DETAILS OF STANDARD TYPE B APPROACH GUTTERS	2016B		7-14-10
38	DETAILS OF STANDARD TYPE D BRIDGE NAME PLATES	2387		1-25-11
39	DETAILS OF PERMISSIBLE TYPE PERMANENT STEEL BRIDGE DECK FORMS FOR STEEL AND CONCRETE GIRDER SPANS	14991		4-10-03
40	CONCRETE DITCH PAVING	CDP-1		11-17-10
41	GUARD RAIL DETAILS	GR-8		7-14-10
42	GUARD RAIL DETAILS	GR-9		4-17-08
43	GUARD RAIL DETAILS	GR-9A		4-17-08
44	GUARD RAIL DETAILS	GR-10		7-14-10
45	GUARD RAIL DETAILS	GR-10A		7-14-10
46	GUARD RAIL DETAILS	GRT-1		7-14-10
47	MAILBOX DETAILS	MB-1		11-18-04
48	CONCRETE PIPE CULVERT FILL HEIGHTS & BEDDING	PCC-1		5-18-00
49	METAL PIPE CULVERT FILL HEIGHTS & BEDDING	PCM-1		3-30-00
50	PAVEMENT MARKING DETAILS	PM-1		11-17-10
51	DETAILS OF PIPE UNDERDRAINS	PU-1		4-10-03
52	TABLES AND METHOD OF SUPERELEVATION FOR TWO-WAY TRAFFIC	SE-2		10-18-96
53	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION	TC-1		11-17-10
54	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION	TC-2		3-11-10
55	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION	TC-3		10-15-09
56	TEMPORARY EROSION CONTROL DEVICES	TEC-1		11-18-98
57	TEMPORARY EROSION CONTROL DEVICES	TEC-2		6-02-94
58	TEMPORARY EROSION CONTROL DEVICES	TEC-3		11-03-94
59-61	CROSS SECTIONS			

GOVERNING SPECIFICATIONS

ARKANSAS STATE HIGHWAY COMMISSION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EDITION OF 2003, AND THE FOLLOWING SPECIAL PROVISIONS AND SUPPLEMENTAL SPECIFICATIONS:



NUMBER	TITLE
ERRATA	ERRATA FOR THE BOOK OF STANDARD SPECIFICATIONS
FHWA-1273	FHWA-1273 REVISIONS
FHWA-1273	REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - NOTICE TO CONTRACTORS
FHWA-1273	SUPPLEMENT - SPECIFIC EQUAL EMPLOYMENT OPPORTUNITY RESPONSIBILITIES (23 U.S.C. 140)
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - GOALS AND TIMETABLES
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - FEDERAL STANDARDS
FHWA-1273	SUPPLEMENT - POSTERS AND NOTICES REQUIRED FOR FEDERAL-AID PROJECTS
FHWA-1273	SUPPLEMENT - WAGE RATE DETERMINATION
100-2	MANUAL FOR ASSESSING SAFETY HARDWARE (MASH)
103-1	DETERMINATION OF DBE PARTICIPATION
105-1	CONSTRUCTION CONTROL MARKINGS
105-2	EQUIPMENT AND MATERIAL STORAGE ON BRIDGE STRUCTURES
107-1	WORKER VISIBILITY
108-1	LIQUIDATED DAMAGES
110-1	PROTECTION OF WATER QUALITY AND WETLANDS
303-1	AGGREGATE BASE COURSE
404-1	PRODUCTION VERIFICATION OF ASPHALT CONCRETE HOT MIX
409-1	MINERAL AGGREGATES
410-3	DENSITY TESTING FOR ACHM LEVELING COURSES AND BOND BREAKERS
411-1	ASPHALT CONCRETE COLD PLANT MIX
600-1	WATER FOR VEGETATION
603-1	MAINTENANCE OF TRAFFIC
604-1	RETROREFLECTIVE SHEETING FOR TRAFFIC CONTROL DEVICES IN CONSTRUCTION ZONES
606-1	PIPE CULVERTS FOR SIDE DRAINS
718-2	REFLECTORIZED PAINT PAVEMENT MARKINGS
JOB 100723	APPROACH SLABS AND GUTTERS
JOB 100723	BROADBAND INTERNET SERVICE FOR ASPHALT CONCRETE PLANT
JOB 100723	BROADBAND INTERNET SERVICE FOR FIELD OFFICE
JOB 100723	CONSTRUCTION IN SPECIAL FLOOD HAZARD AREAS
JOB 100723	DRIVEN STEEL PILING BY METHOD B
JOB 100723	GOALS FOR DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION
JOB 100723	HIGH PERFORMANCE PAVEMENT MARKING
JOB 100723	INTERNET BIDDING
JOB 100723	NESTING SITES OF MIGRATORY BIRDS
JOB 100723	SHORING
JOB 100723	STEEL SHELL PILES
JOB 100723	STORM WATER POLLUTION PREVENTION PLAN
JOB 100723	SUBMISSION OF ASPHALT CONCRETE HOT MIX ACCEPTANCE TEST RESULTS
JOB 100723	UTILITY ADJUSTMENTS
JOB 100723	WARM MIX ASPHALT

GENERAL NOTES

- GRADE LINE DENOTES FINISHED GRADE WHERE SHOWN ON PLANS.
- ALL PIPE LINES, POWER, TELEPHONE AND TELEGRAPH LINES TO BE MOVED OR LOWERED BY THE RESPECTIVE OWNERS AS PER AGREEMENT WITH SUCH OWNERS.
- ANY EQUIPMENT OR APPURTENANCE THAT INTERFERES WITH THE PROPOSED CONSTRUCTION AND WHICH MAY BE THE PROPERTY OF UTILITY SERVICE ORGANIZATIONS SHALL BE MOVED BY THE OWNERS UNLESS OTHERWISE PROVIDED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING U. S. MAILBOXES WITHIN THE PROJECT LIMITS IN SUCH A MANNER THAT THE PUBLIC MAY RECEIVE CONTINUED MAIL SERVICE. PAYMENT WILL BE CONSIDERED INCLUDED IN THE PRICE BID FOR THE VARIOUS BID ITEMS.
- ALL LAND MONUMENTS LOCATED WITHIN THE CONSTRUCTION AREA SHALL BE PROTECTED IN ACCORDANCE WITH SECTION 107.12 OF THE STANDARD SPECIFICATIONS.
- ALL TREES THAT DO NOT DIRECTLY INTERFERE WITH THE PROPOSED CONSTRUCTION SHALL BE SPARED AS DIRECTED BY THE ENGINEER. CARE AND DISCRETION SHALL BE USED TO INSURE THAT ALL TREES NOT TO BE REMOVED SHALL BE HARMED AS LITTLE AS POSSIBLE DURING THE CONSTRUCTION OPERATIONS.
- THIS PROJECT IS COVERED UNDER A NATIONWIDE 14 SECTION 404 PERMIT. REFER TO SECTION 110 OF THE STANDARD SPECIFICATIONS, EDITION OF 2003, FOR PERMIT REQUIREMENTS.
- THE EXISTING ASPHALT PAVEMENT TO BE REMOVED FROM THE REMAINING PAVEMENT SHALL BE SEPARATED BY SAWING ALONG A NEAT LINE. AFTER SAWING, THE PAVEMENT TO BE REMOVED SHALL BE CAREFULLY REMOVED IN A MANNER THAT WILL NOT DAMAGE THE PAVEMENT THAT IS TO REMAIN. ANY DAMAGE OF THE ASPHALT PAVEMENT THAT IS TO REMAIN IN PLACE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- ALL FLEXIBLE BASE AND ASPHALTIC PAVEMENTS REMOVED SHALL BE PAID FOR UNDER THE ITEM NO. 210 UNCLASSIFIED EXCAVATION.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 100723	3	61

② TYPICAL SECTIONS OF IMPROVEMENT



TYPICAL SECTION OF IMPROVEMENT
NOTCH & WIDEN
STA. 101+00.01 TO STA. 103+78.45
STA. 111+39.48 TO 112+39.48

NOTES:

REFER TO CROSS SECTIONS FOR DEVIATION FROM THE NORMAL SLOPES. NO CHANGES SHALL BE MADE FROM THE PLANNED SLOPES WITHOUT THE APPROVAL OF THE ENGINEER.


THE THICKNESS OF AGGREGATE BASE COURSE SHALL BE WITHIN PLUS OR MINUS ONE INCH OF THE PLAN THICKNESS SHOWN. THE CONTRACTOR WILL CORRECT ANY DEFICIENT THICKNESS THAT DOES NOT MEET TOLERANCE INDICATED. PAYMENT WILL NOT BE MADE FOR MATERIAL PLACED IN EXCESS OF THE TOLERANCE INDICATED.

ASPHALT FOR LEVELING OF EXISTING PAVEMENT SHALL BE PLACED ONLY IF AND WHERE DIRECTED BY THE ENGINEER. CALCULATIONS FOR THE AMOUNT OF LEVELING AND/OR LEVELING OPERATIONS SHALL BE PERFORMED BEFORE CONSTRUCTING NOTCH AND WIDENING.

THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.

WITH THE APPROVAL OF THE ENGINEER, THE CONTRACTOR WILL BE ALLOWED TO SUBSTITUTE, AT NO ADDITIONAL COST TO THE DEPARTMENT, THE FIRST LIFT OF ACHM SURFACE (1/2") IN LIEU OF AGGREGATE BASE COURSE ON THE SHOULDERS.

AFTER PLACING FINAL 2" OF SURFACE COURSE, THE EXISTING SLOPE SHALL BE REDRESSED AS DIRECTED BY THE ENGINEER PRIOR TO SEEDING IN ORDER TO MAINTAIN A UNIFORM SLOPE. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR VARIOUS CONTRACT ITEMS.





TYPICAL SECTION OF IMPROVEMENT
FULL DEPTH
STA. 103+78.45 TO STA. 104+98.45
STA. 106+16.55 TO 111+39.48


TYPICAL SECTIONS OF IMPROVEMENT

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		4	61

2 TYPICAL SECTIONS OF IMPROVEMENT



DETOUR
TANGENT SECTION
TYPICAL SECTION OF IMPROVEMENT



DETOUR
SUPERELEVATION SECTION
TYPICAL SECTION OF IMPROVEMENT

NOTES:
REFER TO CROSS SECTIONS FOR DEVIATION FROM THE NORMAL SLOPES. NO CHANGES SHALL BE MADE FROM THE PLANNED SLOPES WITHOUT THE APPROVAL OF THE ENGINEER.



THE THICKNESS OF AGGREGATE BASE COURSE SHALL BE WITHIN PLUS OR MINUS ONE INCH OF THE PLAN THICKNESS SHOWN. THE CONTRACTOR WILL CORRECT ANY DEFICIENT THICKNESS THAT DOES NOT MEET TOLERANCE INDICATED. PAYMENT WILL NOT BE MADE FOR MATERIAL PLACED IN EXCESS OF THE TOLERANCE INDICATED.

THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.

AFTER PLACING FINAL 2" OF SURFACE COURSE, THE EXISTING SLOPE SHALL BE REDRESSED AS DIRECTED BY THE ENGINEER PRIOR TO SEEDING IN ORDER TO MAINTAIN A UNIFORM SLOPE. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR VARIOUS CONTRACT ITEMS.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 100723	5	61

② SPECIAL DETAILS




A.C.H.M. SURFACE COURSE (1/2") (220 LBS./SQ. YD.) & AGGREGATE BASE COURSE (CLASS 7) (7" COMPACTED DEPTH)

AGGREGATE BASE COURSE (CLASS 7) 7" COMP. DEPTH OR CONFORM TO EXISTING DRIVEWAY

TURNOUTS SHALL BE MODIFIED AS NECESSARY TO MEET LOCAL CONDITIONS AS DIRECTED BY THE ENGINEER.


DETAIL FOR DRIVEWAY TURNOUTS



ASPHALT CONCRETE HOT MIX SURFACE COURSE (1/2") (220 LBS. PER SQ. YD.) AND AGGREGATE BASE COURSE (CLASS 7) (7" COMPACTED DEPTH)


TURNOUTS SHALL BE MODIFIED AS NECESSARY TO MEET LOCAL CONDITIONS, AS SHOWN IN PLANS AND IF AND WHERE DIRECTED BY THE ENGINEER.

DETAIL FOR COUNTY ROAD TURNOUT




DETAIL OF WIDENING FOR GUARDRAIL

• REFER TO STD. DWG. GR-9A FOR SLOPE REQUIREMENTS BEHIND GUARDRAIL.




DETAIL SHOWING TAPER TO EXISTING PAVEMENT


• TO BE USED AS DIRECTED BY THE ENGINEER



DETAIL OF SILT FENCE AT CROSS DRAINS




DITCH LINING DETAIL




SPECIAL DETAIL OF APPROACH SLAB

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		6	61

2 TEMPORARY EROSION CONTROL DETAILS



CLEARING AND GRUBBING
 STA. 100+00.00 - STA. 113+00.00 13 STA.



STA 101+00.01 - BEGIN
 JOB 100723
 L.M. 1.82

STA 111+99.99 - END
 JOB 100723
 LOG MILE 1.61

SAND BAG DITCH CHECKS (E-5)

STA.	RT. OF DETOUR	INSTALLATION	BAGS
STA. 101+00	RT. OF DETOUR	1 INSTALLATION	20 BAGS
STA. 102+00	RT. OF DETOUR	1 INSTALLATION	20 BAGS
STA. 104+00	LT. & RT. OF DETOUR	2 INSTALLATIONS	40 BAGS
STA. 107+00	LT. & RT. OF DETOUR	2 INSTALLATIONS	40 BAGS
STA. 109+00	LT. & RT. OF DETOUR	2 INSTALLATIONS	40 BAGS
STA. 111+00	RT. OF DETOUR	1 INSTALLATION	20 BAGS
			180 BAGS

SILT FENCE (E-11)

STA.	RT. OF CL. CONST.	LT. OF CL. CONST.	FT.
STA. 100+00 - STA. 113+00	LT. OF CL. CONST.		1470 LIN. FT.
STA. 102+00 - STA. 113+00	RT. OF C.L. DETOUR		1960 LIN. FT.
			3430 LIN. FT.

REVISION BOX



DATE	REVISION

TEMPORARY EROSION CONTROL DETAILS
 STAGE I

r100723.dgn 2-25-2011

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		7	61

2 TEMPORARY EROSION CONTROL DETAILS



STA 101+00.01 - BEGIN
JOB 100723
L.M. 1.82

STA 111+99.99 - END
JOB 100723
LOG MILE 1.61

SAND BAG DITCH CHECKS (E-5)			
STA. 101+00	RT. OF DETOUR	1 INSTALLATION	RETAIN
STA. 102+00	RT. OF DETOUR	1 INSTALLATION	RETAIN
STA. 104+00	LT. & RT. OF DETOUR	2 INSTALLATIONS	RETAIN
STA. 107+00	LT. & RT. OF DETOUR	2 INSTALLATIONS	RETAIN
STA. 109+00	LT. & RT. OF DETOUR	2 INSTALLATIONS	RETAIN
STA. 111+00	RT. OF DETOUR	1 INSTALLATION	RETAIN
STA. 100+00	LT. OF C.L. CONST.	1 INSTALLATION	20 BAGS
STA. 101+30	LT. OF C.L. CONST.	1 INSTALLATION	20 BAGS
STA. 102+00	LT. & RT. OF C.L. CONST.	2 INSTALLATIONS	40 BAGS
STA. 104+00	LT. & RT. OF C.L. CONST.	2 INSTALLATIONS	40 BAGS
STA. 111+00	LT. OF C.L. CONST.	1 INSTALLATION	20 BAGS
STA. 112+00	LT. OF C.L. CONST.	1 INSTALLATION	20 BAGS
			160 BAGS

SEDIMENT BASIN (E-14)				OBLITERATION OF SEDIMENT BASIN			SEDIMENT REMOVAL & DISPOSAL		
STA. 104+60	LT.	12.5' x 25' x 3.5'	41 CU. YD.	41 CU. YD.	41 CU. YD.	20 CU. YD.	20 CU. YD.	20 CU. YD.	
STA. 105+45	RT.	12.5' x 25' x 3.5'	41 CU. YD.	41 CU. YD.	41 CU. YD.	20 CU. YD.	20 CU. YD.	20 CU. YD.	
STA. 106+50	RT.	12.5' x 25' x 3.5'	41 CU. YD.	41 CU. YD.	41 CU. YD.	20 CU. YD.	20 CU. YD.	20 CU. YD.	
			123 CU. YD.	123 CU. YD.	123 CU. YD.	60 CU. YD.	60 CU. YD.	60 CU. YD.	

REVISION BOX




DATE	REVISION

SILT FENCE (E-11)			
STA. 100+00 - STA. 113+00	LT. OF CL. CONST.	RETAIN	RETAIN
STA. 102+00 - STA. 113+00	RT. OF C.L. DETOUR	RETAIN	RETAIN

TEMPORARY EROSION CONTROL DETAILS
STAGE 2

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		8	61


② MAINTENANCE OF TRAFFIC DETAILS




MAINTENANCE OF TRAFFIC DETAILS
ADVANCE WARNING SIGNS

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						100723	9	61

② MAINTENANCE OF TRAFFIC DETAILS




TYPICAL PLACEMENT OF VERTICAL PANELS



TRAFFIC DRUMS = 6 EACH

TYPICAL PLACEMENT OF TRAFFIC DRUMS AT DRIVEWAY DETAIL



TYPICAL PLACEMENT OF TRAFFIC DRUMS

SEQUENCING:

STAGE 1: MAINTAIN TRAFFIC ON EXISTING ROADWAY. CONSTRUCT TEMPORARY PIPE CULVERT. NOTCH AND WIDEN AND CONSTRUCT EMBANKMENT/PAVEMENT FOR DETOUR ON RT. UTILIZE VERTICAL PANELS AT THE NOTCH AT 50' O.C. SPACING. PLACE CONSTRUCTION PAVEMENT MARKINGS AND RAISED PAVEMENT MARKERS (TYPE II).

STAGE 2: SHIFT TRAFFIC ONTO DETOUR. REMOVE EXISTING BRIDGE STRUCTURE AND CONSTRUCT NEW BRIDGE. NOTCH AND WIDEN ON LT. UTILIZE VERTICAL PANELS AT THE NOTCH AT 50' O.C. SPACING ON LT. AND TRAFFIC DRUMS AT 100' O.C. SPACING AT LANE EDGE ON RT. PERFORM LEVELING OPERATIONS.

STAGE 3: INSTALL FINAL SURFACE COURSE AND FINAL STRIPING. OBLITERATE DETOUR.

CONSTRUCTION PAVEMENT MARKINGS:


DETOUR:
AS DIRECTED BY THE ENGINEER:
RT. AND LT. EDGE LINES = 2496 LIN. FT.
DBL. CENTERLINE = 2496 LIN. FT.
RAISED PAVEMENT MARKERS:
TYPE II (YEL./YEL.) 40' O.C. ON CENTERLINE = 33 EACH

MAIN LANES:
RT. AND LT. EDGE LINES = 2600 LIN. FT.
DBL. CENTERLINE = 2600 LIN. FT.
REMOVAL OF CONSTRUCTION PAVEMENT MARKERS = 2600 LIN. FT.

FINAL STRIPING:

REFLECTORIZED PAINT PAVEMENT MARKINGS:
RT. AND LT. EDGE LINES = 2600 LIN. FT. WHITE
DBL. CENTERLINE = 2364 LIN. FT. YELLOW

HIGH PERFORMANCE PAVEMENT MARKER:
DBL. CENTERLINE = 236 LIN. FT. YELLOW




FINAL STRIPING DETAIL

MAINTENANCE OF TRAFFIC DETAILS


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
JOB NO.							100723	10	61

2 MAINTENANCE OF TRAFFIC DETAILS



STA 101+00.01 - BEGIN
JOB 100723
L.M. 1.82

STA 111+99.99 - END
JOB 100723
LOG MILE 1.61



SEQUENCING:

STAGE 1: MAINTAIN TRAFFIC ON EXISTING ROADWAY. CONSTRUCT TEMPORARY PIPE CULVERT, NOTCH AND WIDEN AND CONSTRUCT EMBANKMENT/PAVEMENT FOR DETOUR ON RT. UTILIZE VERTICAL PANELS AT THE NOTCH AT 50' O.C. SPACING. PLACE CONSTRUCTION PAVEMENT MARKINGS AND RAISED PAVEMENT MARKERS (TYPE III).


STAGE 2: SHIFT TRAFFIC ONTO DETOUR. REMOVE EXISTING BRIDGE STRUCTURE AND CONSTRUCT NEW BRIDGE, NOTCH AND WIDEN ON LT. UTILIZE VERTICAL PANELS AT THE NOTCH AT 50' O.C. SPACING ON LT. AND TRAFFIC DRUMS AT 100' O.C. SPACING AT LANE EDGE ON RT. PERFORM LEVELING OPERATIONS.

STAGE 3: INSTALL FINAL SURFACE COURSE AND FINAL STRIPING. OBLITERATE DETOUR.

MAINTENANCE OF TRAFFIC DETAILS
STAGE 1

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		100723	12	61

② QUANTITIES



ADVANCE WARNING SIGNS AND DEVICES, CONSTRUCTION PAVEMENT MARKINGS, AND PERMANENT PAVEMENT MARKINGS

SIGN NUMBER	DESCRIPTION	SIGN SIZE	STAGE 1	STAGE 2	END OF JOB	MAXIMUM NUMBER REQUIRED	TOTAL SIGNS REQUIRED		TRAFFIC DRUMS	VERTICAL PANELS	BARRICADES (TYPE II)		RAISED PAVEMENT MARKER TYPE II (YEL/YEL)	CONSTRUCTION PAVEMENT MARKINGS	REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS	REFLECTORIZED PAINT PAVEMENT MARKINGS		HIGH PERFORMANCE CONTRAST PAVEMENT MARKING	
							NO.	SQ. FT.			EACH	LIN. FT.				EACH	4"		
																	WHITE		YELLOW
			SQ. FT. - LIN. FT. - EACH				NO.	SQ. FT.		EACH	LIN. FT.						WHITE	YELLOW	4" YELLOW
W20-1	ROAD WORK 1500 FT.	48"x48"	2	2	2	2	2	32.0											
W20-1	ROAD WORK 1000 FT.	48"x48"	2	2	2	2	2	32.0											
W20-1	ROAD WORK 500 FT.	48"x48"	2	2	2	2	2	32.0											
G20-2	END ROAD WORK	48"x24"	2	2	2	2	2	10.0											
R4-1	DO NOT PASS	24"x30"	2	2	2	2	2	10.0											
R11-2	ROAD CLOSED	48x30"	2	4	4	4	4	40.0											
W1-6	ARROW	48"x24"		2	2	2	2	16.0											
W1-4aL	REVERSE CURVE	48"x48"		1		1	1	16.0											
W1-4aR	REVERSE CURVE	48"x48"		1		1	1	16.0											
W13-1	SPEED ADVISORY	18"x18"		2		2	2	4.5											
W1-8	CHEVRON	18"x24"		16		16	16	48.0											
OM-3L	OBJECT MARKER	12"x36"		2		2	2	6.0											
OM-3R	OBJECT MARKER	12"x36"		2		2	2	6.0											
	TRAFFIC DRUMS		42	68		68			68										
	VERTICAL PANELS		15			15				15									
	TYPE III BARRICADE - LT. (8')			8		8					8								
	TYPE III BARRICADE - RT. (8')			8		8						8							
	TYPE III BARRICADE - LT. (16')		16	16		16					16								
	TYPE III BARRICADE - RT. (16')		16	16		16						16							
	CONSTRUCTION PAVEMENT MARKINGS		5200	4992		10192							10192						
	RAISED PAVEMENT MARKERS TYPE II (YEL/YEL)		33			33						33							
	REFLECTORIZED PAINT PAVEMENT MARKINGS-WHITE (4")				2600	2600										2600			
	REFLECTORIZED PAINT PAVEMENT MARKINGS-YELLOW (4")				2364	2364											2364		
	REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS				2600	2600								2600					
	HIGH PERFORMANCE CONTRAST PAVEMENT MARKING YELLOW (4")																		236
TOTALS:								268.5	68	15	24	24	33	10192	2600	2600	2364		236

NOTE: THIS IS A LOW TRAFFIC VOLUME ROAD AS DEFINED IN SECTION 604.03 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EDITION OF 2003.


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		14	61

COLD MILLING

STATION	STATION	LOCATION	COLD MILLING ASPHALT PAVEMENT SQ. YD.
100+00.00	101+00.01	BEGIN TRANSITION	222
112+39.71	113+00.02	END TRANSITION	134
TOTAL:			356

AVG. 1" DEPTH

② QUANTITIES



APPROACH GUTTERS AND SLABS

STATION	STATION	APPROACH GUTTER (TYPE B) (W=4')	APPROACH SLABS (TYPE SPECIAL)	REINFORCING STEEL-ROADWAY (GRADE 60)	AGGREGATE BASE COURSE (CLASS 7) (6" COMP. DEPTH)
		CU.YD.	CU.YD.	POUND	TON
104+98	106+17	15.00	85.00	21256	44.0
TOTALS:		15.00	85.00	21256	44.0

CONCRETE DITCH PAVING

STATION	STATION	LOCATION	*CONCRETE DITCH PAVING (TYPE B) (W=4'-0") SQ.YD.	SOLID SODDING	WATER M.GAL.
ENTIRE PROJECT		IF AND WHERE DIRECTED BY THE ENGINEER	600	600	7.6
TOTALS:			600	600	7.6

* QUANTITY ESTIMATED. SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS.
BASIS OF ESTIMATE:
WATER..... 12.6 GAL. / SQ. YD. OF SOLID SODDING.
NOTE: EXPANSION JOINTS TO BE PLACED 45' ON CENTERS.

SELECTED PIPE BEDDING & BACKFILL

LOCATION	SELECTED PIPE BEDDING	SELECTED PIPE BACKFILL
	CU.YD.	
ENTIRE PROJECT - TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER.	50	100
TOTALS:	50	100

NOTE: QUANTITIES ARE ESTIMATED.
SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS.

TEMPORARY PIPE CULVERTS

STATION	DESCRIPTION	72" TEMPORARY CULVERT	STD. DWG. NOS.
		LIN. FT.	
205+95	INSTALL QUINT. 72"x102' @30° RT. FWD. SKEW TEMPORARY PIPE CULVERT	510	PCC-1, PCM-1
TOTAL:		510	

4" PIPE UNDERDRAIN

LOCATIONS	4" PIPE UNDERDRAIN	UNDERDRAIN OUTLET PROTECTORS
	LIN.FT.	EACH
ENTIRE PROJECT AS DIRECTED BY THE ENGINEER	1000	8
TOTALS:	1000	8


NOTE: QUANTITIES ARE ESTIMATED.
SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS.

GUARDRAIL

STATION	STATION	SIDE	GUARDRAIL	THRIE BEAM	TERMINAL	BRIDGE
			(TYPE A) LIN.FT.	GUARDRAIL TERMINAL	ANCHOR POST (TYPE 1) EACH	END TERMINAL
104+85.00	104+95.00	RT				1
103+88.31	104+82.06	LT	75	1	1	
106+32.94	107+26.69	RT	75	1	1	
106+18.96	108+37.71	LT	200	1	1	
TOTALS:			350	3	3	1

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		15	61

② QUANTITIES



EROSION CONTROL

STATION	STATION	LOCATION	PERMANENT EROSION CONTROL					TEMPORARY EROSION CONTROL							
			SEEDING	LIME	MULCH COVER	WATER	SECOND SEEDING APPLICATION	TEMPORARY SEEDING	MULCH COVER	WATER	SAND BAG DITCH CHECKS (E-5)	SILT FENCE (E-11)	SEDIMENT BASIN (E-14)	OBLITERATION OF SEDIMENT BASIN	*SEDIMENT REMOVAL & DISPOSAL
			ACRE	TON	ACRE	M.GAL.	ACRE	ACRE	ACRE	M.GAL.	BAG	LIN.FT.	CU. YD.		
100+00.00	113+00.02	DETOUR (STAGE 1)	1.62	3	1.62	165.2	1.62	1.62	1.62	33.0	180	3430		647	
100+00.00	113+00.02	MAIN LANES (STAGE 2)	2.62	5	2.62	267.2	2.62	2.62	2.62	53.4	160		123	300	
TOTALS:			4.24	8	4.24	432.4	4.24	4.24	4.24	86.4	340	3430	123	947	

BASIS OF ESTIMATE:

- LIME 2 TONS / ACRE OF SEEDING
- WATER 102.0 M.G. / ACRE OF SEEDING.
- WATER 20.4 M.G. / ACRE OF TEMPORARY SEEDING.
- SAND BAG DITCH CHECKS 20 BAGS / LOCATION

NOTE: THE TEMPORARY EROSION CONTROL DEVICES SHOWN ABOVE AND ON THE PLANS SHALL BE INSTALLED IN SUCH A SEQUENCE AS TO DETER EROSION AND SEDIMENTATION ON U.S. WATERWAYS AS EXPLAINED BY THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT.

*TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER. QUANTITY IS ESTIMATED. SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS.

BENCH MARKS

STATION	DESCRIPTION	BENCH MARK
		EACH
104+98.45	CLEAR ROADWAY BRIDGE ON LT.	1
TOTAL:		1

NOTE: SHOWN FOR INFORMATION PURPOSES ONLY. BENCH MARKS TO BE FURNISHED, PLACED, AND RECORDED BY STATE FORCES.

MAILBOXES

LOCATION	MAILBOXES	MAILBOX SUPPORTS (SINGLE)
	EACH	
ENTIRE PROJECT	4	4
TOTALS:	4	4

A.C.H.M. PATCHING OF EXISTING ROADWAY

DESCRIPTION	TON
ENTIRE PROJECT - TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER	50
TOTAL:	50

NOTE: QUANTITY IS ESTIMATED SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS.

ASPHALT CONCRETE PATCHING FOR MAINTENANCE OF TRAFFIC

LOCATION	ASPH. CONC. PATCHING FOR M.O.T.	TACK COAT
	TON	GALLON
ENTIRE PROJECT - TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER	50	100
TOTALS:	50	100

NOTE: QUANTITY IS ESTIMATED. SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS.


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		160/601	
				① 07225 - QUANTITIES		- 52154		

SCHEDULE OF BRIDGE QUANTITIES - JOB NO. 100723

BRIDGE NO. CODE NO. NAME PLATE TITLE	UNIT OF STRUCTURE	ITEM NO.	205	801	802	802	803	804	804	SP & 805	SP & 805	805	805	807	812	816	816
		ITEM	REMOVAL OF EXISTING BRIDGE STRUCTURE (SITE NO.)	UNCLASSIFIED EXCAVATION FOR STRUCTURES-BRIDGE	CLASS S CONCRETE-BRIDGE	CLASS S(AE) CONCRETE-BRIDGE	CLASS 1 PROTECTIVE SURFACE TREATMENT	REINFORCING STEEL-BRIDGE (GRADE 60)	EPOXY COATED REINFORCING STEEL (GRADE 60)	① STEEL SHELL PILING (16" DIA.)	① STEEL SHELL PILING (24" DIA.)	① PILE ENCASEMENT	PREBORING	STRUCTURAL STEEL IN BEAM SPANS (M 270, GRADE 50W)	BRIDGE NAME PLATE (TYPE D)	FILTER BLANKET	DUMPED RIPRAP
		UNIT	LUMP SUM	CU. YD.	CU. YD.	CU. YD.	GAL.	LB.	LB.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LB.	EACH	SQ. YD.	CU. YD.
07225 X071 DITCH NO. 6	BENTS 1 & 4			21	28.14			2356	1579	736			80			405	227
	BENTS 2 & 3				34.76			2574	351		920	116					
	117' INTEGRAL W-BEAM UNIT					164.10	10.0	39390	1060				57420	1			
	EXIST. BR. NO. M2051 (SITE NO. 1)		1														
TOTALS FOR JOB NO. 100723				21	62.90	164.10	10.0	44320	2990	736	920	116	80	57420	1	405	227

① PILES AND PILE ENCASEMENT SHALL CONFORM TO DWG. NO. 52159.

RICK ELLIS
DESIGN SECTION SUPERVISOR




SCHEDULE OF BRIDGE QUANTITIES
CLEAR LAKE STR. & APPRS. (S)
MISSISSIPPI COUNTY

ROUTE 148 SEC. 1
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: CJR DATE: 06/11/11 FILENAME: b100723-ql.dgn
 CHECKED BY: KDH DATE: 6-13-11 SCALE: NONE
 DESIGNED BY: -- DATE: --
 BRIDGE NO. 07225 DRAWING NO. 52154

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 100723	18	61

2 SURVEY CONTROL DETAILS



SURVEY CONTROL COORDINATES

Project Name: s100723
 Date: 4/6/2010
 Coordinate System: ARKANSAS STATE PLANE - NORTH ZONE BASED ON GPS CONTROL, PROJECTED TO GROUND.
 Units: U.S. SURVEY FOOT

Point Name	Northing	Easting	Elev	Feature	Description
1	563844.7931	1951742.0594	252.36	CTL	*5/8" REBAR W/ 2" CAP
2	563881.0525	1952358.3630	248.41	CTL	*5/8" REBAR W/ 2" CAP
3	563862.0289	1953027.4818	249.64	CTL	*5/8" REBAR W/ 2" CAP
100	563869.8847	1955695.9978	251.88	GPS	*AHTD GPS 470016
101	563926.0721	1954152.8203	253.42	GPS	*AHTD GPS 470016A
900	564053.7854	1961874.6111	275.72	TBM	*H BEAM GATE POST ON LEVEE
901	563977.0362	1958418.3591	255.36	TBM	*2" REBAR/CAP
990	566744.6690	1964613.7473	273.64	BM	*NGS MARK T 213
991	562502.5975	1960344.7513	270.59	BM	*NGS MARK U 213

*Note - Rebar and Cap - Standard - 5/8" Rebar with 2" Aluminum Cap stamped *(standard markings common to all caps), or as indicated (other markings indicated in the point description of the individual point). ALL DISTANCES ARE GROUND.
 USE CAF = 1.0 FOR STAKEOUT FOR THIS PROJECT.
 A PROJECT CAF OF XXXXX HAS BEEN USED TO COMPUTE THE ABOVE GROUND COORDINATES. THIS CAF IS INTENDED FOR USE WITHIN THE PROJECT LIMITS.
 GRID DISTANCE = GROUND DISTANCE X CAF.
 GRID COORDINATES ARE STORED UNDER FILE NAME, s100723gi.ct1
 HORIZONTAL DATUM: NAD 83 (1997)
 VERTICAL DATUM: NAVD 88 POSITIONAL ACCURACY THIRD ORDER, UNLESS SPECIFIED OTHERWISE AT A SPECIFIC POINT.

REFERENCE POINTS (1500 SERIES) ARE TO BE USED TO ESTABLISH CONTROL IF THE PRIMARY CONTROL POINTS LISTED ABOVE HAVE BEEN DESTROYED. REFERENCE POINTS ARE NOT TO BE USED FOR VERTICAL CONTROL

BASIS OF BEARING:
 ARKANSAS STATE PLANE GRID BEARINGS - 0301-NORTH ZONE
 DETERMINED FROM GPS CONTROL POINTS: 470016-470016A
 CONVERGENCE ANGLE: 01 15 29.2 RIGHT AT LT: 35-51-47.0 LG: 89-50-16.5
 GRID AZIMUTH = ASTRONOMICAL AZIMUTH - CONVERGENCE ANGLE.

C.L. CONSTRUCTION

		Station	Northing	Easting
POB	8000	100+00.00	563858.84	1951870.07
P. I.	8010	101+00.01	563858.82	1951970.08
P. I.	8010	101+00.01	563858.82	1951970.08
P. I.	8001	111+99.99	563875.15	1953069.93
P. I.	8001	111+99.99	563875.15	1953069.93
POE	8002	113+00.02	563879.26	1953169.88

C.L. DETOUR

		Station	Northing	Easting
POB	8000	200+00.00	563858.84	1951870.07
P. C.	8003	200+04.18	563858.90	1951874.25
P. I.		201+00.00	563860.32	1951970.05
P. T.	8004	201+95.07	563841.12	1952063.93
P. C.		203+12.94	563817.51	1952179.41
P. I.		204+08.75	563798.31	1952273.28
P. T.		205+03.82	563799.74	1952369.09
P. C.		208+07.53	563804.25	1952672.76
P. I.		209+03.60	563805.67	1952768.82
P. T.		209+98.92	563827.76	1952862.32
P. C.	8009	211+20.49	563855.71	1952980.64
P. I.		212+12.18	563876.79	1953069.88
P. T.	8012	213+03.22	563879.05	1953161.54
POE	8002	213+11.56	563879.26	1953169.88

STA. 100+52 IN PLACE
24" X 28" C.M. PIPE CULVERT
LT. SIDE DRAIN
REMOVE AND INSTALL
24" X 28" PIPE CULVERT
LT. SIDE DRAIN
CONST. APPR. = 40 CU. YDS.

STA. 101+55 IN PLACE
24" X 27" C.M. PIPE CULVERT
LT. SIDE DRAIN
REMOVE AND INSTALL
24" X 28" PIPE CULVERT
LT. SIDE DRAIN
CONST. APPR. = 20 CU. YDS.



STA. 103+09 IN PLACE
15" X 24" C.M. PIPE CULVERT
LT. SIDE DRAIN
REMOVE AND INSTALL
24" X 28" PIPE CULVERT
LT. SIDE DRAIN
CONST. APPR. = 25 CU. YDS.

STA. 104+99.78 TO STA. 106+14.63- IN PLACE
115' X 24' CLEAR ROADWAY BRIDGE NO. M2051 CONSISTING OF
A SIX SPAN CONCRETE DECK WITH TIMBER STRINGERS & PILING
REMOVE AS EXISTING BRIDGE STRUCTURE (SITE NO. 1) = 1.00 LUMP SUM

STA. 105+83 LT. IN PLACE
18" X 40" STEEL PIPE CULVERT
FOR FIELD DRAIN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.	100723	20	61

PLAN & PROFILE STA 100+00.00 - STA 111+14.72




STA 101+00.01 - BEGIN
JOB 100723
L.M. 1.82

STA. 104+30 IN PLACE
DBL. 30" X 38" C.M. PIPE CULVERT
RT. SIDE DRAIN
REMOVE AND INSTALL
DBL. 30" X 82" PIPE CULVERT
RT. SIDE DRAIN
CONSTR. APPR. = 485 CU. YDS.

STA. 104+98.45 BRIDGE END
BRIDGE NO. 07225
117'-0" INTEGRAL UNIT
(36', 45', 36')
30' CLEAR ROADWAY BRIDGE
118'-1 1/4" BRIDGE LENGTH
STA. 106+16.55 BRIDGE END

STATION	STATION	SIDE	GUARDRAIL (TYPE A) LIN. FT.	THRRE BEAM GUARDRAIL TERMINAL EACH	TERMINAL ANCHOR POSTS (TYPE 1) EACH	BRIDGE END TERMINAL
104+85.44	104+95.44	RT.	75	1	1	1
103+88.31	104+82.06	LT.	75	1	1	1
106+32.94	107+26.69	RT.	200	1	1	1
106+18.96	108+37.71	LT.	200	1	1	1

STA 111+99.99 - END
JOB 100723
L.M. 1.61




THE GPS POINTS AND CTL POINTS LISTED IN THE SURVEY CONTROL DETAILS MAY BE USED AS BENCH MARKS.

DATE REVISED	DATE FILED	DATE REVISED	DATE FILED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
JOB NO.							100723	21	61


② DETOUR PLAN & PROFILE STA. 200+00-STA. 213+09.06



7-22-14




DETOUR



For R/W Data, See Rdwy. Plans

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		22	61
				07225 -	LAYOUT		- 52155	



Note: The Contractor shall excavate the channel as shown using 1V:2H slopes to Elev. 240.00. Approx. 100 cu. yds. of excavation.

Dumped Riprap 1'-6" thick placed on Filter Blanket. Top of Riprap Elev. 244.00. See Std. Dwg. No. 1891F.

Place Type B Approach Gutters ('w' = 4'-0") and Type Special Approach Slab at both ends of bridge. See Dwg. Nos. 2016B & 52167.

GENERAL NOTES

BENCH MARK: 5/8" Rebar with 2" Cap - 16.47 ft. Left of C. Sta. 104+88.59, Elev. 248.41.

CONSTRUCTION SPECIFICATIONS: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2003 edition) with applicable supplemental specifications and special provisions. Section and Subsection refer to the Standard Construction Specification unless otherwise noted in the Plans.

DESIGN SPECIFICATIONS: AASHTO LRFD Bridge Design Specifications (5th Edition, 2010 with 2010 Interims).

LIVE LOADING: HL-93 SEISMIC ZONE: 4

MATERIALS AND STRENGTHS:
 Class S(AE) Concrete (superstructure) f'c = 4,000 psi
 Class S Concrete (substructure) f'c = 3,500 psi
 Reinforcing Steel (AASHTO M31 or M53, Gr. 60) fy = 60,000 psi
 Structural Steel (AASHTO M270, Gr. 36) Fy = 36,000 psi
 Structural Steel (AASHTO M270, Gr. 50W) Fy = 50,000 psi

BORING LOGS: Boring logs may be obtained from the Programs and Contracts Division.

STEEL SHELL PILING: Piling for Bents 1 & 4 shall be 16" diameter concrete filled steel shell piles and shall be driven to a minimum ultimate bearing capacity of 220 tons per pile and to a tip elevation of 153.0 or lower. Piling for Bents 2 & 3 shall be 24" diameter concrete filled steel shell piles and shall be driven to a minimum ultimate bearing capacity of 240 tons per pile and to a tip elevation of 153.0 or lower. All piling shall be driven with an approved air, steam, or diesel hammer. Piling in end bents shall be driven after embankment to bottom of cap is in place.

Length of piling shown are assumed for estimating quantities only. Actual lengths to be determined in the field. No payment will be made for cut-off or build-up. Test piles are not required but may be driven for the Contractor's information in accordance with Subsection 805.08(g). No piles will be paid for as test piles.

DRIVING SYSTEM: The driving system approval and ultimate bearing capacity determination for piling shall be based on the requirements of Subsection 805.09(b) "Method B - Wave Equation Analysis (WEAP)". It is estimated that a minimum rated hammer energy of 75,000 ft. lbs. per blow will be required to obtain the ultimate bearing capacity at Bent Nos. 1 & 4. It is estimated that a minimum rated hammer energy of 88,000 ft. lbs. per blow will be required to obtain the ultimate bearing capacity at Bent Nos. 2 & 3.

PREBORING: BENTS 1 & 4: Preboring is required for all piles in bents 1 and 4. Preboring shall have a 22" diameter for a depth of 10' below the bottom of the cap. This 10' depth shall be backfilled with sand or pea gravel after the piles are in place, and temporary casings or other methods may be required to maintain a 3" annulus until the backfill is placed. Temporary casings, if used, and backfilling will not be paid for directly but shall be considered subsidiary to the item "Preboring".

BENTS 1 THRU 4: Additional preboring, water jetting or other methods approved by the Engineer may be needed to achieve minimum pile penetration. Preboring shall be in accordance with Subsection 805.08(a). Size and depth of prebored holes shall be determined by the Engineer. Any cost for additional preboring, water jetting or other methods shall be included in the item "Steel Shell Piling (16" Dia.)" or "Steel Shell Piling (24" Dia.)"

PILE ENCASEMENTS: Pile encasements are required for Bents 2 and 3. See Dwg. No. 52159.

BRIDGE DECK: The concrete bridge deck shall be given a fine finish as specified for final finishing in Subsection 802.19 for Class 5 Tined Bridge Roadway Surface Finish.

PIPE UNDERDRAIN: One pipe underdrain with outlet protectors shall be installed behind each bridge end in accordance with Section 611. Pipe underdrains and outlet protectors will not be paid for directly but shall be considered subsidiary to "Unclassified Excavation".




DETAIL DRAWINGS:	DRAWING NO.
End Bents	52157
Int. Bents	52158
Concrete Filled Steel Shell Piles	52159
117" Integral W-Beam Unit	52160-52166
Type Special Approach Slabs	52167
Type B Approach Gutters	20168

EXISTING BRIDGE: Existing Bridge No. M2051 (log mile 1.72) is 25.5' wide and 115' long and consists of six 19' spans composed of a concrete deck with timber stringers supported by timber trestle pile bents. The existing bridge occupies the same location as the proposed new bridge.

REMOVAL AND SALVAGE: After the detour road is opened to traffic, the Existing Bridge No. M2051 shall be removed in accordance with Section 205. All material from the existing bridge shall become the property of the Contractor.

MAINTENANCE OF TRAFFIC: See Roadway Plans.

Temporary Shoring may be required during construction. Payment for this work, if required, shall be incidental to the various bid items. See SP Job 100723 "Shoring".



Before driving any piling, the Contractor shall verify no interference exists between the existing and proposed piling. Any adjustments necessary to fit the new bridge to the existing conditions shall be submitted for the Engineer's approval.

Note: For Hydraulic Data and Soil Boring Information, see Dwg. No. 52156.


SHEET 1 OF 2
 LAYOUT OF BRIDGE OVER
 DITCH NO. 6
 CLEAR LAKE STR. & APPRS. (S)
 MISSISSIPPI COUNTY



ROUTE 148 SEC. 1
 ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 9-8-10 FILENAME: b100723_ll.dgn
 CHECKED BY: CSR DATE: 6/22/11 SCALE: 1" = 20'
 DESIGNED BY: MCR DATE: 8/10
 BRIDGE NO. 07225 DRAWING NO. 52155

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		100723	23	(6)
				07225 -	LAYOUT			52156



- BORING LEGEND**
- AI-Moist, Stiff, Brown Clay with Sand and some Organic Matter
 - BI-Moist, Very Stiff, Brown and Dark Gray Clay with Sand and some Organic Matter
 - CI-Wet, Loose, Gray Silt with Sand
 - DI-Wet, Medium Dense, Gray Sandy Silt
 - EI-Wet, Soft, Gray Clay
 - FI-Wet, Medium Dense, Gray and Brown Sand with Trace of Gravel and Organic Matter
 - GI-Wet, Dense, Gray Sand
 - HI-Wet, Medium Dense, Gray Sand with Clay and some Organic Matter
 - JI-Wet, Medium Dense, Gray Sand with Trace of Organic Matter
 - KI-Wet, Dense, Gray Sand with Trace of Organic Matter
 - LI-Wet, Dense, Gray Sand with some Gravel
 - MI-Wet, Medium Dense, Gray Silt
 - NI-Wet, Medium Dense, Gray Sand with Trace of Gravel
 - PI-Wet, Medium Dense, Gray Sand with some Gravel
 - QI-Wet, Dense, Gray Sand with Trace of Gravel
 - RI-Hard, Gray Siltstone
 - SI-Wet, Very Dense, Gray Sand
 - TI-Wet, Medium Dense, Gray and Brown Sand with Trace of Gravel
 - UI-Moist, Medium Stiff, Dark Brown Clay with some Organic Matter (Roots)
 - VI-Moist, Medium Stiff, Brown and Gray Clay
 - WI-Moist, Soft, Dark Gray Clay with some Organic Matter
 - XI-Moist, Very Soft, Dark Gray Clay with some Organic Matter
 - YI-Wet, Very Soft, Dark Gray Clay with Sand
 - ZI-Wet, Very Soft, Gray Clay with Sand
 - A2-Wet, Medium Dense, Gray Sand with some Organic Matter
 - B2-Wet, Dense, Gray Sand with Trace of Gravel and Organic Matter
 - C2-Wet, Medium Dense, Gray Sand with some Gravel and Organic Matter
 - D2-Wet, Loose, Gray Sand with Organic Matter (Wood)
 - E2-Wet, Medium Dense, Gray Sand with Gravel
 - F2-Wet, Medium Dense, Gray Sand with Gravel and Trace of Organic Matter
 - G2-Wet, Very Dense, Gray Sand with Gravel and Trace of Organic Matter
 - H2-Wet, Very Dense, Gray Sand with Trace of Gravel
 - J2-Wet, Very Dense, Gray Sand with Trace of Organic Matter

HYDRAULIC DATA

FLOOD DESCRIPTION	FREQUENCY	DISCHARGE	*NATURAL WATER SURFACE ELEVATION	WATER SURFACE ELEV. WITH BACKWATER
	YEARS		CFS	FEET
Design	50	3060	243.7	244J
Base	100	3430	244J	244.5
Extreme	500	4260	244.8	245.3
Overtopping	>500	-	-	-

* Unconstricted water surface without structure or roadway approaches.
 Drainage area = 33 square miles.
 Historical H.W. Elev. = 244.3 ft.
 0100 Backwater Elev. for existing structure = 244.3 ft.
 Proposed Low Bridge Chord Elev. = 247.11 ft.

SHEET 2 OF 2
 LAYOUT OF BRIDGE OVER
 DITCH NO. 6
 CLEAR LAKE STR. & APPRS. (S)
 MISSISSIPPI COUNTY

ROUTE 148 SEC. 1
 ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.
 DRAWN BY: KDH DATE: 9-8-10 FILENAME: b100723.il.dgn
 CHECKED BY: CSR DATE: 6/22/11 SCALE: 1" = 20'
 DESIGNED BY: MAS DATE: 8/10
 BRIDGE NO. 07225 DRAWING NO. 52156



BRIDGE ENGINEER


104+00

105+00


106+00

107+00


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 100723							24	61
07225 - END BENTS - 52157								



PLAN
Scale: 3/8" = 1'-0"



ELEVATION
Looking Back - Bent 1
Looking Ahead - Bent 4
Scale: 3/8" = 1'-0"



TYP. ANCHOR BOLT LOCATION
No Scale

GENERAL NOTES

All concrete shall be Class "S" with a minimum 28-day compressive strength $f'_c=3500$ psl. Concrete shall be poured in the dry and all exposed corners to be chamfered 3/4" unless otherwise noted.

All reinforcing steel shall conform to AASHTO M31 or M53, Grade 60 ($f_y = 60,000$ psl).

Granular backfill and pipe underdrain required behind cap. See Dwg. No. 52162.

For details of steel shell piles, see Dwg. No. 52159.


For details of anchor bolts, see Dwg. No. 52161.

For additional information, see Layout.


BAR LIST-PER BENT

MARK	NO. REQ'D.	LENGTH	P.D.	BENDING DIAGRAMS
B401	43	11'-6"	2"	<p>Dimensions are out to out of bars.</p>
B402	12	8'-1"	2"	
B403	2	36'-3"	Str.	
B404	4	12'-7"	2"	
B405	4	13'-4"	2"	
B406E	8	8'-5"	Str.	
B407E	8	7'-3"	2"	
B408E	7	4'-8"	Str.	
B501E	64	10'-3"	2 1/2"	
B601	6	37'-7"	4 1/2"	
B602	6	36'-3"	Str.	

Note: Bars with an "E" suffix are to be epoxy coated.



SECTION A-A
Scale: 3/4" = 1'-0"



**DETAILS OF END BENTS
DITCH NO. 6**

ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: CJR DATE: 4/15/2011 FILENAME: bl00723-bl.dgn
CHECKED BY: KDH DATE: 5-2-11 SCALE: AS NOTED
DESIGNED BY: MCB DATE: 01/11
BRIDGE NO. 07225 DRAWING NO. 52157


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723	25	(0)	
				07225 - INT. BENTS - 52158				

BAR LIST-PER BENT


MARK	NO. REQ'D.	LENGTH	P.D.	BENDING DIAGRAMS	
B401	44	13'-6"	2"		
B402	20	9'-7"	2"		
B403	4	36'-3"	Str.		
D401E	70	3'-9"	Str.		
B601	6	37'-7"	4 1/2"		
B602	6	36'-3"	Str.		

Dimensions are out to out of bars.


Note: Bars with an "E" suffix are to be epoxy coated.




PLAN
Scale: 3/8" = 1'-0"



ELEVATION
Scale: 3/8" = 1'-0"



SECTION A-A
Scale: 3/4" = 1'-0"



TYP. ANCHOR BOLT LOCATION
No Scale

GENERAL NOTES


All concrete shall be Class "S" with a minimum 28 day compressive strength $f'_c = 3,500$ psi. Concrete shall be poured in the dry and all exposed corners to be chamfered 3/4" unless otherwise noted.

All reinforcing steel shall conform to AASHTO M31 or M53, Grade 60 (yield strength = 60,000 psi).

For details of steel shell piles, & pile encasement, see Dwg. No. 52159.

For details of anchor bolt, see Dwg. No. 52161.

For additional information, see layout.




DETAILS OF INTERMEDIATE BENTS
DITCH NO. 6

ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: CJR DATE: 4/13/11 FILENAME: b100723_b2.dgn
CHECKED BY: KDH DATE: 5-2-11 SCALE: AS NOTED
DESIGNED BY: MCB DATE: 01/11
BRIDGE NO. 07225 DRAWING NO. 52158


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		26	61
				07225 - STEEL SHELL PILES - 52159				



Note: Steel pile tip will not be paid for directly, but shall be subsidiary to the item "Steel Shell Piling".

CONCRETE FILLED STEEL SHELL PILE

① Pile anchorage shall be placed to minimize interference with anchor bolts and reinforcing in cap or footing.




GENERAL NOTES FOR CONCRETE FILLED STEEL SHELL PILES:

Steel shells shall conform ASTM A252, Grade 3 (Fy = 45,000 psi).
 Concrete used for filling of steel shell shall be Class S with a minimum 28-day compressive strength, f'c = 3,500 psi. and shall be poured in the dry.
 Steel shell piling that extends above the ground and is not protected by pile encasement shall be painted in accordance with subsection 805.02.
 See Bridge Layout for size and estimated length of steel shell piles and for additional driving information.


Concrete, structural steel, reinforcing steel (including welding), and painting will not be paid for separately, but will be considered subsidiary to the item "Steel Shell Piling".

ALTERNATE PILE ANCHORAGE DETAIL



② Welding shall comply with ANSI/AWS D1.4 Structural Welding Code-Reinforcing Steel and applicable portions of ANSI/AWS D1.5 Bridge Welding Code.


HOOKED BAR DETAIL



PART SECTION

ELEVATION


ALTERNATE FLAT TIP DETAIL



PART SECTION

ELEVATION

ALTERNATE VANED TIP DETAIL



TYPICAL SPLICE DETAILS

TABLE OF VARIABLES

BRIDGE NUMBER	OUTSIDE DIAMETER "D"	NOMINAL SHELL THICKNESS "T"	PLATE THICKNESS "X"	PILE STRAPS	
				PLATE	REINFORCING
07225	16"	0.50"	1"	2 @ 1/2" x 1 5/8"	5 - #6
	24"	0.50"	1 3/4"	2 @ 1/2" x 2 1/2"	8 - #7


GENERAL NOTES FOR PILE ENCASEMENTS:

See Bridge Layout for required location of pile encasements. Only interior trestle pile bents shall have pile encasements.

Concrete shall be Class S with a minimum 28-day compressive strength, f'c = 3,500 psi. If concrete cannot be placed in the dry, Seal Concrete may be used from top to bottom of encasement.

Reinforcing steel shall conform to AASHTO M 31 or M 53, Grade 60.

Concrete, welded wire fabric or reinforcing steel, and galvanized pipe will not be paid for separately, but will be considered included in the unit price bid for "Pile Encasement".




PILE ENCASEMENT DETAIL FOR STEEL SHELL PILES

(Shown with Encasement to Bottom of Cap) ⑤

③ Unless otherwise noted on Bridge Layout.

④ See Bridge Layout for height of pile encasement (3'-0" Minimum).

⑤ Pile encasement, when not extended to bottom of cap, shall have 2" concrete taper for water runoff as shown in the detail for partial height encasement.




ALTERNATE PILE ENCASEMENT DETAIL FOR STEEL SHELL PILES

(Shown with Partial Height Encasement)


DETAILS OF CONCRETE FILLED STEEL SHELL PILES AND PILE ENCASEMENTS

ROUTE 867
 ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.



DRAWN BY: KDH DATE: 6-13-11 FILENAME: b100723.ssp.dgn
 CHECKED BY: mcb DATE: 6/15/11 SCALE: AS NOTED
 DESIGNED BY: DATE: BRIDGE NO. 07225 DRAWING NO. 52159

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		27	61
				07225 - 117 FT. UNIT - 52160				




- ① Tolerance: Minus = 1/4", Plus equal to amount of Slab Thickening used to meet Slab Thickness Tolerance - see "Adjustment for Slab Thickness Tolerance".
- ② Refer to "Adjustment for Slab Thickness Tolerance".
- ③ Measured at ℓ Bearing & ℓ Beam
- ④ To Working Point - See "Rounding Detail"

TABLE FOR WELD


Material Thickness of Thicker Part Joined (Inches)	Minimum Size of Fillet Weld (Inches)	Single Pass Weld Must Be Used
To 3/4" Inclusive	1/4"	
Over 3/4"	5/16"	Used

Note: When a fillet weld size, as shown on the plans, is larger than the minimum, the first pass shall be that specified for minimum size of fillet weld.

*If permanent steel bridge deck forms are used, the fabricator shall clip the plate as necessary to accommodate the deck form support.



Note: Bolts in connections shall be properly installed and tightened in accordance with Subsection 807.71.




**Tolerance when removable deck forming is used is +1/2", -1/4". Haunch forming is required and shall be adjusted to maintain slab thickness tolerance.

Note: t_s = slab thickness as shown in "Typical Roadway Section".

Haunch dimension may vary within the following limits to maintain the grade and slab thickness tolerance: Minimum - occurs when top flange contacts bottom reinforcing steel; Maximum - top flange thickness plus 1 3/4". No increase in concrete and structural steel quantities will be made to maintain tolerances.

Tolerances shown are applicable only when removable deck forming is used. See Std. Dwg. No. 14991 for tolerances when permanent steel deck forms are used. Payment for concrete shall be based on removable deck forming.

ADJUSTMENT FOR SLAB THICKNESS TOLERANCE
No Scale




NOTE: Working Point matches Theoretical Roadway Grade.

SHEET 1 OF 7
 DETAILS OF 117' INTEGRAL
 W-BEAM UNIT
 DITCH NO. 6

ROUTE 6
 ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 3-29-11 FILENAME: bi00723_sl.dgn
 CHECKED BY: CSR DATE: 6/21/11 SCALE: AS NOTED
 DESIGNED BY: mcb DATE: 12/10
 BRIDGE NO. 07225 DRAWING NO. 52160



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	100723		28	61
				07225 - 117 FT. UNIT - 52161				
















TABLE OF DEAD LOAD DEFLECTIONS-INCHES

Span	Point of Deflection	Structural Steel	Structural Steel + Slab	Structural Steel + Slab + Rail
1	1.00	0	0	0
	1.25	0.017	0.141	0.144
	1.50	0.020	0.167	0.171
	1.75	0.009	0.073	0.073
	2.00	0	0	0
2	2.25	0.017	0.148	0.164
	2.50	0.029	0.255	0.280

Note: Table is symmetrical about C.L. Unit.



Stud Shear Connectors shown shall be 3/8" x 4" long, granular flux filled, solid fluxed or equal, and automatically end welded to the beam flange in accordance with the recommendations of the Manufacturer. 3/4" studs may be used in place of the 3/8" studs shown, at the ratio of 1.361 - 3/4" studs in place of one 3/8" stud. 3/8" studs will be used as basis for measurement of structural steel in shear connectors. Maximum stud spacing = 24".



SHEET 2 OF 7
DETAILS OF 117' INTEGRAL
W-BEAM UNIT
DITCH NO. 6

ROUTE 117
SEC. 6
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.


BRIDGE NO. 07225
DRAWING NO. 52161

DATE: 3-30-11
FILENAME: bi00723_s2.dgn
SCALE: AS NOTED

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
							JOB NO. 100723	29/61
							07225 - 117 FT. UNIT - 52162	


① Full-Depth Parapet Joint (1/4" to 1" max.) Stop 4" from top of slab. Typ. both sides of Rdwy.

② Partial-Depth Parapet Joint (1/4" to 1" max.) Stop 1'-2" from top of slab. Typ. both sides of Rdwy.



REINFORCING PLAN


Scale: 3/8" = 1'-0"



SECTION AT END BENT


No Scale

Notes:
 Rolls and wings above required construction joint are included in span construction and are included in span quantities.
 Unless otherwise noted, required slab joints and pouring sequence construction joints shall align with parapet open joints at the gutterline.
 For "VIEW N-N" and "VIEW P-P", see Dwg. No. 52163.
 For "VIEW R-R" and "SECTION S-S", see Dwg. No. 52164.
 Construction joints shown are based on Alternate No. 1 Pouring Sequence, see Dwg. No. 52166.



DETAIL W

No Scale




DETAIL U

Scale: 3/8" = 1'-0"

DETAIL V

Scale: 3/8" = 1'-0"

*** See End Bent Details on Dwg. No. 52157 for reinforcing and additional details.



SLAB JOINT DETAIL

No Scale

Use Type 3, 4, or 6 Joint Sealer. See subsections 501.02 (h) and 501.05 (j). Backer Rod filler will not be required. Joint Sealer shall be measured and paid for as Class (SAE) Concrete-Bridge. Slab joints shall extend to the outside edge of the deck slab. Slab joints shall be installed before the parapet railing is poured. If slab joints are to be sawed, they shall be sawed as soon as the concrete has sufficiently set to allow sawing of the joint without damage to the slab. Slab joints shall be placed at all pouring sequence construction joints and required slab joint locations. The joint sealer shall extend across the deck slab (gutterline to gutterline).



BRIDGE ENGINEER

SHEET 3 OF 7
 DETAILS OF 117' INTEGRAL
 W-BEAM UNIT
 DITCH NO. 6


ROUTE 117
 ARKANSAS STATE HIGHWAY COMMISSION

LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 3-31-11 FILENAME: b100723_s3.dgn
 CHECKED BY: CSR DATE: 6/21/11 SCALE: AS NOTED
 DESIGNED BY: mcb DATE: 12/10
 BRIDGE NO. 07225 DRAWING NO. 52162


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		100723	30	601

07225 - 117 FT. UNIT - 52163




VIEW N-N
At End Bents
No Scale

*See Dwg. No. 52157 for reinforcing details and placement.




SECTION T-T
No Scale




VIEW P-P
At Int. Bents
No Scale

** See Dwg. No. 52158 for reinforcing details and placement.



SECTION G-G
No Scale




SHEET 4 OF 7
DETAILS OF 117' INTEGRAL
W-BEAM UNIT
DITCH NO. 6

ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 4-4-11 FILENAME: b100723_s4.dgn
CHECKED BY: CSL DATE: 6/21/11 SCALE: AS NOTED
DESIGNED BY: mcb DATE: 10/10
BRIDGE NO. 07225 DRAWING NO. 52163

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		100723	31601	


BAR LIST ① 07225 - 117 FT. UNIT - 52164




SECTION S-S
Scale: 1/2" = 1'-0"

Note: Modify the bridge rail and connection detail above the gutterline as required by the manufacturer of the bridge end terminal. Reinforcing bars that are relocated or bent to fit the modified bridge rail shall have minimum plan concrete cover. See Layout for location of bridge end terminal.


VIEW R-R
Scale: 1/2" = 1'-0"



SECTION W-W
Scale: 3/4" = 1'-0"




SECTION X-X
3/4" = 1'-0"




SECTION Y-Y
3/4" = 1'-0"

MARK	NO. REQ'D.	LENGTH	P.D.
S401	324	31'-5"	Str.
S402	6	36'-2"	Str.
S403	48	9'-7"	Str.
S404	32	3'-0"	Str.
S405	70	8'-5"	2"
P401	392	5'-6"	3"
P402	76	4'-10"	3"
P403	72	4'-5"	Str.
P404	28	4'-8"	Str.
P405	56	8'-8"	Str.
P406	56	10'-8"	Str.
P407	28	13'-2"	Str.
R401	16	3'-11"	2"
R402	16	4'-0"	2"
R403	24	9'-8"	Str.
R404	24	4'-5"	Str.
W401	20	4'-7"	2"
W402	20	5'-8"	Str.
S501	82	33'-6"	3"
S502	83	32'-10"	Str.
S503-S521	2 each	Var. 7'-3" to 31'-5"	Str.
S522	4	35'-11"	3 3/4"
S523	128	7'-0"	2 1/2"
P501	392	4'-10"	3 3/4"
D501E	32	6'-2"	3 3/4"
S601	83	32'-10"	Str.
S602-S620	2 each	Var. 7'-3" to 31'-5"	Str.
S621	12	6'-3"	4 1/2"
S622	6	7'-3"	4 1/2"
S623	6	9'-6"	4 1/2"
S624E	142	4'-0"	4 1/2"
S625	108	27'-9"	Str.
S626	108	15'-6"	4 1/2"
S627	6	36'-2"	Str.
R601	32	5'-8"	Str.
R602	12	5'-0"	Str.
S701	184	11'-10"	6 3/4"
W701	12	12'-1"	Str.
W702	32	12'-8"	5 1/4"



Note: Bars with an "E" suffix are to be epoxy coated.




BRIDGE ENGINEER

SHEET 5 OF 7
DETAILS OF 117' INTEGRAL
W-BEAM UNIT
DITCH NO. 6
ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 4-4-11 FILENAME: b100723_s5.dgn
CHECKED BY: CSR DATE: 6/2/11 SCALE: AS NOTED
DESIGNED BY: mcb DATE: 12/10
BRIDGE NO. 07225 DRAWING NO. 52164


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		32	61
				JOB NO.	100723		07225 - 117 FT. UNIT - 52165	



① Full-Depth Parapet Joint (1/4" to 1" max.) as shown in "Reinforcing Plan", Dwg. No. 52162. Stop 4" from top of slab.

DETAILS OF PARAPET RAIL
Scale: 3/8" = 1'-0"

② Partial-Depth Parapet Joint (1/4" to 1" max.) as shown in "Reinforcing Plan", Dwg. No. 52162. Stop 1'-2" from top of slab.



All panels shall be braced as required to prevent racking. All parapet joints shall be sawed as soon as practical to a minimum width of 1/4". To control cracking before sawing, all joints must be grooved before the concrete is set. Sawing of the joints must be controlled so it will follow the grooved joint.

The extruded parapet shall conform to the horizontal and vertical lines shown on the plans or as directed by the Engineer and shall present a smooth, uniform appearance and texture. Exposed surface may be given a light brush finish or a Class 3, Textured Coating Finish, in place of the Class 2, Rubbed Finish.


DETAILS OF OPTIONAL SLIPFORMING OF CONCRETE PARAPET RAIL

No Scale

TABLE OF PARAPET RAIL VARIABLES


"A" Closed Parapet	"B"	P4xx Bar	"C" Open Parapet	"D"	"E"	"F"	"G"	P4xx Bar
5'-0"	9	P404	11'-0"	4'-0"	7	5	3'-0"	P406
9'-0"	17	P405	13'-6"	5'-0"	9	6	3'-6"	P407

Note: For location of Open and Closed Parapet panels, see "Reinforcing Plan", Dwg. No. 52162.




THREE DIMENSIONAL VIEW OF INTEGRAL BENT


No Scale




SECTION J-J
Scale: 3/4" = 1'-0"



SECTION K-K
Scale: 3/4" = 1'-0"



DETAIL Y
No Scale



DETAIL Z
No Scale

Note: The surfaces of the 3/8" plates which will not be in contact with concrete shall be painted with aluminum epoxy paint in accordance with Section 638, or as approved by the Engineer. Only one coat is required and shall be applied in the fabricator's shop. Painting will not be paid for directly, but will be considered subsidiary to "Structural Steel in Beam Spans (M270, Gr. 50W)."

Parapet studs shall be 5' long, granular flux filled, solid fluxed or equal, and automatically end welded to the plate. Studs and plates shall meet the requirements of Section 807 and shall be measured and paid for as "Structural Steel in Beam Spans (M270, Gr. 50W)."



SHEET 6 OF 7
DETAILS OF 117' INTEGRAL
W-BEAM UNIT
DITCH NO. 6

ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION

LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 4-4-11 FILENAME: bi00723_s6.dgn
CHECKED BY: CSE DATE: 6/21/11 SCALE: AS NOTED
DESIGNED BY: MCB DATE: 12/10
BRIDGE NO. 07225 DRAWING NO. 52165

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		100723	33	61
				07225 - 117 FT. UNIT		- 52166		

GENERAL NOTES

CONSTRUCTION SPECIFICATIONS: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2003 edition) with applicable supplemental specifications and special provisions.

DESIGN SPECIFICATIONS: AASHTO LRFD Bridge Design Specifications (5th Edition, 2010 with 2010 Interims).

MATERIALS AND STRENGTHS

Class (S(AE)) Concrete $f'_c = 4,000$ psi.
 Reinforcing Steel (AASHTO M31 or M53, Gr. 60) $f_y = 60,000$ psi.
 Structural Steel (AASHTO M 270, Gr. 50W) $F_y = 50,000$ psi.
 Structural Steel (AASHTO M 270, Gr. 36) $F_y = 36,000$ psi.

CONCRETE: Concrete shall be poured in the dry and all exposed corners to be chamfered $\frac{3}{4}$ " unless otherwise noted. All concrete shall be Class (S(AE)) with a minimum 28 day compressive strength $f'_c = 4,000$ psi.

The superstructure details shown are for use when removable deck forming is used and are the basis for measurement of Class (S(AE)) Concrete. See Standard Drawing No. 14991 for allowable modifications and for tolerances when Permanent Steel Bridge Deck Forms are used.

Concrete in bridge superstructure shall be placed, consolidated and screeded off for the entire pour before any concrete has taken its initial set. This may require the use of a retarding agent.

The concrete deck shall be given a fine finish in accordance with subsection 802.19 for Class 5 Tined Bridge Roadway Surface Finish. Movement of the finishing machine across new concrete shall be on planks placed on the surface and shall be prohibited for 72 hours after finishing the pour. Sufficient concrete must be placed ahead of the strike-off to fully load the beam. If a longitudinal strike-off is used, a vertical camber adjustment must be made in the strike-off to account for the future dead load deflection due to the railing. A minimum of 72 hours shall elapse between completion of the slab and the pouring of the parapet railing.

Removable forms shall be used for concrete diaphragms.

REINFORCING STEEL: All reinforcing steel shall conform to AASHTO M31 or M53, Grade 60. The reinforcing steel is to be accurately located in the forms and firmly held in place by steel wire supports, sufficient in number and size to prevent displacement during the course of construction. The wire supports will not be paid for directly, but will be considered subsidiary to the item "Reinforcing Steel - Bridge (Grade 60)".

STRUCTURAL STEEL: Structural steel shall be AASHTO M 270, Grade 50W unless otherwise noted and shall be paid for as "Structural Steel in Beam Spans (M270, Gr. 50W)", Grade 50W steel shall not be painted. All exposed surfaces shall be cleaned in accordance with subsection 807.84(e) unless otherwise noted. Structural steel completely embedded in concrete may be AASHTO M270, Gr. 36 unless otherwise noted.

Drawings show general features of design only. Shop drawings shall be made in accordance with the specifications, submitted and approval secured before fabrication is begun.

Requests for substitution of structural steel shapes shown with shapes of greater size must be submitted by the Contractor to the Engineer for approval. Steels of equal or greater strengths will be accepted only when shown on the approved shop drawings. Payment will be based on the basis of shapes and materials shown in the plans, and no additional compensation will be made for any adjustments due to substitutions.

Beams and field splice plates are considered main load carrying members and shall meet the Longitudinal Charpy V-Notch Test specified in subsection 807.05. This work and material will not be paid for directly, but shall be considered subsidiary to the item "Structural Steel in Beam Spans (M270, Gr. 50W)".

All beams shall be blocked in their true position in the shop with webs horizontal in groups as specified in subsection 807.54(b)(2). The camber, length of sections, and distance between bearings shall be measured with the beams in their true position and this information shall become part of the permanent records for this job. The component parts shall be match marked in this assembly and these marks shall be shown on the erection diagram. All beam dimensions are based on a temperature of 60 degrees F. A tolerance of $\frac{1}{4}$ " +/- is allowed for camber.


Flange field splice plates shall be cut and fabricated so that the primary direction of rolling is parallel to the direction of the main tensile and/or compressive stresses.

All welding that is to be done during fabrication of structural steel, including temporary welds, shall be detailed on the shop drawings and submitted for approval. If additional welds are required, whether permanent or temporary, a formal request with detailed drawings shall be submitted to the Engineer for approval; however, additional welds used for attaching falsework support devices or screed rail supports to the structural steel that do not exceed the limitations of subsection 802.13 will not require approval prior to construction. All welding shall conform to subsection 807.26.


Field connections shall be bolted with high-strength bolts and shall be $\frac{3}{4}$ " ϕ bolts unless otherwise noted. Open holes shall be $\frac{1}{8}$ " ϕ unless otherwise noted. Bolts shall be placed with heads on the outside face of the exterior beam webs and on the bottom of the beam flanges. Holes for $\frac{3}{4}$ " ϕ high-strength bolts may be $\frac{1}{2}$ " ϕ diameter if a washer is supplied for use under both the nut and head of the bolt.

Diaphragms shall be installed as beams are erected. All bolts in diaphragms and field splices shall be installed and tightened in accordance with subsection 807.71 prior to pouring the concrete deck.

All stud shear connectors shall be granular flux filled, solid fluxed or equal and shall be automatically end welded in accordance with the recommendations of the manufacturer.



ALTERNATE NO. 1




ALTERNATE NO. 2

CONCRETE POURING SEQUENCE

No Scale

Note: Pours with the same number may be placed simultaneously or separately. All Pours (1) must be placed before Pours (2) can be placed. All Pours (2) must be placed before Pours (3) can be placed. 48 hours shall elapse between the end of a pour and the start of the next pour. 72 hours shall elapse between the end of a pour and the start of an adjacent pour. Any railing pours made before the entire slab unit has been placed must be approved by the Engineer. The Contractor must obtain approval from the Engineer for any deviation from the pouring sequences shown.


If concrete diaphragms at intermediate bents are poured separately, a minimum of 48 hours shall elapse between the diaphragm pour and the slab pour. Concrete diaphragms at end bents shall be poured monolithically with the slab.



Note: At the Contractor's Option, the Transverse Screed may be placed parallel to the skew or perpendicular to ϕ Bridge.

CONCRETE PLACEMENT PROCEDURE

No Scale



BRIDGE ENGINEER


SHEET 7 OF 7
 DETAILS OF 117' INTEGRAL
 W-BEAM UNIT
 DITCH NO. 6

ROUTE SEC.
 ARKANSAS STATE HIGHWAY COMMISSION


LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 4-5-11 FILENAME: b100723_s7.dgn
 CHECKED BY: CSP DATE: 10/21/11 SCALE: AS NOTED
 DESIGNED BY: MCB DATE: 12/10
 BRIDGE NO. 07225 DRAWING NO. 52166


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
04-10-2003				6	ARK.		35	
							JOB NO.	
(1) EMBANKMENT & BACKFILL								1888A




EMBANKMENT CONSTRUCTION AND FOOTING BACKFILL AT VERTICAL WALL ABUTMENTS




EMBANKMENT CONSTRUCTION AT SPILL-THROUGH PILE END BENTS




EMBANKMENT CONSTRUCTION AND FOOTING BACKFILL AT SPILL-THROUGH END BENTS




VERTICAL WALL ABUTMENTS



SPILL-THROUGH END BENTS WITH STUB WING



SPILL-THROUGH END BENTS WITH TURNBACK WING




SPILL-THROUGH END BENTS WITH TRANSITION WING

METHOD OF DETERMINING FILL SLOPE LOCATION AT BRIDGE ENDS

GENERAL NOTES

The Bridge End Embankment shall be defined as a section of embankment, not less than 20 feet long adjacent to the bridge end, together with the side slopes and slopes under the bridge end including around the end of wingwalls. Embankment adjacent to structures shall be constructed in 4 inch horizontal layers (loose measure) and compacted by the use of mechanical equipment to the satisfaction of the Engineer. Refer to subsections 210.09, 210.10 and 801.08 of the Specifications for construction requirements.


Revised and redrawn MJT 04-10-2003
Chk'd. By: csp 04-10-2003




EMBANKMENT CONSTRUCTION AND BACKFILL AT BRIDGE ENDS
ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: MJT DATE: 04-10-2003 FILENAME: B1888A.STD
CHECKED BY: CJF DATE: 04-10-2003 SCALE: NO SCALE
DESIGNED BY: STD DATE: _____
BRIDGE NO. _____ DRAWING NO. 1888A


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
04-10-2003				6	ARK.		36	
							JOB NO.	
							1	RIP. & EXCAV. 1891F




EXCAVATION FOR STRUCTURES - ABUTMENT IN NEW EMBANKMENT INTERIOR BENT IN NEW EMBANKMENT AND NATURAL GROUND



EXCAVATION FOR STRUCTURES - BRIDGE LOCATION WITH DESIGNATED CHANNEL CHANGE




PLAN OF DUMPED RIPRAP




ELEVATION OF RIPRAP BERME WITH RIPRAP


ELEVATION OF RIPRAP BERME WITHOUT RIPRAP




EXCAVATION FOR STRUCTURES - ABUTMENT IN NATURAL GROUND



EXCAVATION FOR STRUCTURES - ABUTMENT IN NEW EMBANKMENT INTERIOR BENT IN NATURAL GROUND




SECTION A-A (TOE EXCAVATION IN SOIL)




SECTION B-B

OPEN ABUTMENT WITH TURNBACK WINGS



SECTION A-A (TOE EXCAVATION IN ROCK)



DETAIL C

NOTE: USE THIS TYPE OF TOE WHEN ROCK IS ENCOUNTERED WHICH IS IN A STABLE CONDITION.

NOTE: IN LIEU OF AN AGGREGATE FILTER BLANKET, A SYNTHETIC FIBER GEOTEXTILE FABRIC COMPLYING WITH THE REQUIREMENTS OF SUBSECTION 816.02(a) MAY BE USED.

NOTE: DETAILS FOR COMPUTING EXCAVATION FOR STRUCTURES ARE INCLUDED FOR INFORMATION AS TO HOW PLAN QUANTITIES WERE CALCULATED AND FOR USE WHEN ADJUSTING QUANTITIES WHEN CHANGING FOOTING ELEVATION.




BRIDGE ENGINEER


Revised and redrawn MJT 04-10-2003
Chk'd. By: CJF 04-10-2003

DETAILS FOR DUMPED RIPRAP AND FILTER BLANKET AND DETAILS FOR COMPUTING EXCAVATION FOR STRUCTURES
ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: MJT DATE: 04-10-2003 FILENAME: B1891F.STD
CHECKED BY: CJF DATE: 04-10-2003 SCALE: NO SCALE
DESIGNED BY: STD DATE: _____
BRIDGE NO. _____ DRAWING NO. 1891F




EXCAVATION FOR STRUCTURES - BENT IN ROADWAY FILL SECTION AND NATURAL GROUND




EXCAVATION FOR STRUCTURES - ABUTMENT IN NATURAL GROUND AND NEW EMBANKMENT

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
4-10-2003				6	ARK.		37	
07-14-2010								
JOB NO.							TYPE B GUTTERS 2016B	




HALF PLAN OF APPROACH GUTTERS FOR SQUARE BRIDGE


② Length varies. See End Bent details for actual length. Quantities shown are for 10'-0" Transition Rail.



Bj



PLAN OF APPROACH GUTTERS FOR SKEWED BRIDGE




SECTION A - A


Slab Depth Varies - See Span and Bent Details

① Construct gutter curb with height-transition as shown if drop inlet is not placed at end of gutter.

Construct gutter curb full height (no height-transition) if drop inlet is placed at end of gutter. Curb height transition placed on drop inlet. See drop inlet details.



SECTION C - C
N.T.S.



SECTION B - B
N.T.S.

QUANTITIES FOR ONE SQUARE APPROACH GUTTER

"W" Width (ft.)	Reinforcing Steel (lbs.)	Concrete (cubic yards)
3	252	3.00
4	319	3.75
6	459	5.25
8	590	6.75

*** BAR LIST ②
TYPE B GUTTER

Mark	No. Required for Width "W"				Length	Square or Skewed
	3'-0"	4'-0"	6'-0"	8'-0"		
G401 - G405	1 each	1 each	1 each	1 each	"W" - 3" to "W" + 3"	Square
G406	1	1	1	1	"W" + 3"	Square
G407	12	12	12	12	"W" + 10"	Square
G408	13	13	13	13	"W" + 10"	Skewed
G409	1	1	1	1	"W" + 3"	Skewed
G410	8	8	8	8	*	Skewed
G501	6	8	12	16	26'-8"	Square
G502	1	1	1	1	22'-2"	Square
G503	1	1	1	1	17'-8"	Square
G504	1	1	1	1	*	Skewed
G505	1	1	1	1	*	Skewed
G506-G5...*	1 each	1 each	1 each	1 each	*	Skewed

* Bar Lengths vary with Skew.
** G512 for "W" = 3'
G514 for "W" = 4'
G518 for "W" = 6'
G522 for "W" = 8'


GENERAL NOTES

- Concrete shall be Class S or Class (SAE) or mixture used for Portland Cement Concrete Pavement.
- Reinforcement Steel shall conform to AASHTO M31 or M53, Grade 60 (fy = 60,000 psi).
- Approach Gutters will be measured and paid for in accordance with Section 504 of the Standard Specifications.
- Revised and redrawn 4-10-2003, By KDH Ck. By: CJF 4-10-2003
- Added joint sealer type & revised transition rail length 07-14-2010 by MJT Checked by: CJF 07-14-2010

DETAILS OF STANDARD TYPE B APPROACH GUTTERS

ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 4-10-2003 FILENAME: B2016B.STD
CHECKED BY: CJF DATE: 4-10-2003 SCALE: 3/8" = 1'-0"
DESIGNED BY: STD DATE: BRIDGE NO. DRAWING NO. 2016B



BRIDGE ENGINEER

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
4-17-07		01-08-09		6	ARK.		38	
8-16-07		11-23-10						
12-10-08		01-25-11						

The name of the bridge as shown on the plans shall be placed on Lines 1 - 3 using 1/8" raised letters and numerals 3/8" high.

	Example 1	Example 2	Example 3	Example 4
Line 1	Red River	Southern	Saline	Highway 5
Line 2	Relief	Rd road	River	
Line 3		Overpass	Relief	


GENERAL NOTES

Specifications: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction, (2003 Edition) with applicable Supplemental Specifications and Special Provisions.

Name plates shall be cast bronze and shall meet the material requirements as specified in Section 812 of the Standard Specifications.

Body of plate shall be 1/4" thick and shall include four tapering cone lugs 3/8" to 7/8" x 2" long. The border and all lettering shall be raised 1/8" above the face of plate and shall be polished.

All lettering shall be plain gothic, square cut and not tapered. The number of plates required and the location and name on the plate for each bridge shall be as designated on the plans.




Place the design live loading here using 1/8" raised letters and numerals 1/4" high. Examples: HS 20 HL-93

Place the Year in which Contract was awarded here using 1/8" raised numerals 3/8" high. Example: 2001

Place the name of the company awarded the construction contract here using 1/8" raised letters and numerals 3/8" high. Example: ABCD CONSTRUCTION, INC.

Place the Bridge number here using 1/8" raised letters and numerals 1/4" high. Examples: A1234 05432

TYPICAL BRIDGE NAME PLATE




DETAILS OF STANDARD TYPE D BRIDGE NAME PLATE
 SEC. ROUTE
 ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 4-17-07 FILENAME: B2387.STD
 CHECKED BY: CJF DATE: 4-17-07 SCALE: 1" = 1'-0" OR AS NOTED
 DESIGNED BY: STD. DATE: ———
 BRIDGE NO. DRAWING NO. 2387

- 6 Revised Commission Names 01-25-11 MJT Checked By: CJF Date: 01-25-11
- 5 Revised Commission Names 11-23-10 MJT Checked By: CJF Date: 11-23-10
- 4 Revised Commission Names 01-08-09 MJT Checked By: CJF Date: 01-08-09
- 3 Revised Commission Names 12-10-08 MJT Checked By: CJF Date: 12-10-08
- 2 Added Dimension 8-16-07 KDH Checked By: SWP Date: 8-16-07
- 1 Revised and Redrawn 4-17-07 KDH Checked By: CJF


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
11-27-96						6	ARK.		39	
04-10-2003										

BR. DECK FORMS 14991




PART PLAN - SQUARE SPAN
3/8" = 1'-0"


PART PLAN - SKEWED SPAN
3/8" = 1'-0"




SECTION A-A
N.T.S.
(Angle at end of span)




SECTION A-A
N.T.S.
(Channel at end of span)




SECTION C-C - ALTERNATE
1" = 1'-0"




SKETCH OF PERMISSIBLE SUPPORTS
N.T.S.




SECTION B-B
1" = 1'-0"



SECTION B-B
1" = 1'-0"



SECTION B-B
1" = 1'-0"



SECTION B-B
1" = 1'-0"


(Showing permissible support for tension flange where shear connectors are used, and for all compression flanges)

③ Minimum weld: 1/8" x 1" @ 18". More weld may be required; maximum length per weld = 1/2" (typ.)

(Showing permissible support for tension flange where shear connectors are used and for all compression flanges)


(Showing permissible support for tension flange where shear connectors are not used)

(Showing permissible support for tension flange where shear connectors are not used)




SECTION B-B
1" = 1'-0"

(Showing Z Closure)




SECTION B-B (FOR CONCRETE GIRDERS)
1" = 1'-0"

(Showing support by Insert cast in girder)



SECTION B-B (FOR CONCRETE GIRDERS)
1" = 1'-0"

(Showing support by Strap)



SECTION D-D
1" = 1'-0"

Note: Only Bottom Reinforcing is shown.

GENERAL NOTES
*t_s = slab thickness as shown on superstructure detail drawings.

Permanent steel deck forms may be used at the Contractor's option and shall be at no additional cost to the Department. Such use may result in changes to the dead load deflection of the girder. Any cost for adjustments due to a change in the dead load deflection will be borne by the Contractor. Payment for deck concrete and structural steel will not be increased due to use of permanent steel deck forms.

Permanent steel deck forms shall conform to subsection 802.14(b) of the Standard Specifications. Detailed plans, including detailed calculations and manufacturer's technical brochure, shall be submitted to and approved by the Bridge Engineer before work of forming the bridge deck is started.

Welding of form supports to the tension flange of steel girders will be permitted only in areas where shear connectors are used. When welding is not allowed, the method of fastening Z or L supports to the flange must be approved by the Bridge Engineer.

Form sheets shall be fastened to supporting members and to each other with galvanized metal screws sufficient in size and number to provide a secure attachment. Alternate methods of attachment must be approved by the Bridge Engineer.

When the pitch of form corrugations match the reinforcing spacing, transversely align form sheets across the bridge to maintain the correct orientation of continuous reinforcing bars in the corrugations.

Bar support rods, when used, shall be sized and spaced to adequately support the bottom reinforcing mat at the required position.

High chairs shall be sized to support the top mat of reinforcing at the proper position. High chairs shall be placed at locations shown on the detail drawings.

Specifications: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2003 Edition), with applicable supplemental specifications and special provisions.

DETAILS OF PERMISSIBLE TYPE PERMANENT STEEL BRIDGE DECK FORMS FOR STEEL & CONCRETE GIRDER SPANS
ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.


DRAWN BY: MJT DATE: 10-17-96
CHECKED BY: CPB DATE: 10-17-96 SCALE: as noted
DESIGNED BY: STD DATE: ---
BRIDGE NO. DRAWING NO. 14991



Redrawn and revised 11/27/96; MJT


Revised for 2003 AHTD Construction Specifications and CPB Seal, MJT 04-10-2003
Chk'd. By: CCF 04-10-2003

REFER TO TABULATION OF QUANTITIES FOR 'W' & 'B' DIMENSIONS




TYPE A

REFER TO TABULATION OF QUANTITIES FOR 'W' DIMENSIONS




TYPE B

THE STEEL AND ADDITIONAL CONCRETE FOR THE WALLS SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID FOR 'CONCRETE DITCH PAVING.'




TOE WALL DEPTH MAY BE ALTERED TO 1'-0" WHEN DIRECTED BY THE ENGINEER IN ROCK EXCAVATION

TOE WALL DETAIL FOR CONCRETE DITCH PAVING



NUMBER OF ELEMENTS PER ROW VARIES WITH WIDTH OF PAVING SPECIFIED

ENERGY DISSIPATORS TO BE USED FOR THE ENTIRE LENGTH OF DITCH WHEN SLOPE OF DITCH PAVING EXCEEDS 7%. THE DISSIPATORS WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED TO BE UNINCLUDED IN THE PRICE BID FOR CONCRETE DITCH PAVING.



ENERGY DISSIPATORS
(NO SCALE)

GENERAL NOTES:



- THE FULL WIDTH OF EACH SECTION SHALL BE POURED MONOLITHICALLY.
- TOE WALLS TO BE CONSTRUCTED FULL WIDTH AT EACH END OF DITCH PAVING, AND POURED MONOLITHICALLY.
- SOLID SOD ALONG DITCH PAVING TO BE PLACED WITHIN 14 DAYS OF DITCH PAVING CONSTRUCTION.
- 1' WIDE TRANSVERSE EXPANSION JOINTS SHALL BE PLACED IN CONCRETE DITCH PAVING AT 45' INTERVALS. THE SPACE SHALL BE FILLED WITH APPROVED JOINT FILLER COMPLYING WITH AASHTO M213.

DATE	REVISION	DATE FILM'D
11-17-10	ADDED GENERAL NOTE	
6-2-94	ADDED GENERAL NOTE ABOUT SOLID SODDING	
11-30-8	ELIMINATED MIN. ROWS OF ELEMENTS	111-30-89
7-16-88	REVISED DISSIPATOR NOTE	653-7-15-88
4-3-87	REVISED ENERGY DISSIPATOR	671-4-3-87
1-9-87	MODIFIED NOTE ON ENERGY DISS.	532-1-9-87
11-3-86	ADDED NOTE TO ENERGY DISS.	599-12-1-86
11-1-84	ENERGY DISSIPATOR DETAILS	508-11-1-84
11-1-84	ADDED	
11-1-84	EXCAVATION DETAILS ADDED	
10-2-72	TYPED A & B	
10-2-72	REVISED AND REDRAWN	508-10-2-72


ARKANSAS STATE HIGHWAY COMMISSION

CONCRETE DITCH PAVING




STANDARD DRAWING CDP-1




DETAILS OF W-BEAM GUARD RAIL
RAIL SECTION OF CLOSELY SIMILAR DIMENSIONS AND COMPARABLE STRENGTH MAY BE SUBSTITUTED IF APPROVED BY THE ENGINEER.



SPLICE BOLT
POST BOLT - SAME EXCEPT LENGTH




WOOD BLOCKOUT (W-BEAM)




PLASTIC BLOCKOUT (W-BEAM)


NOTES:
1. SIMILAR SHAPED PLASTIC BLOCKOUTS MAY BE USED AS LONG AS THEY MEET NCHRP-350 TEST LEVEL 3 SPECIFICATIONS OR REQUIREMENTS FOR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH).
2. DIMENSIONS ARE SUBJECT TO MANUFACTURERS TOLERANCES.




STEEL POST



DETAILS OF STEEL LINE POST CONNECTIONS (W-BEAM)



WOOD BLOCKOUT CONNECTIONS
PLASTIC BLOCKOUT CONNECTIONS
DETAILS OF STEEL LINE POST CONNECTIONS (W-BEAM)



WOOD BLOCKOUT CONNECTIONS
PLASTIC BLOCKOUT CONNECTIONS
DETAILS OF WOOD LINE POST CONNECTIONS (W-BEAM)

-GENERAL NOTES-

ALL BOLTS SHALL BE SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND NO MORE THAN 3/4\"/>

WHERE W-BEAM GUARD RAIL CONTINUES, THE INTERMEDIATE SECTIONS SHALL HAVE A POST SPACING OF 6'-3\"/>

W-BEAM GUARD RAIL REPRESENTING INTERMEDIATE SECTIONS WILL BE MEASURED ALONG THE ROADWAY FACE FROM CENTERLINE OF POST TO CENTERLINE OF POST.

USE W-BEAM GUARD RAIL COMPONENTS OF SAME MATERIAL FOR ENTIRE JOB. FOR EXTENSIONS OR MODIFICATION OF EXISTING GUARD RAIL, W-BEAM GUARD RAIL COMPONENTS OF THE SAME TYPE AS THOSE EXISTING SHALL BE USED.

ANY BACKFILLING UNDER OR AROUND POST SHALL BE DAMP SAND THOROUGHLY TAMPED IN PLACE.

WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER S.7f (400 F) OR NO. 1 1350 F SOUTHERN PINE.


CONTRACTOR SHALL HAVE THE OPTION OF USING WOOD BLOCKOUTS FOR W-BEAM GUARD RAIL OR PLASTIC BLOCKOUTS, AS LONG AS BLOCKOUT USED MEETS NCHRP-350 TEST LEVEL 3 SPECIFICATIONS OR REQUIREMENTS FOR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) FOR W-BEAM GUARD RAIL.

7-14-10	RAISED HEIGHT OF GUARD RAIL 1"	
10-15-09	ADDED REFERENCE TO MASH	
4-10-03	REVISED GENERAL NOTES	
8-22-02	REVISED DIMENSION ON WOOD & PLASTIC BLOCKOUT CONNECTIONS & ON STEEL POST	
11-16-01	REVISED WOOD BLOCKOUT & DETAILS OF WOOD LINE POST CONNECTIONS	
3-30-00	REMOVED GUARD RAIL AT BRIDGE ENDS	
1-12-00	ADDED PLASTIC BLOCKOUT	
8-12-98	REV. BLOCKOUTS TO WOOD, DELETED CONC. POST & REV. GENERAL NOTE, DELETED DET. OF GUARD RAIL REPLACE, BEHIND CURB & DET. OF POST PLACE, IN SOLID ROCK, & ADDED DETAILS OF STEEL LINE POST CONN. REMOVED BACK-UP PLATE, REVISED HOLES IN STEEL POLES	
4-3-97	REMOVED "LAP IN DIRECTION OF TRAFFIC" NOTE & PLACED ARROWS ON WASHERS	
10-18-96	REVISED WOOD POST NOTE	
6-2-94	ADDED ALT. STEEL POST SIZE	
8-5-93	REVISED STEEL POST SIZE	8-5-93
10-1-92	REDRAWN & REVISED	10-1-92
8-15-91	REVISED WASHER NOTE	8-15-91
8-2-90	REV. GEN. NOTE & DEPTH OF ANC. POST IN ROCK	8-2-90
7-15-88	REVISED SECTION 3 & GENERAL NOTES	
3-4-88	REV. ANCHOR POST, ELEV. NOTES & POST IN ROCK	780-3-4-88
10-30-87	REVISED WOOD LINE POST DETAIL	546-10-30-87
10-9-87	REDRAWN & REVISED	802-10-9-87
DATE	REVISION	DATE FILM


ARKANSAS STATE HIGHWAY COMMISSION

GUARD RAIL DETAILS


STANDARD DRAWING GR-8



METHODS OF INSTALLATION OF GUARD RAIL AT LESS THAN FULL SHOULDER WIDTH BRIDGES USING GUARD RAIL TERMINAL (TYPE 2)







METHOD OF INSTALLATION OF GUARD RAIL AT FULL SHOULDER WIDTH BRIDGES USING GUARD RAIL TERMINAL (TYPE 2)




METHOD OF INSTALLATION OF GUARD RAIL USING GUARD RAIL TERMINAL (TYPE 1) (FULL SHOULDER WIDTH OR LESS BRIDGES)

ARKANSAS STATE HIGHWAY COMMISSION		
GUARD RAIL DETAILS		
STANDARD DRAWING GR-9		
4-17-08	REVISED LAYOUTS	
11-10-05	REMOVED GUARD RAIL NOTES AND DETAILS	
11-16-01	DELETED NOTE-METHOD OF INSTALLATION OF GUARD RAIL USING GUARD RAIL TERM. (TY. 1)	
1-12-00	ADDED CONSTRUCTION NOTE	1-12-00
6-26-97	REVISED LAYOUT	
10-1-92	REDRAWN & REVISED	10-1-92
	ADDED NOTE	
10-9-87	REDRAWN & REVISED	
DATE	REVISION	DATE FILM









DETAILS OF WIDENING FOR GUARD RAIL

DETAILS SHOWING POSITION OF GUARD RAIL ON HIGHWAY





METHOD OF INSTALLATION OF GUARD RAIL AT FIXED OBSTACLE

				ARKANSAS STATE HIGHWAY COMMISSION	
				GUARD RAIL DETAILS	
				STANDARD DRAWING GR-9A	
4-17-08	MINOR REVISION				
11-10-05	DRAWN				
DATE	REVISION			DATE	FILM



NOTE: BLOCKS SHALL BE THE SAME TYPE THROUGHOUT THE PROJECT LIMITS.




- (1) VERIFY BOLT SPACING FROM RAIL TRANSITION PRODUCER.
- (2) REFER TO APPROACH GUTTER DETAILS.
- (3) LENGTH OF BLOCKOUT ON POST 8 TO BE MODIFIED TO FIT RAIL WIDTH.


THRIE BEAM GUARD RAIL CONNECTION AT BRIDGE ENDS

GENERAL NOTES:
 THE THRIE BEAM RAIL, SPECIAL END SHOE, AND THE TRANSITION SECTION SHALL BE MADE OF STEEL AND SHALL BE 12 GAGE. ZINC COATING SHALL BE TYPE 1.
 RAIL POSTS SHALL BE SET PERPENDICULAR TO THE ROADWAY PROFILE GRADE AND VERTICALLY IN CROSS SECTION.
 ALL BOLTS SHALL BE SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND NO MORE THAN 3/4" BEYOND IT.
 ALL LAP SPLICES, INCLUDING SPECIAL END SHOES, SHALL BE MADE IN THE DIRECTION SHOWN ON STANDARD DRAWINGS GR-9 & GR-11.
 WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER 9.7f (1400 f) OR NO. 1 1350 f SOUTHERN PINE.
 REFER TO STD. DRWG. GR-10A FOR POST DETAILS.
 USE THRIE BEAM GUARD RAIL COMPONENTS OF SAME MATERIAL FOR ENTIRE JOB.
 THRIE BEAM POSTS SHALL BE SAME MATERIAL AS W-BEAM POSTS FOR ENTIRE JOB.

7-14-10	RAISED HEIGHT OF W-BEAM 1"		ARKANSAS STATE HIGHWAY COMMISSION
11-29-07	ADDED PLASTIC BLOCKOUTS		
11-10-05	ADDED NOTE FOR ATTACHING STEEL BLOCKOUT		GUARD RAIL DETAILS
11-18-04	REVISED GENERAL NOTES		
10-9-03	REVISED GENERAL NOTES		STANDARD DRAWING GR-10
4-10-03	REVISED GENERAL NOTES		
8-22-02	REVISED NOTE (2)		
6-29-00	MOVED DIMENSION LINES		
5-18-00	ADDED NOTE		
3-30-00	DRAWN & ISSUED		
DATE	REVISION	DATE FILED	




THRIE BEAM RAIL WITH STEEL TUBING BLOCKOUT AND STEEL POST
POSTS 1-7




W-BEAM TO THRIE BEAM TRANSITION RAIL WITH WOOD OR PLASTIC BLOCKOUT AND STEEL POST
POST 8


* NOTE:
THESE DIMENSIONS WILL NEED TO BE ADJUSTED IN THE FIELD TO MAKE THE TRANSITION FROM 21" MID POINT OF THRIE BEAM TO 22" MID POINT OF W-BEAM.



THRIE BEAM RAIL WITH WOOD OR PLASTIC BLOCKOUTS & WOOD POSTS
POSTS 1-6



THRIE BEAM RAIL WITH WOOD OR PLASTIC BLOCKOUT & WOOD POST
POST 7




W-BEAM TO THRIE BEAM TRANSITION RAIL WITH WOOD OR PLASTIC BLOCKOUT & WOOD POST
POST 8


GENERAL NOTES:
RAIL POSTS SHALL BE SET PERPENDICULAR TO THE ROADWAY PROFILE GRADE AND VERTICALLY IN CROSS SECTION.
WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER 9.7f (1400 f) OR NO. 1 1350 f SOUTHERN PINE.

DATE	REVISION	DATE FILED
7-14-10	REVISED POST 8 DIMENSIONS	
11-29-07	ADDED PLASTIC BLOCKOUTS	
8-22-02	REVISED LIP CURB NOTE	
3-30-00	DRAWN & ISSUED	

ARKANSAS STATE HIGHWAY COMMISSION
GUARD RAIL DETAILS
STANDARD DRAWING GR-10A




PLAN - GUARD RAIL TERMINAL (TYPE I)




ELEVATION - GUARD RAIL TERMINAL (TYPE I)

NOTE:
SECTIONS 1 AND 2 OF GUARD RAIL TERMINAL
SHALL BE PAID FOR AT THE PRICE BID PER
LINEAR FOOT OF THE TYPE OF GUARD RAIL SPECIFIED.



SECTION 1

TERMINAL SECTION



ELEVATION

SECTION


NOTE: GALVANIZE UPPER
15" OF ANCHOR POST AND
ANCHOR ASSEMBLY

4 3/4" x 2" AASHTO M 164 HIGH STRENGTH BOLTS &
NUTS WITH TWO CUT STEEL WASHERS FOR EACH BOLT.
INSTALLED IN ACCORDANCE WITH SUBSECTION
B07.7(K) OF THE STANDARD SPECIFICATIONS.


DETAIL OF TERMINAL
ANCHOR POST (TYPE I)

NOTE: RAIL MEMBERS MAY BE BOLTED TO ANGLE AT TERMINAL ANCHOR AND THE TWO
ASSEMBLIES POSITIONED TO PROPER ALIGNMENT PRIOR TO PLACING CONCRETE
AROUND 8 W/ 17 POST IF CONTRACTOR SO DESIRES.


ARKANSAS STATE HIGHWAY COMMISSION		
GUARD RAIL DETAILS		
7-14-10	RAISED HEIGHT OF GUARD RAIL 1"	
6-26-97	REVISED LAP NOTE	
10-18-96	REVISED ASTM REF. TO AASHTO	
11-3-94	DIMENSION TERMINAL DETAIL	
11-11-92	ADDED NOTE FOR PAYMENT	11-11-92
10-1-92	DRAWN & ISSUED	10-1-92
DATE	REVISION	DATE FILM
STANDARD DRAWING GRT-I		




SHELF



PLATFORM




SINGLE INSTALLATION




BRACKET

GENERAL NOTES


1. MAILBOX POSTS MAY BE WOOD OR METAL. WOOD POSTS SHALL BE PRESSURE TREATED FOR GROUND CONTACT IN ACCORDANCE WITH SECTION 637.02 OF THE STANDARD SPECIFICATIONS.
2. ANTI-TWIST PLATES SHALL BE USED ONLY ON METAL POSTS.
3. MAILBOX SHELF, BRACKET & PLATFORM SHALL BE GALVANIZED OR PAINTED STEEL, HOWEVER TREATED WOOD MAY BE USED WITH WOODEN POSTS. THE WOODEN SHELF, BRACKET & PLATFORM SHALL BE A MINIMUM OF 3/4" THICK AND SHALL BE ASSEMBLED WITH BOLTS OF THE APPROPRIATE LENGTH WITH SIX 8 X 3/4" FLATHEAD WOOD SCREWS USED TO ATTACH THE MAILBOX TO THE PLATFORM.
4. THE MAILBOX SHELF AND PLATFORM THAT IS SHOWN IS FOR STANDARD SIZE MAILBOXES. THE SHELF AND PLATFORM SIZE SHALL BE MODIFIED TO FIT MAILBOXES OF A DIFFERENT SIZE.
5. METAL PIPE FOR MAILBOX SUPPORT SHALL BE 2" OUTSIDE DIAMETER STEEL WITH A WALL THICKNESS OF 0.145" AND A WEIGHT OF 2.72 LBS PER FT. OUTSIDE DIAMETER AND WEIGHT SHALL HAVE A TOLERANCE OF +/- 5% ACCORDING TO AASHTO M 181.
6. MAILBOX SUPPORT SYSTEM DIFFERING FROM THOSE SHOWN MAY BE USED, PROVIDED THEY ARE ON THE AHTD QUALIFIED PRODUCTS LIST FOR MAILBOX SUPPORTS.




DOUBLE INSTALLATION




ANTI-TWIST PLATE



CLAMP



SPACER



SPACING FOR MULTIPLE POST INSTALLATION

11-18-04		REVISED NOTES
10-9-03		REVISED NOTE 6
8-22-02		REVISED NOTE 6
10-18-96		CORRECTED AASHTO
10-1-92		CORRECTED SPELLING
9-26-91		NEW PHONE NUMBER
8-15-91		ADDED NOTE
11-30-89		ADJUSTED HEIGHT & ADDED NOTE
2-16-89		DELETED SLOTS FROM SHELF & PLTF
11-17-88	10-1-92	ADJUSTED DIMENSIONS OF STEEL POSTS
7-15-88	120-7-15-88	ISSUED
DATE	FILMED	REVISION

ARKANSAS STATE HIGHWAY COMMISSION


MAILBOX DETAILS

STANDARD DRAWING MB-1


CONSTRUCTION SEQUENCE

1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. PLACE AND COMPACT THE HAUNCH AREA UP TO THE MIDDLE OF THE PIPE.
5. COMPLETE BACKFILL ACCORDING TO SPECIFICATIONS.

NOTE: HAUNCH AND STRUCTURAL BEDDING MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF CONCRETE PIPE.



1. MATERIAL IN THE LOWER SIDE, HAUNCH, AND OUTER STRUCTURAL BEDDING SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.



1. MATERIAL IN THE HAUNCH AND OUTER STRUCTURAL BEDDING SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.
2. FOR TRENCHES WITH WALLS OF NATURAL SOIL, THE DENSITY OF THE SOIL IN THE LOWER SIDE ZONE SHALL BE AS FIRM AS THE 95% DENSITY REQUIRED FOR THE HAUNCH. IF THE EXISTING SOIL DOES NOT MEET THIS CRITERIA, IT SHALL BE REMOVED AND RECOMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OF MATERIAL USED.

REINFORCED CONCRETE ARCH PIPE DIMENSIONS

EQUIV. DIA.	• SPAN		• RISE	
	AASHTO M 206	AHD NOMINAL	AASHTO M 206	AHD NOMINAL
INCHES	INCHES			
15	18	18	11	11
18	22	22	13 1/2	14
21	26	26	15 1/2	16
24	28 1/2	29	18	18
30	36 1/2	36	22 1/2	23
36	43 3/4	44	26 3/8	27
42	51 1/4	51	31 7/8	31
48	58 1/2	59	36	36
54	65	65	40	40
60	73	73	45	45
72	88	88	54	54
84	102	102	62	62
90	115	115	72	72
96	122	122	77 1/4	77
108	136	136	87 1/8	87
120	154	154	96 7/8	97
132	168 3/4	169	106 1/2	107

• THE MEASURED SPAN AND RISE SHALL NOT VARY MORE THAN ± 2 PER CENT FROM THE VALUES SPECIFIED BY AASHTO M 206.

GENERAL NOTES

1. ALL PIPE SHALL BE PROTECTED DURING CONSTRUCTION BY A COVER SUFFICIENT TO PREVENT DAMAGE FROM PASSAGE OF EQUIPMENT.
2. THE MINIMUM TRENCH WIDTH SHALL BE THE OUTSIDE DIAMETER OF THE PIPE PLUS 24 INCHES.
3. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PRACTICABLE FOR WORKING CONDITIONS.
4. MULTIPLE PIPE CULVERTS SHALL BE INSTALLED WITH A MINIMUM CLEARANCE OF 24 INCHES BETWEEN STRINGS OF PIPE.
5. REFER TO STD. DWG. FES-2 FOR MINIMUM CLEARANCE WHERE FLARED END SECTIONS ARE USED.
6. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
7. NOT MORE THAN ONE LIFTING HOLE MAY BE PROVIDED IN CONCRETE PIPE TO FACILITATE HANDLING. HOLE MAY BE CAST IN PLACE, CUT INTO THE FRESH CONCRETE AFTER FORMS ARE REMOVED, OR DRILLED. THE HOLE SHALL NOT BE MORE THAN TWO INCHES IN DIAMETER OR TWO INCHES SQUARE. CUTTING OR DISPLACEMENT OF REINFORCEMENT WILL NOT BE PERMITTED. SPALLED AREAS AROUND THE HOLE SHALL BE REPAIRED IN A WORKMANLIKE MANNER. LIFTING HOLE SHALL BE FILLED WITH MORTAR, CONCRETE, OR OTHER METHOD AS APPROVED BY THE ENGINEER.
8. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS 'STRUCTURAL BEDDING' ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS 'SELECTED PIPE BEDDING.'
9. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED ABOVE AS THE HAUNCH), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF 'SELECTED PIPE BACKFILL.'

INSTALLATION TYPE	* MATERIAL REQUIREMENTS FOR HAUNCH AND STRUCTURAL BEDDING
TYPE 1	AGGREGATE BASE COURSE (CLASS 5 OR CLASS 7)
TYPE 2	SELECTED MATERIALS (CLASS SM-1, SM-2, OR SM-3) OR TYPE 1 INSTALLATION MATERIAL
TYPE 3	AASHTO CLASSIFICATION A-1 THRU A-6 SOIL OR TYPE 1 OR 2 INSTALLATION MATERIAL

* MATERIALS SHALL NOT INCLUDE ORGANIC MATERIALS OR STONES LARGER THAN 3 INCHES.

MAXIMUM HEIGHT OF FILL OVER R.C. PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE		
	CLASS III	CLASS IV	CLASS V
	FEET		
TYPE 1	21	32	50
TYPE 2	17	27	41
TYPE 3	13	20	32

NOTE: IF FILL HEIGHT EXCEEDS 50 FEET, A SPECIAL DESIGN CONCRETE PIPE WILL BE REQUIRED USING TYPE 1 INSTALLATION.


- LEGEND -

- D_i = NORMAL INSIDE DIAMETER OF PIPE
- D_o = OUTSIDE DIAMETER OF PIPE
- H = FILL COVER HEIGHT OVER PIPE (FEET)
- MIN. = MINIMUM
- UNDISTURBED SOIL

ARKANSAS STATE HIGHWAY COMMISSION		
CONCRETE PIPE CULVERT FILL HEIGHTS & BEDDING		
STANDARD DRAWING PCC-1		
5-18-00	REVISED TYPE 3 BEDDING & ADDED NOTE	
3-30-00	REVISED INSTALLATIONS	
11-06-97	ISSUED	
DATE	REVISION	DATE FILMED

PIPE DIAMETER (INCHES)	MINIMUM COVER TOP OF PIPE TO TOP OF SUBGRADE (INCHES)	MAX. FILL HEIGHT ABOVE TOP OF PIPE (FEET)						
		METAL THICKNESS IN INCHES						
		0.064	0.079	0.109	0.138	0.168		
2 1/2 INCH BY 1/2 INCH CORRUGATION RIVETED, WELDED, OR HELICAL								
12	12	84	91					
18	12	67	73					
24	12	66	61					
30	12	42	46	59				
36*	12	34	36	47				
42*	12		30	39	41		70	50
48*	12		43	46	67	48	61	47
			37	45	58	46	61	47
3 INCH BY 1 INCH OR 5 INCH BY 1 INCH CORRUGATION** RIVETED, WELDED, HELICAL, OR BOLTED								
36	12	48	60	78	88	89	111	101
42	12	41	51	64	72	71	90	79
48	12	36	45	57	64	61	77	66
54	12	32	40	52	59	55	71	59
60*	12	29	36	49	53	51	64	54
66	12	26	33	47	53	49	58	51
72*	12	24	30	44	47	47	53	49
78	12		28	41	46	49	47	54
84*	12		26	38	45	45	46	51
90	12		24	35	43	44	45	
96*	12		22	33	40	42	44	
102	24			31	38	38	42	
108*	24			30	35	35	39	
114	24			28	34	34	37	
120*	24			27	32	32	35	

* MAX. FILL CAN BE INCREASED IN THESE DIAMETER PIPES BY USING THE NEXT LARGER CORRUGATION. REFER TO 'CORRUGATED METAL PIPE', REVISED 1970, PUBLISHED BY U.S. DEPARTMENT OF TRANSPORTATION, F.H.W.A., B.P.R.
 ** WHERE THE STANDARD 2 1/2 x 1/2 CORRUGATION AND GAUGE IS SPECIFIED FOR A GIVEN DIAMETER A 3 x 1 OR 5 x 1 CORRUGATION PIPE OF THE SAME DIAMETER MAY BE SUBSTITUTED, PROVIDING IT IS GAUGED FOR A FILL HEIGHT CONDITION EQUAL TO OR GREATER THAN THE MAXIMUM FILL HEIGHT CONDITION FOR THE SPECIFIED GAUGE AND CORRUGATION



TYPE 2 EMBANKMENT AND TRENCH INSTALLATIONS

1. STRUCTURAL BACKFILL, EMBANKMENT, AND OUTER STRUCTURAL BEDDING MATERIAL SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.

CORRUGATED ALUMINUM PIPE (ROUND) H-20 LOADING

PIPE DIAMETER (INCHES)	MINIMUM COVER TOP OF PIPE TO TOP OF SUBGRADE (INCHES)	MAX. FILL HEIGHT ABOVE TOP OF PIPE (FEET)				
		METAL THICKNESS IN INCHES				
		0.060	0.075	0.105	0.135	0.164
2 1/2 INCH BY 1/2 INCH CORRUGATION RIVETED OR HELICAL						
12	12	45	45			
18	12	30	30	52		
24	12	22	22	39	41	
30	12	18	18	31	32	34
36	12		15	26	27	28
42	12		26	43	43	44
48	12			40	41	43
54	12			35	37	38
60	12				33	34
66	12				30	31
72	12					29

EQUIVALENT METAL THICKNESSES AND GAUGES

METAL THICKNESS IN INCHES			GAUGE NUMBER
STEEL			
ZINC COATED	UNCOATED	ALUMINUM	
0.064	0.0598	0.060	16
0.079	0.0747	0.075	14
0.109	0.1046	0.105	12
0.138	0.1345	0.135	10
0.168	0.1644	0.164	8
0.188	0.1838		7
0.218	0.2145		5
0.249	0.2451		3
0.280	0.2758		1

CORRUGATED METAL PIPE ARCHES (H - 20 LOADING)

EQUIV. DIA. (INCHES)	PIPE DIMENSION SPAN X RISE (INCHES)	MINIMUM CORNER RADIUS (INCHES)	MIN. COVER TOP OF PIPE TO TOP OF SUBGRADE FOR 2 TONS PER SQ. FT. (INCHES)	STEEL			ALUMINUM		
				MINIMUM THICKNESS REQUIRED INCHES	MAX. FILL HEIGHTS ABOVE TOP OF PIPE (IN FT.) FOR THE FOLLOWING CORNER BEARING PRESSURE IN TONS PER SQ. FT.		MINIMUM THICKNESS REQUIRED INCHES	MAX. FILL HEIGHTS ABOVE TOP OF PIPE (IN FT.) FOR THE FOLLOWING CORNER BEARING PRESSURE IN TONS PER SQ. FT.	
					2 TONS	3 TONS		2 TONS	3 TONS
2 1/2 INCH BY 1/2 INCH CORRUGATION RIVETED, WELDED, OR HELICAL									
15	17x13	3	12	0.064	13	15+	0.060	15	
18	21x15	3	12	0.064	12	15+	0.060	14	
21	24x18	3	12	0.064	10	15+	0.060	12	15+
24	28x20	3	12	0.064	10	15	0.060	10	15+
30	35x24	3	12	0.079	9	14	0.075	9	14
36	42x29	3 1/2	12	0.079	9	13	0.075	9	13
42	49x33	4	12	0.079	8	12	0.105	8	12
48	57x38	5	12	0.109	8	12	0.135	8	12
54	64x43	6	12	0.109	8	12	0.135	8	12
60	71x47	7	12	0.138	8	12	0.164	8	12
66	77x52	8	12	0.168	8	12	0.164	8	12
72	83x57	9	12	0.168	9	13		8	12
3 INCH BY 1 INCH OR 5 INCH BY 1 INCH CORRUGATION** RIVETED, WELDED, OR HELICAL									
36	40x31	5	12	0.079	15	15+			
42	46x36	6	12	0.079	15	15+			
48	53x41	7	12	0.079	15	15+			
54	60x46	8	12	0.079	15	15+			
60	66x51	9	12	0.079	15	15+			
66	73x55	12	12	0.079	15	15+			
72	81x59	14	18	0.079	15	15+			
78	87x63	14	18	0.079	14	15+			
84	95x67	16	18	0.109	13	15+			
90	103x71	16	24	0.109	12	15+			
96	112x75	18	24	0.109	11	15+			
102	117x79	18	24	0.109	10	15			
108	128x83	18	24	0.138	9	14			

1 WHERE BEARING PRESSURE EXCEEDING 2 TONS PER SQUARE FOOT IS REQUIRED FOR GIVEN FILL HEIGHTS, THE FOUNDATION MATERIAL SHALL BE INVESTIGATED TO DETERMINE THE BEARING CAPACITY.
 ** WHERE THE STANDARD 2 1/2 x 1/2 CORRUGATION AND GAUGE IS SPECIFIED FOR A GIVEN DIAMETER, A 3 x 1 OR 5 x 1 CORRUGATION PIPE OF THE SAME DIAMETER MAY BE SUBSTITUTED, PROVIDING IT IS GAUGED FOR A FILL HEIGHT CONDITION EQUAL TO OR GREATER THAN THE MAXIMUM FILL HEIGHT CONDITION FOR THE SPECIFIED GAUGE AND CORRUGATION.

CONSTRUCTION SEQUENCE

1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. COMPLETE STRUCTURAL BACKFILL OPERATION BY WORKING FROM SIDE TO SIDE OF THE PIPE, THE SIDE TO SIDE STRUCTURAL BACKFILL DIFFERENTIAL SHALL NOT EXCEED 24 INCHES OR 1/3 THE SIZE OF THE PIPE, WHICHEVER IS LESS.

NOTE: STRUCTURAL BACKFILL AND STRUCTURAL BEDDING MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF METAL PIPE.

GENERAL NOTES

1. ALL PIPE SHALL BE PROTECTED DURING CONSTRUCTION BY A COVER SUFFICIENT TO PREVENT DAMAGE FROM PASSAGE OF EQUIPMENT.
2. THE MINIMUM TRENCH WIDTH SHALL BE THE OUTSIDE DIAMETER OF THE PIPE PLUS 24 INCHES.
3. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PRACTICABLE FOR WORKING CONDITIONS.
4. MULTIPLE PIPE CULVERTS SHALL BE INSTALLED WITH A MINIMUM CLEARANCE OF 24 INCHES BETWEEN STRINGS OF PIPE.
5. REFER TO STD. DWG. FES-2 FOR MINIMUM CLEARANCE WHERE FLARED END SECTIONS ARE USED.
6. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
7. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS 'STRUCTURAL BEDDING' ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS 'SELECTED PIPE BEDDING.'
8. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED ABOVE AS STRUCTURAL BACKFILL), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF 'SELECTED PIPE BACKFILL.'



- LEGEND -

- D_o = OUTSIDE DIAMETER OF PIPE
- MAX. = MAXIMUM
- MIN. = MINIMUM
- [Hatched Pattern] = STRUCTURAL BACKFILL MATERIAL
- [Diagonal Lines] = UNDISTURBED SOIL
- ELONG. = ELONGATED
- EQUIV. DIA. = EQUIVALENT DIAMETER
- H = FILL COVER HEIGHT OVER PIPE (FEET)


ARKANSAS STATE HIGHWAY COMMISSION		
METAL PIPE CULVERT FILL HEIGHTS & BEDDING		
STANDARD DRAWING PCM-1		
3-30-00	REVISED INSTALLATIONS	
11-06-97	ISSUED	
DATE	REVISION	DATE FILMED

NOTES:


1. ALL LINES SHALL HAVE A WIDTH OF 4 INCHES.
2. THE THICKNESS AND RATE OF PAINT APPLICATION SHALL BE AS SPECIFIED IN SECTION 718 OF THE STANDARD SPECIFICATIONS.
3. THIS DRAWING SHALL BE USED IN CONJUNCTION WITH THE LATEST REVISED ADDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
4. RAISED PAVEMENT MARKERS SHALL BE CENTERED BETWEEN SKIP LINES ON 40 FEET SPACING UNLESS OTHERWISE SHOWN ON THE PLANS.




BROKEN LINE STRIPING




SOLID LINE STRIPING ON CONCRETE PAVEMENT



SOLID LINE STRIPING ON ASPHALT PAVEMENT



ASPHALT PAVEMENT




CONCRETE PAVEMENT

STRIPING AT ADJACENT NO PASSING LANES

GENERAL NOTES:
THIS DRAWING SHOULD BE CONSIDERED AS TYPICAL ONLY AND THE FINAL LOCATION OF THE STRIPING AND RAISED PAVEMENT MARKERS SHALL BE DETERMINED BY THE ENGINEER.


THIS DRAWING SHOULD BE USED IN CONJUNCTION WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", LATEST REVISION.

NOTE:
DIMENSIONS SHOWN FOR RAISED PAVEMENT MARKERS ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR MARKERS WITH THE APPROVAL OF THE ENGINEER. REQUESTING APPROVAL FOR SIMILAR MARKERS MAY BE MADE BY REFERRING TO THE AHTD QUALIFIED PRODUCTS LIST.




CROSSWALK AND STOPBAR DETAILS

2" FOR ASPHALT OR CONCRETE PAVEMENT
6" FOR BITUMINOUS SURFACE TREATMENT



PAVEMENT EDGE LINE MARKING



NOTE:
THE RED LENS OF THE TYPE II R.P.M. SHALL FACE THE INCORRECT TRAFFIC MOVEMENT.

DETAIL OF STANDARD RAISED PAVEMENT MARKERS


DATE	REVISION	FILMED
11-17-10	REVISED GENERAL NOTES & REMOVED FLOWABLE PVMT MRKRS	
11-18-04	REVISED NOTE 2 & GENERAL NOTES	
8-22-02	ADDED CROSSWALK & STOPBAR DTLS.	
7-02-98	ADDED DETAILS OF STD. RAISED PAV'T. MARKERS	
4-26-96	REV. NOTES 3&4; ADDED R.P.M.	
9-30-80	DRAWN	1-9-30-80

ARKANSAS STATE HIGHWAY COMMISSION


PAVEMENT MARKING DETAILS

STANDARD DRAWING PM-1


NOTE:
 1. GRANULAR BACKFILL TO BE SUBSIDIARY TO PIPE UNDERDRAIN.
 2. UNLESS OTHERWISE SPECIFIED ON THE PLANS, THE UNDERDRAIN COVER SHALL BE THOROUGHLY COMPACTED EARTH AND SHALL BE SUBSIDIARY TO PIPE UNDERDRAIN.
 3. GRANULAR MATERIAL SHALL BE WRAPPED WITH GEOTEXTILE FABRIC, LAP FABRIC 12" OR THE WIDTH OF THE TRENCH AT THE TOP.





PLAN VIEW




DETAIL OF HOLE FOR 4" PIPE




DETAIL OF RODENT SCREEN



SIDE VIEW




FRONT VIEW



DETAILS OF PIPE UNDERDRAIN

FERNCO 1056-44 (4" CI/PLASTIC) OR FERNCO 1051-44 (4" AC/DIOR 4" CI/PLASTIC) COUPLING OR EQUAL WITH 2 CLAMPS (TYPICAL)



*NOTE:
 LATERALS SHALL BE INSTALLED AT ALL SAGS AND AT 250' INTERVALS ON GRADES. THE 250' DISTANCE MAY BE EXCEEDED ONLY WHERE NECESSARY FOR AN ACCEPTABLE OUTLET.

DETAIL OF PIPE UNDERDRAIN LATERALS WHEN PLACED ALONG PAVEMENT EDGE

NOTE: PVC PIPE FOR LATERALS SHALL MEET THE REQUIREMENTS OF ASTM D 1785 (LATEST REVISION) FOR SCHEDULE 40 PIPE.

4-10-03	REVISED NOTE 3	
1-12-00	REVISED DETAIL OF UNDERDRAIN LATERALS	
11-18-98	REVISED NOTE	
10-18-96	REVISED MIN. DEPTH & GEOTEXTILE FABRIC	
4-26-96	ADDED LATERAL NOTE; 5 1/2" TO 5"	
11-22-95	REVISED LATERALS	
7-20-95	REVISED LATERALS & ADDED NOTE	
11-3-94	REVISED FOR DUAL LATERALS	11-3-94
10-1-92	SUBSTITUTED GEOTEXTILE	10-1-92
8-15-91	ADDED POLYETHYLENE PIPE	8-15-91
11-8-90	DELETED ALTERNATE NOTE	11-8-90
1-25-90	ADDED 4" SNAP ADAPTER	1-25-90
11-30-89	DEL. (SUBGRADE); ADDED (WHERE REQUIRED)	11-30-89
7-15-88	ISSUED P.L.M.	647-7-15-88
DATE	REVISION	DATE FILMED

ARKANSAS STATE HIGHWAY COMMISSION

DETAILS OF PIPE UNDERDRAIN

STANDARD DRAWING PU-1

SUPERELEVATION TABLE FOR TWO - WAY TRAFFIC

DEGREE OF CURVE	30 MPH		40 MPH		50 MPH		55 MPH		60 MPH		70 MPH	
	Ls (FT)		Ls (FT)		Ls (FT)		Ls (FT)		Ls (FT)		Ls (FT)	
	MINIMUM	DESIRABLE	MINIMUM	DESIRABLE	MINIMUM	DESIRABLE	MINIMUM	DESIRABLE	MINIMUM	DESIRABLE	MINIMUM	DESIRABLE
0° 15'	N.C.		N.C.		N.C.		N.C.		N.C.		N.C.	
0° 30'	N.C.		N.C.		N.C.		N.C.		N.C.		N.C.	
0° 45'	N.C.		N.C.		N.C.		N.C.		N.C.		N.C.	
1° 00'	N.C.		N.C.		N.C.		N.C.		N.C.		N.C.	
1° 15'	N.C.		N.C.		N.C.		N.C.		N.C.		N.C.	
1° 30'	N.C.		N.C.		N.C.		N.C.		N.C.		N.C.	
1° 45'	N.C.		N.C.		N.C.		N.C.		N.C.		N.C.	
2° 00'	R.C.		0.025		0.031		0.043		0.049		0.054	
2° 15'	R.C.		0.028		0.040		0.048		0.055		0.062	
2° 30'	R.C.		0.031		0.045		0.053		0.061		0.070	
2° 45'	R.C.		0.034		0.049		0.058		0.067		0.075	
3° 00'	R.C.		0.037		0.053		0.063		0.072		0.085	
3° 15'	R.C.		0.040		0.057		0.067		0.077		0.091	
3° 30'	R.C.		0.043		0.061		0.072		0.082		0.098	
3° 45'	R.C.		0.046		0.065		0.076		0.086		0.100	
4° 00'	R.C.		0.049		0.069		0.080		0.090		0.100	
4° 15'	R.C.		0.051		0.072		0.083		0.093		0.100	
4° 30'	R.C.		0.056		0.078		0.087		0.096		0.100	
4° 45'	R.C.		0.061		0.083		0.091		0.098		0.100	
5° 00'	R.C.		0.066		0.088		0.094		0.098		0.100	
5° 15'	R.C.		0.070		0.092		0.096		0.098		0.100	
5° 30'	R.C.		0.074		0.095		0.096		0.098		0.100	
5° 45'	R.C.		0.078		0.098		0.099		0.099		0.100	
6° 00'	R.C.		0.081		0.099		0.099		0.099		0.100	
6° 15'	R.C.		0.084		0.087		0.087		0.087		0.087	
6° 30'	R.C.		0.087		0.089		0.089		0.089		0.089	
6° 45'	R.C.		0.091		0.094		0.094		0.094		0.094	
7° 00'	R.C.		0.094		0.094		0.094		0.094		0.094	
7° 15'	R.C.		0.097		0.097		0.097		0.097		0.097	
7° 30'	R.C.		0.099		0.099		0.099		0.099		0.099	
7° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
8° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
8° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
8° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
8° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
9° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
9° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
9° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
9° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
10° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
10° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
10° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
10° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
11° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
11° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
11° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
11° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
12° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
12° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
12° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
12° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
13° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
13° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
13° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
13° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
14° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
14° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
14° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
14° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
15° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
15° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
15° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
15° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
16° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
16° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
16° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
16° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
17° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
17° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
17° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
17° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
18° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
18° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
18° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
18° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
19° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
19° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
19° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
19° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
20° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
20° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
20° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
20° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
21° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
21° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
21° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
21° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
22° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
22° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
22° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
22° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
23° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	
23° 15'	R.C.		0.100		0.100		0.100		0.100		0.100	
23° 30'	R.C.		0.100		0.100		0.100		0.100		0.100	
23° 45'	R.C.		0.100		0.100		0.100		0.100		0.100	
24° 00'	R.C.		0.100		0.100		0.100		0.100		0.100	

ABBREVIATIONS


- NC - NORMAL CROWN
- RC - REVERSE CROWN, SUPERELEVATION AT NORMAL CROWN SLOPE
- e - RATE OF SUPERELEVATION (FT. PER FT.)
- Ls - LENGTH OF SUPERELEVATION TRANSITION (FT.)
- L - DISTANCE FROM BEGINNING OF SUPERELEVATION TRANSITION TO ANY POINT (FT.)
- d - WIDTH OF PAVEMENT (FT.) OR WIDTH OF SUBGRADE (FT.)
- C - NORMAL CROWN (FT.)

GENERAL NOTES

- ON PAVEMENT WITH TWO-WAY TRAFFIC, THE SUPERELEVATION SHALL BE REVOLVED ON THE INSIDE PAVEMENT EDGE UNLESS OTHERWISE NOTED ON THE PLANS.
- SUPERELEVATION VALUES SHOWN ON THE CROSS SECTIONS ARE VALUES (+) OR (-) TO BE ADDED TO OR SUBTRACTED FROM THE POINT OF CONTROL.
- LENGTHS FOR L MAY BE ROUNDED IN MULTIPLES OF 25 FT. OR 50 FT. TO PERMIT SIMPLER CALCULATIONS.
- PAVEMENTS WIDER THAN 2 LANES SHALL HAVE ADDITIONAL TRANSITION LENGTHS AS FOLLOWS:

- 3 LANE UNDIVIDED - - - - +20%
- 4 LANE UNDIVIDED - - - - +50%
- 5 LANE UNDIVIDED - - - - +80%
- 6 LANE UNDIVIDED - - - - +100%


NOTE: MAINTAIN NORMAL CROWN ON INSIDE UNTIL SUPERELEVATION EXCEEDS 2C.
RATE OF SUPERELEVATION SHALL BE COMPUTED ON STRAIGHT LINE METHOD USING APPLICABLE Ls.



STANDARD METHOD WHEN SUPERELEVATION REVOLVES AROUND INNER SUBGRADE POINT OR INNER PAVEMENT EDGE

NOTE: MAINTAIN NORMAL CROWN ON INSIDE UNTIL SUPERELEVATION EXCEEDS 2C.

SUPERELEVATION FORMULA = $\frac{Lde}{Ls}$
















































STANDARD METHOD WHEN SUPERELEVATION REVOLVES AROUND CENTER LINE


ARKANSAS STATE HIGHWAY COMMISSION

TABLES AND METHOD OF SUPERELEVATION FOR TWO-WAY TRAFFIC


STANDARD DRAWING SE-2

10-18-96	ADDED FORMULA	10-18-96
01-09-87	ISSUED	532-1-9-87
DATE	REVISION	DATE FILMED


							ADVANCE DISTANCES (XXXX)																																																
<p>RI-1</p>  <p>STANDARD 30"X30" EXPRESSWAY 36"X36" SPECIAL 48"X48"</p>	<p>RI-2</p>  <p>STD. 36"X36"X36" EXPWY. 48"X48"X48" FWY. 60"X60"X60"</p>	<p>R2-1</p>  <p>STD. 24"X30" EXPWY. 36"X48" FWY. 48"X60"</p>	<p>R2-5A</p>  <p>STD. 24"X30" EXPWY. 36"X48" FWY. 48"X60"</p>	<p>R2-5C</p>  <p>STD. 24"X30" EXPWY. 36"X48" FWY. 48"X60"</p>	<p>R4-1</p>  <p>STD. 24"X30" EXPWY. 36"X48" FWY. 48"X60"</p>	<p>R4-2</p>  <p>STD. 24"X30" EXPWY. 36"X48" FWY. 48"X60"</p>	<p>500 FT 1/2 MILE 1000 FT 3/4 MILE 1500 FT 1 MILE AHEAD</p>																																																
<p>R5-1</p>  <p>STD. 30"X30" EXPWY. 36"X36" SPECIAL 48"X48"</p>	<p>R11-2</p>  <p>48"X30"</p>	<p>R11-3A</p>  <p>60"X30"</p>	<p>R11-4</p>  <p>60"X30"</p>	<p>RSP-1</p>  <p>48"X30"</p>	<p>WI-1</p>  <p>STD. 36"X36" FWY. 48"X48"</p>	<p>WI-2</p>  <p>STD. 36"X36" FWY. 48"X48"</p>	<p>GENERAL NOTES:</p> <ol style="list-style-type: none"> ALL TRAFFIC CONTROL DEVICES USED ON ROAD CONSTRUCTION SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION, AND TO THE STANDARD HIGHWAY SIGNS, LATEST EDITION, OR AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION. TRAFFIC CONTROL DEVICES SHALL BE SET UP JUST BEFORE THE START OF CONSTRUCTION OPERATIONS AND SHALL BE PROPERLY MAINTAINED DURING THE TIME SUCH CONDITIONS EXIST. THEY SHALL REMAIN IN PLACE ONLY AS LONG AS NEEDED AND REMOVED THEREAFTER. EXISTING SIGNS AND CONSTRUCTION SIGNS SHALL BE KEPT IN PROPER POSITION, AND BE CLEAN AND LEGIBLE AT ALL TIMES. SIGNS THAT DO NOT APPLY TO EXISTING CONDITIONS SHALL BE REMOVED. SIGNS THAT ARE DAMAGED, DEFAUCED, OR THAT ACCUMULATE DIRT DURING CONSTRUCTION SHALL BE CLEANED, REPAIRED, OR REPLACED. SIGNS ARE USUALLY MOUNTED ON A SINGLE POST, ALTHOUGH THOSE WIDER THAN 36" OR LARGER THAN 10 SQ. FT. SHALL BE MOUNTED ON TWO POSTS OR ABOVE A TYPE III BARRICADE. SIGN POSTS DIRECT BURIED IN SOIL SHALL BE 2 LB. MINIMUM CHANNEL POST OR 4"x4" WOOD POSTS. CHANNEL POSTS SHALL BE PAINTED GREEN. WOOD POSTS SHALL BE PAINTED WHITE. ALL POSTS SHALL BE NEATLY CONSTRUCTED, AND SHALL BE REPLUMBED, CLEANED, OR REPAIRED AS NEEDED FOR THE DURATION OF THE JOB. THERE SHALL NOT BE MORE THAN 2 POSTS IN A 7' PATH FOR WOOD OR CHANNEL POSTS. ANY CHANNEL POST SPLICE SHALL BE IN ACCORDANCE WITH STANDARD DRAWING TC-3. POST MOUNTED SIGNS IN RURAL AREAS SHALL BE CONSTRUCTED WITH THE NEAR EDGE OF THE SIGN FROM 6 TO 12 FEET FROM THE PAVEMENT EDGE. SIGNS IN URBAN AREAS AND BARRICADE MOUNTED SIGNS SHALL BE MOUNTED A MINIMUM OF 2 FEET FROM THE PAVEMENT EDGE. ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN URBAN AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE. ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN RURAL AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE, EXCEPT A MINIMUM OF 6' SHALL BE USED WHEN MOUNTING AN ADVISORY SIGN BELOW A WARNING SIGN. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR INTERMEDIATE TERM STATIONARY WORK CONDITIONS. THE SIGNS MINIMUM MOUNTING HEIGHT SHALL BE 5'. RETROREFLECTIVE DEVICES SHALL BE USED. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR SHORT-TERM, SHORT DURATION, AND MOBILE CONDITIONS. THEY SHALL BE NO LESS THAN ONE (1) FOOT ABOVE THE TRAVELED WAY. LONG-TERM STATIONARY SIGNS SHALL BE DIRECT BURIED IN SOIL, UNLESS CONDITIONS NECESSITATE THE USE OF PORTABLE SIGNS, OR AS APPROVED BY THE ENGINEER. CONCRETE PADS, CONCRETE OR ROCK BALLAST, OR OTHER SOLID MATERIALS SHALL NOT BE UTILIZED WITH PORTABLE SIGN SUPPORTS. FLAGGERS SHALL USE REFLECTORIZED STOP-SLOW PADDLES. FLAGS MAY BE USED ONLY FOR EMERGENCY SITUATIONS. MOST OF THE SIGNS SHOWN ARE ORIENTED TO THE RIGHT. HOWEVER, THIS DOES NOT PRECLUDE THE USE OF MIRROR IMAGES OF THESE SIGNS WHERE THE REVERSE ORIENTATION MIGHT BETTER CONVEY TO MOTORISTS THE PROPER DIRECTION OF MOVEMENT. R55-1 SIGNS SHALL BE PLACED AT LEAST 1500' BUT NOT MORE THAN 1 MILE IN ADVANCE OF THE WORK ZONE. IF A SPEED LIMIT REDUCTION IS IN EFFECT, THE SIGN SHALL BE PLACED A MINIMUM OF 500' IN ADVANCE OF THE "REDUCED SPEED AHEAD" SIGN. <p>* NOTE: SUPPORTS FOR SIGNS, BARRICADES, AND VERTICAL PANELS THAT ARE DIFFERENT FROM THE REQUIREMENTS SHOWN IN NOTES 4 & 5, BUT MEET THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH), WILL BE ACCEPTED. COMPLIANCE WITH THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) IS REQUIRED FOR ALL PROJECTS.</p> <table border="1"> <tr> <td>11-17-10</td> <td>DELETED W8-9a & ADDED W8-9</td> <td></td> </tr> <tr> <td>10-15-09</td> <td>ADDED REFERENCE TO MASH & ADDED SIGN W24-1</td> <td></td> </tr> <tr> <td>4-17-08</td> <td>REVISED SIGN DESIGNATIONS</td> <td></td> </tr> <tr> <td>11-18-04</td> <td>REVISED NOTES</td> <td></td> </tr> <tr> <td>10-9-03</td> <td>REVISED NOTE 1</td> <td></td> </tr> <tr> <td>11-16-01</td> <td>REVISED NOTE 7</td> <td></td> </tr> <tr> <td>9-28-00</td> <td>REVISED NOTE</td> <td></td> </tr> <tr> <td>11-18-98</td> <td>ADDED NOTE</td> <td></td> </tr> <tr> <td>6-26-97</td> <td>REVISED NOTE 5</td> <td></td> </tr> <tr> <td>4-03-97</td> <td>REVISED NOTE 5</td> <td></td> </tr> <tr> <td>10-18-96</td> <td>ADDED CONTROLLED ACCESS HWY. SIGN & TO NOTE 7</td> <td></td> </tr> <tr> <td>10-12-95</td> <td>ADDED R55-1</td> <td></td> </tr> <tr> <td>6-8-95</td> <td>REVISED TO CORRECT SIGN ILLUSTRATIONS</td> <td>6-8-95</td> </tr> <tr> <td>2-2-95</td> <td>REVISED PER PART VI, MUTCD SEPT. 3, 1993</td> <td></td> </tr> <tr> <td>8-15-91</td> <td>DRAWN AND PLACED IN USE</td> <td></td> </tr> <tr> <td>DATE</td> <td>REVISION</td> <td>FILMED</td> </tr> </table>	11-17-10	DELETED W8-9a & ADDED W8-9		10-15-09	ADDED REFERENCE TO MASH & ADDED SIGN W24-1		4-17-08	REVISED SIGN DESIGNATIONS		11-18-04	REVISED NOTES		10-9-03	REVISED NOTE 1		11-16-01	REVISED NOTE 7		9-28-00	REVISED NOTE		11-18-98	ADDED NOTE		6-26-97	REVISED NOTE 5		4-03-97	REVISED NOTE 5		10-18-96	ADDED CONTROLLED ACCESS HWY. SIGN & TO NOTE 7		10-12-95	ADDED R55-1		6-8-95	REVISED TO CORRECT SIGN ILLUSTRATIONS	6-8-95	2-2-95	REVISED PER PART VI, MUTCD SEPT. 3, 1993		8-15-91	DRAWN AND PLACED IN USE		DATE	REVISION	FILMED
11-17-10	DELETED W8-9a & ADDED W8-9																																																						
10-15-09	ADDED REFERENCE TO MASH & ADDED SIGN W24-1																																																						
4-17-08	REVISED SIGN DESIGNATIONS																																																						
11-18-04	REVISED NOTES																																																						
10-9-03	REVISED NOTE 1																																																						
11-16-01	REVISED NOTE 7																																																						
9-28-00	REVISED NOTE																																																						
11-18-98	ADDED NOTE																																																						
6-26-97	REVISED NOTE 5																																																						
4-03-97	REVISED NOTE 5																																																						
10-18-96	ADDED CONTROLLED ACCESS HWY. SIGN & TO NOTE 7																																																						
10-12-95	ADDED R55-1																																																						
6-8-95	REVISED TO CORRECT SIGN ILLUSTRATIONS	6-8-95																																																					
2-2-95	REVISED PER PART VI, MUTCD SEPT. 3, 1993																																																						
8-15-91	DRAWN AND PLACED IN USE																																																						
DATE	REVISION	FILMED																																																					
<p>WI-3</p>  <p>STD. 48"X48"</p>	<p>WI-4</p>  <p>STD. 48"X48"</p>	<p>WI-6</p>  <p>STD. 48"X24" SPECIAL 60"X30"</p>	<p>WI-8</p>  <p>STD. 18"X24" SPECIAL 24"X30" EXPWY. 30"X36" FWY. 36"X48"</p>	<p>W3-1</p>  <p>STD. 36"X36" SPECIAL 48"X48"</p>	<p>W3-2</p>  <p>STD. 36"X36" SPECIAL 48"X48"</p>	<p>W4-2</p>  <p>STD. 36"X36" FWY. 48"X48"</p>																																																	
<p>W5-1</p>  <p>STD. 36"X36" SPECIAL 48"X48"</p>	<p>W6-3</p>  <p>EXPWY. 36"X36" SPECIAL 48"X48"</p>	<p>W8-7</p>  <p>EXPWY. 36"X36" FWY. 48"X48"</p>	<p>W9-2</p>  <p>STD. 36"X36" FWY. 48"X48"</p>	<p>W13-1</p>  <p>STD. 24"X24"</p>	<p>W20-1</p>  <p>STD. 48"X48"</p>	<p>W20-2</p>  <p>STD. 48"X48"</p>	<p>W20-3</p>  <p>STD. 48"X48"</p>																																																
<p>W20-4</p>  <p>STD. 48"X48"</p>	<p>W20-5</p>  <p>STD. 48"X48"</p>	<p>W20-7a</p>  <p>STD. 36"X36" FWY. 48"X48"</p>	<p>W21-2</p>  <p>STD. 30"X30" SPECIAL 36"X36"</p>	<p>W21-5</p>  <p>STD. 30"X30" SPECIAL 36"X36"</p>	<p>W24-1</p>  <p>STD. 36"X36"</p>	<p>WI-4b</p>  <p>STD. 48"X48"</p>	<p>R56-1</p>  <p>STD. 18"X18"</p>																																																
<p>W8-11</p>  <p>STD. 36"X36" FWY. 48"X48"</p>	<p>W8-9</p>  <p>STD. 36"X36" FWY. 48"X48"</p>	<p>G20-1</p>  <p>60"X24"</p>	<p>G20-2</p>  <p>48"X24"</p>	<p>OM-3L OM-3R</p>  <p>12"X36"</p>	<p>M4-9</p>  <p>STD. 30"X24" SPECIAL 48"X36" SPECIAL 60"X48"</p>	<p>M4-10</p>  <p>48"X18"</p>	<p>R55-1</p>  <p>36"X60"</p> <p>WHEN WORKERS ARE PRESENT **</p> <p>* USE 6" C LETTERS ** USE 4" D LETTERS</p>																																																




(A) Typical application of traffic control devices on a 2-lane highway where the entire roadway is closed and a bypass detour is provided.



(B) Typical application - 4-lane divided roadway where one roadway is closed.




(C) Typical application - 4-lane undivided roadway where half of the roadway is closed.




Taper formulae:
 $L = S \times W$ for speeds of 45mph or more.
 $L = \frac{WS^2}{60}$ for speeds of 40mph or less.
 Where:
 L = Minimum length of taper.
 S = Numerical value of posted speed limit prior to work or 85th percentile speed.
 W = Width of offset.


GENERAL NOTES:
 1. Advisory speed posted on W1-3 or W1-4 curve warning signs to be determined at site. Use W1-4 when speed is greater than 30mph and W1-3 when 30mph or less.
 2. When the existing speed limit is 45mph and the plans require a speed limit of 55mph, the R2-1(45) shall be omitted and the R2-5A shall be installed at that location. Additional R2-145mph speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(45) shall be installed to match original speed limit.
 3. When the existing speed limit is 65mph and the plans require a speed limit of 55mph, the R2-1(45) shall be omitted. Additional R2-155mph speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(45) shall be installed to match original speed limit.
 4. The maximum spacing between channelizing devices in a taper should be approximately equal in feet to the speed limit. Beyond the taper, maximum spacing shall be two times the speed limit, or as directed by the Engineer.
 5. Warning lights and/or flags may be mounted to signs or channelizing devices at night as needed.
 6. Pavement markings no longer applicable which might create confusion in the minds of vehicle operators shall be removed or obliterated as soon as practicable.
 7. Trailer mounted devices such as arrow panels and portable changeable message signs shall be delineated by affixing conspicuity material in a continuous line on the face of the trailer. When placed on or adjacent to the shoulder and not behind a positive barrier, these devices shall be delineated by placing five (5) traffic drums, equally spaced along the traffic side of the device.



(D) Typical application - roadway closed beyond detour point.




(E) Typical application of traffic control devices on 2-lane highway where one lane is closed and flagging is provided.




(F) Typical application - 4-lane undivided roadway with inside lane closed.

DATE	REVISION	FILMED
3-11-10	ADDED (AFAD)	
11-20-08	REVISED SIGN DESIGNATIONS	
8-18-04	ADDED GENERAL NOTE	
10-8-96	ADDED R55-1	
4-26-96	CORRECTED (a) BEHIND G20-2	
6-8-95	CORRECTED SIGN IDENT. ON W1-4A	6-8-95
2-2-95	REVISED PER PART VI, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	

ARKANSAS STATE HIGHWAY COMMISSION
 STANDARD TRAFFIC CONTROLS
 FOR HIGHWAY CONSTRUCTION
 STANDARD DRAWING TC-2



(A) Typical application - daytime maintenance operations of short duration on a 4-lane divided roadway where half of the roadway is closed.




(B) Typical application - 3-lane oneway roadway where center lane is closed.


- KEY:
- Arrow Panel (if Required)
 - Channelizing Device
 - Traffic drum

GENERAL NOTES:

1. A speed limit reduction may be implemented ONLY when designated in the plan or when recommended by the Roadway Design Division.
2. When the existing speed limit is 55mph and the plans require a speed limit of 45mph, the R2-1(55) shall be omitted and the R2-5a shall be installed at that location. Additional R2-1 45mph speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
3. When the existing speed limit is 65mph and the plans require a speed limit of 55mph, the R2-1(45) shall be omitted. Additional R2-1 55mph speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
4. The maximum spacing between channelizing devices in a taper should be approximately equal in feet to the speed limit. Beyond the taper, maximum spacing shall be two times the speed limit or as directed by the Engineer.
5. Warning lights and/or flags may be mounted to signs or channelizing devices at night as needed.
6. Pavement markings no longer applicable which might create confusion in the minds of vehicle operators shall be removed or obliterated as soon as practicable.
7. The G20-1 sign will be required on jobs of over two miles in length. When the lane closure is not at the beginning of the project, the G20-1 sign shall be erected 125' in advance of the job limit. Additional W20-1(1/2 MILE) signs are not required in advance of lane closures that begin inside the project limits.
8. Flaggers shall use STOP/SLOW paddles for controlling traffic through work zones. Flags may be used only for emergency situations.
9. All plastic drums and cones shall meet the requirements of NCHRP-350 or Manual for Assessing Safety Hardware (MASH).
10. Trailer mounted devices such as arrow panels and portable changeable message signs shall be delineated by affixing conspicuity material in a continuous line on the face of the trailer. When placed on or adjacent to the shoulder and not behind a positive barrier, these devices shall be delineated by placing five (5) traffic drums, equally spaced along the traffic side of the device.




(C) Typical application - construction operations of intermediate to long term duration on a 4-lane divided roadway where half of the roadway is closed.








(D) Typical application - closing multiple lanes of a multilane highway.

Channelizing devices




CONES



NOTE: For all road closures, the Type III barricades shall be of sufficient length to extend across entire roadway.


VERTICAL PANEL PLACEMENT





TRAFFIC CONTROL DEVICES FOR VERTICAL PAVEMENT DIFFERENTIALS

VERTICAL DIFFERENTIAL	LOCATIONS	TRAFFIC CONTROL
1" to 3"	Centerline, lane lines	W8-11
1" to 3"	Edge of shoulder	W8-9
Greater than 3"	Lane lines	Standard lane closure required
Greater than 3"	Edge of traveled lane	*RSP-1 and vertical panels, drums or concrete barrier
Greater than 3"	Edge of shoulder	*Vertical panels, drums or concrete barrier


* When shown on the plans concrete barrier will be used. When the shoulder area is used as part of the traveled lane and there is insufficient width to place drums on the remaining shoulder width, then vertical panels shall be used.



STOP SLOW PADDLE



- NOTES:
- USE SPLICES ONLY WHEN NECESSARY FOR INSTALLATION. TYPICAL INSTALLATION SHOULD HAVE NO SPLICES (SEE STD. DRAWING NO. SHS-2)
 - NORMAL INSTALLATIONS WILL REQUIRE 1/4" DIA. BOLTS TO MOUNT SIGNS TO POST AND 5/16" DIA. BOLTS TO ASSEMBLE THE VARIOUS POST SUPPORTS. EACH OF THESE BOLTS SHALL BE CARRIAGE BOLTS.
 - SIGN POSTS SHALL BE PAINTED GREEN; SIGNS SHALL NOT BE PAINTED, AND ALL SIGN POSTS SHALL BE PLUMB.




DATE	REVISION	FILED
10-15-09	ADDED REFERENCE TO MASH	
11-20-08	REVISED SIGN DESIGNATIONS	
11-18-04	ADDED NOTE	
10-1-98	ADDED NOTE	
4-03-97	ADDED (SP) TO W6-1 & REVISED TRAFFIC CONTROL DEVICES NOTE	
10-18-96	ADDED R55-1	
10-12-95	MOVED UPPER SPLICE	
6-8-95	REVISED SPLICE DETAIL, TEXT	6-8-95
2-2-95	REVISED PER PART VI, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	

ARKANSAS STATE HIGHWAY COMMISSION STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION


GENERAL NOTES

1. STRAW BALES SHALL BE INSTALLED SO THAT THE BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES. THE BALES SHALL BE A MINIMUM OF 30 INCHES IN LENGTH.
2. STRAW BALES SHALL BE KEYPED INTO SOIL A MINIMUM OF 4' AND NO GAPS SHALL BE LEFT BETWEEN BALES.




BALED STRAW DITCH CHECK (E-1)


NUMBER OF SAND BAGS AND ARRANGEMENT VARIABLE WITH ON-SITE CONDITIONS. PLACE SAND BAGS AT BASE OF DITCH CHECK IN AREA OF OVERFLOW.




SAND BAG DITCH CHECK (E-5)



ROCK DITCH CHECK (E-6)



DROP INLET SILT FENCE (E-7)




SILT FENCE ON R/W FENCE (E-4)


GENERAL NOTES
 GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST, OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.

GENERAL NOTES

1. STRAW BALES SHALL BE INSTALLED SO THAT THE BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES. THE BALES SHALL BE A MINIMUM OF 30 INCHES IN LENGTH.
2. NO GAPS SHALL BE LEFT BETWEEN BALES.
3. BALED STRAW FILTER BARRIERS COMPLETED AND ACCEPTED WILL BE MEASURED BY THE BALE IN PLACE AS AUTHORIZED BY THE ENGINEER AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE BID PER BALE FOR BALED STRAW DITCH CHECKS.




BALED STRAW FILTER BARRIER (E-2)



SILT FENCE (E-11)


GENERAL NOTES
 GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST, OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.

11-18-98	ADDED NOTES	11-18-98	ARKANSAS STATE HIGHWAY COMMISSION
7-02-98	ADDED BALED STRAW FILTER BARRIER (E-2)	7-20-95	TEMPORARY EROSION CONTROL DEVICES
7-20-95	REVISED SILT FENCE E-4 AND E-11	6-2-94	
7-15-94	Rev. E-4 & E-11 Min. 13' Buried End of Fabric		STANDARD DRAWING TEC-1
6-2-94	Revised E-1,4,7, & 11 Deleted E-2 & 3		
4-1-93	REDRAWN		
10-1-92	REDRAWN		
8-2-76	ISSUED R.O.M.	298-7-28-76	
DATE	REVISION	FILMED	




NOTE:
SIZE OF BASIN TO BE DETERMINED
BY VOLUME REQUIRED; HOWEVER
A MINIMUM LENGTH-TO-WIDTH
RATIO OF 2:1 SHALL BE USED.

SEDIMENT BASIN WITH RIPRAP OUTLET (E-9)




NOTE:
SIZE OF BASIN TO BE DETERMINED
BY VOLUME REQUIRED; HOWEVER
A MINIMUM LENGTH-TO-WIDTH
RATIO OF 2:1 SHALL BE USED.


SEDIMENT BASIN WITH PIPE OUTLET (E-10)



DIVERSION DITCH (E-8)



SLOPE DRAIN (E-12)



SEDIMENT BASIN (E-14)


		ARKANSAS STATE HIGHWAY COMMISSION	
		TEMPORARY EROSION CONTROL DEVICES	
		STANDARD DRAWING TEC-2	
6-2-94	Revised E-8 & E-12; Added E-14 & Deleted E-13		
4-1-93	ISSUED		
DATE	REVISION		FILMED

CLEARING AND GRUBBING

CONSTRUCTION SEQUENCE

1. PLACE PERIMETER CONTROLS (I.E. SILT FENCES , DIVERSION DITCHES, SEDIMENT BASINS, ETC.)
2. PERFORM CLEARING AND GRUBBING OPERATION.

EXCAVATION



NOTE:
NUMBER OF PHASES WILL VARY.
THREE PHASES SHOWN FOR
ILLUSTRATION.


GENERAL NOTE

ALL CUT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE EXCAVATED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.

CONSTRUCTION SEQUENCE

1. EXCAVATE AND STABILIZE INTERCEPTOR AND/OR DIVERSION DITCHES.
2. PERFORM PHASE 1 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
3. PERFORM PHASE 2 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
4. PERFORM FINAL PHASE OF EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING. STABILIZE DITCHES. CONSTRUCT DITCH CHECKS, DIVERSION DITCHES, SEDIMENT BASINS, OR OTHER EROSION CONTROL DEVICES AS REQUIRED.

EMBANKMENT



NOTE:
NUMBER OF PHASES WILL VARY.
THREE PHASES SHOWN FOR
ILLUSTRATION.

GENERAL NOTE

ALL EMBANKMENT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE CONSTRUCTED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.


CONSTRUCTION SEQUENCE

1. CONSTRUCT DIVERSION DITCHES, DITCH CHECKS, SEDIMENT BASINS, SILT FENCES, OR OTHER EROSION CONTROL DEVICES AS SPECIFIED.
2. PLACE PHASE 1 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
3. PLACE PHASE 2 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
4. PLACE FINAL PHASE OF EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PLACE DIVERSION DITCHES AND SLOPE DRAINS AND MAINTAIN UNTIL ENTIRE SLOPE IS STABILIZED.

ARKANSAS STATE HIGHWAY COMMISSION		
TEMPORARY EROSION CONTROL DEVICES		
11-03-94	CORRECTED SPELLING	
6-2-94	Drawn & Issued	6-2-94
DATE	REVISION	FILMED
STANDARD DRAWING TEC-3		

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 100723							59	61

2 CROSS SECTIONS







CROSS SECTION STA. 100+00 TO STA. 104+98

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		60	61
				JOB NO.		100723		

2 CROSS SECTIONS

MAIN LANES DETOUR OBLITERATION OF DETOUR

MAIN LANES DETOUR OBLITERATION OF DETOUR



CROSS SECTION STA. 105+00 TO STA. 107+00






DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 100723							61	61

2 CROSS SECTIONS

MAIN LANES DETOUR OBLITERATION OF DETOUR
 AREA CUT 0
 AREA FILL 0

STA. 111+84 IN PLACE
 18"x30" C.M. PIPE CULVERT
 LT. SIDE DRAIN
 REMOVE AND INSTALL
 24"x28" PIPE CULVERT
 LT. SIDE DRAIN
 CONST. APPR. = 25 CU. YD.

113+00.00 MAIN LANES DETOUR OBLITERATION OF DETOUR
 CUT VOLUME 41
 FILL VOLUME 28



CROSS SECTION STA. 108+00 TO STA. 112+00