

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	1	81

② EAST FORK POINT REMOVE CREEK - NORTH & SOUTH GRADE IMPVTS. (S)


ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
CONSTRUCTION PLANS FOR STATE HIGHWAY

**EAST FORK
POINT REMOVE CREEK -
NORTH & SOUTH
GRADE IMPVTS. (S)**

CONWAY COUNTY
ROUTE 95 SECTION 1

JOB 080386


FED. AID PROJ. STP-0018(23)




ARK. HWY. DIST. NO. 8

• DESIGN TRAFFIC DATA •

DESIGN YEAR	-----	2023
2013 ADT	-----	4300
2033 ADT	-----	5000
2033 DHV	-----	550
DIRECTIONAL DISTRIBUTION	-----	0.60
TRUCKS	-----	14%
DESIGN SPEED	-----	55 MPH




VICINITY MAP



STRUCTURE OVER 20' -0 SPAN

STA. 208+96 - IN PLACE
DBL. 54" X 51' C.M. PIPE CULV'T
REMOVE AND CONSTRUCT
SEXT. 11' X 6' X 74' R.C. BOX CULV'T.
WITH 3:1 WINGS LT. & RT.
Q25= 3400 cfs; D.A. = N/A
SPAN = 70' -4'



STA. 200+00.00
BEGIN JOB 080386
LOG MILE 7.25

STA. 231+75.33
END JOB 080386
LOG MILE 7.85

APPROVED

STATE OF ARKANSAS
REGISTERED PROFESSIONAL ENGINEER
No. 3917
FRANK VOZEL

1/23/13
DEPUTY DIRECTOR
AND CHIEF ENGINEER

BEGINNING OF PROJECT	MID-POINT OF PROJECT	END OF PROJECT
LAT. = N 35°15' 15"	LAT. = N 35°15' 31"	LAT. = N 35°15' 47"
LONG. = W 92°43' 59"	LONG. = W 92°43' 59"	LONG. = W 92°43' 58"

GROSS LENGTH OF PROJECT	3175.00	FEET	OR	0.601	MILES
NET " " ROADWAY	3104.67	"	"	0.588	"
NET " " BRIDGES	70.33	"	"	0.013	"
NET " " PROJECT	3175.00	"	"	0.601	"

P.E. JOB 080386
F.A.P. L24R-0018-023

RO80471.DGN 1/22/2013

INDEX OF SHEETS

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		2	81

2 INDEX OF SHEETS, GOV. SPECS. & GEN. NOTES



SHEET NO.	TITLE	BRIDGE NO.	DRWG. NO.	DATE
1	TITLE SHEET			
2	INDEX OF SHEETS, GOVERNING SPECIFICATIONS AND GENERAL NOTES			
3 - 4	TYPICAL SECTIONS OF IMPROVEMENT			
5 - 13	SPECIAL DETAILS			
14 - 16	TEMPORARY EROSION CONTROL DETAILS			
17 - 22	MAINTENANCE OF TRAFFIC			
23 - 24	PERMANENT PAVEMENT MARKING DETAILS			
25 - 28	QUANTITY SHEETS			
29	SUMMARY OF QUANTITIES AND REVISIONS			
30 - 32	SURVEY CONTROL DETAILS			
33 - 35	PLAN AND PROFILE SHEETS			
36	SCOUR PREVENTION DETAILS EAST FORK POINT REMOVE CREEK	05586	51992	
37	DETAILS FOR DUMPED RIPRAP AND FILTER BLANKET AND DETAILS FOR COMPUTING EXCAVATION FOR STRUCTURES		1891F	4-10-03
38	MAILBOX DETAILS		MB-1	11-18-04
39	PRECAST CONCRETE BOX CULVERTS		PBC-1	12-15-11
40	CONCRETE PIPE CULVERT FILL HEIGHTS & BEDDING		PCC-1	12-15-11
41	METAL PIPE CULVERT FILL HEIGHTS & BEDDING		PCM-1	12-15-11
42	PLASTIC PIPE CULVERT (HIGH DENSITY POLYETHYLENE)		PCP-1	12-15-11
43	PLASTIC PIPE CULVERT (PVC F949)		PCP-2	12-15-11
44	PAVEMENT MARKING DETAILS		PM-1	11-17-10
45	DETAILS OF PIPE UNDERDRAIN		PU-1	4-10-03
46	REINFORCED CONCRETE BOX CULVERT DETAILS		RCB-1	7-26-12
47	EXCAVATION PAY LIMITS, BACKFILL, & SOLID SODDING FOR BOX CULVERTS		RCB-2	11-20-03
48	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-1	12-15-11
49	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-2	3-11-10
50	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-3	10-15-09
51	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION-TEMPORARY PRECAST BARRIER		TC-4	10-15-09
52	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION-TEMPORARY PRECAST BARRIER		TC-5	10-15-09
53	TEMPORARY EROSION CONTROL DEVICES		TEC-1	12-15-11
54	TEMPORARY EROSION CONTROL DEVICES		TEC-2	6-02-94
55	TEMPORARY EROSION CONTROL DEVICES		TEC-3	11-03-94
56	WIRE FENCE WATER GAPS		WF-2	4-20-79
57	WIRE FENCE TYPE C AND D		WF-4	8-22-02
58 - 81	CROSS SECTIONS			

GOVERNING SPECIFICATIONS

ARKANSAS STATE HIGHWAY COMMISSION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EDITION OF 2003, AND THE FOLLOWING SPECIAL PROVISIONS AND SUPPLEMENTAL SPECIFICATIONS:

NUMBER	TITLE
ERRATA	ERRATA FOR THE BOOK OF STANDARD SPECIFICATIONS
FHWA-1273	REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - NOTICE TO CONTRACTORS
FHWA-1273	SUPPLEMENT - SPECIFIC EQUAL EMPLOYMENT OPPORTUNITY RESPONSIBILITIES (23 U.S.C. 140)
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - GOALS AND TIMETABLES
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - FEDERAL STANDARDS
FHWA-1273	SUPPLEMENT - POSTERS AND NOTICES REQUIRED FOR FEDERAL-AID PROJECTS
FHWA-1273	SUPPLEMENT - WAGE RATE DETERMINATION
100-2	MANUAL FOR ASSESSING SAFETY HARDWARE (MASH)
102-1	BIDDING REQUIREMENTS AND CONDITIONS
103-1	DETERMINATION OF DBE PARTICIPATION
105-1	CONSTRUCTION CONTROL MARKINGS
105-2	EQUIPMENT AND MATERIAL STORAGE ON BRIDGE STRUCTURES
105-3	CONTROL OF WORK
107-1	WORKER VISIBILITY
108-1	LIQUIDATED DAMAGES
110-1	PROTECTION OF WATER QUALITY AND WETLANDS
303-1	AGGREGATE BASE COURSE
404-1	PRODUCTION VERIFICATION OF ASPHALT CONCRETE HOT MIX
404-2	DESIGN AND QUALITY CONTROL OF ASPHALT MIXTURES
409-1	MINERAL AGGREGATES
410-3	DENSITY TESTING FOR ACHM LEVELING COURSES AND BOND BREAKERS
411-1	ASPHALT CONCRETE COLD PLANT MIX
600-1	WATER FOR VEGETATION
603-1	MAINTENANCE OF TRAFFIC
604-1	RETROREFLECTIVE SHEETING FOR TRAFFIC CONTROL DEVICES IN CONSTRUCTION ZONES
604-2	INSPECTION OF TRAFFIC CONTROL DEVICES IN CONSTRUCTION ZONES
606-1	PIPE CULVERTS FOR SIDE DRAINS
718-2	REFLECTORIZED PAINT PAVEMENT MARKINGS
719-2	THERMOPLASTIC PAVEMENT MARKING MATERIAL
804-1	INSTALLATION OF DOWEL BARS AND TIE BARS
JOB 080386	BROADBAND INTERNET SERVICE FOR ASPHALT CONCRETE PLANT
JOB 080386	BROADBAND INTERNET SERVICE FOR FIELD OFFICE
JOB 080386	CLEARING AND GRUBBING
JOB 080386	CONSTRUCTION IN SPECIAL FLOOD HAZARD AREAS
JOB 080386	FOUNDATION PROTECTION RIPRAP
JOB 080386	GOALS FOR DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION
JOB 080386	INTERNET BIDDING
JOB 080386	LRFD PRECAST REINFORCED CONCRETE BOX CULVERTS
JOB 080386	PARTNERING REQUIREMENTS
JOB 080386	PLASTIC PIPE
JOB 080386	SECTION 404 NATIONWIDE 14 PERMIT REQUIREMENTS
JOB 080386	SOIL STABILIZATION
JOB 080386	STORM WATER POLLUTION PREVENTION PLAN
JOB 080386	SUBMISSION OF ASPHALT CONCRETE HOT MIX ACCEPTANCE TEST RESULTS
JOB 080386	TEMPORARY IMPACT ATTENUATION BARRIER
JOB 080386	UTILITY ADJUSTMENTS
JOB 080386	VALUE ENGINEERING
JOB 080386	WARM MIX ASPHALT

NOTE: CROSS SECTIONS NOT NORMALLY INCLUDED IN PLANS SOLD TO PROSPECTIVE BIDDERS, BUT MAY BE HAD UPON REQUEST.

GENERAL NOTES

- GRADE LINE DENOTES FINISHED GRADE WHERE SHOWN ON PLANS.
- ALL PIPE LINES, POWER, TELEPHONE AND TELEGRAPH LINES TO BE MOVED OR LOWERED BY THE RESPECTIVE OWNERS AS PER AGREEMENT WITH SUCH OWNERS.
- ANY EQUIPMENT OR APPURTENANCE THAT INTERFERES WITH THE PROPOSED CONSTRUCTION AND WHICH MAY BE THE PROPERTY OF UTILITY SERVICE ORGANIZATIONS SHALL BE MOVED BY THE OWNERS UNLESS OTHERWISE PROVIDED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING U. S. MAILBOXES WITHIN THE PROJECT LIMITS IN SUCH A MANNER THAT THE PUBLIC MAY RECEIVE CONTINUED MAIL SERVICE. PAYMENT WILL BE CONSIDERED INCLUDED IN THE PRICE BID FOR THE VARIOUS BID ITEMS.
- ALL LAND MONUMENTS LOCATED WITHIN THE CONSTRUCTION AREA SHALL BE PROTECTED IN ACCORDANCE WITH SECTION 107.12 OF THE STANDARD SPECIFICATIONS.
- ALL TREES THAT DO NOT DIRECTLY INTERFERE WITH THE PROPOSED CONSTRUCTION SHALL BE SPARED AS DIRECTED BY THE ENGINEER. CARE AND DISCRETION SHALL BE USED TO INSURE THAT ALL TREES NOT TO BE REMOVED SHALL BE HARMED AS LITTLE AS POSSIBLE DURING THE CONSTRUCTION OPERATIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A FENCE TO CONTROL LIVESTOCK IN AREAS WHERE PASTURES ARE SEVERED. WIRE FENCE MAY BE CONSTRUCTED INITIALLY, OR IN LIEU THEREOF, THE CONTRACTOR AT HIS OWN EXPENSE, MAY ELECT TO PROVIDE TEMPORARY FENCING SUITABLE TO CONTAIN LIVESTOCK.
- ALL FLEXIBLE BASE AND ASPHALTIC PAVEMENTS REMOVED SHALL BE PAID FOR UNDER THE ITEM NO. 210 - UNCLASSIFIED EXCAVATION.
- THE EXISTING ASPHALT PAVEMENT TO BE REMOVED FROM THE REMAINING PAVEMENT SHALL BE SEPARATED BY SAWING ALONG A NEAT LINE. AFTER SAWING, THE PAVEMENT TO BE REMOVED SHALL BE CAREFULLY REMOVED IN A MANNER THAT WILL NOT DAMAGE THE PAVEMENT THAT IS TO REMAIN. ANY DAMAGE OF THE ASPHALT PAVEMENT THAT IS TO REMAIN IN PLACE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.


INDEX OF SHEETS, GOV. SPECS. & GEN. NOTES

11/6/2012

RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							3	81

2 TYPICAL SECTIONS OF IMPROVEMENT



TANGENT SECTION NOTCH AND WIDEN

*TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER

STA. 201+00 - STA. 202+00
 STA. 222+40 - STA. 227+50

NOTES:


REFER TO CROSS SECTIONS FOR DEVIATION FROM THE NORMAL SLOPES. NO CHANGES SHALL BE MADE FROM THE PLANNED SLOPES WITHOUT THE APPROVAL OF THE ENGINEER.

THE THICKNESS OF AGGREGATE BASE COURSE SHALL BE WITHIN PLUS OR MINUS ONE INCH OF THE PLAN THICKNESS SHOWN. THE CONTRACTOR WILL CORRECT ANY DEFICIENT THICKNESS THAT DOES NOT MEET TOLERANCE INDICATED. PAYMENT WILL NOT BE MADE FOR MATERIAL PLACED IN EXCESS OF THE TOLERANCE.

ASPHALT FOR LEVELING OF EXISTING PAVEMENT SHALL BE PLACED ONLY IF AND WHERE DIRECTED BY THE ENGINEER. CALCULATIONS FOR THE AMOUNT OF LEVELING AND/OR LEVELING OPERATIONS SHALL BE PERFORMED BEFORE CONSTRUCTING NOTCH AND WIDENING.

THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.

WITH THE APPROVAL OF THE ENGINEER, THE CONTRACTOR WILL BE ALLOWED TO SUBSTITUTE, AT NO ADDITIONAL COST TO THE DEPARTMENT, THE FIRST LIFT OF ACHM SURFACE COURSE (1/2") IN LIEU OF AGGREGATE BASE COURSE ON THE SHOULDERS.



TANGENT SECTION FULL DEPTH

STA. 202+00 - STA. 222+40


TYPICAL SECTIONS OF IMPROVEMENT

1/17/2013

RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		4	81

2 TYPICAL SECTIONS OF IMPROVEMENT



*TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER

TANGENT SECTION
OVERLAY


STA. 227+50.00 - STA. 231+75.00

NOTES:


REFER TO CROSS SECTIONS FOR DEVIATION FROM THE NORMAL SLOPES. NO CHANGES SHALL BE MADE FROM THE PLANNED SLOPES WITHOUT THE APPROVAL OF THE ENGINEER.

THE THICKNESS OF AGGREGATE BASE COURSE SHALL BE WITHIN PLUS OR MINUS ONE INCH OF THE PLAN THICKNESS SHOWN. THE CONTRACTOR WILL CORRECT ANY DEFICIENT THICKNESS THAT DOES NOT MEET TOLERANCE INDICATED. PAYMENT WILL NOT BE MADE FOR MATERIAL PLACED IN EXCESS OF THE TOLERANCE. THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.

WITH THE APPROVAL OF THE ENGINEER, THE CONTRACTOR WILL BE ALLOWED TO SUBSTITUTE, AT NO ADDITIONAL COST TO THE DEPARTMENT, THE FIRST LIFT OF ACHM SURFACE COURSE (1/2") IN LIEU OF AGGREGATE BASE COURSE ON THE SHOULDERS.



STA. 201+00 - STA. 208+50 RT.




STA. 200+00 - STA. 224+50 LT.

11/6/2012


RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		5	81


② SPECIAL DETAILS





DETAILS OF RUMBLE STRIPS




LOCATION PLAN OF RUMBLE STRIPS
LEFT OR RIGHT SHOULDER



DETAIL FOR RUMBLE STRIP GAP
AT DRIVEWAY TURNOUTS



PLAN VIEW



DETAIL FOR GAP PATTERN RUMBLE STRIP


NOTE: GAP PATTERN SHALL BE ADJUSTED BY THE ENGINEER IN THE FIELD ALLOWING FOR DRIVEWAYS TO SERVE AS THE GAP.

GENERAL NOTES

- RUMBLE STRIPS SHALL NOT BE INSTALLED ON CURB SECTIONS, BRIDGE DECKS, APPROACH SLABS, INTERSECTING STREETS OR ROADWAYS, RESIDENTIAL OR COMMERCIAL DRIVEWAYS OR ACROSS TRANSVERSE JOINTS OF CONCRETE SHOULDERS.
- RUMBLE STRIPS SHALL NOT BE INSTALLED ON A PAVED SHOULDER THAT IS USED AS A DECELERATION LANE FOR THE LENGTH DEEMED APPROPRIATE BY THE ENGINEER.
- THE 4" OFFSET FROM THE EDGE LINE MAY BE INCREASED TO AVOID LONGITUDINAL JOINTS. IN ALL CASES, THE LATERAL DEVIATION FROM THE PLANNED OFFSET SHOULD BE KEPT TO A MINIMUM.
- RUMBLE STRIPS SHALL BE MEASURED BY THE LINEAR FOOT LONGITUDINALLY ALONG THE SHOULDER. PAYMENT SHALL ONLY INCLUDE THAT PORTION OF THE SHOULDER ON WHICH RUMBLE STRIPS HAVE BEEN CONSTRUCTED. NO MEASUREMENT OR PAYMENT WILL BE MADE FOR GAPS, DRIVEWAYS, TURNOUTS, OR OTHER PUBLIC ROAD INTERSECTIONS WHERE RUMBLE STRIPS HAVE NOT BEEN CONSTRUCTED.
- THE 3/8" DEPTH SHALL GENERALLY APPLY FOR THE ENTIRE 12" LENGTH. SOME VARIATION TO SUIT SHOULDER SLOPE BREAKS MAY BE NECESSARY.


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							6	81

2 SPECIAL DETAILS




DETAIL FOR DRIVEWAYS AND ROAD TURNOUTS

- ASPHALT CONCRETE HOT MIX SURFACE COURSE (1/2") (220 LBS. PER SQ. YD.) AND AGGREGATE BASE COURSE (CLASS 7) 7" COMP. DEPTH IF ASPHALT DRIVE EXISTS; OR 6" CONCRETE IF CONCRETE DRIVE EXISTS.
- AGGREGATE BASE COURSE (CLASS 7) 9" COMP. DEPTH OR CONFORM TO EXISTING DRIVEWAY.



METHOD OF RAISING GRADE

- NOTES:
- THIS DETAIL TO BE USED ONLY IF AND WHERE DIRECTED BY THE ENGINEER.
 - QUANTITIES FOR METHOD OF GRADE RAISE USING ASPHALT WERE CALCULATED ON THIS PROJECT AT LOCATIONS WHERE THE DISTANCE BETWEEN THE EXISTING ASPHALT ROADWAY AND THE PROPOSED SUBGRADE WAS ONE FOOT OR LESS.
 - IN LOCATIONS WHERE THE DISTANCE BETWEEN THE PROPOSED SUBGRADE AND THE EXISTING ASPHALT ROADWAY IS MORE THAN ONE FOOT, SCARIFICATION OF THE EXISTING ASPHALT ROADWAY WILL BE REQUIRED AS STATED IN SECTION 210, SUBSECTION 210.09 OF THE STANDARD SPECIFICATIONS, EDITION OF 2003.




DETAIL FOR TRANSITIONS


11/6/2012 R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							7	81

2 SPECIAL DETAILS



DETAIL OF UNDERCUT



DETAIL OF STAGE CONSTRUCTION SECTION B

SPECIAL DETAILS

11/6/2012
ROB0386.DGN

MID-SECTION

Table with columns for R.C. BOX SECTION, DESIGN FILL DEPTH, CLEAR SPAN, CLEAR HEIGHT, TOP SLAB THK, BOTTOM SLAB THK, SIDE WALL THK, INTERIOR WALL THK, OVER ALL WIDTH, OVER ALL HEIGHT, SECTION LENGTH, TOP SLAB REINFORCING STEEL, BOTTOM SLAB REINFORCING STEEL, SIDE WALL REINFORCING STEEL, INTERIOR WALL REINFORCING STEEL, TOP SLAB DISTRIBUTION REINF. STEEL, BOTTOM SLAB DISTRIBUTION REINF. STEEL, SIDE WALL DISTRIBUTION REINF. STEEL, INTERIOR WALL DISTRIBUTION REINF. STEEL.

Table with columns: CLASS 'S' CONCRETE, REINFORCING STEEL (GR. 60), ADTL. REINF. PER LONG LAP LOCATION(S), ADTL. REINF. FOR TRANS. LAP, ADDITIONAL CONCRETE FOR HDWL, TOTAL ADTL. REINF. FOR HDWL.

SHEET 1 OF 2
DETAILS OF R.C. BOX CULVERT
SEXTUPLE BARREL BOX CULVERT
Sta. 208+96
SPECIAL DETAILS

SPECIAL DETAILS



INLET SLOPE SECTION(S)

Table with columns for R.C. BOX SECTION, DESIGN FILL DEPTH, CLEAR SPAN, CLEAR HEIGHT, TOP SLAB THK, BOTTOM SLAB THK, SIDE WALL THK, INTERIOR WALL THK, OVER ALL WIDTH, OVER ALL HEIGHT, SECTION LENGTH, TOP SLAB REINFORCING STEEL, BOTTOM SLAB REINFORCING STEEL, SIDE WALL REINFORCING STEEL, INTERIOR WALL REINFORCING STEEL, TOP SLAB DISTRIBUTION REINF. STEEL, BOTTOM SLAB DISTRIBUTION REINF. STEEL, SIDE WALL DISTRIBUTION REINF. STEEL, INTERIOR WALL DISTRIBUTION REINF. STEEL.

Table with columns: CLASS 'S' CONCRETE, REINFORCING STEEL (GR. 60), ADTL. REINF. PER LONG LAP LOCATION, ADTL. REINF. FOR TRANS. LAP, ADDITIONAL CONCRETE FOR HDWL, TOTAL ADTL. REINF. FOR HDWL.

Bar Lap - Add one long lap for each Slope Section, and one additional long lap for Slope Sections greater than 40'-0" in length.

Table with columns: Design Fill Depth, Range of Actual Fill Depth.

Data shown for Mid-Section, Slope Section(s), and Skewed End Section is based on the design fill depth shown in the table, see PLAN AND PROFILE SHEETS for actual fill depth.

INLET SKEWED END SECTION

Table with columns for SKEW (DEGREE), SLOPE, DESIGN FILL DEPTH, CLEAR SPAN, CLEAR HEIGHT, SECTION LENGTH, TOP SLAB THK, HDWL THK, BOTTOM SLAB THK, SIDE WALL THK, INTERIOR WALL THK, OVER ALL WIDTH, OVER ALL HEIGHT, TOP SLAB REINFORCING STEEL, BOTTOM SLAB REINFORCING STEEL, SIDE WALL REINFORCING STEEL, INTERIOR WALL REINFORCING STEEL, TOP SLAB DISTRIBUTION REINFORCING STEEL, BOTTOM SLAB DISTRIBUTION REINFORCING STEEL, SIDE WALL DISTRIBUTION REINFORCING STEEL, INTERIOR WALL DISTRIBUTION REINFORCING STEEL.

Table with columns: CLASS 'S' CONCRETE (includes HDWL), REINFORCING STEEL (GR. 60) (includes HDWL), CU. YDS., LBS.

Any Bar Lap Required for the Skewed End Section shall be considered subsidiary to the item "Reinforcing Steel - Roadway (Gr. 60)."

INLET WINGWALL TABLE

Large table with columns for OVER ALL WIDTH, CLEAR HEIGHT, FOOTING THK, WING WALL THK, BOX SKEW (DEG.), SLOPE, HDWL LENGTH, HEEL, WALL HEIGHT, WINGWALL ANGLE, FOOTING WIDTH AT WALL END, WIDTH OF WING FOOTINGS AT HDWL, FOOTING DIMENSION PARALLEL WITH HDWL, LENGTH OF WING WALLS, INSIDE FOOTING DIMENSIONS, CLASS 'S' CONCRETE, REINFORCING STEEL.

MID-SECTION BAR LAP TABLE

Table with columns: # of Long Laps Req'd, SL = Section Length.

Table with columns: Min. Bar Lap Length, #4, #5, #6, #7, #8.

Table with columns: Bar Pn Dia. Table, #4, #5, #6, #7, #8.

This drawing to be used in conjunction with SHEET 1 OF 4, "GENERAL DETAILS OF R.C. BOX CULVERT", "GENERAL NOTES & LONGITUDINAL SECTION LENGTH SCHEDULE", SHEET 3 OF 4, "GENERAL DETAILS OF R.C. BOX CULVERT", "DETAILS OF MULTI-BARREL R.C. BOX CULVERT", SHEET 4 OF 4, "GENERAL DETAILS OF R.C. BOX CULVERT", "DETAILS OF WING WALLS", and STANDARD DRAWING RCB-2. For additional information and outlet sections, see Sheet 2 of 2.

TABULAR DATA BY: ACP DATE: 01/17/13
CHECKED BY: ARS DATE: 1/17/13




Table with columns: DATE REVISED, DATE FILMED, DATE REVISED, DATE FILMED, FED. ROAD DIST. NO., STATE, FED. AID PROJ. NO., SHEET NO., TOTAL SHEETS, JOB NO., 080386, 8, 81.



TABULAR DATA BY: ACP DATE: 01/17/13
 CHECKED BY: AMS DATE: 1/17/13

OUTLET WINGWALL TABLE

OVER ALL WIDTH		CLEAR HEIGHT	FOOTING THK.		BOX SKEW (DEG.)	SLOPE		HEEL		WINGWALL ANGLE (DEGREE)		FOOTING WIDTH AT WALL END		WIDTH OF WING FOOTINGS AT HDWL		FOOTING DIMENSION PARALLEL WITH HDWL		LENGTH OF WINGWALLS		INSIDE FOOTING DIMENSIONS		CLASS "S" CONCRETE (Includes apron)	REINFORCING STEEL (Includes apron and laps if required)
OW	H	WB	CW	SK	SL	K	HL	WH1	WH2	AF1	AF2	WE	WF1	WF2	G1	G2	W1	W2	W4	W5			
70'-4"	6'-0"	0'-9"	0'-8"	0	3:1	70'-4"	2'-0"	6'-10"	2'-0"	30	30	3'-2"	3'-5"	3'-5"	1'-0 5/8"	1'-0 5/8"	16'-6"	16'-6"	16'-2"	16'-2"	13.91	954	

Min. Bar Lap Length

#4	1'-9"
#5	2'-2"
#6	2'-7"
#7	3'-6"
#8	4'-7"

Bar Pin Dia. Table

#4	3"
#5	3 3/4"
#6	4 1/2"
#7	5 1/4"
#8	6"

Any Bar Lap Required for the Skewed End Section shall be considered subsidiary to the item "Reinforcing Steel - Roadway (Gr. 60)."

OUTLET SKEWED END SECTION

SK	SLOPE	DESIGN FILL DEPTH (FT.)	CLEAR SPAN (FT.)	CLEAR HEIGHT (FT.)	SECTION LENGTH	TOP SLAB THK.	HDWL THK.	BOTTOM SLAB THK.	SIDE WALL THK.	INTERIOR WALL THK.	OVER ALL WIDTH	OVER ALL HEIGHT	TOP SLAB REINFORCING STEEL			BOTTOM SLAB REINFORCING STEEL			SIDE WALL REINFORCING STEEL			INTERIOR WALL REINFORCING STEEL			TOP SLAB DISTRIBUTION REINFORCING STEEL			BOTTOM SLAB DISTRIBUTION REINFORCING STEEL			SIDE WALL DISTRIBUTION REINFORCING STEEL			INTERIOR WALL DISTRIBUTION REINFORCING STEEL		
													a	b	c	d	e	f	g	h	i	j	k	l	m	n	o	p	q	r	s	t	u	v	w	x

CLASS "S" CONCRETE (Includes HDWL)	REINFORCING STEEL (Gr 60) (Includes HDWL)
CU. YDS.	LBS.

OUTLET SLOPE SECTION(S)

R.C. BOX SECTION	DESIGN FILL DEPTH (FT.)	CLEAR SPAN (FT.)	CLEAR HEIGHT (FT.)	TOP SLAB THK.	BOTTOM SLAB THK.	SIDE WALL THK.	INTERIOR WALL THK.	OVER ALL WIDTH	OVER ALL HEIGHT	SECTION LENGTH (FT.)	TOP SLAB REINFORCING STEEL				BOTTOM SLAB REINFORCING STEEL				SIDE WALL REINFORCING STEEL "f"			INTERIOR WALL REINFORCING STEEL "f1"			TOP SLAB DISTRIBUTION REINF. STEEL "g"			BOTTOM SLAB DISTRIBUTION REINF. STEEL "e"			SIDE WALL DISTRIBUTION REINF. STEEL "d1"			INTERIOR WALL DISTRIBUTION REINF. STEEL "d2"					
											a	Bent b	c	NO. REQ'D	d	Bent b1	f	NO. REQ'D	SIZE	SPACING	NO. REQ'D	LENGTH	SIZE	SPACING	NO. REQ'D	LENGTH	SIZE	SPACING	NO. REQ'D	LENGTH	SIZE	SPACING	NO. REQ'D	LENGTH	SIZE	SPACING	NO. REQ'D	LENGTH	SIZE
2	11	6																																					

CLASS "S" CONCRETE	REINFORCING STEEL (Gr. 60)	ADTL. REINF. PER LONG. LAP LOCATION	ADTL. REINF. FOR TRANS. LAP	ADDITIONAL CONCRETE FOR HDWL	TOTAL ADTL. REINF. FOR HDWL
CU. YDS. PER LIN. FT.	LBS. PER LIN. FT.	LBS.	LBS. PER LIN. FT.	CU. YDS.	LBS.
				0.65	186

Bar Lap - Add one long lap for each Slope Section, and one additional long lap for Slope Sections greater than 40'-0" in length.

SHEET 2 OF 2
 DETAILS OF R.C. BOX CULVERT
 SEXTUPLE BARREL BOX CULVERT
 Sta. 208+96

SPECIAL DETAILS




The required number of bars shown is for estimating purpose only. The actual number required shall be determined in field.

Unless otherwise noted, all dimensions are in inches.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		10	81


JOB NO. 080386 SPECIAL DETAILS



2:1 Slope	20'-0"	10'-0"	10'-0"	10'-0"	10'-0"	10'-0"	10'-0"
3:1 Slope	30'-0"	15'-0"	15'-0"	15'-0"	15'-0"	15'-0"	15'-0"
4:1 Slope	40'-0"	20'-0"	20'-0"	20'-0"	20'-0"	20'-0"	20'-0"

Note: For fill depths 5' and under, use Mid-Section full length of box culvert.


* LL = Skewed End Section Length - See "Skewed End Section Details" Length LL varies with skew angle, overall box width and fill depth and may eliminate the need for some slope section lengths as shown.



Slope Section Length @ 2:1 Slope	A=12'-0"	B=6'-0"	C=6'-0"	D=6'-0"	E=6'-0"	F=6'-0"	G=6'-0"	Mid-Section Length - Varies
Slope Section Length @ 3:1 Slope	A=22'-0"	B=11'-0"	C=11'-0"	D=11'-0"	E=11'-0"	F=11'-0"	G=11'-0"	Mid-Section Length - Varies
Slope Section Length @ 4:1 Slope	A=32'-0"	B=16'-0"	C=16'-0"	D=16'-0"	E=16'-0"	F=16'-0"	G=16'-0"	Mid-Section Length - Varies

LONGITUDINAL SECTION LENGTH SCHEDULE FOR VARYING FILL DEPTHS OVER 5'

Lengths for Non-Skewed Boxes



SKewed SECTION LAYOUT FOR VARYING FILL DEPTHS OVER 5'

GENERAL NOTES:

CONSTRUCTION SPECIFICATIONS: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2003 edition) with applicable supplemental specifications and special provisions. Section and Subsection refer to the Standard Construction Specifications unless otherwise noted in the Plans.

DESIGN SPECIFICATIONS: AASHTO LRFD Bridge Design Specifications, Fifth Edition (2010) with 2010 interim revisions.

LIVE LOADING: HL-93

All concrete shall be Class S with a minimum 28-day compressive strength of 3,500 psi and shall be poured in the dry. All exposed corners to have 1/4" chamfers.

Reinforcing Steel shall be AASHTO M 31 or M 53, Grade 60.

Reinforcing Steel Tolerances: the tolerances for reinforcing steel shall meet those listed in 'Manual of Standard Practice' published by Concrete Reinforcing Steel Institute (CRSI) except that the tolerance for truss bars such as Figure 3 on page 7-4 of the CRSI Manual shall be minus zero to plus 1/2 inch.

Excavation and backfilling shall be in accordance with the requirements of Section 801.

Membrane Waterproofing shall conform to the requirements of Section 815 of the Standard Specifications. Membrane Waterproofing shall be Type C and as directed by the Engineer applied to all construction joints in the top slab and the sidewalls of R.C. Box culverts and to the construction joint between wingwalls and R.C. Box culvert walls.


Weep Holes in box culvert walls shall have a maximum horizontal spacing of 10'-0" and shall be spaced to clear all reinforcing steel. The drain opening shall be 4" diameter and shall be placed 12" above the top of the bottom slab.

Weep Holes in wingwalls shall have a maximum horizontal spacing of 10'-0" and shall be spaced to clear all reinforcing steel. There shall be a minimum of two (2) weep holes in each wingwall. The drain opening shall be 4" diameter and shall be placed 12" above the top of the wingwall footing.

Construction Joints between footings and walls shall be made only where shown on the Plans. The maximum length of culvert for which a continuous pour will be permitted is 75 ft. For longer culvert construction, joints shall be provided in slabs and walls at intervals not greater than 50 ft. Joints shall be normal to the centerline of barrel and shall be keyed. Longitudinal reinforcing shall be continuous through joints unless shown otherwise.


Membrane Waterproofing, Weep Holes, Geotextile Filter Fabric, and Drainage Fill Material will not be paid for directly but shall be considered subsidiary to Class S Concrete.

When precast reinforced concrete box culverts are substituted for cast in place box culverts, they shall be manufactured according to ASTM C 1577 and meet the requirements of Special Provision "LRFD Precast Reinforced Concrete Box Culverts".



CULVERT DRAINAGE DETAIL FOR ROCK FILL

This detail shall be used when rock fill is specified for embankment construction.



WINGWALL & CULVERT DRAINAGE DETAIL

For Details of Excavation and Pay Limits, see Standard Drawing RCB-2.

**SHEET 1 OF 4
GENERAL DETAILS OF R.C. BOX CULVERT
GENERAL NOTES &
LONGITUDINAL SECTION LENGTH SCHEDULE**



SPECIAL DETAILS




b080386_culvert.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		11	81
JOB NO. 080386								

① SPECIAL DETAILS




TYPICAL SECTION M-M




LONGITUDINAL LAP DETAIL AT CHANGE IN SECTIONS

TOP SLAB SHOWN, BOTTOM SLAB SIMILAR




TOP SLAB REINFORCEMENT




WINGWALL ATTACHMENT

See "Details of Wingwalls" for additional information and wingwall details.




TYPICAL KEYWAY DETAIL




PART LONGITUDINAL SECTION

(Non-Skewed Ends)



PART LONGITUDINAL SECTION N-N

(Skewed Ends)



SKewed END SECTION DETAILS

SHEET 2 OF 4
GENERAL DETAILS OF R.C. BOX CULVERT

DETAILS OF SINGLE BARREL
R.C. BOX CULVERT



SPECIAL DETAILS



b080386_culvert.dgn

DATE REVISED	DATE FILMED	REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		12	81

JOB NO. 080386 SPECIAL DETAILS




TYPICAL SECTION M-M



Top Slab
Straight "c" bars shall alternate with Bent "b" bars in top.
Straight "a" bars shall alternate with Bent "b" bars in bottom.

Bottom Slab
Straight "d" bars shall alternate with Bent "bl" bars in top.
Straight "f" bars shall alternate with Bent "bl" bars in bottom.


*2" clr. for fill depth (D) greater than 2 ft.
2 1/2" clr. for fill depth (D) equal to or less than 2 ft.



Bent "b" bars or Bent "bl" bars sketch




TYPICAL KEYWAY DETAIL




Optional Lap Detail
For Bent "b" bars and Bent "bl" bars

At the Contractor's option in lieu of providing Bent "b" or Bent "bl" bars, one bar top and bottom of equivalent size may be substituted for each bent bar. Payment for the reinforcing will be based on the weight of the "b" or "bl" bar.




TOP SLAB REINFORCEMENT
Straight "c" bars in top.
Straight "a" bars in bottom.




BOTTOM SLAB REINFORCEMENT
Straight "d" bars in top.
Straight "f" bars in bottom.


SKewed END SECTION DETAILS



PART LONGITUDINAL SECTION
(Non-Skewed Ends)




PART LONGITUDINAL SECTION N-N
(Skewed Ends)



LONGITUDINAL LAP DETAIL AT CHANGE IN SECTIONS
TOP SLAB SHOWN, BOTTOM SLAB SIMILAR

Longitudinal Bar Spacing at individual sections shall be maintained, which may result in noncontact bar laps.



WINGWALL ATTACHMENT



See "Details of Wingwalls" for additional information and wingwall details.

SHEET 3 OF 4
GENERAL DETAILS OF R.C. BOX CULVERT
DETAILS OF MULTI-BARREL
R.C. BOX CULVERT
SPECIAL DETAILS


b080386_culvert.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		080386	13	81

SPECIAL DETAILS




END ELEVATION




PART PLAN

Note: WF1 and WF2 are measured at outside corner of culvert wall.




WINGWALL ELEVATION
Showing Back Face Reinforcement


Note: See "Wingwall Cross-Section" for additional details and reinforcing




WINGWALL PLAN




WINGWALL SECTION P-P




F1, F2, F3, & F6 SKETCH



F12 SKETCH



CONSTRUCTION JOINTS



TYPICAL KEYWAY DETAIL



SHEET 4 OF 4
GENERAL DETAILS OF R.C. BOX CULVERT
DETAILS OF WINGWALLS
SPECIAL DETAILS



b080386_culvert.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		14	81
				JOB NO. 080386				

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS



DATE	REVISION

LEGEND	
(E-5)	SAND BAG DITCH CHECKS
(E-6)	ROCK DITCH CHECKS
(E-4)	SILT FENCE

TEMPORARY EROSION CONTROL DETAILS
STAGE 1

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		15	81

2 TEMPORARY EROSION CONTROL DETAILS




REVISIONS

DATE	REVISION

LEGEND

E-5	SAND BAG DITCH CHECKS
E-6	ROCK DITCH CHECKS
E-11	SILT FENCE



TEMPORARY EROSION CONTROL DETAILS STAGE 2



11/6/2012

R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	16	81

RETAIN TEMPORARY EROSION CONTROL DEVICES FROM STAGE 2


2 TEMPORARY EROSION CONTROL DETAILS



REVISIONS	
DATE	REVISION

LEGEND	
(E-5)	SAND BAG DITCH CHECKS
(E-6)	ROCK DITCH CHECKS
(E-11)	SILT FENCE


RETAIN TEMPORARY EROSION CONTROL DEVICES FROM STAGE 2





TEMPORARY EROSION CONTROL DETAILS
STAGE 3

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		17	81

2 MAINTENANCE OF TRAFFIC



NOTE: RETAIN ADVANCE SIGNS FOR ALL STAGES



STAGE 1 OPERATIONS



- NOTCH RIGHT SIDE OF EXISTING ROADWAY WHERE SHOWN ON PLANS AND WIDEN TO CARRY STAGE 2 TRAFFIC
- PLACE ENOUGH EMBANKMENT LEFT OF EXISTING ROADWAY TO SUPPORT PRECAST CONCRETE BARRIER WHERE SHOWN ON PLANS.
- INSTALL PRECAST CONCRETE BARRIER AS SHOWN
- BEGIN CONSTRUCTION OF SEXT. BOX CULVERT AT STA. 208+96

MAINTENANCE OF TRAFFIC STAGE 1

11/6/2012 R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							18	81

② MAINTENANCE OF TRAFFIC



STA.231+75.33
 END JOB 080386
 LOG MILE 8.14

NOTE: RETAIN ADVANCE SIGNS FOR ALL STAGES

MAINTENANCE OF TRAFFIC
 STAGE 1

11/6/2012


RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		19	81
JOB NO. 080386								

② MAINTENANCE OF TRAFFIC




STA. 200+00.00
BEGIN JOB 080386
LOG MILE 7.25



REMOVAL OF PERMANENT PAVEMENT MARKINGS
RT. EDGE LINE & EXISTING CENTERLINE
STA. 203+25 - STA. 208+33 - 635 LIN.FT.

CONSTRUCTION PAVEMENT MARKINGS
LT. & RT. EDGE LINES - DBL. CENTERLINE
STA. 300+00 - STA. 308+32.68 STAGE 2 ALIGNMENT - 3332 LIN.FT.





STAGE 2 OPERATIONS
PLACE ACHM FOR GRADE RAISE & INSTALL CONSTRUCTION PAVEMENT MARKINGS
SHIFT TRAFFIC ONTO STAGE 2 ALIGNMENT WHERE SHOWN.
PARTIALLY-CONSTRUCT NEW ALIGNMENT LEFT OF EXISTING

MAINTENANCE OF TRAFFIC STAGE 2

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		20	81
				JOB NO. 080386				

② MAINTENANCE OF TRAFFIC



11/6/2012
R080386.DGN


MAINTENANCE OF TRAFFIC
STAGE 2

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		21	81


2 MAINTENANCE OF TRAFFIC



PRECAST CONCRETE BARRIER STA. 202+80 - STA. 210+53
RT. OF STAGE 3 TRAFFIC
RELOCATING PRECAST CONCRETE BARRIER - 393 LIN. FT.
THIS INCLUDES (1) SPECIAL END UNIT
FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER - 380 LIN. FT.



REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS
LT. EDGE LINE • DBL. CENTERLINE
STA. 200+00 - STA. 201+25 • 375 LIN. FT.




MAINTENANCE OF TRAFFIC STAGE 3

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		22	81
				JOB NO.		080386		

② MAINTENANCE OF TRAFFIC




MAINTENANCE OF TRAFFIC
STAGE 3

11/6/2012


R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		23	81

2 PERMANENT PAVEMENT MARKING DETAILS



PERMANENT PAVEMENT MARKINGS
THERMOPLASTIC PAVEMENT MARKINGS
LT. & RT. EDGE LINES ENTIRE JOB - 6350 LIN.FT. 4" WHITE
DBL. CENTERLINE ENTIRE JOB - 6350 LIN.FT. 4" YELLOW
NOTE: CONTACT MAINTENANCE DIVISION TO DETERMINE NO PASSING ZONE.






END OF JOB OPERATIONS
REMOVE WORN CENTERLINE MARKINGS FROM BRIDGE DECK
PLACE FINAL LIFT OF ACHM SURFACE
PLACE PERMANENT PAVEMENT MARKINGS
INCLUDING HIGH PERFORMANCE CONTRAST PAVEMENT MARKINGS
ON BRIDGE CENTERLINE

PERMANENT PAVEMENT MARKING DETAILS

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		24	81

② PERMANENT PAVEMENT MARKING DETAILS



PERMANENT PAVEMENT MARKING DETAILS

11/6/2012

R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		25	81
				JOB NO.	080386			

2 QUANTITIES



CONSTRUCTION PAVEMENT MARKINGS AND PERMANENT PAVEMENT MARKINGS

DESCRIPTION	STAGE 1	STAGE 2	STAGE 3	END OF JOB	MAXIMUM NUMBER REQUIRED	REMOVAL OF PERMANENT PAVEMENT MARKINGS	CONSTRUCTION PAVEMENT MARKINGS	REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS	THERMOPLASTIC PAVEMENT MARKINGS	
						LIN.FT.	LIN.FT.	LIN.FT.	4" WHITE	4" YELLOW
									LIN.FT.	LIN.FT.
REMOVAL OF PERMANENT PAVEMENT MARKINGS		635			635	635				
CONSTRUCTION PAVEMENT MARKINGS	3340	3332	11000		17672		17672			
REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS			375		375			375		
THERMOPLASTIC PAVEMENT MARKINGS WHITE (4")				6350	6350				6350	
THERMOPLASTIC PAVEMENT MARKINGS YELLOW (4")				6350	6350					6350
TOTALS						635	17672	375	6350	6350

NOTE: THIS IS A HIGH TRAFFIC VOLUME ROAD AS DEFINED IN SECTION 604.03, STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 2003 EDITION.

ADVANCE WARNING SIGNS AND DEVICES

SIGN NUMBER	DESCRIPTION	SIGN SIZE	STAGE 1	STAGE 2	STAGE 3	END OF JOB	MAXIMUM NUMBER REQUIRED	TOTAL SIGNS REQUIRED		TRAFFIC DRUMS	BARRICADES (TYPE III)		FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER	RELOCATING PRECAST CONCRETE BARRIER	TEMPORARY IMPACT ATTENUATION BARRIER	TEMPORARY IMPACT ATTENUATION BARRIER (REPAIR)	VERTICAL PANELS		
								NO.	SQ. FT.		EACH	LIN.FT.						LIN.FT.	EACH
W20-1	ROAD WORK 1500 FT.	48"x48"	2	2	2	2		2	32.0										
W20-1	ROAD WORK 1000 FT.	48"x48"	2	2	2	2		2	32.0										
W20-1	ROAD WORK 500 FT.	48"x48"	2	2	2	2		2	32.0										
G20-2	END ROAD WORK	48"x24"	2	2	2	2		2	16.0										
W1-6	LARGE ARROW	48"x24"		2				2	16.0										
RSP-1	SHOULDER CLOSED	48"x30"	2	2	2			2	20.0										
R11-2	ROAD CLOSED	48"x30"	2	3	2			3	30.0										
R4-1	DO NOT PASS	24"x30"	2	2	2			2	10.0										
	TRAFFIC DRUMS		11	45	26		45			45									
	VERTICAL PANELS		17		11		17										17		
	TYPE III BARRICADE-RT. (8')		1				1				8								
	TYPE III BARRICADE-LT. (8')		1				1					8							
	TYPE III BARRICADE-RT. (16')			2	2		2				32								
	TYPE III BARRICADE-LT. (16')			1			1					16							
	FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER		406		380		786					786							
	RELOCATING PRECAST CONCRETE BARRIER				393		393						393						
	TEMPORARY IMPACT ATTENUATION BARRIER				1		1							1					
	TEMP. IMPACT ATTEN.BARRIER (REPAR)				1		1									1			
TOTALS								188.0	45	45	40	24	786	393	1	1	17		

NOTE: THIS IS A HIGH TRAFFIC VOLUME ROAD AS DEFINED IN SECTION 604.03, STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 2003 EDITION.

QUANTITIES

11/6/2012

RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		26	81

CLEARING AND GRUBBING

STATION	STATION	CLEARING	GRUBBING
		STATION	
201+00	214+00	13	13
220+00	221+00	1	1
224+00	226+00	2	2
TOTALS		16	16

REMOVAL AND DISPOSAL OF PIPE CULVERTS

STATION	DESCRIPTION	PIPE CULVERTS
		EACH
208+96	DBL. 54" X 51" C.M. PIPE CULV'T. CROSS DRAIN	2
220+08	24" X 48" C.M. PIPE LT. SIDE DRAIN	1
222+40	12" X 24" C.M. PIPE RT. SIDE DRAIN	1
225+85	18" X 41" C.M. PIPE RT. SIDE DRAIN	1
TOTAL		5

NOTE: QUANTITIES SHOWN ABOVE INCLUDE REMOVAL AND DISPOSAL OF ALL HEADWALLS AND FLARED END SECTIONS IF APPLICABLE.

② QUANTITIES



EARTHWORK

STATION	STATION	LOCATION	UNCLASSIFIED EXCAVATION	COMPACTED EMBANKMENT	SOIL STABILIZATION
			CU. YD.		TON
ENTIRE PROJECT		STAGE 1 - UNDERCUT & BACKFILL	812	812	
200+00	211+00	STAGE 1 - DETOUR CONSTRUCTION	263	1539	
ENTIRE PROJECT		STAGE 2 - UNDERCUT & BACKFILL	6683	6683	
ENTIRE PROJECT		STAGE 2 - MAIN LANES	1417	11779	
ENTIRE PROJECT		STAGE 3 - MAIN LANES	5127	2063	
* 232+40	233+00	CHANNEL UNDER BRIDGE	1357		
208+96		CHANNEL CHANGE FOR R.C. BOX CULVERT	990		
ENTIRE PROJECT		APPROACHES		660	
** ENTIRE PROJECT TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER.					200
TOTALS			16649	23536	200

* SEE SHEET 73 FOR ADDITIONAL INFORMATION.

** QUANTITY ESTIMATED. SEE SECTION 104.03 OF THE STD. SPECS.

SOIL LOG

STATION	LATITUDE			LONGITUDE			LOCATION	DEPTH FEET	AASHTO CLASSIFICATION	LIQUID LIMIT	PLASTICITY INDEX	REMARKS
	DEG	MIN	SEC	DEG	MIN	SEC						
201+00	35	15	16.60	92	43	58.50	5' RT	0-5	A-6(11)	32	14	BROWN
201+00	35	15	16.60	92	43	58.30	25' RT	0-5	A-6(15)	35	17	BROWN
210+00	35	15	25.50	92	43	58.60	CL	0-5	A-4(7)	26	9	BROWN
217+00	35	15	32.10	92	43	58.30	CL	0-5	A-4(4)	24	7	BROWN
225+00	35	15	43.30	92	43	58.00	4' LT	0-5	A-6(6)	28	14	BROWN
225+00	35	15	43.30	92	43	58.10	13' LT	0-5	A-4(1)	21	7	BROWN
225+00	35	15	43.33	92	43	58.30	24' LT	0-5	A-6(7)	28	14	BROWN
236+00	35	15	50.90	92	43	57.50	5' RT	0-4.0 Z	A-6(6)	35	21	BROWN
236+00	35	15	50.90	92	43	57.40	14' RT	0-3.0 Z	A-4(0)	20	2	BROWN
236+00	35	15	50.90	92	43	57.20	25' RT	0-5	A-6(12)	32	13	BROWN
236+00	35	15	50.90	92	43	57.20	25' RT	0-5	A-6(8)	29	11	BROWN

SOIL CHARACTERISTICS TABULATED ABOVE ARE REPRESENTATIVE AT THE LOCATION OF THE SAMPLE, AND FROM SURFACE INDICATIONS ARE TYPICAL FOR THE LIMITS SHOWN. THESE DATA ARE SHOWN FOR INFORMATION ONLY. THE STATE WILL NOT BE RESPONSIBLE FOR VARIATIONS IN THE SOIL CHARACTERISTICS AND/OR EXTENT OF SAME DIFFERING FROM THE ABOVE TABULATIONS. Z-AUGER REFUSAL

SELECTED PIPE BEDDING

LOCATION	SELECTED PIPE BEDDING CU.YD.
ENTIRE PROJECT TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER	20
TOTAL	20

NOTE: QUANTITY ESTIMATED. SEE SECTION 104.03 OF THE STD. SPECS.

STRUCTURES

STATION	DESCRIPTION	SIDE DRAINS			REINFORCED CONCRETE BOX CULVERTS											
		18"	24"	36"	SPAN	HEIGHT	LENGTH	CLASS S CONCRETE (ROADWAY)	REINF. STEEL-ROADWAY (GRADE 60)	UNCL. EXC. FOR STR. (ROADWAY)	SOLID SODDING	WATER				
		LIN. FT.											LINEAR FEET			CU.YD.
220+08	INSTALL SIDE DRAIN ON LT			44												
222+40	INSTALL SIDE DRAIN ON RT			44												
225+85	INSTALL SIDE DRAIN ON RT	58	52													
TOTALS FOR STRUCTURES UNDER 20'-0" SPAN		58	52	88												
208+96	CONST. SECT. 11' X 6' X 74' R.C. BOX CULV'T. W/3:1 WINGS LT. & RT.				11	6	74	499.89	72103	283	46	0.58				
TOTALS FOR STRUCTURES OVER 20'-0" SPAN								499.89	72103	283	46	0.58				
TOTALS		58	52	88				499.89	72103	283	46	0.58				

BASIS OF ESTIMATE:
WATER.....12.6 GAL. / SQ. YD. OF SOLID SODDING.

NOTE: FOR R.C. PIPE CULVERT INSTALLATIONS USE TYPE 3 BEDDING UNLESS OTHERWISE SPECIFIED.
NOTE: FOR C.M. PIPE CULVERT INSTALLATIONS USE TYPE 2 BEDDING UNLESS OTHERWISE SPECIFIED.

FENCING

STATION	STATION	SIDE	WIRE FENCE (TYPE D)	*16'-0" GATES
			LIN. FT.	EACH
201+41	206+46	RT	495	
206+46	208+43	RT	197	
220+08		LT		1
TOTALS			692	1

* DENOTES ALTERNATE BID ITEM.

QUANTITIES

DRIVEWAYS

STATION	DESCRIPTION	WIDTH	AGGREGATE BASE COURSE (CLASS 7)	ACHM SURFACE COURSE (1/2") 220 LBS. PER SQ. YD. (PG 64-22)
		FEET	TON	TON
220+08	DRIVEWAY ON LT.	16.0	61.4	2.7
222+40	DRIVEWAY ON RT.	16.0	66.1	2.7
225+85	DRIVEWAY ON RT.	16.0	66.1	2.7
227+81	DRIVEWAY ON LT.	16.0	28.8	2.7
228+72	DRIVEWAY ON RT.	16.0	28.8	2.7
*ENTIRE PROJECT TEMPORARY DRIVES			100.0	
TOTALS			351.2	13.5

BASIS OF ESTIMATE:

ACHM SURFACE COURSE (1/2").....94.5% MIN. AGGR.....5.5% ASPHALT BINDER
 MAXIMUM NUMBER OF GYRATIONS = 115

*QUANTITY ESTIMATED.


SEE SECTION 104.03 OF THE STD. SPECS.

RUMBLE STRIPS IN ASPHALT SHOULDERS

STATION	STATION	LOCATION	RUMBLE STRIPS
			LIN.FT.
201+00	219+75	LT. OF CL CONST.	1500
201+00	222+07	RT. OF CL CONST.	1686
220+41	227+48	LT. OF CL CONST.	566
222+73	225+52	RT. OF CL CONST.	224
226+18	228+39	RT. OF CL CONST.	176
228+14	230+03	LT. OF CL CONST.	152
229+05	231+75	RT. OF CL CONST.	216
230+69	231+75	LT. OF CL CONST.	84
TOTAL			4604

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		27	81
				JOB NO. 080386				

2 QUANTITIES



MAIN LANE BASE AND SURFACING

STATION	STATION	LOCATION	LENGTH FEET	AGGREGATE BASE COURSE (CLASS 7)		TACK COAT				ACHM BINDER COURSE (1")				ACHM SURFACE COURSE (1/2")			
				TON / STATION	TON	TOTAL WID. FEET	SQ.YD.	GALLONS / SQ.YD.	GALLON	AVG. WID. FEET	SQ.YD.	POUND / SQ.YD.	PG (64-22) TON	AVG. WID. FEET	SQ.YD.	POUND / SQ.YD.	PG (64-22) TON
201+00	208+50	WIDENING RT. FOR M.O.T.	750.0		600.0	2.0	166.7	0.03	5.0					13.0	1083.3	440.0	238.3
200+00	201+00	TRANSITION NOTCH & WIDEN MAIN LANES	100.0	15.5	15.5	9.5	105.6	0.03	3.2	5.0	55.6	440.0	12.2	4.5	50.0	220.0	5.5
200+00	201+00	TRANSITION FULL DEPTH LT. SHLDR	100.0	21.9	21.9	8.0	88.9	0.03	2.7	4.0	44.4	440.0	9.8	4.0	44.4	220.0	4.9
200+00	201+00	TRANSITION RT. SHLDR	100.0	37.4	37.4												
200+00	201+00	TRANSITION FINAL LIFT ACHM SURFACE	100.0														
201+00	202+00	NOTCH & WIDEN MAIN LANES	100.0	15.5	15.5	9.5	105.6	0.03	3.2	5.0	55.6	440.0	12.2	32.0	355.6	220.0	39.1
201+00	202+00	FULL WIDTH FULL DEPTH LT. SHLDR	100.0	43.8	43.8	16.0	177.8	0.03	5.3	8.0	88.9	440.0	19.6	4.5	50.0	220.0	5.5
201+00	202+00	FULL WIDTH RT SHOULDER	100.0	74.8	74.8									8.0	88.9	220.0	9.8
201+00	202+00	FINAL LIFT ACHM SURFACE	100.0														
202+00	222+40	FULL DEPTH MAIN LANES	2040.0	93.3	1903.3	49.5	11220.0	0.03	336.6	25.0	5666.7	440.0	1246.7	40.0	444.4	220.0	48.9
202+00	222+40	FULL WIDTH FULL DEPTH LT. SHLDR	2040.0	43.8	893.5	16.0	3626.7	0.03	108.8	8.0	1813.3	440.0	398.9	24.5	5553.3	220.0	610.9
202+00	222+40	FULL WIDTH RT SHOULDER	2040.0	74.8	1525.9									8.0	1813.3	220.0	199.5
202+00	222+40	FINAL LIFT ACHM SURFACE	2040.0														
222+40	225+00	FULL DEPTH MAIN LANES	260.0	50.5	131.3	27.1	782.9	0.03	23.5	13.8	398.7	440.0	87.7	40.0	9066.7	220.0	997.3
222+40	225+00	FULL WIDTH FULL DEPTH LT. SHLDR	260.0	43.8	113.9	16.0	462.2	0.03	13.9	8.0	231.1	440.0	50.8	13.0	375.6	220.0	41.3
222+40	225+00	OVERLAY RT. SHOULDER	260.0			8.0	231.1	0.10	23.1					8.0	231.1	220.0	25.4
225+00	227+50	NOTCH & WIDEN MAIN LANES	250.0	15.5	38.8	9.5	263.9	0.03	7.9	5.0	138.9	440.0	30.6	8.0	231.1	220.0	25.4
225+00	227+50	FULL WIDTH RT & LT. SHOULDERS	250.0	149.5	373.8									4.5	125.0	220.0	13.8
225+00	227+50	FINAL LIFT ACHM SURFACE	250.0														
227+50	231+75	OVERLAY	425.0			40.0	1888.9	0.03	56.7					40.0	1111.1	220.0	122.2
201+00	202+00	LEVELING	100.0			20.0	222.2	0.10	22.2					40.0	1888.9	220.0	207.8
222+40	229+75	LEVELING	735.0			20.0	1455.6	0.10	145.6					20.0	222.2	VAR	24.4
TOTALS					5789.4		20798.1		757.7		8493.2	3960.0	1868.5		24368.2	3740.0	2780.1

BASIS OF ESTIMATE:

ACHM SURFACE COURSE (1/2").....94.5% MIN. AGGR.....5.5% ASPHALT BINDER
 ACHM BINDER COURSE (1").....95.5% MIN. AGGR.....4.5% ASPHALT BINDER
 MAXIMUM NUMBER OF GYRATIONS = 115


11/6/2012

RO80386.DGN

QUANTITIES

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		28	81

2 QUANTITIES



EROSION CONTROL

STATION	STATION	LOCATION	PERMANENT EROSION CONTROL					TEMPORARY EROSION CONTROL								
			SEEDING	LIME	MULCH COVER	SECOND SEEDING APPLICATION	WATER	TEMPORARY SEEDING	MULCH COVER	WATER	SAND BAG DITCH CHECKS	ROCK DITCH CHECKS	SILT FENCE	SEDIMENT BASIN	OBLITERATION OF SEDIMENT BASIN	SEDIMENT REMOVAL AND DISPOSAL
			ACRE	TON	ACRE	ACRE	M.GAL.	ACRE	ACRE	M.GAL.	(E-5) BAG	(E-6) CU.YD.	(E-11) LIN.FT.	(E-14) CU.YD.		
200+00	212+00	STAGE 1 RT & LT. OF CL CONST.						1.00	1.00	20.4	66	7				
ENTIRE PROJECT		STAGE 2 LT. OF CL CONST.	2.00	4.00	2.00	2.00	204.0	1.00	1.00	20.4	110	36	450			
ENTIRE PROJECT		STAGE 3 RT. OF CL CONST.	2.00	4.00	2.00	2.00	204.0				66	38				
*ENTIRE PROJECT TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER								11.00	11.00	224.4				228	228	100
TOTALS			4.00	8.00	4.00	4.00	408.0	13.00	13.00	265.2	242	81	450	228	228	100

BASIS OF ESTIMATE:

LIME2 TONS / ACRE OF SEEDING
 WATER.....102.0 M.G. / ACRE OF SEEDING.
 WATER.....20.4 M.G. / ACRE OF TEMPORARY SEEDING.
 SAND BAG DITCH CHECKS.....22 BAGS / LOCATION

NOTE: THE TEMPORARY EROSION CONTROL DEVICES SHOWN ABOVE AND ON THE PLANS SHALL BE INSTALLED IN SUCH A SEQUENCE AS TO DETER EROSION AND SEDIMENTATION ON U.S. WATERWAYS AS EXPLAINED BY THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT.

*QUANTITY ESTIMATED.
 SEE SECTION 104.03 OF THE STD. SPECS.

COLD MILLING

STATION	STATION	LOCATION	AVG. WIDTH	COLD MILLING ASPHALT PAVEMENT
			FEET	SQ. YD.
200+00	201+00	MAIN LANES	20	222
230+75	231+75	MAIN LANES	20	222
TOTAL				444

ASPHALT CONCRETE PATCHING FOR MAINTENANCE OF TRAFFIC

LOCATION	ASPH. CONC. PATCHING FOR M.O.T.	TACK COAT
	TON	GALLON
ENTIRE PROJECT - TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER	15	30
TOTALS	15	30

NOTE: QUANTITY ESTIMATED.
 SEE SECTION 104.03 OF THE STD. SPECS.

DUMPED RIPRAP AND FILTER BLANKET

STATION	LOCATION	DUMPED RIPRAP	FOUNDATION PROTECTION RIPRAP	FILTER BLANKET
		CU. YDS.	TON	SQ. YDS.
131+38.08	EAST FORK POINT REMOVE CREEK BRIDGE ENDS BR. NO 05586	559	1117	1033
TOTALS:		559	1117	1033

*NOTE: QUANTITIES ARE ESTIMATED.
 SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS

NOTE: FILTER BLANKET SHALL BE GEOTEXTILE FABRIC (TYPE 5).

A.C.H.M. PATCHING OF EXISTING ROADWAY

DESCRIPTION	TON
ENTIRE PROJECT - TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER	30
TOTAL	30

NOTE: QUANTITY ESTIMATED.
 SEE SECTION 104.03 OF THE STD. SPECS.

MAILBOXES

LOCATION	MAILBOXES	MAILBOX SUPPORTS (SINGLE)
	EACH	
ENTIRE PROJECT	1	1
TOTALS	1	1

BENCH MARKS

STATION	DESCRIPTION	BENCH MARKS
		EACH
208+96	RT. SIDE OF R.C. BOX CULVERT	1
TOTAL		1

NOTE: SHOWN FOR INFORMATION ONLY. BENCHMARKS SHALL BE FURNISHED AND PLACED BY STATE FORCES.

QUANTITIES

SUMMARY OF QUANTITIES

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
JOB NO.							080386	29	81

② SUMMARY OF QUANTITIES AND REVISIONS



ITEM NUMBER	ITEM	QUANTITY	UNIT
SP & 201	CLEARING	16	STATION
SP & 201	GRUBBING	16	STATION
202	REMOVAL AND DISPOSAL OF PIPE CULVERTS	5	EACH
210	UNCLASSIFIED EXCAVATION	16649	CU.YD.
210	COMPACTED EMBANKMENT	23536	CU.YD.
SP & 210	SOIL STABILIZATION	200	TON
SS & 303	AGGREGATE BASE COURSE (CLASS 7)	6141	TON
401	TACK COAT	788	GALLON
SP,SS & 406	MINERAL AGGREGATE IN ACHM BINDER COURSE (1")	1785	TON
SP,SS & 406	ASPHALT BINDER (PG 64-22) IN ACHM BINDER COURSE (1")	84	TON
SP,SS & 407	MINERAL AGGREGATE IN ACHM SURFACE COURSE (1/2")	2640	TON
SP,SS & 407	ASPHALT BINDER (PG 64-22) IN ACHM SURFACE COURSE (1/2")	154	TON
412	COLD MILLING ASPHALT PAVEMENT	444	SQ.YD.
SP,SS & 414	ASPHALT CONCRETE PATCHING FOR MAINTENANCE OF TRAFFIC	15	TON
SP,SS & 415	ACHM PATCHING OF EXISTING ROADWAY	30	TON
601	MOBILIZATION	1.00	LUMP SUM
SP & 602	FURNISHING FIELD OFFICE	1	EACH
SS & 603	MAINTENANCE OF TRAFFIC	1.00	LUMP SUM
SS & 604	SIGNS	188	SQ.FT.
SS & 604	BARRICADES	64	LIN.FT.
SS & 604	TRAFFIC DRUMS	45	EACH
SS & 604	FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER	786	LIN.FT.
SS & 604	RELOCATING PRECAST CONCRETE BARRIER	393	LIN.FT.
SS & 604	CONSTRUCTION PAVEMENT MARKINGS	17672	LIN.FT.
604	REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS	375	LIN.FT.
604	REMOVAL OF PERMANENT PAVEMENT MARKINGS	635	LIN.FT.
SS & 604	VERTICAL PANELS	17	EACH
SP,SS & 606	18" SIDE DRAIN	58	LIN.FT.
SP,SS & 606	24" SIDE DRAIN	52	LIN.FT.
SP,SS & 606	36" SIDE DRAIN	88	LIN.FT.
606	SELECTED PIPE BEDDING	20	CU.YD.
619	WIRE FENCE (TYPE D)	692	LIN.FT.
619	16' STEEL GATES (ALTERNATE NO. 1)	1	EACH
619	16' ALUMINUM GATES (ALTERNATE NO. 2)	1	EACH
620	LIME	8	TON
620	SEEDING	4.00	ACRE
620	MULCH COVER	17.00	ACRE
SS & 620	WATER	673.8	M.GAL.
621	TEMPORARY SEEDING	13.00	ACRE
621	SILT FENCE	450	LIN.FT.
621	SAND BAG DITCH CHECKS	242	BAG
621	SEDIMENT BASIN	228	CU.YD.
621	OBLITERATION OF SEDIMENT BASIN	228	CU.YD.
621	SEDIMENT REMOVAL AND DISPOSAL	100	CU.YD.
621	ROCK DITCH CHECKS	81	CU.YD.
623	SECOND SEEDING APPLICATION	4.00	ACRE
624	SOLID SODDING	46	SQ.YD.
635	ROADWAY CONSTRUCTION CONTROL	1.00	LUMP SUM
637	MAILBOXES	1	EACH
637	MAILBOX SUPPORTS (SINGLE)	1	EACH
642	RUMBLE STRIPS IN ASPHALT SHOULDERS	4604	LIN.FT.
SS & 719	THERMOPLASTIC PAVEMENT MARKING WHITE (4")	6350	LIN.FT.
SS & 719	THERMOPLASTIC PAVEMENT MARKING YELLOW (4")	6350	LIN.FT.
SP	TEMPORARY IMPACT ATTENUATION BARRIER	1	EACH
SP	TEMPORARY IMPACT ATTENUATION BARRIER (REPAIR)	1	EACH
STRUCTURES OVER 20' SPAN			
801	UNCLASSIFIED EXCAVATION FOR STRUCTURES-ROADWAY	283	CU. YD.
802	CLASS S CONCRETE-ROADWAY	499.89	CU. YD.
SS & 804	REINFORCING STEEL-ROADWAY (GRADE 60)	72103	POUND
SP & 816	FOUNDATION PROTECTION RIPRAP	1117	TON
816	FILTER BLANKET	1033	SQ. YD.
816	DUMPED RIPRAP	559	CU.YD.

REVISIONS

DATE	REVISION	SHEET NUMBER

SUMMARY OF QUANTITIES AND REVISIONS

* DENOTES ALTERNATE BID ITEM

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	30	81

2 SURVEY CONTROL DETAILS



1-22-12

APPROXIMATE MIDPOINT
 LT: 35-15-39
 LG: 92-43-57

SURVEY CONTROL COORDINATES

Project Name: 080386
 Date: 4/21/2011
 Coordinate System: ARKANSAS STATE PLANE - NORTH ZONE BASED ON GPS CONTROL,
 PROJECTED TO GROUND.
 Units: U.S. SURVEY FOOT

Point Name	Northing	Easting	Elev	Feature	Description
20	333958.1955	1093512.5108	334.906	CTL	2' REBAR & ** ALUM. CAP
21	334807.7227	1093542.3385	317.309	CTL	2' REBAR & ** ALUM. CAP
22	335636.7537	1093571.8841	319.154	CTL	2' REBAR & ** ALUM. CAP
23	336376.3267	1093598.9967	303.939	CTL	2' REBAR & ** ALUM. CAP
24	337069.6771	1093625.5422	302.778	CTL	2' REBAR & ** ALUM. CAP
25	337786.6288	1093654.7798	301.816	CTL	2' REBAR/CAP, 18.5' E CNT LINE HWY 95
26	338425.8250	1093653.6698	308.115	CTL	2' REBAR/CAP, 19' E CNT LINE HWY 95
27	339195.1677	1093687.0227	311.336	CTL	2' REBAR & ** ALUM. CAP
28	339805.3404	1093708.4839	308.270	CTL	2' REBAR & ** ALUM. CAP
29	340537.5879	1093761.3989	340.404	CTL	2' REBAR & ** ALUM. CAP
30	341270.0115	1093742.4158	375.258	CTL	2' REBAR & ** ALUM. CAP
31	341821.7848	1093819.5762	369.586	CTL	2' REBAR & ** ALUM. CAP
102	325375.3403	1093211.0547	349.215	GPS	*AHTD GPS #150008
103	327294.8092	1093231.4665	369.110	GPS	*AHTD GPS #150008A
104	341578.1210	1093015.5366	363.675	GPS	*AHTD GPS #150009
105	341938.2685	1091294.8480	409.609	GPS	*AHTD GPS #150009A
904	324060.4997	1093117.0423	348.088	TBM	*CHSLD SQ SE CORNER OF
905	330671.4189	1093365.4274	373.135	TBM	2' REBAR & ** ALUM. CAP
906	333623.1314	1093470.3624	330.533	TBM	*CHSLD SQ E HEADWALL
920	334694.3122	1093552.9891	319.210	TBM	*CHSLD SQ N END OF HW
921	339203.2022	1093652.8987	312.605	TBM	*BRASS CAP STAMPED WR1 GAGE
922	339485.9942	1093696.4682	312.573	TBM	*CHSLD SQ NE CORNER OF BRIDGE
923	340203.9790	1093685.2246	308.725	TBM	*CHSLD SQ HEAD WALL

*Note - Rebar and Cap - Standard - ** Rebar with 2' Aluminum Cap stamped
 (standard markings common to all caps), or as indicated
 (other markings indicated in the point description of the individual point).
 ALL DISTANCES ARE GROUND.
 USE CAF = 1.0 FOR STAKEOUT FOR THIS PROJECT.
 A PROJECT CAF OF 0.99994324 HAS BEEN USED TO COMPUTE THE ABOVE GROUND COORDINATES.
 THIS CAF IS INTENDED FOR USE WITHIN THE PROJECT LIMITS.
 GRID DISTANCE = GROUND DISTANCE X CAF.
 GRID COORDINATES ARE STORED UNDER FILE NAME: s080386g1.CTL
 HORIZONTAL DATUM: NAD 83 (1997)
 VERTICAL DATUM: NAVD 88 POSITIONAL ACCURACY THIRD ORDER, UNLESS SPECIFIED OTHERWISE
 AT A SPECIFIC POINT.

REFERENCE POINTS (1500 SERIES) ARE TO BE USED TO ESTABLISH CONTROL
 IF THE PRIMARY CONTROL POINTS LISTED ABOVE HAVE BEEN DESTROYED.
 REFERENCE POINTS ARE NOT TO BE USED FOR VERTICAL CONTROL

BASIS OF BEARING:
 ARKANSAS STATE PLANE GRID BEARINGS - 0301-NORTH ZONE
 DETERMINED FROM GPS CONTROL POINTS: 150008 & 150009
 CONVERGENCE ANGLE: 00 25 34.9 LEFT
 GRID AZIMUTH = ASTRONOMICAL AZIMUTH - CONVERGENCE ANGLE.

C.L. HWY. 95 - MAIN LANES

POINT NAME	CENTERLINE STATION	NORTHING	EASTING
8000	200+00.00	336042.18680	1093569.69650
8001	201+11.91	336154.02964	1093573.50305
8002	204+11.98	336543.81462	1082120.97837
8003	207+11.91	336753.94266	1093578.20754
8004	208+54.70	336896.70914	1093575.58917
8005	212+41.55	337106.83718	1105032.81834
8006	216+28.10	337669.87195	1093587.50288
8007	234+65.01	339504.56374	1093677.75774
8008	235+15.01	340067.59851	1082232.44228
8009	235+65.01	339604.46313	1093682.23528
8010	237+95.73	339834.99240	1093691.56001
8011	238+66.90	339371.85702	1105141.35300
8012	239+38.07	339977.18220	1093698.19630
8013	242+18.40	340257.12149	1093713.00465
8014	244+73.39	340511.78670	1093725.70163
8015	249+50.00	340987.72812	1093751.02457
8026	231+75.00	339214.90413	1093663.50838

C.L. DETOUR


POINT NAME	CENTERLINE STATION	NORTHING	EASTING
8000	300+00.00	336042.18680	1093569.69650
8016	300+39.22	336081.38008	1093571.03044
8017	301+11.91	336042.40158	1094716.28291
8018	301+84.40	336225.78440	1093585.13602
8019	301+84.41	336225.79125	1093585.13713
8020	302+64.23	336409.17407	1092453.99024
8021	303+43.79	336384.37798	1093599.63752
8022	303+85.40	336425.97624	1093600.53786
8023	304+84.96	336591.28351	1085962.88932
8024	305+84.51	336625.07759	1093602.25184
8025	308+32.68	336873.24076	1093601.15405

11/6/2012

RO80386.DGN



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		31	81

2 SURVEY CONTROL DETAILS





STA. 200+00.00
 BEGIN JOB 080386
 BEGIN WIDENING
 LOG MILE 7.25

DETOUR P.I. 302+64.23 $\Delta = 7^{\circ}58'07.8''$ LT. D = 5'00'00" T = 79.82' L = 159.38' P.C. 301+84.41 P.T. 303+43.79	DETOUR P.I. 204+11.98 $\Delta = 3^{\circ}00'00''$ LT. D = 0'30'00" T = 300.07' L = 600.00' P.C. 201+11.91 P.T. 207+11.91	DETOUR P.I. 304+84.96 $\Delta = 1^{\circ}29'36.1''$ LT. D = 0'45'00" T = 99.56' L = 199.11' P.C. 303+85.40 P.T. 305+84.51
--	---	--



DETOUR
 P.I. 301+11.91
 $\Delta = 7^{\circ}15'34.0''$ RT.
 D = 5'00'00"
 T = 72.69'
 L = 145.19'
 P.C. 300+39.22
 P.T. 301+84.40



P.I. 212+41.55
 $\Delta = 3^{\circ}52'01.2''$ RT.
 D = 0'30'00"
 T = 386.85'
 L = 773.40'
 P.C. 208+54.70
 P.T. 216+28.10

SURVEY CONTROL DETAILS

11/6/2012

R080386.DGN





DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							32	81

P.I. 235+15.01
 $\Delta = 0^{\circ}30'00''$ LT.
 $D = 0^{\circ}30'00''$
 $T = 50.00'$
 $L = 100.00'$
P.C. 234+65.01
P.T. 235+65.01

2 SURVEY CONTROL DETAILS



1-23-13



SURVEY CONTROL DETAILS

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		33	81

2 PLAN AND PROFILE SHEETS




STA. 200+00.00
 BEGIN JOB 080386
 BEGIN WIDENING
 LOG MILE 7.25

DETOUR 16
 P.I. 302+64.23
 $\Delta = 7^{\circ}58'07.8''$ LT.
 $D = 5^{\circ}00'00''$
 $T = 79.82'$
 $L = 159.38'$
 P.C. 301+84.41
 P.T. 303+43.79
 $e = NC$

P.I. 204+11.98
 $\Delta = 3^{\circ}00'00''$ LT.
 $D = 0^{\circ}30'00''$
 $T = 300.07'$
 $L = 600.00'$
 P.C. 201+11.91
 P.T. 207+11.91
 $e = NC$

DETOUR 17
 P.I. 304+84.96
 $\Delta = 1^{\circ}29'36.1''$ LT.
 $D = 0^{\circ}45'00''$
 $T = 99.56'$
 $L = 199.11'$
 P.C. 303+85.40
 P.T. 305+84.51
 $e = NC$




DETOUR 15
 P.I. 301+11.91
 $\Delta = 7^{\circ}15'34.0''$ RT.
 $D = 5^{\circ}00'00''$
 $T = 72.69'$
 $L = 145.19'$
 P.C. 300+39.22
 P.T. 301+84.40
 $e = NC$

WIRE FENCE (TYPE D)

STA.	STA.	SIDE	LENGTH
201+41	206+46	RT.	495 LIN. FT.
206+46	208+43	RT.	197 LIN. FT.

STA. 208+96 - IN PLACE
 DBL. 54' X 51' C.M. PIPE CULV'T
 REMOVE AND CONSTRUCT
 SEXT. 11' X 6' X 74' R.C. BOX CULV'T.
 WITH 3:1 WINGS LT. & RT.
 $Q25 = 3400$ cfs; D.A. = N/A





11/6/2012
 R080386.DGN

STA. 220+08 - IN PLACE
 24" X 48" C.M. PIPE
 LT. SIDE DRAIN
 REMOVE AND INSTALL
 24" X 50" PIPE CULVERT
 LT. SIDE DRAIN
 CONSTRUCT APPROACH = 225 CU. YD.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		34	81
JOB NO. 080386								


2 PLAN AND PROFILE SHEETS

GATES
 STA. 220+08 LT. 16' GATES
 1 EACH



P.I. 212+41.55
 $\Delta = 3^{\circ}52'01.2''$ RT.
 $D = 0^{\circ}30'00''$
 $T = 386.85'$
 $L = 773.40'$
 $P.C. 208+54.70$
 $P.T. 216+28.10$
 $e = NC$

STA. 222+40 - IN PLACE
 12" X 24" C.M. PIPE
 RT. SIDE DRAIN
 REMOVE AND INSTALL
 18" X 44" PIPE CULVERT
 RT. SIDE DRAIN
 CONSTRUCT APPROACH = 125 CU. YD.



11/6/2012
 RO80386.DGN

STA. 227+81 - IN PLACE
36" X 40" C.M. PIPE
LT. SIDE DRAIN
RETAIN




STA. 230+36
CONSTRUCT APPROACH ON LT.

STA. 231+75.33
END JOB 080386
END OVERLAY
LOG MILE 7.85

P.I. 235+15.01
 $\Delta = 0^{\circ}30'00''$ LT.
 $D = 0^{\circ}30'00''$
 $T = 50.00'$
 $L = 100.00'$
P.C. 234+65.01
P.T. 235+65.01
 $e = NC$

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		35	81
				JOB NO. 080386				

2 PLAN AND PROFILE SHEETS



11/6/2012 RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386	36	81	
				05586	SCOUR PREVENTION	51992		

GENERAL NOTES

BENCH MARK: CHSLD SO NE Corner of Bridge, 19.60' Rt. of Sta. 234+47.38, Elevation = 312.57.

CONSTRUCTION SPECIFICATIONS: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2003 edition) with applicable supplemental specifications and special provisions. Section and subsection refer to the Standard Construction Specifications unless otherwise noted in the Plans.

The proposed work consists of placing Dumped Riprap with Filter Blanket on the embankment slopes at Bent Nos. 1 and 4 as shown. Additionally, the channel shall be excavated between Bent Nos. 2 and 3 and backfilled with Foundation Protection Riprap. Care shall be taken to avoid damaging the bridge during excavation and placement of the riprap under the spans and around the bents. The Foundation Protection Riprap may be placed underwater in a manner that maintains the required gradation. The Engineer shall take soundings before and after placement of the riprap to determine thickness and distribution.

Excavated material shall be hauled away and disposed of by the Contractor. See Section 210. All excavation shall be paid for as "Unclassified Excavation".

Drift and debris in the channel and on the slopes that interferes with the work shall be removed and disposed of prior to placement of the riprap. Payment for drift and debris removal will not be made directly, but shall be considered subsidiary to the other items. Securing disposal sites for drift and debris shall be the responsibility of the Contractor.

Previous foundations maybe encountered during the work and may remain in place.

TABLE OF BRIDGE QUANTITIES

LOCATION	UNIT			
	CU. YD.	TON	CU. YD.	SQ. YD.
BENT 1	318		318	592
BENTS 2 AND 3	798	1117		
BENT 4	241		241	441
TOTALS	1357	1117	559	1033

HYDRAULIC DATA



FLOOD DESCRIPTION	FREQUENCY YEARS	DISCHARGE CFS	WATER SURFACE ELEV. UNDER EXISTING CONDITIONS FEET	WATER SURFACE ELEV. WITH GRADE IMPVTS. FEET
Design	25	25,220	305.4	306.4
Base	100	35,620	306.6	307.6
Extreme	500	49,740	308.1	308.8
Overtopping	35	25,300	-	306.4

Existing Low Bridge Chord Elev. = 309.0
Drainage area = 122.0 square miles

**SCOUR PREVENTION DETAILS
EAST FORK POINT REMOVE CREEK-
NORTH & SOUTH GRADE IMPVTS. (S)
CONWAY COUNTY**

ROUTE 95 SEC. 1
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: PGT DATE: 2-12 FILENAME: b080386.br .dgn
CHECKED BY: AMS DATE: 5-17-12 SCALE: 1" = 20' or As Noted
DESIGNED BY: PGT DATE: 2-12
BRIDGE NO. 05586 DRAWING NO. 51992




Note: Place Dumped Riprap 1'-6" thick on Filter Blanket as shown. Top of Riprap Elev. 308.0 (typ. both ends of bridge). For Details, see Std. Drwg. No. 1891F.

- BORING LEGEND**
- AI-Wet, Medium Stiff, Gray and Brown Sandy Clay
 - BI-Wet, Very Loose, Gray Clayey Sand
 - CI-Wet, Stiff, Gray Sandy Clay with Organic Matter (Wood)
 - DI-SHALE - Dark Gray, Weathered, Medium Hard
 - EI-SHALE WITH WEATHERED SHALE AND SANDSTONE SEAMS - Dark Gray, Laminated, Medium Hard, with Slight Dip
 - FI-SANDSTONE WITH SHALE PARTINGS - Gray, Medium Bedded, Slightly Weathered, Cemented, with Slight Dip
 - GI-SANDSTONE WITH SHALE PARTINGS - Gray, Thick Bedded, Slightly Weathered, Cemented, with Slight Dip
 - HI-Moist, Stiff, Brown and Gray Sandy Clay with Concrete Rubble
 - JL-Moist, Medium Stiff, Brown Clay with Hard, Organic Matter (Wood)
 - KI-Wet, Medium Stiff, Gray Clay with Organic Matter (Wood)
 - LI-Wet, Medium Stiff, Gray Clay with Organic Matter (Wood) and some Gravel
 - MI-SANDSTONE - Gray, Poorly-Cemented
 - NI-SANDSTONE - Gray, Cemented
 - PI-Wet, Very Loose, Brown Clayey Sand
 - OI-Wet, Medium Stiff, Brown Sandy Clay
 - RI-Moist to Wet, Medium Stiff, Brown Sandy Clay (Sandstone Fragments)
 - SI-Wet, Very Stiff, Brown Sandy Clay with Gravel (Sandstone Fragments)
 - TI-Moist, Soft, Brown Sandy Clay
 - UI-Wet, Very Loose, Gray and Brown Clayey Sand
 - VI-Wet, Very Stiff, Brown Sandy Clay with Gravel (Sandstone Fragments) and Cobbles
 - WI-Wet, Hard, Brown Sandy Clay with Gravel (Sandstone Fragments) and Cobbles


"N" VALUES

Station	Left of C.L. of Constr.	Right of C.L. of Constr.
Sta. 232+29	5.1 - 6.1, N=5	4.8 - 5.8, N=12
Sta. 232+45	10.1 - 11.1, N=0	9.8 - 10.4, N=92(7')
Sta. 233+50	15.1 - 16.1, N=1	14.8 - 15.8, N=8
Sta. 233+71	20.1 - 21.1, N=9	19.8 - 20.8, N=8
Sta. 233+71	25.1 - 25.1, N=60(6')	24.3 - 24.6, N=60(4')



PLAN

ELEVATION



Note: Top of Dumped Riprap shall be flush with surface of existing slope (typ.)

Bottom of riprap @ Elev. 281.0 or lower to provide min. thickness of 2'-6".

Excavate channel as shown











Foundation Protection Riprap from face of column to face of column

Construct 5' x 5' toewall along full length of riprap, this side only.

Foundation Protection Riprap, Top of Riprap Shall be flush with existing channel bottom (See Job Special Provision)

BRIDGE ENGINEER

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
04-10-2003				6	ARK.		37	
JOB NO.							1891F	



NOTE: USE THIS TYPE OF TOE WHEN ROCK IS ENCOUNTERED WHICH IS IN A STABLE CONDITION.

NOTE: IN LIEU OF AN AGGREGATE FILTER BLANKET, A SYNTHETIC FIBER GEOTEXTILE FABRIC COMPLYING WITH THE REQUIREMENTS OF SUBSECTION 816.02(e) MAY BE USED.

NOTE: DETAILS FOR COMPUTING EXCAVATION FOR STRUCTURES ARE INCLUDED FOR INFORMATION AS TO HOW PLAN QUANTITIES WERE CALCULATED AND FOR USE WHEN ADJUSTING QUANTITIES WHEN CHANGING FOOTING ELEVATION.

DETAIL C

EXCAVATED CHANNEL WIDTH

RIPRAP AREA

EXCAVATED CHANNEL


Revised and redrawn MJT 04-10-2003
Chk'd. By: CJF 04-10-2003

DETAILS FOR DUMPED RIPRAP AND FILTER BLANKET AND DETAILS FOR COMPUTING EXCAVATION FOR STRUCTURES


ROUTE SEC.
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: MJT DATE: 04-10-2003 FILENAME: B1891F.STD
CHECKED BY: CJF DATE: 04-10-2003 SCALE: NO SCALE
DESIGNED BY: STD. DATE: BRIDGE NO. DRAWING NO. 1891F


STATE OF ARKANSAS
REGISTERED PROFESSIONAL ENGINEER
No. 4337
CHARLES P. BRAND
BRIDGE ENGINEER




SHELF



PLATFORM




SINGLE INSTALLATION




BRACKET


- GENERAL NOTES**
1. MAILBOX POSTS MAY BE WOOD OR METAL. WOOD POSTS SHALL BE PRESSURE TREATED FOR GROUND CONTACT IN ACCORDANCE WITH SECTION 637.02 OF THE STANDARD SPECIFICATIONS.
 2. ANTI-TWIST PLATES SHALL BE USED ONLY ON METAL POSTS.
 3. MAILBOX SHELF, BRACKET & PLATFORM SHALL BE GALVANIZED OR PAINTED STEEL, HOWEVER TREATED WOOD MAY BE USED WITH WOODEN POSTS. THE WOODEN SHELF, BRACKET & PLATFORM SHALL BE A MINIMUM OF 3/4" THICK AND SHALL BE ASSEMBLED WITH BOLTS OF THE APPROPRIATE LENGTH WITH SIX 8 X 3/4" FLATHEAD WOOD SCREWS USED TO ATTACH THE MAILBOX TO THE PLATFORM.
 4. THE MAILBOX SHELF AND PLATFORM THAT IS SHOWN IS FOR STANDARD SIZE MAILBOXES. THE SHELF AND PLATFORM SIZE SHALL BE MODIFIED TO FIT MAILBOXES OF A DIFFERENT SIZE.
 5. METAL PIPE FOR MAILBOX SUPPORT SHALL BE 2" OUTSIDE DIAMETER STEEL WITH A WALL THICKNESS OF 0.145" AND A WEIGHT OF 2.72 LBS PER FT. OUTSIDE DIAMETER AND WEIGHT SHALL HAVE A TOLERANCE OF +/- 5% ACCORDING TO AASHTO M 181.
 6. MAILBOX SUPPORT SYSTEM DIFFERING FROM THOSE SHOWN MAY BE USED, PROVIDED THEY ARE ON THE AHTD QUALIFIED PRODUCTS LIST FOR MAILBOX SUPPORTS.




DOUBLE INSTALLATION




ANTI-TWIST PLATE



CLAMP



SPACER




SPACING FOR MULTIPLE POST INSTALLATION

11-18-04	REVISED NOTES
10-9-03	REVISED NOTE 6
8-22-02	REVISED NOTE 6
10-18-96	CORRECTED AASHTO
10-1-92	CORRECTED SPELLING
9-26-91	NEW PHONE NUMBER
8-15-91	ADDED NOTE
11-30-89	ADJUSTED HEIGHT & ADDED NOTE
2-16-89	DELETED SLOTS FROM SHELF & PLTF
11-17-88	ADJUSTED DIMENSIONS OF STEEL POSTS
7-15-88	ISSUED
DATE	FILMED
	REVISION

ARKANSAS STATE HIGHWAY COMMISSION

MAILBOX DETAILS
STANDARD DRAWING MB-1



BAR LIST

BAR	NO.	SIZE	LENGTH	BAR BENDING DIAGRAM
H	2	#4	.	
I	.	#4	.	
J	.	#4	1'-5"	
L	.	#4	3'-2"	
M	.	#4	1'-8"	

NOTE: LENGTH AND NUMBER OF BARS VARIES WITH SIZE OF CULVERT

GENERAL NOTES

WINGS, CURTAIN WALLS AND APRONS SHALL BE TIED TO THE PRECAST CULVERT SECTION BY CASTING BARS IN CULVERT END SECTIONS AS SHOWN OR BY DOWELING AND GROUTING. J BARS AND M BARS SHALL BE EMBEDDED A MINIMUM OF 10" IN PRECAST BOX.

WINGS, FOOTINGS, APRONS AND CURTAIN WALLS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE APPLICABLE WING DRAWING, STEEL AND CONCRETE QUANTITIES WILL BE ADJUSTED TO FIT THE IN-PLACE WIDTH & HEIGHT OF THE PRECAST CONCRETE BOX CULVERTS.

ALL EXPOSED CORNERS TO HAVE 3/4" CHAMFERS.

WINGWALLS AND FOOTINGS MAY BE ADJUSTED IN THE FIELD AS DIRECTED BY THE ENGINEER.

ALL CONCRETE, REINFORCING STEEL, LEAN GROUT, MEMBRANE WATERPROOFING, DRAINAGE FILL MATERIAL, GEOTEXTILE FILTER FABRIC, LABOR, MATERIALS AND EQUIPMENT REQUIRED FOR INSTALLING PRECAST BOX CULVERTS WILL NOT BE PAID FOR DIRECTLY BUT WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID FOR THE ITEMS AS SPECIFIED IN SECTION 607 OF THE STANDARD SPECIFICATIONS.

LEAN GROUT SHALL CONSIST OF A SAND CEMENT MIXTURE MEETING THE FOLLOWING REQUIREMENTS:
 PORTLAND CEMENT SHALL BE TYPE I AND SHALL MEET THE REQUIREMENTS OF AASHTO M 85.

SAND SHALL MEET THE REQUIREMENTS OF FINE AGGREGATE AS SPECIFIED IN SECTION 802.02 OF THE STANDARD SPECIFICATIONS. THE SAND CEMENT MIXTURE SHALL CONSIST OF NOT LESS THAN 1.5 SACKS OF PORTLAND CEMENT PER TON OF MATERIAL MIXTURE. THE MIXTURE SHALL CONTAIN SUFFICIENT WATER TO HYDRATE THE CEMENTS. THE SAND CEMENT MIXTURE SHALL BE PLACED IN MAXIMUM 8 INCH THICK LIFTS, LOOSE MEASURE, AND THOROUGHLY RODDED AND TAMPED AROUND BOX TO THOROUGHLY FILL ALL VOIDS.

MEMBRANE WATERPROOFING CONFORMING TO THE REQUIREMENTS OF SECTION 815 OF THE STANDARD SPECIFICATIONS SHALL BE APPLIED TO ALL BOX CULVERT JOINTS.



THE MEMBRANE WATERPROOFING WILL BE REQUIRED ON THE TOP EXTERNAL JOINT AND SHALL EXTEND 1 FOOT DOWN THE SIDES OF THE CULVERT.

IN OUTER BARRELS, ONE WEEP HOLE IS REQUIRED IN EXTERIOR WALLS OF EACH PRECAST CULVERT SECTION. WEEP HOLES SHALL HAVE A MAXIMUM HORIZONTAL SPACING OF 10'-0" IN THE ASSEMBLED CULVERT AND SHALL BE SPACED TO CLEAR ALL REINFORCING STEEL. THE DRAIN OPENING SHALL BE 4" DIAMETER AND SHALL BE PLACED 12" ABOVE THE TOP OF THE BOTTOM SLAB.

DRAINAGE FILL MATERIAL WITH GEOTEXTILE FABRIC IS REQUIRED AT THE EXTERIOR WALLS OF THE ASSEMBLED CULVERT, SEE DETAILS ON THIS DRAWING.

MINIMUM WIDTH SHALL BE 12" (6" ON EACH SIDE OF JOINT). ON MULTIPLE BARREL CULVERTS, MEMBRANE WATERPROOFING SHALL BE APPLIED TO EACH BARREL AS DESCRIBED ABOVE.

WITH THE APPROVAL OF THE ENGINEER, THE CONTRACTOR WILL BE ALLOWED TO SUBSTITUTE, AT NO ADDITIONAL COST TO THE DEPARTMENT, FLOWABLE SELECT MATERIAL CONFORMING TO SECTION 206 OF THE STANDARD SPECIFICATIONS IN LIEU OF LEAN GROUT.



DATE	ISSUED BY	REVISION	DATE FILMED
12-15-11		ADDED NOTE & DTLS FOR WEEP HOLE AND DRAINAGE FILL	
10-15-09		ADDED GENERAL NOTE	
11-10-05		REVISED SPACING OF "M" BARS	
4-10-03		REVISED GENERAL NOTES	
10-18-96		CORRECTED AASHTO REF.	
10-1-92		ADDED NOTE FOR MEMBRANE WATERPROOFING	
8-15-91		ADDED NOTE FOR LEAN GROUT	
11-8-90		REVISED FOR 1991 SPECS	
11-30-89		ISSUED; JABE	

ARKANSAS STATE HIGHWAY COMMISSION

PRECAST CONCRETE BOX CULVERTS

STANDARD DRAWING PBC-1

REINFORCED CONCRETE ARCH PIPE DIMENSIONS

EQUIV. DIA. INCHES	SPAN INCHES		RISE INCHES	
	AASHTO M 206	AHTD NOMINAL	AASHTO M 206	AHTD NOMINAL
15	18	18	11	11
18	22	22	13 1/2	14
21	26	26	15 1/2	16
24	28 1/2	29	18	18
30	36 1/4	36	22 1/2	23
36	43 3/8	44	26 3/8	27
42	51 1/8	51	31 1/16	31
48	58 1/2	59	36	36
54	65	65	40	40
60	73	73	45	45
72	88	88	54	54
84	102	102	62	62
90	115	115	72	72
96	122	122	77 1/2	77
108	138	138	87 1/8	87
120	154	154	96 1/8	97
132	168 3/4	169	106 1/2	107

THE MEASURED SPAN AND RISE SHALL NOT VARY MORE THAN ± 2 PERCENT FROM THE VALUES SPECIFIED BY AASHTO M206.

REINFORCED CONCRETE HORIZONTAL ELLIPTICAL PIPE DIMENSIONS

EQUIV. DIA. INCHES	AASHTO M 207 INCHES	
	SPAN	RISE
18	23	14
24	30	19
27	34	22
30	38	24
33	42	27
36	45	29
39	49	32
42	53	34
48	60	38
54	68	43
60	76	48
66	83	53
72	91	58
78	98	63
84	106	68

THE MEASURED SPAN AND RISE SHALL NOT VARY MORE THAN ± 2 PERCENT FROM THE VALUES SPECIFIED BY AASHTO M207.

CONSTRUCTION SEQUENCE

1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. PLACE AND COMPACT THE HAUNCH AREA UP TO THE MIDDLE OF THE PIPE.
5. COMPLETE BACKFILL ACCORDING TO SUBSECTION 606.03.(f)(ii).


NOTE: HAUNCH AND STRUCTURAL BEDDING MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF CONCRETE PIPE.

- LEGEND -

- D_i = NORMAL INSIDE DIAMETER OF PIPE
- D_o = OUTSIDE DIAMETER OF PIPE
- H = FILL COVER HEIGHT OVER PIPE (FEET)
- MIN. = MINIMUM
- [Hatched Pattern] = UNDISTURBED SOIL

INSTALLATION TYPE	MATERIAL REQUIREMENTS FOR HAUNCH AND STRUCTURAL BEDDING
TYPE 1	AGGREGATE BASE COURSE (CLASS 5 OR CLASS 7)
TYPE 2	SELECTED MATERIALS (CLASS SM-1, SM-2, OR SM-4) OR TYPE 1 INSTALLATION MATERIAL*
TYPE 3**	AASHTO CLASSIFICATION A-1 THRU A-6 SOIL OR TYPE 1 OR 2 INSTALLATION MATERIAL

- * SM-3 WILL NOT BE ALLOWED.
- ** MATERIALS SHALL NOT INCLUDE ORGANIC MATERIALS OR STONES LARGER THAN 3 INCHES.



EMBANKMENT AND TRENCH INSTALLATIONS

1. MATERIAL IN THE HAUNCH AND OUTER STRUCTURAL BEDDING SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.
2. FOR TRENCHES WITH WALLS OF NATURAL SOIL, THE DENSITY OF THE SOIL IN THE LOWER SIDE ZONE SHALL BE AS FIRM AS THE 95% DENSITY REQUIRED FOR THE HAUNCH. IF THE EXISTING SOIL DOES NOT MEET THIS CRITERIA, IT SHALL BE REMOVED AND RECOMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OF MATERIAL USED.
3. FOR EMBANKMENTS, THE MATERIAL IN THE LOWER SIDE ZONE SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.

GENERAL NOTES

1. CONCRETE PIPE CULVERT CONSTRUCTION SHALL CONFORM TO ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2003 EDITION), WITH APPLICABLE SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS. UNLESS OTHERWISE NOTED IN THE PLANS, SECTION AND SUBSECTION REFER TO THE STANDARD CONSTRUCTION SPECIFICATIONS.
2. CONCRETE PIPE CULVERT DESIGN SHALL CONFORM TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, FIFTH EDITION (2010) WITH 2010 INTERIMS.
3. ALL PIPE SHALL CONFORM TO SECTION 606. CIRCULAR R.C. PIPE CULVERTS SHALL CONFORM TO AASHTO M170, R.C. ARCH PIPE CULVERTS SHALL CONFORM TO AASHTO M206 AND HORIZONTAL ELLIPTICAL PIPE CULVERTS SHALL CONFORM TO AASHTO M207.
4. ALL PIPE SHALL BE PROTECTED DURING CONSTRUCTION BY A COVER SUFFICIENT TO PREVENT DAMAGE FROM PASSAGE OF EQUIPMENT.
5. THE MINIMUM TRENCH WIDTH SHALL BE THE OUTSIDE DIAMETER OF THE PIPE PLUS 24 INCHES. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PRACTICABLE FOR WORKING CONDITIONS.
6. MULTIPLE PIPE CULVERTS SHALL BE INSTALLED WITH A MINIMUM CLEARANCE OF 24 INCHES BETWEEN STRINGS OF PIPE. REFER TO STD. DWG. FES-2 FOR MINIMUM CLEARANCE WHERE FLARED END SECTIONS ARE USED.
7. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
8. NOT MORE THAN ONE LIFTING HOLE MAY BE PROVIDED IN CONCRETE PIPE TO FACILITATE HANDLING. HOLE MAY BE CAST IN PLACE, CUT INTO THE FRESH CONCRETE AFTER FORMS ARE REMOVED, OR DRILLED. THE HOLE SHALL NOT BE MORE THAN TWO INCHES IN DIAMETER OR TWO INCHES SQUARE. CUTTING OR DISPLACEMENT OF REINFORCEMENT WILL NOT BE PERMITTED. SPALLED AREAS AROUND THE HOLE SHALL BE REPAIRED IN A WORKMANLIKE MANNER. LIFTING HOLE SHALL BE FILLED WITH MORTAR, CONCRETE, OR OTHER METHOD AS APPROVED BY THE ENGINEER.
9. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS "STRUCTURAL BEDDING" ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS "SELECTED PIPE BEDDING."
10. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED ABOVE AS THE HAUNCH), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF "SELECTED PIPE BACKFILL."

MINIMUM HEIGHT OF FILL "H" OVER CIRCULAR R.C. PIPE CULVERTS

PIPE ID (IN.)	CLASS OF PIPE			
	CLASS III		CLASS IV	CLASS V
INSTALLATION TYPE	TYPE 1 OR 2	TYPE 3	ALL	ALL
12-15	2	2.5	2	1
18-24	2.5	3	2	1
27-33	3	4	2	1
36-42	3.5	5	2	1
48	4.5	5.5	2	1
54-60	5	7	2	1
66-78	6	8	2	1
84-108	7.5	8	2	1

NOTE: FOR MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM OF 12" OF PAVEMENT AND/OR BASE.

MAXIMUM HEIGHT OF FILL "H" OVER CIRCULAR R.C. PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE		
	CLASS III	CLASS IV	CLASS V
TYPE 1	21	32	50
TYPE 2	16	25	39
TYPE 3	12	20	30

NOTE: IF FILL HEIGHT EXCEEDS 50 FEET, A SPECIAL DESIGN CONCRETE PIPE WILL BE REQUIRED USING TYPE 1 INSTALLATION.

MINIMUM HEIGHT OF FILL "H" OVER R.C. ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE	
	CLASS III	CLASS IV
TYPE 2 OR TYPE 3	2.5	1.5

NOTE: TYPE 1 INSTALLATION WILL NOT BE ALLOWED FOR ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS.

NOTE: FOR MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM OF 12" OF PAVEMENT AND/OR BASE.

MAXIMUM HEIGHT OF FILL "H" OVER R.C. ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE	
	CLASS III	CLASS IV
TYPE 2	13	21
TYPE 3	10	16

NOTE: TYPE 1 INSTALLATION WILL NOT BE ALLOWED FOR ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS.

DATE	REVISION	DATE FILMED
12-15-11	REVISED FOR LRFD DESIGN SPECIFICATIONS	
5-18-00	REVISED TYPE 3 BEDDING & ADDED NOTE	
3-30-00	REVISED INSTALLATIONS	
11-06-97	ISSUED	

ARKANSAS STATE HIGHWAY COMMISSION

CONCRETE PIPE CULVERT FILL HEIGHTS & BEDDING

STANDARD DRAWING PCC-1



CORRUGATED STEEL PIPE (ROUND)

PIPE DIAMETER (INCHES)	① MINIMUM COVER TOP OF PIPE TO TOP OF GROUND "H" (FEET)	MAX. FILL HEIGHT "H" ABOVE TOP OF PIPE (FEET)				
		METAL THICKNESS (INCHES)				
		0.064	0.079	0.109	0.138	0.168
2 3/4 INCH BY 1/2 INCH CORRUGATION RIVETED, WELDED, OR HELICAL LOCK-SEAM						
12	1	84	91			
15	1	67	73			
18	1	56	61			
24	1	42	46	59		
30	2	34	36	47		
36	2		30	39	41	
42	2		43	67	70	73
48	2		37	58	61	64
② 3 INCH BY 1 INCH OR 5 INCH BY 1 INCH CORRUGATION RIVETED, WELDED, BOLTED, OR HELICAL LOCK-SEAM						
36	1	48	60	88	111	118
42	1	41	51	72	90	102
48	1	36	45	64	77	85
54	2	32	40	59	71	79
60	2	29	36	53	64	71
66	2	26	33	47	58	64
72	2	24	30	44	53	59
78	2		28	41	49	54
84	2		26	38	45	51
90	2		24	35	43	45
96	2		22	33	40	44
102	2			31	38	42
108	2			30	35	39
114	2			28	34	37
120	2			27	32	35

CONSTRUCTION SEQUENCE


1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. COMPLETE STRUCTURAL BACKFILL OPERATION BY WORKING FROM SIDE TO SIDE OF THE PIPE. THE SIDE TO SIDE STRUCTURAL BACKFILL DIFFERENTIAL SHALL NOT EXCEED 24 INCHES OR 1/3 THE SIZE OF THE PIPE, WHICHEVER IS LESS.

NOTE: STRUCTURAL BACKFILL AND STRUCTURAL BEDDING MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF METAL PIPE.

INSTALLATION TYPE	MATERIAL REQUIREMENTS FOR STRUCTURAL BACKFILL AND STRUCTURAL BEDDING
TYPE 1	AGGREGATE BASE COURSE (CLASS 4, 5, 6, OR 7)
TYPE 2	SELECTED MATERIALS (CLASS SM-1, SM-2, OR SM-4) OR TYPE 1 INSTALLATION MATERIAL ③

③ SM-3 WILL NOT BE ALLOWED.

- LEGEND -
- D_o = OUTSIDE DIAMETER OF PIPE
 - MAX. = MAXIMUM
 - MIN. = MINIMUM
 - ==== = STRUCTURAL BACKFILL MATERIAL
 - ===== = UNDISTURBED SOIL
 - EQUIV. DIA. = EQUIVALENT DIAMETER
 - H = FILL COVER HEIGHT OVER PIPE (FEET)



EMBANKMENT AND TRENCH INSTALLATIONS

1. STRUCTURAL BACKFILL, EMBANKMENT, AND OUTER STRUCTURAL BEDDING MATERIAL SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.
2. INSTALLATION TYPE 1 OR 2 MAY BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE (ROUND).
3. INSTALLATION TYPE 1 SHALL BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE ARCHES WITH 2 3/4" X 1/2" CORRUGATION.
4. INSTALLATION TYPE 1 OR 2 MAY BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE ARCHES WITH 3" X 1" OR 5" X 1" CORRUGATION.

GENERAL NOTES

1. METAL PIPE CULVERT CONSTRUCTION SHALL CONFORM TO ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2003 EDITION), WITH APPLICABLE SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS. UNLESS OTHERWISE NOTED IN THE PLANS, SECTION AND SUBSECTION REFER TO THE STANDARD CONSTRUCTION SPECIFICATIONS.
2. METAL PIPE CULVERT DESIGN SHALL CONFORM TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, FIFTH EDITION (2010) WITH 2010 INTERIMS.
3. METAL PIPE CULVERT MATERIALS AND INSTALLATIONS SHALL CONFORM TO SECTION 606 AND JOB SPECIAL PROVISION "METAL PIPE".
4. ALL PIPE SHALL BE PROTECTED DURING CONSTRUCTION BY A COVER SUFFICIENT TO PREVENT DAMAGE FROM PASSAGE OF EQUIPMENT.
5. THE MINIMUM TRENCH WIDTH SHALL BE THE OUTSIDE DIAMETER OF THE PIPE PLUS 24 INCHES. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PRACTICABLE FOR WORKING CONDITIONS.
6. MULTIPLE PIPE CULVERTS SHALL BE INSTALLED WITH A MINIMUM CLEARANCE OF 24 INCHES BETWEEN STRINGS OF PIPE. REFER TO STD. DWG. FES-2 FOR MINIMUM CLEARANCE WHERE FLARED END SECTIONS ARE USED.
7. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
8. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS "STRUCTURAL BEDDING" ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS "SELECTED PIPE BEDDING."
9. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED AS STRUCTURAL BACKFILL), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF "SELECTED PIPE BACKFILL."

CORRUGATED ALUMINUM PIPE (ROUND)

PIPE DIAMETER (INCHES)	① MINIMUM COVER TOP OF PIPE TO TOP OF GROUND "H" (FEET)	MAX. FILL HEIGHT "H" ABOVE TOP OF PIPE (FEET)				
		METAL THICKNESS IN INCHES				
		0.060	0.075	0.105	0.135	0.164
2 3/4 INCH BY 1/2 INCH CORRUGATION RIVETED OR HELICAL LOCK-SEAM						
12	1	45	45	52		
18	2	30	30	39		
24	2	22	22	31	41	34
30	2		18	31	32	34
36	2.5		15	26	27	28
42	2			43	43	44
48	2			40	41	43
54	2			35	37	38
60	2				33	34
66	2					31
72	2					29

EQUIVALENT METAL THICKNESSES AND GAUGES

METAL THICKNESS IN INCHES			GAUGE NUMBER	
STEEL				
ZINC COATED	UNCOATED	ALUMINUM		
0.064	0.0598	0.060		16
0.079	0.0747	0.075		14
0.109	0.1046	0.105		12
0.138	0.1345	0.135		10
0.168	0.1644	0.164		8

CORRUGATED METAL PIPE ARCHES

EQUIV. DIA. (INCHES)	PIPE DIMENSION SPAN X RISE (INCHES)	MINIMUM CORNER RADIUS (INCHES)	STEEL				ALUMINUM				
			MIN. THICKNESS REQUIRED INCHES	① MIN. HEIGHT OF FILL, "H" (FT.)		MIN. THICKNESS REQUIRED INCHES	① MIN. HEIGHT OF FILL, "H" (FT.)				
				INSTALLATION	INSTALLATION		INSTALLATION	INSTALLATION			
				TYPE 1	TYPE 1		TYPE 1	TYPE 1			
2 3/4 INCH BY 1/2 INCH CORRUGATION RIVETED, WELDED, OR HELICAL LOCK-SEAM							2 3/4 INCH BY 1/2 INCH CORRUGATION RIVETED OR HELICAL LOCK-SEAM				
15	17x13	3	0.064	2	15	0.060	2	15			
18	21x15	3	0.064	2	15	0.060	2	15			
21	24x18	3	0.064	2.25	15	0.060	2.25	15			
24	28x20	3	0.064	2.5	15	0.075	2.5	15			
30	35x24	3	0.079	3	12	0.075	3	12			
36	42x29	3/2	0.079	3	12	0.105	3	12			
42	49x33	4	0.079	3	12	0.105	3	12			
48	57x38	5	0.109	3	13	0.135	3	13			
54	64x43	6	0.109	3	14	0.135	3	14			
60	71x47	7	0.138	3	15	0.164	3	15			
66	77x52	8	0.168	3	15						
72	83x57	9	0.168	3	15						
② 3 INCH BY 1 INCH OR 5 INCH BY 1 INCH CORRUGATION RIVETED, WELDED, OR HELICAL LOCK-SEAM							② 3 INCH BY 1 INCH OR 5 INCH BY 1 INCH CORRUGATION RIVETED OR HELICAL LOCK-SEAM				
			INSTALLATION		INSTALLATION						
			TYPE 2	TYPE 1	TYPE 2	TYPE 1					
36	40x31	5	0.079	3	2	12	15				
42	46x36	6	0.079	3	2	13	15				
48	53x41	7	0.079	3	2	13	15				
54	60x46	8	0.079	3	2	13	15				
60	66x51	9	0.079	3	2	13	15				
66	73x55	12	0.079	3	2	15	15				
72	81x59	14	0.079	3	2	15	15				
78	87x63	14	0.079	3	2	15	15				
84	95x67	16	0.109	3	2	15	15				
90	103x71	16	0.109	3	2	15	15				
96	112x75	18	0.109	3	2	15	15				
102	117x79	18	0.109	3	2	15	15				
108	128x83	18	0.138	3	2	15	15				

① FOR MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM 12" OF PAVEMENT AND/OR BASE.

② WHERE THE STANDARD 2 2/3" X 1/2" CORRUGATION AND GAUGE IS SPECIFIED FOR A GIVEN DIAMETER, A PIPE OF THE SAME DIAMETER WITH A 3" X 1" OR 5" X 1" CORRUGATION MAY BE SUBSTITUTED, PROVIDING IT IS GAUGED FOR A FILL HEIGHT CONDITION EQUAL TO OR GREATER THAN THE MAXIMUM FILL HEIGHT CONDITION FOR THE SPECIFIED GAUGE AND CORRUGATION.

DATE	REVISION	DATE FILMED
12-15-11	REVISED FOR LRFD DESIGN SPECS	
3-30-00	REVISED INSTALLATIONS	
11-06-97	ISSUED	

ARKANSAS STATE HIGHWAY COMMISSION

METAL PIPE CULVERT
FILL HEIGHTS & BEDDING

STANDARD DRAWING PCM-1


INSTALLATION TYPE	•• MATERIAL REQUIREMENTS FOR STRUCTURAL BACKFILL AND STRUCTURAL BEDDING
TYPE 2	•SELECTED MATERIALS (CLASS SM-1, SM-2 OR SM-4)

- AGGREGATE BASE COURSE (CLASS 4, 5, 6, OR 7) MAY BE USED IN LIEU OF SELECTED MATERIAL.
- SM3 WILL NOT BE ALLOWED.
- STRUCTURAL BEDDING MATERIAL SHALL HAVE A MAXIMUM PARTICLE SIZE OF 1/4 INCH. STRUCTURAL BACKFILL MATERIAL SHALL BE FREE OF ORGANIC MATERIAL, STONES LARGER THAN 1.50 INCH IN GREATEST DIMENSION, OR FROZEN LUMPS.
- STRUCTURAL BACKFILL AND STRUCTURAL BEDDING MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF HDPE PIPE.

MINIMUM TRENCH WIDTH BASED ON FILL HEIGHT "H"

PIPE DIAMETER	TRENCH WIDTH (FEET)	
	"H" < 10'-0"	"H" >OR= 10'-0"
18"	4'-6"	4'-6"
24"	5'-0"	6'-0"
30"	5'-6"	7'-6"
36"	6'-0"	9'-0"
42"	7'-0"	10'-6"
48"	8'-0"	12'-0"

①NOTE:
18" MIN. (18" - 30" DIAMETERS)
24" MIN. (36" - 48" DIAMETERS)
MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM 12" OF PAVEMENT AND/OR BASE.



TYPE 2 EMBANKMENT AND TRENCH INSTALLATIONS

1. STRUCTURAL BACKFILL, EMBANKMENT, AND OUTER STRUCTURAL BEDDING MATERIAL SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.

MULTIPLE INSTALLATION OF HIGH DENSITY POLYETHYLENE PIPES

PIPE DIAMETER	CLEAR DISTANCE BETWEEN PIPES
18"	1'-6"
24"	2'-0"
30"	2'-6"
36"	3'-0"
42"	3'-6"
48"	4'-0"

MINIMUM COVER FOR CONSTRUCTION LOADS

PIPE DIAMETER	② MIN. COVER (FEET) FOR INDICATED CONSTRUCTION LOADS			
	18.0-50.0 (KIPS)	50.0-75.0 (KIPS)	75.0-110.0 (KIPS)	110.0-175.0 (KIPS)
36" OR LESS	2'-0"	2'-6"	3'-0"	3'-0"
42" OR GREATER	3'-0"	3'-0"	3'-6"	4'-0"

②MINIMUM COVER SHALL BE MEASURED FROM TOP OF PIPE TO TOP OF THE MAINTAINED CONSTRUCTION ROADWAY SURFACE. THE SURFACE SHALL BE MAINTAINED.

CONSTRUCTION SEQUENCE

1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. THE STRUCTURAL BACKFILL SHALL BE PLACED AND COMPACTED IN LAYERS NOT EXCEEDING 8". THE LAYERS SHALL BE BROUGHT UP EVENLY AND SIMULTANEOUSLY TO THE ELEVATION OF THE MINIMUM COVER.
5. PIPE INSTALLATION MAY REQUIRE THE USE OF RESTRAINTS, WEIGHTING OR OTHER APPROVED METHODS IN ORDER TO HELP MAINTAIN GRADE AND ALIGNMENT.

- LEGEND -

H = FILL HEIGHT (FT.)
D_o = OUTSIDE DIAMETER OF PIPE
MAX. = MAXIMUM
MIN. = MINIMUM

==== = STRUCTURAL BACKFILL MATERIAL
===== = UNDISTURBED SOIL

GENERAL NOTES

1. PIPE SHALL CONFORM TO AASHTO M294, TYPE S. INSTALLATION SHALL CONFORM TO JOB SPECIAL PROVISION "PLASTIC PIPE" AND SECTION 606 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 2003 EDITION.
2. PLASTIC PIPE CULVERT DESIGN SHALL CONFORM TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, FIFTH EDITION (2010) WITH 2010 INTERIMS.
3. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PLUS A SUFFICIENT WIDTH TO ENSURE WORKING ROOM TO PROPERLY AND SAFELY PLACE AND COMPACT HAUNCHING AND OTHER BACKFILL MATERIAL.
4. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
5. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS "STRUCTURAL BEDDING" ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS "SELECTED PIPE BEDDING."
6. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED ABOVE AS STRUCTURAL BACKFILL), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF "SELECTED PIPE BACKFILL."
7. FOR PIPE TYPES THAT ARE NOT SMOOTH ON THE OUTSIDE (CORRUGATED OR PROFILE WALLS), BACKFILL GRADATIONS SHOULD BE SELECTED THAT WILL PERMIT THE FILLING OF THE CORRUGATION OR PROFILE VALLEY.
8. HIGH DENSITY POLYETHYLENE PIPES OF DIAMETERS OTHER THAN SHOWN WILL NOT BE ALLOWED.
9. JOINTS FOR HDPE PIPE SHALL MEET THE REQUIREMENTS FOR SOIL TIGHTNESS AS SPECIFIED IN AASHTO SECTION 26.4.2.4 AND 30.4.2 "AASHTO LRFD BRIDGE CONSTRUCTION SPECIFICATIONS." JOINTS SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.

DATE	REVISION	DATE FILMED
12-15-11	REVISED GENERAL NOTES & MINIMUM COVER NOTE	
11-17-10	ISSUED	

ARKANSAS STATE HIGHWAY COMMISSION

PLASTIC PIPE CULVERT
(HIGH DENSITY POLYETHYLENE)

STANDARD DRAWING PCP-1

INSTALLATION TYPE	•• MATERIAL REQUIREMENTS FOR STRUCTURAL BACKFILL AND STRUCTURAL BEDDING
TYPE 2	•SELECTED MATERIALS (CLASS SM-1, SM-2, OR SM-4)

• AGGREGATE BASE COURSE (CLASS 4, 5, 6, OR 7) MAY BE USED IN LIEU OF SELECTED MATERIAL.
SM3 WILL NOT BE ALLOWED.

•• STRUCTURAL BEDDING MATERIAL SHALL HAVE A MAXIMUM PARTICLE SIZE OF 1/4 INCH. STRUCTURAL BACKFILL MATERIAL SHALL BE FREE OF ORGANIC MATERIAL, STONES LARGER THAN 1.50 INCH IN GREATEST DIMENSION, OR FROZEN LUMPS.

STRUCTURAL BACKFILL AND STRUCTURAL BEDDING MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF PVC PIPE.

MAXIMUM FILL HEIGHT
BASED ON STRUCTURAL BACKFILL

PIPE DIAMETER	"H"
18"	45'-0"
24"	45'-0"
30"	40'-0"
36"	40'-0"

① NOTE:
12" MIN. (18" - 36" DIAMETERS)
MINIMUM COVER VALUE, "H"
SHALL INCLUDE A MINIMUM 12"
OF PAVEMENT AND/OR BASE.

MINIMUM TRENCH WIDTH
BASED ON FILL HEIGHT "H"

PIPE DIAMETER	TRENCH WIDTH (FEET)	
	"H" < 10'-0"	"H" > OR = 10'-0"
18"	4'-6"	4'-6"
24"	5'-0"	6'-0"
30"	5'-6"	7'-6"
36"	6'-0"	9'-0"


MULTIPLE INSTALLATION OF
PVC PIPES

PIPE DIAMETER	CLEAR DISTANCE BETWEEN PIPES
18"	1'-6"
24"	2'-0"
30"	2'-6"
36"	3'-0"

MINIMUM COVER FOR
CONSTRUCTION LOADS

PIPE DIAMETER	② MIN. COVER (FEET) FOR INDICATED CONSTRUCTION LOADS			
	18.0-50.0 (KIPS)	50.0-75.0 (KIPS)	75.0-110.0 (KIPS)	110.0-175.0 (KIPS)
18" THRU 36"	2'-0"	2'-6"	3'-0"	3'-0"

② MINIMUM COVER SHALL BE MEASURED FROM TOP OF PIPE TO TOP OF THE MAINTAINED CONSTRUCTION ROADWAY SURFACE. THE SURFACE SHALL BE MAINTAINED.



TYPE 2 EMBANKMENT AND TRENCH INSTALLATIONS

1. STRUCTURAL BACKFILL, EMBANKMENT, AND OUTER STRUCTURAL BEDDING MATERIAL SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.

CONSTRUCTION SEQUENCE

1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. THE STRUCTURAL BACKFILL SHALL BE PLACED AND COMPACTED IN LAYERS NOT EXCEEDING 8". THE LAYERS SHALL BE BROUGHT UP EVENLY AND SIMULTANEOUSLY TO THE ELEVATION OF THE MINIMUM COVER.
5. PIPE INSTALLATION MAY REQUIRE THE USE OF RESTRAINTS, WEIGHTING OR OTHER APPROVED METHODS IN ORDER TO HELP MAINTAIN GRADE AND ALIGNMENT.

- LEGEND -

H = FILL HEIGHT (FT.)
D_o = OUTSIDE DIAMETER OF PIPE
MAX. = MAXIMUM
MIN. = MINIMUM

==== = STRUCTURAL BACKFILL MATERIAL
===== = UNDISTURBED SOIL

GENERAL NOTES

1. PIPE SHALL CONFORM TO ASTM F949, CELL CLASS 12454. INSTALLATION SHALL CONFORM TO JOB SPECIAL PROVISION "PLASTIC PIPE" AND SECTION 606 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 2003 EDITION.
2. PLASTIC PIPE CULVERT DESIGN SHALL CONFORM TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, FIFTH EDITION (2010) WITH 2010 INTERIMS.
3. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PLUS A SUFFICIENT WIDTH TO ENSURE WORKING ROOM TO PROPERLY PLACE AND COMPACT HAUNCHING AND OTHER BACKFILL MATERIAL.
4. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
5. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS "STRUCTURAL BEDDING" ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS "SELECTED PIPE BEDDING."
6. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED ABOVE AS STRUCTURAL BACKFILL), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF "SELECTED PIPE BACKFILL."
7. FOR PIPE TYPES THAT ARE NOT SMOOTH ON THE OUTSIDE (CORRUGATED OR PROFILE WALLS), BACKFILL GRADATIONS SHOULD BE SELECTED THAT WILL PERMIT THE FILLING OF THE CORRUGATION OR PROFILE VALLEY.
8. PVC PIPES OF DIAMETERS OTHER THAN SHOWN WILL NOT BE ALLOWED.
9. JOINTS FOR PVC PIPE SHALL MEET THE REQUIREMENTS FOR SOIL TIGHTNESS AS SPECIFIED IN AASHTO SECTION 26.4.2.4 AND 30.4.2 "AASHTO LRFD BRIDGE CONSTRUCTION SPECIFICATIONS." JOINTS SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.


12-15-11	REV GENERAL NOTES & MINIMUM COVER NOTE; DELETED SM3 MATERIAL	
11-17-10	ISSUED	
DATE	REVISION	DATE FILMED

ARKANSAS STATE HIGHWAY COMMISSION


PLASTIC PIPE CULVERT
(PVC F949)

STANDARD DRAWING PCP-2






CONCRETE PAVEMENT




ASPHALT PAVEMENT


BROKEN LINE STRIPING




SOLID LINE STRIPING ON CONCRETE PAVEMENT



SOLID LINE STRIPING ON ASPHALT PAVEMENT




ASPHALT PAVEMENT



CONCRETE PAVEMENT

STRIPING AT ADJACENT NO PASSING LANES




CROSSWALK AND STOPBAR DETAILS


NOTES:

1. ALL LINES SHALL HAVE A WIDTH OF 4 INCHES.
2. THE THICKNESS AND RATE OF PAINT APPLICATION SHALL BE AS SPECIFIED IN SECTION 718 OF THE STANDARD SPECIFICATIONS.
3. THIS DRAWING SHALL BE USED IN CONJUNCTION WITH THE LATEST REVISED ADDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
4. RAISED PAVEMENT MARKERS SHALL BE CENTERED BETWEEN SKIP LINES ON 40 FEET SPACING UNLESS OTHERWISE SHOWN ON THE PLANS.

2" FOR ASPHALT OR CONCRETE PAVEMENT
6" FOR BITUMINOUS SURFACE TREATMENT



PAVEMENT EDGE LINE MARKING



NOTE:
THE RED LENS OF THE TYPE II R.P.M. SHALL FACE THE INCORRECT TRAFFIC MOVEMENT.

DETAIL OF STANDARD RAISED PAVEMENT MARKERS

GENERAL NOTES:

THIS DRAWING SHOULD BE CONSIDERED AS TYPICAL ONLY AND THE FINAL LOCATION OF THE STRIPING AND RAISED PAVEMENT MARKERS SHALL BE DETERMINED BY THE ENGINEER.


THIS DRAWING SHOULD BE USED IN CONJUNCTION WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", LATEST REVISION.

NOTE:
DIMENSIONS SHOWN FOR RAISED PAVEMENT MARKERS ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR MARKERS WITH THE APPROVAL OF THE ENGINEER. REQUESTING APPROVAL FOR SIMILAR MARKERS MAY BE MADE BY REFERRING TO THE AHTD QUALIFIED PRODUCTS LIST.


DATE	REVISION	FILMED
11-17-10	REVISED GENERAL NOTES & REMOVED PLOWABLE PVMT MRKRS	
11-18-04	REVISED NOTE 2 & GENERAL NOTES	
8-22-02	ADDED CROSSWALK & STOPBAR DTLS.	
7-02-98	ADDED DETAILS OF STD. RAISED PAV'T. MARKERS	
4-26-96	REV. NOTES 3&4; ADDED R.P.M.	
9-30-80	DRAWN	1-9-30-80

ARKANSAS STATE HIGHWAY COMMISSION	
PAVEMENT MARKING DETAILS	
STANDARD DRAWING PM-1	


NOTE:
 1. GRANULAR BACKFILL TO BE SUBSIDIARY TO PIPE UNDERDRAIN.
 2. UNLESS OTHERWISE SPECIFIED ON THE PLANS, THE UNDERDRAIN COVER SHALL BE THOROUGHLY COMPACTED EARTH AND SHALL BE SUBSIDIARY TO PIPE UNDERDRAIN.
 3. GRANULAR MATERIAL SHALL BE WRAPPED WITH GEOTEXTILE FABRIC. LAP FABRIC 12" OR THE WIDTH OF THE TRENCH AT THE TOP.





PLAN VIEW




DETAIL OF HOLE FOR 4" PIPE




DETAIL OF RODENT SCREEN



SIDE VIEW




FRONT VIEW



DETAILS OF PIPE UNDERDRAIN

FERNCO 1056-44 (4" CI/PLASTIC) OR FERNCO 1051-44 (4" AC/DIOR 4" CI/PLASTIC) COUPLING OR EQUAL WITH 2 CLAMPS (TYPICAL)



*NOTE:
 LATERALS SHALL BE INSTALLED AT ALL SAGS AND AT 250' INTERVALS ON GRADES. THE 250' DISTANCE MAY BE EXCEEDED ONLY WHERE NECESSARY FOR AN ACCEPTABLE OUTLET.

DETAIL OF PIPE UNDERDRAIN LATERALS WHEN PLACED ALONG PAVEMENT EDGE

NOTE: PVC PIPE FOR LATERALS SHALL MEET THE REQUIREMENTS OF ASTM D 1785 (LATEST REVISION) FOR SCHEDULE 40 PIPE.

4-10-03	REVISED NOTE 3	
1-12-00	REVISED DETAIL OF UNDERDRAIN LATERALS	
11-18-98	REVISED NOTE	
10-18-96	REVISED MIN. DEPTH & GEOTEXTILE FABRIC	
4-26-96	ADDED LATERAL NOTE; 5 1/2" TO 5"	
11-22-95	REVISED LATERALS	
7-20-95	REVISED LATERALS & ADDED NOTE	
11-3-94	REVISED FOR DUAL LATERALS	11-3-94
10-1-92	SUBSTITUTED GEOTEXTILE	10-1-92
8-15-91	ADDED POLYETHYLENE PIPE	8-15-91
11-8-90	DELETED ALTERNATE NOTE	11-8-90
1-25-90	ADDED 4" SNAP ADAPTER	1-25-90
11-30-89	DEL. (SUBGRADE); ADDED (WHERE REQUIRED)	11-30-89
7-15-88	ISSUED P.L.M.	647-7-15-88
DATE	REVISION	DATE FILMED

ARKANSAS STATE HIGHWAY COMMISSION


DETAILS OF PIPE UNDERDRAIN

STANDARD DRAWING PU-1

STEEL FABRICATION: REINFORCING STEEL FABRICATION SHALL CONFORM TO THE DIMENSIONS LISTED IN THE TABLE BELOW:

BAR SIZE	PIN DIAMETER	HOOK EXTENSION "K"
3	2 1/4"	4"
4	3"	4 1/2"
5	3 3/4"	5"
6	4 1/2"	6"
7	5 1/4"	7"
8	6"	8"

IF THE OVERALL HEIGHT OF THE HOOK (SEE DIAGRAM BELOW) FOR A "b", "b1", "b2" or "b3" BENT BAR IS GREATER THAN THE CORRESPONDING TOP OR BOTTOM SLAB THICKNESS, LESS 2 3/4 INCHES, EACH BENT BAR SHALL BE REPLACED WITH ONE HOOKED BAR AND ONE STRAIGHT BAR, USING LENGTHS AS SHOWN IN THE TABLE BELOW. THE TWO BARS SHALL BE THE SAME DIAMETER AS, AND PLACED AT THE SAME SPACING AS, THE "b", "b1", "b2" OR "b3" BENT BARS THEY REPLACE.



NOTE: DIMENSIONS OF BARS ARE MEASURED OUT TO OUT OF BARS.

OVERALL HEIGHT OF HOOKED BAR DIAGRAM


THE HOOKED BARS SHALL BE PLACED IN THE BOTTOM OF THE TOP SLAB AND THE TOP OF THE BOTTOM SLAB. THE STRAIGHT BARS SHALL BE PLACED IN THE TOP OF THE TOP SLAB AND THE BOTTOM OF THE BOTTOM SLAB. SEE TABLE BELOW FOR LENGTHS OF REPLACEMENT HOOKED AND STRAIGHT BARS.

FOR SKEWED CULVERTS, THE REPLACEMENT STRAIGHT BAR MAY HAVE TO BE CUT IN FIELD TO FIT.

REPLACEMENT BAR LENGTHS TABLE

BAR SIZE: "b", "b1", "b2" OR "b3"	LENGTH OF HOOKED BAR	LENGTH OF STRAIGHT BAR
#4	L + 1' - 0"	SEE "c" BAR LENGTH
#5	L + 1' - 2"	SEE "c" BAR LENGTH
#6	L + 1' - 4"	SEE "c" BAR LENGTH
#7	L + 1' - 8"	SEE "c" BAR LENGTH
#8	L + 1' - 10"	SEE "c" BAR LENGTH
#9	L + 2' - 6"	SEE "c" BAR LENGTH

L = "OW" - 3 INCHES



WINGWALL & CULVERT DRAINAGE DETAIL

REINFORCED CONCRETE BOX CULVERT GENERAL NOTES

CONCRETE SHALL BE CLASS S WITH A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3500 PSI. REINFORCING STEEL SHALL BE AASHTO M 31 OR M 53, GRADE 60.

CONSTRUCTION AND MATERIALS FOR WINGWALL & CULVERT DRAINAGE, INCLUDING WEEP HOLES AND GRANULAR MATERIAL, SHALL BE SUBSIDIARY TO THE BID ITEM, "CLASS S CONCRETE".

MEMBRANE WATERPROOFING SHALL CONFORM TO THE REQUIREMENTS OF SECTION 815 OF THE STANDARD SPECIFICATIONS.


MEMBRANE WATERPROOFING SHALL BE APPLIED TO ALL CONSTRUCTION JOINTS IN THE TOP SLAB AND THE SIDEWALLS OF R.C. BOX CULVERTS AS DIRECTED BY THE ENGINEER. NO PAYMENT SHALL BE MADE FOR THIS ITEM, BUT PAYMENT WILL BE CONSIDERED TO BE INCLUDED IN THE VARIOUS ITEMS BID FOR THE R.C. BOX CULVERT.

REINFORCING STEEL TOLERANCES: THE TOLERANCES FOR REINFORCING STEEL SHALL MEET THOSE LISTED IN "MANUAL OF STANDARD PRACTICE" PUBLISHED BY CONCRETE REINFORCING STEEL INSTITUTE (CRSI) EXCEPT THAT THE TOLERANCE FOR TRUSS BARS SUCH AS FIGURE 3 ON PAGE 7-4 OF THE CRSI MANUAL SHALL BE MINUS ZERO TO PLUS 1/2 INCH.

WEEP HOLES IN BOX CULVERT WALLS SHALL HAVE A MAXIMUM HORIZONTAL SPACING OF 10'-0" AND SHALL BE SPACED TO CLEAR ALL REINFORCING STEEL. THE DRAIN OPENING SHALL BE 4" DIAMETER AND SHALL BE PLACED 12" ABOVE THE TOP OF THE BOTTOM SLAB.

WEEP HOLES IN WINGWALLS SHALL HAVE A MAXIMUM HORIZONTAL SPACING OF 10'-0" AND SHALL BE SPACED TO CLEAR ALL REINFORCING STEEL. THERE SHALL BE A MINIMUM OF TWO (2) WEEP HOLES IN EACH WINGWALL. THE DRAIN OPENING SHALL BE 4" DIAMETER AND SHALL BE PLACED 12" ABOVE THE TOP OF THE WINGWALL FOOTING.

THE REQUIREMENTS SHOWN ON THIS DRAWING SHALL SUPERCEDE THE CORRESPONDING REQUIREMENTS ON ALL REINFORCED CONCRETE BOX CULVERT STANDARD DRAWINGS.



NOTE: FOR ALL SKEWED R.C. BOX CULVERTS THE LENGTH "K" OF THE MODIFIED HEADWALL SHALL BE EQUAL TO THE ROADWAY LENGTH "RL". THE ENDS OF THE HEADWALL SHALL BE CONSTRUCTED PARALLEL TO THE SKEW ANGLE OF THE BOX CULVERT.




R.C. BOX CULVERT HEADWALL MODIFICATIONS

DATE	REVISION	DATE FILMED
7/26/12	REV. DRAINAGE FILL MATERIAL & DETAIL	
12/15/11	REQUIRE WEEP HOLES IN BOX CULVERT WALLS	
5-25-06	REV. GEN. NOTES AND DETAILS FOR WEEP HOLES; BAR DIAGRAM	
11-16-01	ADDED WINGWALL DRAINAGE DETAIL/EDITED GEN. NOTES	
10-18-96	REV. ASTM REF. TO AASHTO & ADDED BAR DIAGRAM	
10-12-95	MOVED SOLID SODDING DETAIL TO RCB-2	
6-2-94	ADDED SOLID SODDING PLAN DETAIL	
8-5-93	REVISED PIN DIAMETER TO SPECS.	
8-15-91	DRAWN AND ISSUED	



ARKANSAS STATE HIGHWAY COMMISSION

REINFORCED CONCRETE BOX CULVERT DETAILS



STANDARD DRAWING RCB-1




NOTE: LENGTH MEASURED ALONG THE CENTER OF 2' STRIP OF SOLID SODDING.




BACKFILL DETAILS FOR BOX CULVERT



SECTION B-B
DETAILS FOR NEW CHANNELS



SECTION C-C



SECTION A-A
DETAILS THROUGH EXISTING CHANNELS












































GENERAL NOTES:
 ROADWAY EXCAVATION (CHANNEL CHANGE) WILL BE PAID FOR AT R.C. BOX CULVERT LOCATIONS. IT WILL BE PAID TO THE LIMITS ACTUALLY CUT AND WILL BE CONFINED TO THAT PORTION OF THE INDICATED AREA THAT IS ABOVE THE FLOW LINE. ROADWAY EXCAVATION (CHANNEL CHANGE) SHALL BE MEASURED BY CROSS SECTIONS AND VOLUMES COMPUTED BY AVERAGE END AREA METHOD. ALL CHANNEL CHANGES SHALL BE BROUGHT TO GRADE PRIOR TO MAKING ANY EXCAVATION FOR STRUCTURES.
 EXCAVATION FOR STRUCTURES WILL BE PAID FOR AT ALL R.C. BOX CULVERT LOCATIONS. IT WILL BE PAID TO THE LIMITS SHOWN AND SHALL BE CONFINED TO THAT PORTION OF THE INDICATED AREA THAT IS BELOW THE CHANNEL FLOW LINE.
 ROADWAY EXCAVATION SHOWN IN SECTION C-C ABOVE AS SUBSIDIARY WILL NOT BE MEASURED OR PAID FOR DIRECTLY, BUT PAYMENT WILL BE CONSIDERED TO BE INCLUDED IN THE VARIOUS ITEMS OF EXCAVATION.

11-20-03	REVISED SECTION A-A NOTE	
8-22-02	REVISED SECTION B-B NOTE	
10-12-95	COMBINED 1891B AND 1888A	
1-4-83	REVISED GENERAL NOTES AND ADDED MAXIMUM PAY LIMIT NOTES.	674-1-4-83
2-2-76	EXCAV. PAY LIMITS	917-2-2-76
10-2-72	REVISED AND REDRAWN	564-10-16-72
DATE	REVISION	FILMED

ARKANSAS STATE HIGHWAY COMMISSION

EXCAVATION PAY LIMITS, BACKFILL, & SOLID SODDING FOR BOX CULVERTS

STANDARD DRAWING RCB-2

<p>RI-1</p>  <p>STANDARD 30"x30" EXPRESSWAY 36"x36" SPECIAL 48"x48"</p>	<p>RI-2</p>  <p>STD. 36"x36"x36" EXPWY. 48"x48"x48" FWY. 60"x60"x60"</p>	<p>R2-1</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R2-5A</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R2-5C</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R4-1</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R4-2</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>
<p>R5-1</p>  <p>STD. 30"x30" EXPWY. 36"x36" SPECIAL 48"x48"</p>	<p>R11-2</p>  <p>48"x30"</p>	<p>R11-3A</p>  <p>60"x30"</p>	<p>R11-4</p>  <p>60"x30"</p>	<p>RSP-1</p>  <p>48"x30"</p>	<p>W1-1</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W1-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>
<p>W1-3</p>  <p>STD. 48"x48"</p>	<p>W1-4</p>  <p>STD. 48"x48"</p>	<p>W1-6</p>  <p>STD. 48"x24" SPECIAL 60"x30"</p>	<p>W1-8</p>  <p>STD. 18"x24" SPECIAL 24"x30" EXPWY. 30"x36" FWY. 36"x48"</p>	<p>W3-1</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W3-2</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W4-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>
<p>W5-1</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W6-3</p>  <p>EXPWY. 36"x36" SPECIAL 48"x48"</p>	<p>W8-7</p>  <p>EXPWY. 36"x36" FWY. 48"x48"</p>	<p>W9-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W13-1</p>  <p>STD. 24"x24"</p>	<p>W20-1</p>  <p>STD. 48"x48"</p>	<p>W20-2</p>  <p>STD. 48"x48"</p>
<p>W20-4</p>  <p>STD. 48"x48"</p>	<p>W20-5</p>  <p>STD. 48"x48"</p>	<p>W20-7a</p>  <p>500 FEET 18" x 24" W16-2</p> <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W21-2</p>  <p>STD. 30"x30" SPECIAL 36"x36"</p>	<p>W21-5</p>  <p>STD. 30"x30" SPECIAL 36"x36"</p>	<p>W24-1</p>  <p>STD. 36"x36"</p>	<p>W1-4b</p>  <p>STD. 48"x48"</p>
<p>W8-11</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W8-9</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>G20-1</p>  <p>60"x24"</p>	<p>G20-2</p>  <p>48"x24"</p>	<p>OM-3L OM-3R</p>  <p>12"x36"</p>	<p>M4-9</p>  <p>STD. 30"x24" SPECIAL 48"x36" SPECIAL 60"x48"</p>	<p>M4-10</p>  <p>48"x18"</p>
						<p>R55-1</p>  <p>36"x60"</p> <p>WHEN WORKERS ARE PRESENT **</p> <p>• USE 6" C LETTERS •• USE 4" D LETTERS</p>

ADVANCE DISTANCES (XXXX)

500 FT	1/2 MILE
1000 FT	3/4 MILE
1500 FT	1 MILE AHEAD


GENERAL NOTES:

- ALL TRAFFIC CONTROL DEVICES USED ON ROAD CONSTRUCTION SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION, AND TO THE STANDARD HIGHWAY SIGNS, LATEST EDITION, OR AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION.
- TRAFFIC CONTROL DEVICES SHALL BE SET UP JUST BEFORE THE START OF CONSTRUCTION OPERATIONS AND SHALL BE PROPERLY MAINTAINED DURING THE TIME SUCH CONDITIONS EXIST. THEY SHALL REMAIN IN PLACE ONLY AS LONG AS NEEDED AND REMOVED THEREAFTER.
- EXISTING SIGNS AND CONSTRUCTION SIGNS SHALL BE KEPT IN PROPER POSITION, AND BE CLEAN AND LEGIBLE AT ALL TIMES. SIGNS THAT DO NOT APPLY TO EXISTING CONDITIONS SHALL BE REMOVED. SIGNS THAT ARE DAMAGED, DEFACED, OR THAT ACCUMULATE DIRT DURING CONSTRUCTION SHALL BE CLEANED, REPAIRED, OR REPLACED.
- SIGNS ARE USUALLY MOUNTED ON A SINGLE POST, ALTHOUGH THOSE WIDER THAN 36" OR LARGER THAN 10 SQ. FT. SHALL BE MOUNTED ON TWO POSTS OR ABOVE A TYPE III BARRICADE.
- SIGN POSTS DIRECT BURIED IN SOIL SHALL BE 2 LB. MINIMUM CHANNEL POST OR 4"x4" WOOD POSTS. CHANNEL POSTS SHALL BE PAINTED GREEN. WOOD POSTS SHALL BE PAINTED WHITE. ALL POSTS SHALL BE NEATLY CONSTRUCTED, AND SHALL BE REPLUMBED, CLEANED, OR REPAIRED AS NEEDED FOR THE DURATION OF THE JOB. THERE SHALL NOT BE MORE THAN 2 POSTS IN A 7' PATH FOR WOOD OR CHANNEL POSTS. ANY CHANNEL POST SPLICE SHALL BE IN ACCORDANCE WITH STANDARD DRAWING TC-3.
- POST MOUNTED SIGNS IN RURAL AREAS SHALL BE CONSTRUCTED WITH THE NEAR EDGE OF THE SIGN FROM 6 TO 12 FEET FROM THE PAVEMENT EDGE. SIGNS IN URBAN AREAS AND BARRICADE MOUNTED SIGNS SHALL BE MOUNTED A MINIMUM OF 2 FEET FROM THE PAVEMENT EDGE.
- ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN URBAN AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE. ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN RURAL AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE, EXCEPT A MINIMUM OF 6' SHALL BE USED WHEN MOUNTING AN ADVISORY SIGN BELOW A WARNING SIGN. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR INTERMEDIATE TERM STATIONARY WORK CONDITIONS. THE SIGNS MINIMUM MOUNTING HEIGHT SHALL BE 5'. RETROREFLECTIVE DEVICES SHALL BE USED. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR SHORT-TERM, SHORT DURATION, AND MOBILE CONDITIONS. THEY SHALL BE NO LESS THAN ONE (1) FOOT ABOVE THE TRAVELED WAY. LONG-TERM STATIONARY SIGNS SHALL BE DIRECT BURIED IN SOIL, UNLESS CONDITIONS NECESSITATE THE USE OF PORTABLE SIGNS, OR AS APPROVED BY THE ENGINEER. CONCRETE PADS, CONCRETE OR ROCK BALLAST, OR OTHER SOLID MATERIALS SHALL NOT BE UTILIZED WITH PORTABLE SIGN SUPPORTS.


- FLAGGERS SHALL USE REFLECTORIZED STOP-SLOW PADDLES. FLAGS MAY BE USED ONLY FOR EMERGENCY SITUATIONS.
- MOST OF THE SIGNS SHOWN ARE ORIENTED TO THE RIGHT. HOWEVER, THIS DOES NOT PRECLUDE THE USE OF MIRROR IMAGES OF THESE SIGNS WHERE THE REVERSE ORIENTATION MIGHT BETTER CONVEY TO MOTORISTS THE PROPER DIRECTION OF MOVEMENT.
- R55-1 SIGNS SHALL BE PLACED AT LEAST 1500' BUT NOT MORE THAN 1 MILE IN ADVANCE OF THE WORK ZONE. IF A SPEED LIMIT REDUCTION IS IN EFFECT, THE SIGN SHALL BE PLACED A MINIMUM OF 500' IN ADVANCE OF THE "REDUCED SPEED AHEAD" SIGN.

NOTE: SUPPORTS FOR SIGNS, BARRICADES, AND VERTICAL PANELS THAT ARE DIFFERENT FROM THE REQUIREMENTS SHOWN IN NOTES 4 & 5, BUT MEET THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH), WILL BE ACCEPTED. COMPLIANCE WITH THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) IS REQUIRED FOR ALL PROJECTS.


DATE	REVISION	FILMED
12-15-8	REVISED W24-1	
11-17-10	DELETED W8-9a & ADDED W8-9	
10-15-09	ADDED REFERENCE TO MASH & ADDED SIGN W24-1	
4-17-08	REVISED SIGN DESIGNATIONS	
11-18-04	REVISED NOTES	
10-9-03	REVISED NOTE 1	
11-16-01	REVISED NOTE 7	
9-28-00	REVISED NOTE	
11-18-98	ADDED NOTE	
6-26-97	REVISED NOTE 5	
4-03-97	REVISED NOTE 5	
10-18-96	ADDED CONTROLLED ACCESS HWY. SIGN & TO NOTE 7	
10-12-95	ADDED R55-1	
6-8-95	REVISED TO CORRECT SIGN ILLUSTRATIONS	6-8-95
2-2-95	REVISED PER PART VI, MUTCD SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	
DATE	REVISION	FILMED




(A) Typical application of traffic control devices on a 2-lane highway where the entire roadway is closed and a bypass detour is provided.




(B) Typical application - 4-lane divided roadway where one roadway is closed.




(C) Typical application - 4-lane undivided roadway where half of the roadway is closed.




(D) Typical application - roadway closed beyond detour point.



(E) Typical application of traffic control devices on 2-lane highway where one lane is closed and flagging is provided.



(F) Typical application - 4-lane undivided roadway with inside lane closed.




Taper formulae:
 $L = 5xW$ for speeds of 45mph or more.
 $L = \frac{WS^2}{60}$ for speeds of 40mph or less.
 Where:
 L = Minimum length of taper.
 S = Numerical value of posted speed limit prior to work or 85th percentile speed.
 W = Width of offset.


- GENERAL NOTES:
 1. Advisory speed posted on W1-3 or W1-4 curve warning signs to be determined at site. Use W1-4 when speed is greater than 30mph and W1-3 when 30mph or less.
 2. When the existing speed limit is 55mph and the plans require a speed limit of 45mph, the R2-1(55) shall be omitted and the R2-5A shall be installed at that location. Additional R2-145mph speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
 3. When the existing speed limit is 65mph and the plans require a speed limit of 55mph, the R2-1(65) shall be omitted. Additional R2-155mph speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
 4. The maximum spacing between channelizing devices in a taper should be approximately equal in feet to the speed limit. Beyond the taper, maximum spacing shall be two times the speed limit, or as directed by the Engineer.
 5. Warning lights and/or flags may be mounted to signs or channelizing devices at night as needed.
 6. Pavement markings no longer applicable which might create confusion in the minds of vehicle operators shall be removed or obliterated as soon as practicable.
 7. Trailer mounted devices such as arrow panels and portable changeable message signs shall be delineated by affixing conspicuity material in a continuous line on the face of the trailer. When placed on or adjacent to the shoulder and not behind a positive barrier, these devices shall be delineated by placing five (5) traffic drums, equally spaced along the traffic side of the device.

3-11-10	ADDED (AFAD)	
11-20-08	REVISED SIGN DESIGNATIONS	
11-18-04	ADDED GENERAL NOTE	
10-18-96	ADDED R55-1	
4-26-96	CORRECTED (a) BEHIND G20-2	
6-8-95	CORRECTED SIGN IDENT. ON W1-4A	6-8-95
2-2-95	REVISED PER PART VI, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	
DATE	REVISION	FILMED

Channelizing devices



(A) Typical application - daytime maintenance operations of short duration on a 4-lane divided roadway where half of the roadway is closed.




(B) Typical application - 3-lane oneway roadway where center lane is closed.

- KEY:
- Arrow Panel (if Required)
 - Channelizing Device
 - Traffic drum

GENERAL NOTES:




1. A speed limit reduction may be implemented ONLY when designated in the plan or when recommended by the Roadway Design Division.
2. When the existing speed limit is 55mph and the plans require a speed limit of 45mph, the R2-1(55) shall be omitted and the R2-5a shall be installed at that location. Additional R2-1(45) speed limit signs shall be installed at a maximum of 1 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
3. When the existing speed limit is 65mph and the plans require a speed limit of 55mph, the R2-1(65) shall be omitted. Additional R2-1(55) speed limit signs shall be installed at a maximum of 1 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
4. The maximum spacing between channelizing devices in a taper should be approximately equal in feet to the speed limit. Beyond the taper, maximum spacing shall be two times the speed limit or as directed by the Engineer.
5. Warning lights and/or flags may be mounted to signs or channelizing devices at night as needed.
6. Pavement markings no longer applicable which might create confusion in the minds of vehicle operators shall be removed or obliterated as soon as practicable.
7. The G20-1 sign will be required on jobs of over two miles in length. When the lane closure is not at the beginning of the project, the G20-1 sign shall be erected 125' in advance of the job limit. Additional W20-1(1 MILE) signs are not required in advance of lane closures that begin inside the project limits.
8. Flaggers shall use STOP/SLOW paddles for controlling traffic through work zones. Flags may be used only for emergency situations.
9. All plastic drums and cones shall meet the requirements of NCHRP-350 or Manual for Assessing Safety Hardware (MASH).
10. Trailer mounted devices such as arrow panels and portable changeable message signs shall be delineated by affixing conspicuity material in a continuous line on the face of the trailer. When placed on or adjacent to the shoulder and not behind a positive barrier, these devices shall be delineated by placing five (5) traffic drums, equally spaced along the traffic side of the device.





(C) Typical application - construction operations of intermediate to long term duration on a 4-lane divided roadway where half of the roadway is closed.

When cones are used on freeways and multi-lane highways, they shall be 28" min. During hours of darkness, 28" cones shall be used on all roadways, and shall be reflectorized in accordance with the M.U.T.C.D.

CONES




PLASTIC DRUM



TYPE III BARRICADE

NOTE: For all road closures, the Type III barricades shall be of sufficient length to extend across entire roadway.

VERTICAL PANEL PLACEMENT




TRAFFIC CONTROL DEVICES FOR VERTICAL PAVEMENT DIFFERENTIALS

VERTICAL DIFFERENTIAL	LOCATIONS	TRAFFIC CONTROL
1" to 3"	Centerline, lane lines	W8-11
1" to 3"	Edge of shoulder	W8-9
Greater than 3"	Lane lines	Standard lane closure required
Greater than 3"	Edge of traveled lane	*RSP-land vertical panels, drums or concrete barrier
Greater than 3"	Edge of shoulder	*Vertical panels, drums or concrete barrier


When shown on the plans concrete barrier will be used. When the shoulder area is used as part of the traveled lane and there is insufficient width to place drums on the remaining shoulder width, then vertical panels shall be used.

FLAG




Flag shall be of good grade red material


STOP SLOW PADDLE



DETAIL OF SPLICES



NOTES: USE SPLICES ONLY WHEN NECESSARY FOR INSTALLATION. TYPICAL INSTALLATION SHOULD HAVE NO SPLICES (SEE STD. DRAWING NO. SHS-2). NORMAL INSTALLATIONS WILL REQUIRE 1/4" DIA. BOLTS TO MOUNT SIGNS TO POST AND 5/16" DIA. BOLTS TO ASSEMBLE THE VARIOUS POST SUPPORTS. EACH OF THESE BOLTS SHALL BE CARRIAGE BOLTS. SIGN POSTS SHALL BE PAINTED GREEN; SIGNS SHALL NOT BE PAINTED, AND ALL SIGN POSTS SHALL BE PLUMB.














(D) Typical application - closing multiple lanes of a multilane highway.

DATE	REVISION	FILMED
10-15-09	ADDED REFERENCE TO MASH	
11-20-08	REVISED SIGN DESIGNATIONS	
11-18-04	ADDED NOTE	
10-1-98	ADDED NOTE	
4-03-97	ADDED (SP) TO W6-1& REVISED TRAFFIC CONTROL DEVICES NOTE	
10-18-96	ADDED R55-1	
10-12-95	MOVED UPPER SPLICE	
6-8-95	REVISED SPLICE DETAIL, TEXT	6-8-95
2-2-95	REVISED PER PART VI, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	

ARKANSAS STATE HIGHWAY COMMISSION
STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION
STANDARD DRAWING TC-3

REINFORCING BAR TABLE PER BARRIER UNIT			
MARK	LOCATION	BAR SIZE	(NO. BARS)
H-1	HORIZONTAL IN BARRIER TIED INSIDE V-1 BARS	#5	(6)
H-2	CENTERED ABOVE DRAIN SLOTS LONG. & TRANSVERSELY	#5	(6)
H-3	TIED ABOVE H-1 BARS TO SUPPORT H-2, TIED TO V-1	#4	(2)
S-1	OVER LIFT HOLES	#4	(2)
S-2	HORIZ. AROUND SLOTS BETWEEN V-1'S & DRAIN SLOTS	#4	(2)
V-1	VERTICAL IN BARRIER (3) EACH END & (2) AT EACH DRAIN SLOTS	#5	(16)




- General Notes**
- The contractor shall furnish the Precast Concrete Barrier Units and shall be responsible for the manufacture, shipment, storage, placement and removal. At the completion of the project, the precast units will remain the property of the contractor.
 - Materials shall meet the following minimum requirements: Concrete: 2500 psi compressive strength at 28 days. Reinforcing Steel: AASHTO M 31 or M 53, Grade 60. Structural Steels: AASHTO-M270 Grade 36 shall be used for the Connection Pin, Connection Loops, and Stabilization Pins. A One Piece Pin with a 3" rounded top may be used in place of the detailed Connection Pin. Delineators: Delineators shall be mounted at 10' spacing on top of precast barrier.

In applications where barrier walls within 6 feet of a traffic lane, additional delineators shall be placed on the barrier at 10' spacing approximately one (1) foot from the top of the barrier. Delineators shall be on the AHTD Qualified Products List for Construction Concrete Barrier Markers. Delineator color shall be in accordance with the Manual on Uniform Traffic Control Devices. Payment for delineators shall be considered included in the price bid per Lin. Ft. for "Furnishing and installing Precast Concrete Barrier". The contractor shall certify to the Engineer that the material and the design used in the precast barrier units meets the requirements as shown on this standard drawing.
 - Other Precast Concrete Barriers that have been crash tested and approved by the Federal Highway Administration to meet the requirements of NCHRP-350 Test Level 3 or Manual For Assessing Safety Hardware (MASH) will be accepted in lieu of the barrier shown. Drain slots shall be provided as needed or as directed by the Engineer. The Contractor shall furnish a certification of NCHRP Report 350 or Manual For Assessing Safety Hardware (MASH) compliance for any other types of precast barrier to be used. The certification shall state that the precast concrete barrier meets the requirements of NCHRP Report 350 or Manual For Assessing Safety Hardware (MASH) and include a copy of the Federal Highway Administration's (FHWA) approval letter with all attachments. Precast concrete barrier units shall be fabricated and installed in accordance with crash testing and documentation provided in the FHWA approval letter. Mixing of shapes will not be allowed in a continuous line of units.
 - Dowel holes in pavement or bridge slabs that are to remain in place shall be filled. Holes in concrete pavement and bridge slabs shall be filled with an approved non-shrink epoxy grout. Holes in asphalt pavement shall be filled with an approved asphalt joint filler. Payment for drilling and filling holes to be included in the price for various barrier items.
 - Attach Units to Roadway Surface with Stabilization Pins and to Deck Slabs using bolts when required.
 - A 4" White PVC Sleeve may be used to form the Lifting Hole and if used the Sleeve is to be left in place.

DATE	REVISION	FILMED
10-15-09	ADDED REFERENCE TO MASH	
8-5-09	REV. NOTE 3 CONCERNING DRAIN SLOTS	
11-29-07	REVISED NOTE 3	
5-25-06	DELETED GENERAL NOTE 7	
11-18-04	REVISED BARRIER STABILIZATION DETAIL BRIDGE DECKS	
4-10-03	REVISED GENERAL NOTE 2	
8-22-02	ISSUED NEW DRAWING	

ARKANSAS STATE HIGHWAY COMMISSION
 STANDARD TRAFFIC CONTROLS
 FOR HIGHWAY CONSTRUCTION -
 TEMPORARY PRECAST BARRIER
 STANDARD DRAWING TC-4


(A) 4 feet or greater preferred. If less than 4 feet, Precast Units shall be connected to slab (SEE BARRIER STABILIZATION DETAIL-BRIDGE DECKS STD. DRWG. TC-4)



BARRIER PLACEMENT ALONG BRIDGE WITH OFFSET


No Scale

** Offset Distance for Two Way Traffic Only



SECTION J-J

No Scale



BARRIER PLACEMENT ALONG ROADWAY WITH OFFSET

No Scale


** Offset Distance For Two Way Traffic Only

* Offset Distance (See Table)

Offset Distance Table

Speed (MPH)	Offset Distance (FT.)
≤ 45	12
> 45	18

If offset distance is not attainable, then see 'Barrier Placement With Attenuator' Detail shown below.




BARRIER PLACEMENT WITH ATTENUATOR

No Scale

** Offset Distance For Two Way Traffic Only

***Min. 3'-0" From Edge of Travel Lane to Nearest Edge of Attenuator










SPECIAL END UNIT

No Scale


General Notes

When shown on the Plans, the ends of the Temporary Precast Concrete Barrier shall be protected with an NCHRP-350 or Manual For Assessing Safety Hardware (MASH) approved Crash Cushion. Payment for Crash Cushions shall be made under the item of "Temporary Impact Attenuation Barrier."

			ARKANSAS STATE HIGHWAY COMMISSION
			STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION - TEMPORARY PRECAST BARRIER
			STANDARD DRAWING TC-5
10-15-09	ADDED REFERENCE TO MASH		
5-25-06	REVISED BARRIER PLACEMENT		
8-22-02	ISSUED NEW DRAWING		
DATE	REVISION	FILMED	




12-15-11	DELETED BALED STRAW DITCH CHECK & ADDED WATTLE DITCH CHECK		ARKANSAS STATE HIGHWAY COMMISSION
11-18-98	ADDED NOTES		
7-02-98	ADDED BALED STRAW FILTER BARRIER (E-2)		TEMPORARY EROSION CONTROL DEVICES
7-20-95	REVISED SILT FENCE E-4 AND E-11	7-20-95	
7-15-94	REV. E-4 & E-11 MIN. 13" BURIED END OF FABRIC		STANDARD DRAWING TEC-1
6-2-94	REVISED E-1, 4, 7 & 11; DELETED E-2 & 3	6-2-94	
4-1-93	REDRAWN		
10-1-92	REDRAWN		
8-2-76	ISSUED R.D.M.	298-7-28-76	
DATE	REVISION	FILMED	




NOTE:
SIZE OF BASIN TO BE DETERMINED
BY VOLUME REQUIRED; HOWEVER
A MINIMUM LENGTH-TO-WIDTH
RATIO OF 2:1 SHALL BE USED.

SEDIMENT BASIN WITH RIPRAP OUTLET (E-9)




NOTE:
SIZE OF BASIN TO BE DETERMINED
BY VOLUME REQUIRED; HOWEVER
A MINIMUM LENGTH-TO-WIDTH
RATIO OF 2:1 SHALL BE USED.

SEDIMENT BASIN WITH PIPE OUTLET (E-10)




DIVERSION DITCH (E-8)



NOTE:
A T-SECTION SHALL BE USED AT THE INLET
FOR TWO-DIRECTIONAL FLOW.
AN ELBOW SHALL BE USED FOR
ONE-DIRECTIONAL FLOW.

SLOPE DRAIN (E-12)



SEDIMENT BASIN (E-14)

6-2-94	Revised E-8 & E-12; Added E-14 & Deleted E-13		
4-1-93	ISSUED		
DATE	REVISION		FILMED


ARKANSAS STATE HIGHWAY COMMISSION
 TEMPORARY EROSION
 CONTROL DEVICES
 STANDARD DRAWING TEC-2

CLEARING AND GRUBBING

CONSTRUCTION SEQUENCE

1. PLACE PERIMETER CONTROLS (I.E. SILT FENCES, DIVERSION DITCHES, SEDIMENT BASINS, ETC.)
2. PERFORM CLEARING AND GRUBBING OPERATION.

EXCAVATION



NOTE:
NUMBER OF PHASES WILL VARY.
THREE PHASES SHOWN FOR
ILLUSTRATION.


GENERAL NOTE

ALL CUT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE EXCAVATED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.

CONSTRUCTION SEQUENCE

1. EXCAVATE AND STABILIZE INTERCEPTOR AND/OR DIVERSION DITCHES.
2. PERFORM PHASE 1 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
3. PERFORM PHASE 2 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
4. PERFORM FINAL PHASE OF EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING. STABILIZE DITCHES. CONSTRUCT DITCH CHECKS, DIVERSION DITCHES, SEDIMENT BASINS, OR OTHER EROSION CONTROL DEVICES AS REQUIRED.

EMBANKMENT



NOTE:
NUMBER OF PHASES WILL VARY.
THREE PHASES SHOWN FOR
ILLUSTRATION.




GENERAL NOTE

ALL EMBANKMENT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE CONSTRUCTED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.

CONSTRUCTION SEQUENCE


1. CONSTRUCT DIVERSION DITCHES, DITCH CHECKS, SEDIMENT BASINS, SILT FENCES, OR OTHER EROSION CONTROL DEVICES AS SPECIFIED.
2. PLACE PHASE 1 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
3. PLACE PHASE 2 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
4. PLACE FINAL PHASE OF EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PLACE DIVERSION DITCHES AND SLOPE DRAINS AND MAINTAIN UNTIL ENTIRE SLOPE IS STABILIZED.

		ARKANSAS STATE HIGHWAY COMMISSION	
		TEMPORARY EROSION CONTROL DEVICES	
		STANDARD DRAWING TEC-3	
11-03-94	CORRECTED SPELLING		
6-2-94	Drawn & Issued		6-2-94
DATE	REVISION		FILMED



GENERAL NOTES:
 THESE INSTALLATIONS TO BE USED WHERE NORMAL FENCING INSTALLATION WOULD CAUSE THE COLLECTING OF DRIFT IN THE CHANNEL OR THE DEPRESSION WILL NOT PERMIT NORMAL INSTALLATION. INSTALLATIONS WILL BE MADE ONLY WHERE DIRECTED BY THE ENGINEER.
 WHEN A FENCE LINE APPROACHES A DITCH, GULLY OR DEPRESSION, THE LAST POST ON LEVEL GROUND SHALL BE PLACED CLOSE ENOUGH TO THE EDGE OF THE DROP OFF THAT THE FENCE MAY BE STRUNG TO THE POST IN THE DEPRESSION WITHOUT TOUCHING THE GROUND.
 IN TERRAIN OF SUCH EXTREME IRREGULARITY THAT MINOR GRADING WILL NOT BE FEASIBLE, THE NORMAL FENCE SHALL CONTINUE ON GRADE AND THE GULLIES OR DEPRESSIONS TREATED BY AUXILIARY FENCES AS SHOWN.
 PAYMENT FOR THE TYPE INSTALLATION USED WILL NOT BE MADE DIRECTLY BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE BID FOR WIRE FENCE OR CHAIN LINK FENCE.

ARKANSAS STATE HIGHWAY COMMISSION		
WIRE FENCE WATER GAPS		
STANDARD DRAWING		
WF-2		
4-20-79	REVISED TOP RAIL & TENSION WIRE	676-4-20-79
10-2-72	REVISED & REDRAWN	529 10-2-72
DATE	REVISION	DATE FILMD




GENERAL NOTES:
 STEEL LINE POSTS SHALL BE PAINTED OR GALVANIZED. TUBULAR END, CORNER, PULL, OR DIAGONAL BRACES MUST CONFORM TO THE DIMENSIONS AND WEIGHTS SPECIFIED ON STANDARD DRAWING WF-3 (CHAIN LINK). APPROVED ALTERNATES ARE ACCEPTABLE.
 AN ACCEPTABLE TOLERANCE IN LENGTH OF TUBULAR OR WOODEN POSTS SHALL BE - 1\"/>

THE CONTRACTOR SHALL FURNISH AT LEAST 25% OF TIMBER LINE POSTS OF 7 FOOT LENGTHS IN ORDER TO PROVIDE SUFFICIENT SET IN SOFT GROUND OR SMALL DEPRESSIONS.


DRIVEWAY GATES, EITHER SINGLE 12' TO 16' OR DOUBLE 6' TO 8' OPENING OF THE SAME TYPE AS THE PEDESTRIAN GATE, SHALL BE INSTALLED ON THE RIGHT SIDE OF EACH THROUGH LANE ROAD AT LARGE CULVERTS OR BRIDGE CROSS FENCE, FOR USE OF MAINTENANCE EQUIPMENT. LOCATION OF GATES TO BE SHOWN ON PLANS OR AS DESIGNATED BY THE ENGINEER.

AT STREAM CROSSINGS, THE FENCE SHALL NOT BE CONSTRUCTED ACROSS LARGE STREAMS, WHERE CLEARANCE IS SUFFICIENT FROM THE TOP OF THE BANK TO THE BRIDGE STRUCTURE A CROSS CONNECTION SHALL BE CONSTRUCTED BETWEEN THE FENCE ON EACH SIDE OF THE ROAD. WHERE THE CLEARANCE IS NOT SUFFICIENT, THE FENCE SHALL BE TERMINATED WITH CROSS CONNECTIONS AND END POSTS ADJACENT TO BRIDGE ABUTMENTS OR CULVERT WINGWALLS.

TYPE C FENCE (WOOD POSTS)



NOTE: USE 3/4\"/>



DETAIL OF FENCE CONSTRUCTION AT LARGE CULVERTS (5' IN HEIGHT AND OVER)

SPLICE FOR BARBED WIRE BETWEEN PULL POST ASSEMBLY SHALL BE BY THE 'EYE METHOD' AS DESCRIBED AS FOLLOWS: THE ENDS OF THE BARBED WIRE SHALL BE BENT TO FORM A LOOP. THE LOOPS SHALL BE CONNECTED. AFTER THE LOOPS ARE CONNECTED THE ENDS OF THE WIRE SHALL BE WRAPPED AROUND THE PROJECTING WIRES A MINIMUM OF 4 TIMES FOR EACH WIRE LOOP.


SPLICE FOR WOVEN WIRE BETWEEN PULL POST ASSEMBLY SHALL BE BY THE 'WESTERN UNION METHOD' AS DESCRIBED AS FOLLOWS: THE VERTICAL WIRES FOR EACH END OF THE FENCE FABRIC SHALL BE PLACED SIDE BY SIDE AND THE PROJECTING HORIZONTAL WIRES SHALL BE WRAPPED A MINIMUM OF 4 TIMES AROUND THE HORIZONTAL WIRES OF THE FIRST WEB.

STAPLE AT LEAST TOP, BOTTOM AND ALTERNATE WIRES OF WOVEN FABRIC FOR WOOD LINE POSTS.


TYPE C FENCE (STEEL POSTS)




NOTE: RIGHT-OF-WAY MONUMENTS SHALL NOT BE DISTURBED BY FENCE CONSTRUCTION. CORNER POSTS SHALL BE CONSTRUCTED 2' FROM THE RIGHT-OF-WAY MONUMENT OR AS DIRECTED BY THE ENGINEER.
 △ - R/W MONUMENTS
 ○ - FENCE POSTS



OTHER STYLE VEHICULAR GATES MAY BE USED WITH THE APPROVAL OF THE ENGINEER. THE METHOD OF SECURING GATE (LATCH AND/OR LOCK) SHALL MEET THE APPROVAL OF THE ENGINEER.



NOTE: SPACING AND SIZE (EXCEPT LENGTH) OF POSTS, APPROACH SPANS, PULL POST ASSEMBLIES, AND CORNER BRACING FOR TYPE D FENCE SHALL CONFORM TO TYPE C FENCE. USE GALVANIZED STAPLES ON WOOD POSTS AND APPROVED FASTENERS ON STEEL POSTS.




PRIVATE FENCE TERMINAL INSTALLATION WHERE EXISTING FENCE CONSISTS OF STEEL POSTS, USE END POST ASSEMBLY AS SHOWN IN TYPE C FENCE OR OTHER END POST ASSEMBLY AS APPROVED BY THE ENGINEER.

DATE	REVISION	FILMED
8-22-82	REVISED GENERAL NOTES	
10-18-96	REVISED AASHTO	
11-22-95	REVISED R-O-W LOCATION DETAIL	
6-2-94	REVISED BARB WIRE AND ADDED CORNER POST NOTES	6-2-94
8-5-93	REVISED R/W INSTALLATION FENCE	8-5-93
10-1-92	ADDED STAPLE NOTE	10-1-92
8-15-91	ADDED TYPE D-2 FENCE	8-15-91
11-30-89	DELETED CLASS CONCRETE	11-30-89
7-15-88	ADDED SPLICE NOTE	700-7-15-88
10-30-87	GENERAL REVISIONS	549-10-30-87
11-1-84	MAX. POST SPACING MIN. WIRE GAUGE	507-11-1-84
1-4-83	MIN. DIA. LINE POST	648-1-4-83
3-2-81	TOLERANCE FOR POST LENGTH	722-3-2-81
12-1-72	ADDED D-1 & FENCE INSTALLATION	564-12-1-72
10-2-72	REVISED AND REDRAWN	540-10-2-72

ARKANSAS STATE HIGHWAY COMMISSION
WIRE FENCE
TYPE C AND D
 STANDARD DRAWING WF-4

DATE REVISED	DATE FILED	DATE REVISED	DATE FILED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	58	81


2 CROSS SECTIONS



11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		59	81
				JOB NO. 080386				

2 CROSS SECTIONS







11/6/2012
R080386.DGN

CROSS SECTION STA. 202+00 TO STA. 203+50

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		60	81
						JOB NO.	080386	

② CROSS SECTIONS




CROSS SECTION STA. 204+00 TO STA. 205+50

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	61	81


2 CROSS SECTIONS



11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	62	81

2 CROSS SECTIONS




CROSS SECTION STA. 207+50 TO STA. 208+50

11/6/2012
R080386.DCN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		63	81

2 CROSS SECTIONS




STA. 208+96 - IN PLACE DBL. 54" X 51" C.M. PIPE CULV'T REMOVE AND CONSTRUCT SEXT. 11' X 6' X 74' R.C. BOX CULV'T. WITH 3:1 WINGS LT. & RT. Q25= 3400 cfs D.A. = N/A

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							64	81

2 CROSS SECTIONS




CROSS SECTION STA. 210+00 TO STA. 211+00

11/6/2012 R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		65	81

2 CROSS SECTIONS






CROSS SECTION STA. 211+50 TO STA. 212+50

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		66	81

2 CROSS SECTIONS






CROSS SECTION STA. 213+00 TO STA. 214+00

11/6/2012
RO80386.DCN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		67	81

2 CROSS SECTIONS






CROSS SECTION STA. 214+50 TO STA. 215+50

11/6/2012 R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	68	81

2 CROSS SECTIONS






CROSS SECTION STA. 216+00 TO STA. 217+00

11/6/2012

RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							69	81

2 CROSS SECTIONS






CROSS SECTION STA. 217+50 TO STA. 218+50

11/6/2012

RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							70	81

2 CROSS SECTIONS






CROSS SECTION STA. 219+00 TO STA. 220+00

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	71	81

2 CROSS SECTIONS






CROSS SECTION STA. 220+08 TO STA. 221+00

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	72	81

2 CROSS SECTIONS






CROSS SECTION STA. 221+50 TO STA. 222+40

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	73	81

2 CROSS SECTIONS






CROSS SECTION STA. 222+50 TO STA. 223+50

11/6/2012

R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	080386	74

2 CROSS SECTIONS






CROSS SECTION STA. 224+00 TO STA. 225+00

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							75	81

2 CROSS SECTIONS






CROSS SECTION STA. 225+50 TO STA. 226+00

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							76	81

2 CROSS SECTIONS






CROSS SECTION STA. 226+50 TO STA. 227+50

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	77	81

② CROSS SECTIONS



AREA CUT	0.0	AREA CUT	0.0	AREA CUT	0.0	AREA CUT	0.0	AREA CUT	0.0	AREA CUT	0.0	AREA CUT	0.0	AREA CUT	0.0	CUT VOLUME	0.0	CUT VOLUME	0.0	CUT VOLUME	0.0	CUT VOLUME	0.0	CUT VOLUME	0.0	CUT VOLUME	0.0	CUT VOLUME	0.0
AREA FILL	0.0	AREA FILL	0.0	AREA FILL	0.0	AREA FILL	0.0	AREA FILL	0.0	AREA FILL	0.0	AREA FILL	0.0	AREA FILL	0.0	FILL VOLUME	0.0	FILL VOLUME	0.0	FILL VOLUME	0.0	FILL VOLUME	0.0	FILL VOLUME	0.0	FILL VOLUME	0.0	FILL VOLUME	0.0




CROSS SECTION STA. 227+81 TO STA. 228+00

11/6/2012

RO80386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. 080386							78	81

2 CROSS SECTIONS






CROSS SECTION STA. 228+50 TO STA. 229+00

11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. 080386	79	81

2 CROSS SECTIONS






11/6/2012

R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	080386		80	81



② CROSS SECTIONS



11/6/2012
R080386.DGN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO. 080386			81	81

② CROSS SECTIONS



CROSS SECTION STA. 231+50 TO STA. 231+75

11/6/2012

R080386.DGN