

I:\Job\W\X\2600\_AHTD\_Or-Call\2011Task\_Order\_BB013\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\041\Title.dgn 3:04:24 PM 12/9/2014

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB013	1	130
				② SHELL LAKE STR. & APPRS. (S)				


"A FULLY CONTROLLED ACCESS FACILITY"  
 ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT  
 CONSTRUCTION PLANS FOR STATE HIGHWAY

# SHELL LAKE STR. & APPRS. (S)


ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 FEDERAL AID PROJ. NHPP-B40-0(230)

## JOB BB0113

NOT TO SCALE




VICINITY MAP



ARK. HWY. DIST. NO. 1

DESIGN TRAFFIC DATA

DESIGN YEAR	_____	2035
2015 ADT	_____	31,000
2035 ADT	_____	38,000
2035 DHV	_____	4180
DIRECTIONAL DISTRIBUTION	_____	-0.60
TRUCKS	_____	56%
DESIGN SPEED	_____	70 MPH



BRIDGE DATA

- ① STA. 5104+63.36 BR. END  
 562-5 7/8" BRIDGE LENGTH 560'  
 CONT. COMP. W-BEAM SPANS  
 (64', 72', 72', 72', 72', 72', 72' 64')  
 BR. NO. 06939  
 2 - 63'-0" CLEAR ROADWAYS  
 STA. 5110+25.84 BR. END

STA. 5085+00.00  
 BEGIN JOB BB0113  
 (LOG MILE 259.38)



STA. 5131+00.00  
 END JOB BB0113  
 (LOG MILE 260.25)

LENGTH IS COMPUTED ALONG @ MEDIAN & IS SHOWN FOR INFORMATION ONLY

BEGINNING OF PROJECT	MID POINT OF PROJECT	END OF PROJECT
LATITUDE 35° 07' 56" N	LATITUDE 35° 07' 57" N	LATITUDE 35° 07' 58" N
LONGITUDE 90° 29' 46" W	LONGITUDE 90° 29' 20" W	LONGITUDE 90° 28' 53" W

	GROSS LENGTH OF PROJECT	4600.00	FEET OR	0.871	MILES
NET	" " ROADWAY	4037.52	" "	0.765	"
NET	" " BRIDGES	562.48	" "	0.106	"
NET	" " PROJECT	4600.00	" "	0.871	"

P.E. BB0106



12/10/14

INDEX OF SHEETS

SHEET NO.	TITLE	BRIDGE NO.	DRWG.NO.
1.	TITLE SHEET		
2.	INDEX OF SHEETS		
3.	GOVERNING SPECIFICATIONS AND GENERAL NOTES		
4 - 8.	TYPICAL SECTIONS OF IMPROVEMENT		
9 - 14.	SPECIAL DETAILS		
15 - 20.	TEMPORARY EROSION CONTROL DETAILS		
21 - 45.	MAINTENANCE OF TRAFFIC		
46 - 47.	PERMANENT PAVEMENT MARKING DETAILS		
48 - 53.	QUANTITIES		
54.	SCHEDULE OF BRIDGE QUANTITIES	06939	55891A
55.	SUMMARY OF QUANTITIES AND REVISIONS		
56 - 57.	PLAN SHEETS		
58.	INTERCHANGE LAYOUT - HWY. 149		
59.	LAYOUT OF BRIDGE OVER SHELL LAKE (SHEET 1 OF 2)	06939	55929
60.	LAYOUT OF BRIDGE OVER SHELL LAKE (SHEET 2 OF 2)	06939	55930
61.	DETAILS OF STAGE CONSTRUCTION (SHEET 1 OF 4)	06939	55931
62.	DETAILS OF STAGE CONSTRUCTION (SHEET 2 OF 4)	06939	55932
63.	DETAILS OF STAGE CONSTRUCTION (SHEET 3 OF 4)	06939	55933
64.	DETAILS OF STAGE CONSTRUCTION (SHEET 4 OF 4)	06939	55934
65.	DETAILS OF END BENTS 1 & 9 (SHEET 1 OF 6)	06939	55935
66.	DETAILS OF END BENTS 1 & 9 (SHEET 2 OF 6)	06939	55936
67.	DETAILS OF END BENTS 1 & 9 (SHEET 3 OF 6)	06939	55937
68.	DETAILS OF END BENTS 1 & 9 (SHEET 4 OF 6)	06939	55938
69.	DETAILS OF END BENTS 1 & 9 (SHEET 5 OF 6)	06939	55939
70.	DETAILS OF END BENTS 1 & 9 (SHEET 6 OF 6)	06939	55940
71.	DETAILS OF INTERMEDIATE BENTS 2 & 8 (SHEET 1 OF 3)	06939	55941
72.	DETAILS OF INTERMEDIATE BENTS 2 & 8 (SHEET 2 OF 3)	06939	55942
73.	DETAILS OF INTERMEDIATE BENTS 2 & 8 (SHEET 3 OF 3)	06939	55943
74.	DETAILS OF INTERMEDIATE BENTS 3 & 7 (SHEET 1 OF 3)	06939	55944
75.	DETAILS OF INTERMEDIATE BENTS 3 & 7 (SHEET 2 OF 3)	06939	55945
76.	DETAILS OF INTERMEDIATE BENTS 3 & 7 (SHEET 3 OF 3)	06939	55946
77.	DETAILS OF INTERMEDIATE BENTS 4 THRU 6 (SHEET 1 OF 3)	06939	55947
78.	DETAILS OF INTERMEDIATE BENTS 4 THRU 6 (SHEET 2 OF 3)	06939	55948
79.	DETAILS OF INTERMEDIATE BENTS 4 THRU 6 (SHEET 3 OF 3)	06939	55949
80.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 1 OF 14)	06939	55950
81.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 2 OF 14)	06939	55951
82.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 3 OF 14)	06939	55952
83.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 4 OF 14)	06939	55953
84.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 5 OF 14)	06939	55954
85.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 6 OF 14)	06939	55955
86.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 7 OF 14)	06939	55956
87.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 8 OF 14)	06939	55957
88.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 9 OF 14)	06939	55958
89.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 10 OF 14)	06939	55959
90.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 11 OF 14)	06939	55960
91.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 12 OF 14)	06939	55961
92.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 13 OF 14)	06939	55962
93.	DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT (SHEET 14 OF 14)	06939	55963
94.	DETAILS OF ELASTOMERIC BEARINGS (SHEET 1 OF 2)	06939	55964
95.	DETAILS OF ELASTOMERIC BEARINGS (SHEET 2 OF 2)	06939	55965
96.	DETAILS OF TYPE SPECIAL 1 APPROACH SLABS (SHEET 1 OF 3)	06939	55966A
97.	DETAILS OF TYPE SPECIAL 1 APPROACH SLABS (SHEET 2 OF 3)	06939	55967A
98.	DETAILS OF TYPE SPECIAL 1 APPROACH SLABS (SHEET 3 OF 3)	06939	55968A
99.	STANDARD DETAILS FOR EMBANKMENT CONSTRUCTION AND BACKFILL AT BRIDGE ENDS		55000
100.	STANDARD DETAILS FOR DUMPED RIPRAP AND FILTER BLANKET AND COMPUTING EXCAVATION FOR STRUCTURES		55001
101.	STANDARD DETAILS FOR PERMANENT STEEL BRIDGE DECK FORMS FOR STEEL & CONCRETE GIRDER SPANS		55005
102.	STANDARD DETAILS FOR TYPE D BRIDGE NAME PLATE		55010
103.	STANDARD DETAILS FOR CONCRETE FILLED STEEL SHELL PILES AND PILE ENCASEMENTS		55021
104.	STANDARD DETAILS FOR TYPE C APPROACH GUTTERS		55030C
105.	TRANSVERSE & LONGITUDINAL JOINTS FOR CONCRETE PAVEMENT (NON-REINFORCED)		CPT-16A
106.	GUARD RAIL DETAILS		GR-8
107.	GUARD RAIL DETAILS		GR-9A
108.	GUARD RAIL DETAILS		GR-9
109.	GUARD RAIL DETAILS		GR-10
110.	GUARD RAIL DETAILS		GR-10A
111.	GUARD RAIL DETAILS		GR-11
112.	CONCRETE BARRIER WALL (PIER PROTECTION TYPE A)		GR-1
113.	GUARD RAIL DETAILS		IB-1
114.	IMPACT ATTENUATION BARRIER		PCC-1
115.	CONCRETE PIPE CULVERT FILL HEIGHTS & BEDDING		PCM-1
116.	METAL PIPE CULVERT FILL HEIGHTS & BEDDING		PCM-1
117.	PAVEMENT MARKING DETAILS		PM-1
118.	PERMANENT PAVEMENT MARKING ON ACCESS CONTROLLED ROADWAYS		PM-2
119.	TABLE AND METHOD OF SUPERELEVATION FOR ONE-WAY TRAFFIC		SE-1
120.	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-1
121.	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-2
122.	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-3
123.	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION-TEMPORARY PRECAST BARRIER		TC-4
124.	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION-TEMPORARY PRECAST BARRIER		TC-5
125.	TEMPORARY EROSION CONTROL DEVICES		TEC-1
126.	TEMPORARY EROSION CONTROL DEVICES		TEC-2
127.	TEMPORARY EROSION CONTROL DEVICES		TEC-3
128.	DETAILS OF STANDARD TURNOUT FOR ENTRANCE & EXIT RAMP (NON-REINFORCED)		TR-1A
129.	WIRE FENCE TYPE A AND B		WF-1
130.	WIRE FENCE TYPE C AND D		WF-4

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
				JOB NO.		BBO113	2	130	
(2)								INDEX OF SHEETS	



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
2-19-2015				6	ARK.			
				JOB NO.	BBO113	3	130	

2 GOVERNING SPECIFICATIONS AND GENERAL NOTES



### GOVERNING SPECIFICATIONS

ARKANSAS STATE HIGHWAY COMMISSION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EDITION OF 2014, AND THE FOLLOWING SPECIAL PROVISIONS AND SUPPLEMENTAL SPECIFICATIONS:

NUMBER	TITLE
ERRATA	ERRATA FOR THE BOOK OF STANDARD SPECIFICATIONS
FHWA-1273	REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - NOTICE TO CONTRACTORS
FHWA-1273	SUPPLEMENT - SPECIFIC EQUAL EMPLOYMENT OPPORTUNITY RESPONSIBILITIES (23 U.S.C. 140)
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - GOALS AND TIMETABLES
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - FEDERAL STANDARDS
FHWA-1273	SUPPLEMENT - TRAINING PROGRAM - JOB BB0113
FHWA-1273	SUPPLEMENT - POSTERS AND NOTICES REQUIRED FOR FEDERAL-AID PROJECTS
FHWA-1273	SUPPLEMENT - WAGE RATE DETERMINATION
108-1	LIQUIDATED DAMAGES
410-1	CONSTRUCTION REQUIREMENTS AND ACCEPTANCE OF ASPHALT CONCRETE PLANT MIX COURSES
604-1	RETROREFLECTIVE SHEETING FOR TRAFFIC CONTROL DEVICES IN CONSTRUCTION ZONES
620-1	MULCH COVER
JOB BB0113	ASSESSMENT OF WORKING DAYS - SATURDAYS
JOB BB0113	AUTOMATED WORK ZONE INFORMATION SYSTEM
JOB BB0113	BRIDGE CONSTRUCTION CONTROL
JOB BB0113	BROADBAND INTERNET SERVICE FOR ASPHALT CONCRETE PLANT
JOB BB0113	BROADBAND INTERNET SERVICE FOR FIELD OFFICE
JOB BB0113	CONSTRUCTION IN SPECIAL FLOOD HAZARD AREAS
JOB BB0113	COORDINATION OF WORK
JOB BB0113	DISADVANTAGED BUSINESS ENTERPRISE BIDDER'S RESPONSIBILITIES
JOB BB0113	EMPLOYMENT REPORTING
JOB BB0113	FURNISH AND OPERATION OF MOBILE SPEED NOTIFICATION SYSTEM
JOB BB0113	GOALS FOR DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION
JOB BB0113	HIGH PERFORMANCE PAVEMENT MARKING
JOB BB0113	MAINTENANCE OF TRAFFIC
JOB BB0113	MANDATORY USE OF INTERNET BIDDING
JOB BB0113	MODULAR GLARE SHIELD
JOB BB0113	NESTING SITES OF MIGRATORY BIRDS
JOB BB0113	PARTNERING REQUIREMENTS
JOB BB0113	PAVEMENT REINFORCEMENT SYSTEM
JOB BB0113	PERCENT WITHIN LIMITS
JOB BB0113	PORTABLE CONSTRUCTION LIGHTING
JOB BB0113	PROSECUTION AND PROGRESS
JOB BB0113	REMOVAL AND DISPOSAL OF GUARDRAIL
JOB BB0113	REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT
JOB BB0113	ROADWAY CONSTRUCTION CONTROL
JOB BB0113	SECTION 404 NATIONWIDE 23 PERMIT REQUIREMENTS
JOB BB0113	SEQUENCE OF CONSTRUCTION
JOB BB0113	SITE USE (A + C METHOD)
JOB BB0113	SOIL STABILIZATION
JOB BB0113	SPECIAL SAFETY REQUIREMENTS FOR BRIDGES
JOB BB0113	STORM WATER POLLUTION PREVENTION PLAN
JOB BB0113	SUBMISSION OF ASPHALT CONCRETE HOT MIX ACCEPTANCE TEST RESULTS
JOB BB0113	TEMPORARY PORTLAND CEMENT CONCRETE PAVEMENT
JOB BB0113	TRAFFIC CONTROL DEVICES IN CONSTRUCTION ZONES
JOB BB0113	TRENCHING AND SHOULDER PREPARATION
JOB BB0113	UTILITY ADJUSTMENTS
JOB BB0113	VALUE ENGINEERING
JOB BB0113	WARM MIX ASPHALT
JOB BB0113	WELLHEAD PROTECTION

### GENERAL NOTES

- GRADE LINE DENOTES FINISHED GRADE WHERE SHOWN ON PLANS.
- ALL PIPE LINES, POWER, TELEPHONE, AND TELEGRAPH LINES TO BE MOVED OR LOWERED BY THE RESPECTIVE OWNERS AS PER AGREEMENT WITH SUCH OWNERS.
- ANY EQUIPMENT OR APPURTENANCE THAT INTERFERES WITH THE PROPOSED CONSTRUCTION AND WHICH MAY BE THE PROPERTY OF UTILITY SERVICE ORGANIZATIONS SHALL BE MOVED BY THE OWNERS UNLESS OTHERWISE PROVIDED.
- ALL LAND MONUMENTS LOCATED WITHIN THE CONSTRUCTION AREA SHALL BE PROTECTED IN ACCORDANCE WITH SECTION 107.12 OF THE STANDARD SPECIFICATIONS.
- ALL TREES THAT DO NOT DIRECTLY INTERFERE WITH THE PROPOSED CONSTRUCTION SHALL BE SPARED AS DIRECTED BY THE ENGINEER. CARE AND DISCRETION SHALL BE USED TO INSURE THAT ALL TREES NOT TO BE REMOVED SHALL BE HARMED AS LITTLE AS POSSIBLE DURING THE CONSTRUCTION OPERATIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A FENCE TO CONTROL LIVESTOCK IN AREAS WHERE PASTURES ARE SEVERED. WIRE FENCE MAY BE CONSTRUCTED INITIALLY, OR IN LIEU THEREOF, THE CONTRACTOR AT HIS OWN EXPENSE, MAY ELECT TO PROVIDE TEMPORARY FENCING SUITABLE TO CONTAIN LIVESTOCK.
- ALL FLEXIBLE BASE AND ASPHALTIC PAVEMENTS REMOVED SHALL BE PAID FOR UNDER THE ITEM NO. 210 - UNCLASSIFIED EXCAVATION.
- THE EXISTING ASPHALT PAVEMENT TO BE REMOVED FROM THE REMAINING PAVEMENT SHALL BE SEPARATED BY SAWING ALONG A NEAT LINE. AFTER SAWING, THE PAVEMENT TO BE REMOVED SHALL BE CAREFULLY REMOVED IN A MANNER THAT WILL NOT DAMAGE THE PAVEMENT THAT IS TO REMAIN. ANY DAMAGE OF THE ASPHALT PAVEMENT THAT IS TO REMAIN IN PLACE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.


GOVERNING SPECIFICATIONS  
AND GENERAL NOTES

JACOBS

I:\Job\WI\X12500\_AHTD\_Or-Call\2011Task\_Or-der\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\1041.s01.dgn  
 12/9/2014 3:06:35 PM

DATE REVISED	DATE FILED	DATE REVISED	DATE FILED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	4	130	


② TYPICAL SECTIONS OF IMPROVEMENT



LEFT MAIN LANES  
 STA. 5085+00.00 TO STA. 5091+25.00  
 STA. 5091+75.00 TO STA. 5092+35.00  
 STA. 5129+20.00 TO STA. 5131+00.00

RIGHT MAIN LANES  
 STA. 5085+00.00 TO STA. 5091+25.00  
 STA. 5091+75.00 TO STA. 5092+35.00  
 STA. 5127+40.00 TO STA. 5131+00.00

NOTES:  
 THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.  
 THE CONTRACTOR SHALL REPAIR ANY SLOPES DAMAGED DURING THE CONSTRUCTION OPERATIONS. NO PAYMENT WILL BE MADE FOR SLOPE REPAIR.





LEFT MAIN LANES  
 STA. 5092+35.00 TO STA. 5094+75.00

RIGHT MAIN LANES  
 STA. 5092+35.00 TO STA. 5094+75.00  
 STA. 5123+80.00 TO STA. 5127+40.00

T:\Job\W\XM2600\_AHTD\_On-Call\2011 Task Order\_B003\ShellLake\700\_CADD\_Files\777\_Roadway\Drawings\04\ts01.dgn 12/9/2014 3:06:53 PM

DATE REVISED	DATE FILED	DATE REVISED	DATE FILED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113		5	130


② TYPICAL SECTIONS OF IMPROVEMENT



LEFT MAIN LANE  
 STA. 5094+75.00 TO STA. 5099+16.47  
 STA. 5115+72.73 TO STA. 5121+60.00  
 STA. 5123+80.00 TO STA. 5129+20.00

RIGHT MAIN LANES  
 STA. 5094+75.00 TO STA. 5099+16.47  
 STA. 5115+72.73 TO STA. 5123+80.00

NOTES:  
 THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.  
 THE CONTRACTOR SHALL REPAIR ANY SLOPES DAMAGED DURING THE CONSTRUCTION OPERATIONS. NO PAYMENT WILL BE MADE FOR SLOPE REPAIR.




LEFT MAIN LANES  
 STA. 5091+25.00 TO STA. 5091+75.00

RIGHT MAIN LANES  
 STA. 5091+25.00 TO STA. 5091+75.00


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		6	130
				JOB NO.	BBO113		6	130

② TYPICAL SECTIONS OF IMPROVEMENT




TEMPORARY PAVEMENT  
FOR MAINTENANCE OF TRAFFIC  
STA. 5094+75.00 TO STA. 5104+26.86  
STA. 5110+62.34 TO STA. 5121+60.00

NOTE:  
REFER TO SHEET I3 FOR  
ADDITIONAL INFORMATION.



TYPICAL SECTION OF SHOULDER RECONSTRUCTION  
(SHOWN IN DIRECTION OF TRAFFIC)

LT. MAIN LANES	RT. MAIN LANES
STA. 5094+75.00 TO STA. 5103+66.47	STA. 5094+75.00 TO STA. 5103+66.47
STA. 5111+22.72 TO STA. 5121+60.00	STA. 5111+22.73 TO STA. 5123+80.00
STA. 5123+80.00 TO STA. 5129+20.00	



TYPICAL SECTION OF SHOULDER RECONSTRUCTION  
FOR MAINTENANCE OF TRAFFIC  
(SHOWN IN DIRECTION OF TRAFFIC)

LT. MAIN LANES	RT. MAIN LANES
STA. 5092+35.00 TO STA. 5103+95.31	STA. 5092+35.00 TO STA. 5104+58.33
*STA. 5110+30.36 TO STA. 5121+26.94	STA. 5110+93.86 TO STA. 5116+56.62
STA. 5120+00.00 TO STA. 5128+54.66	STA. 5118+35.16 TO STA. 5127+40.00

T:\job\WL\XM2600\_AHTD\_0n-Call 2011 Task Order\_B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\04\rs01.dgn 12/9/2014 3:07:03 PM




T:\Job\WI\2600\_AHTD On-Call 2011 Task Or der 8003\Shell\Task\_Or der\_8003\Drawings\041s01.dgn  
 12/9/2014 3:07:28 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	8	130	

2 TYPICAL SECTIONS OF IMPROVEMENT




\*DENSITY REQUIREMENTS WAIVED.



FULL DEPTH RECONSTRUCTION  
HWY. 149 INTERCHANGE RAMP

RAMP 1 STA. 5109+30.00 TO STA. 5120+87.86  
RAMP 4 STA. 5114+90.00 TO STA. 5118+30.20



FULL DEPTH RECONSTRUCTION  
HWY. 149 INTERCHANGE RAMP

RAMP 1 STA. 5120+87.86 TO STA. 5128+34.88  
RAMP 2 STA. 5120+88.20 TO STA. 5126+88.45  
RAMP 3 STA. 5118+29.38 TO STA. 5123+77.93  
RAMP 4 STA. 5118+30.20 TO STA. 5127+36.17

TYPICAL SECTIONS OF IMPROVEMENT








DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	10	130	

2 SPECIAL DETAILS




\*NOTE: REFER TO SHEET 13 FOR ADDITIONAL INFORMATION.

12/9/14




TYPICAL LAYOUT OF GUARDRAIL ALONG ROADWAY



SECTION DETAIL OF WIDENING FOR GUARDRAIL

NOTE: REFER TO STANDARD DRAWINGS, GR-8, GR-8A, GR-9, GR-9A, GR-10, GR-10A FOR ADDITIONAL INFORMATION.




TYPICAL LAYOUT OF GUARDRAIL AT BRIDGE ENDS

\*NOTE: WHEN LENGTH OF GUARDRAIL EXCEEDS 200', FLATTEN TAPER TO MAINTAIN 14'-6" OFFSET AT APPROACH END.

I:\Job\WI.XM2600.AHTD On-Call 2011 Task Order\B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\04special details.dgn 12/9/2014 3:08:44 PM ... \04special details.dgn


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	II	130	

2 SPECIAL DETAILS




I:\Job\WI.XM2600.AHTD On-Call 2011 Task 0-der\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04special details.dgn 12/9/2014 3:08:22 PM ... \04special details.dgn


- NOTES FOR MEDIAN BARRIER:
1. ALL EXPOSED EDGES SHALL HAVE  $\frac{3}{4}$ " CHAMFERS.
  2. CONTRACTION JOINTS SHALL BE CONSTRUCTED AT 15'-0" MAXIMUM SPACING IN TOP AND SIDES OF MEDIAN BARRIER AND SHALL BE FORMED IN FRESH CONCRETE.
  3. CONTRACTION JOINTS ARE NOT PERMITTED AT THE DOWEL BAR LOCATIONS.
  4. ALL REINFORCING BARS SHALL HAVE 2" MINIMUM COVER.
  5. DOWEL BARS WILL NOT BE REQUIRED IF BARRIER AND BASE ARE CAST AS A COMPLETE UNIT.
  6. DRAINAGE OPENINGS TO BE CONSTRUCTED ADJACENT TO TYPE ST DROP INLETS. DOWEL BARS SHALL NOT BE PLACED WITHIN 3" OF DRAINAGE OPENINGS.




PLAN VIEW  
CONCRETE BARRIER WALL (MEDIAN TYPE SPECIAL) TRANSITION  
NOTE: TRANSITION TO BE CONSTRUCTED AT BEGINNING AND END OF BARRIER WALL.



CONTRACTION JOINT DETAIL



CONCRETE BARRIER WALL (MEDIAN TYPE SPECIAL) (SECTION A-A)  
NOTE: 4" HEIGHT DIMENSION WILL COINCIDE WITH PROPOSED CONCRETE ISLAND HEIGHT DIMENSION.





CONCRETE BARRIER WALL (MEDIAN TYPE SPECIAL) (SECTION B-B)

P.C.C. PAVM'T. (9" U.T.)  
(RAMP TYPICAL SECTION)  
ACHM SURF. CRSE. (3/8")  
110 LBS./SQ.YD.  
CEM. STAB. CRUSHED  
STONE BASE CRSE.  
(6" U.T.)


I:\Job\1\XM2600\_AHTD\_On-Call 2011 Task\_Order\_8003\Shell\lake\700\_CADD\_Files\777\_Roadway\Drawings\104special details.dgn  
 12/9/2014 3:08:30 PM  
 ...104special details.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	12	130	


② SPECIAL DETAILS




PLAN






SECTION B-B



SECTION A-A



LOCATION PLAN OF RUMBLE STRIPS  
LEFT OR RIGHT SHOULDER



PLAN VIEW

NOTES:

1. ALIGNMENT OF RUMBLE STRIPS SHALL GENERALLY BE STRAIGHT AND OFFSET APPROXIMATELY 4" FROM THE OUTER EDGE OF THE EDGE LINE. THIS OFFSET MAY BE ADJUSTED TO ACCOMMODATE VARIATIONS IN THE EDGE LINE AS WELL AS TO AVOID EXISTING LONGITUDINAL JOINTS.
2. THE 1/2" DEPTH SHALL GENERALLY APPLY FOR THE ENTIRE 16" LENGTH. SOME VARIATIONS TO SUIT SHOULDER SLOPE BREAKS MAY BE NECESSARY.
3. RUMBLE STRIPS SHALL NOT BE INSTALLED ON BRIDGE DECKS, APPROACH GUTTERS, OR ACROSS TRANSVERSE JOINTS OF CONCRETE SHOULDERS.


DETAILS OF RUMBLE STRIPS

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	13	130	


2 SPECIAL DETAILS



NOTE: THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THAT THE MINIMUM 16'-0" VERTICAL CLEARANCE IS OBTAINED BETWEEN THE FINAL PAVEMENT GRADE AND THE BOTTOM OF THE STRUCTURE.



PAVEMENT TRANSITION AT OVERPASSES  
STA. 5089+25.00 TO STA. 5093+75.00





NOTE: THE TEMPORARY PORTLAND CEMENT CONCRETE PAVEMENT SHALL BE CONSTRUCTED IN SUCH A WAY AS TO MATCH THE FINAL SURFACE OF THE PAVEMENT TRANSITION AT FISHING LAKE BRIDGE. TEMPORARY PORTLAND CEMENT CONCRETE PAVEMENT OUTSIDE THE TRANSITION SHALL MATCH THE EXISTING SURFACE.

PAVEMENT TRANSITION AT SHELL LAKE BRIDGE  
BRIDGE NO. 06939  
STA. 5099+16.47 TO STA. 5104+16.47  
STA. 5110+72.73 TO STA. 5115+72.73

T:\Job\W\XMP2600\_AHTD\_On-Call\2011 Task Order\_8003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\104special details.dgn 12/9/2014 3:08:47 PM


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	14	130	

2 SPECIAL DETAILS




THE CONTRACTOR SHALL NOT PLACE EMBANKMENT AROUND THE EXISTING SIGN POSTS TO A DEPTH SUCH THAT THE STUB POST BASE PLATE IS BURIED.

DETAILS FOR THE MAINTENANCE OF EXISTING BREAKAWAY SIGN STRUCTURES




PAVEMENT TRANSITION FOR BEGINNING & ENDING OF PROJECT

STA. 5083+00.00 TO STA. 5085+00.00  
STA. 5129+00.00 TO STA. 5131+00.00



SPECIAL DETAIL OF APPROACH SLAB





DETAILS OF JOINT SUPPORT

T:\Job\VI\_XM2600\_AHTD\_On-Call\2011 Task Order\_B003\ShellLake\700\_CADD\_Files\777\_Roadway\Drawings\104special details.dgn 12/9/2014 3:08:59 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		15	130
				JOB NO.	BBO113			

TEMPORARY EROSION CONTROL DETAILS



REVISIONS

DATE	REVISION

LEGEND

	DROP INLET SILT FENCE
	SILT FENCE

STA. 5085+00.00  
BEGIN JOB BBO113  
LOG MILE 259.38


TEMPORARY EROSION CONTROL DETAILS  
PRIOR TO CONSTRUCTION

T:\Job\WL\XM2600\_AHTD\_On-Call\2011Task\_Order\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04\_erosioncontrol\04\_erosioncontrol.dgn  
 12/9/2014 3:09:21 PM

T:\Job\WLM2600\_AHTD\_On-Call\2011 Task Order\B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04\erosioncontrol\2.dgn  
 12/9/2014 3:09:51 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	16	130	

② TEMPORARY EROSION CONTROL DETAILS



STA. 5131+00.00  
END JOB BBO113  
LOG MILE 260.25

BRIDGES  
3902A & B  
ARE  
EXCEPTIONS

REVISIONS

DATE	REVISION

LEGEND

- (E-7) DROP INLET SILT FENCE
- (E-11) SILT FENCE



TEMPORARY EROSION CONTROL DETAILS  
PRIOR TO CONSTRUCTION



T:\Job\WL\XM2600\_AHTD\_On-Cell\Task\_Order\8003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\104erosioncontrol\17.dgn 12/9/2014 3:10:09 PM ...104erosioncontrol\17.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB013	17	130	

2 TEMPORARY EROSION CONTROL DETAILS



REVISIONS	
DATE	REVISION

LEGEND	
	ROCK DITCH CHECK
	SILT FENCE


TEMPORARY EROSION CONTROL DETAILS  
 HWY. 149 INTERCHANGE RAMP  
 RECONSTRUCTION - STAGE 1A



I:\Job\WLM2600\_AHTD\_On-Call\2011 Task Order\_B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\04erosioncontrol\07.dgn 12/9/2014 3:10:34 PM ...\\04erosioncontrol\07.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	18	130	

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS	
DATE	REVISION

LEGEND	
	ROCK DITCH CHECK
	SILT FENCE


TEMPORARY EROSION CONTROL DETAILS  
 HWY. 149 INTERCHANGE RAMP  
 RECONSTRUCTION - STAGE 1B  
**JACOBS**

T:\Job\W\XM2600\_AHTD\_On-Cell\2011Task\_Order\_8003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04erosioncontrol\7.dgn 12/9/2014 3:10:45 PM ...104erosioncontrol\7.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BBO113	19	130

② TEMPORARY EROSION CONTROL DETAILS

STATE OF ARKANSAS  
 REGISTERED PROFESSIONAL ENGINEER  
 No. 11427  
 KEVIN G. TOBLESKY  
 12/9/14



REVISIONS	
DATE	REVISION

LEGEND	
	ROCK DITCH CHECK
	SILT FENCE


TEMPORARY EROSION CONTROL DETAILS  
 HWY. 149 INTERCHANGE RAMP  
 RECONSTRUCTION - STAGE 2A



12/9/2014 3:11:44 PM T:\Job\W\XM2600 AHTD On-Cell\2011 Task Order\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04mot\_advance\_warning\_sign.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	21	130	
				② MAINTENANCE OF TRAFFIC				

NOTE: THESE SIGNS MAY BE TEMPORARILY REPLACED BY SOME OF THE ADVANCE SIGNS FOR LANE CLOSURES WHILE WORK IS UNDER WAY IN THESE AREAS.



PORTABLE CHANGEABLE MESSAGE SIGN AS DIRECTED BY THE ENGINEER

PORTABLE CHANGEABLE MESSAGE SIGN AS DIRECTED BY THE ENGINEER

(LIMITS OF LANE CLOSURE TAPERS)

NOTE: THESE SIGNS MAY BE TEMPORARILY REPLACED BY SOME OF THE ADVANCE SIGNS FOR LANE CLOSURES WHILE WORK IS UNDER WAY IN THESE AREAS.

ADVANCE SIGNS AT BEGINNING AND END OF JOB BBO13 ALL STAGES

MAINTENANCE OF TRAFFIC ADVANCE WARNING SIGNS


12/9/2014 3:42:01 PM T:\Job\WL\XM2600 AHTD On-Call 2011 Task Order\_B003\ShellLake\700\_CADD\_Files\777\_Roadway\Drawings\104mot\_advance\_warning\_sign.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		22	130
				JOB NO.	BBO13			

② MAINTENANCE OF TRAFFIC




12/9/14




NOTE: MAINTAIN MINIMUM 12' LANE WIDTH ON LANE REMAINING OPEN.

PORTABLE CHANGEABLE MESSAGE SIGN TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER

SPEED LIMIT SIGNS ARE ALSO PROVIDED FOR PLACEMENT PAST ENTRANCE RAMP WITHIN THE WORK ZONE.



DIVERSION FOR RT. LANE WORK ZONE





DIVERSION FOR LT. LANE WORK ZONE

12/9/2014 3:12:20 PM T:\Job\WL\XM2600\_AHTD\_0n-Call\2011 Task Order\_B003\Shell Lake\700\_CADD Files\777\_Roadway\Drawings\104mot\_advance\_warning\_sign.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	23	130	

② MAINTENANCE OF TRAFFIC





- HWY. 149 INTERCHANGE
- E.B. ENTRANCE RAMP = 25 TRAFFIC DRUMS
  - E.B. EXIT RAMP = 21 TRAFFIC DRUMS
  - W.B. ENTRANCE RAMP = 25 TRAFFIC DRUMS
  - W.B. EXIT RAMP = 21 TRAFFIC DRUMS

MAINTENANCE OF TRAFFIC  
DETAIL OF RAMPS WITH LANE CLOSURE

12/9/2014 3:42:35 PM ...\\04mot advance warning sign.dgn ...\\04mot advance warning sign.dgn I:\job\WLM2600\_AHTD\_On-Call\Task\_Order\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04mot advance warning sign.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		24	130
				JOB NO.	BB013		24	130
				② MAINTENANCE OF TRAFFIC				

STATE OF ARKANSAS  
 REGISTERED PROFESSIONAL ENGINEER  
 No. 11427  
 KEVIN G. TOBLESKY  
 12/9/14



MAINTENANCE OF TRAFFIC  
 ADVANCE WARNING SIGNS  
 HWY. 149



12/9/2014 3:04 PM I:\job\WLM\2600\_AHTD\_On-Call\2011Task\_Order\B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\04mot\_bridge\_construction.dgn

STAGE 1B  
 REMOVAL OF PERMANENT PAVEMENT MARKINGS  
 YELLOW 4" CONTINUOUS = 3230 LIN. FT.  
 WHITE 4" CONTINUOUS = 3230 LIN. FT.  
 WHITE 4" SKIP = 1620 LIN. FT.  
 WHITE 4" DOT = 468 LIN. FT.  
 CONSTRUCTION PAVEMENT MARKINGS  
 YELLOW 4" CONTINUOUS = 3230 LIN. FT.  
 WHITE 4" CONTINUOUS = 3230 LIN. FT.  
 WHITE 4" SKIP = 1620 LIN. FT.  
 WHITE 4" DOT = 468 LIN. FT.  
 FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER = 5726 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 2 EACH

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BBO113							25	130

② MAINTENANCE OF TRAFFIC



NOTE:  
 SEE SPECIAL DETAILS SHEET 13  
 FOR MEDIAN CONSTRUCTION  
 STA. 5099+16.47 TO STA. 5115+72.73



STA. 5085+00.00  
 BEGIN JOB BBO112  
 LOG MILE 259.38

SEQUENCE OF CONSTRUCTION FOR BRIDGE CONSTRUCTION

- STAGE 1A  
 INSTALL ADVANCE WARNING SIGNS.  
 PLACE TEMPORARY TRAFFIC CONTROL DEVICES.  
 ROUTE 1-40 TRAFFIC TO INSIDE LANE OF W.B. AND E.B. LANES.  
 TRENCH AND SHOULDER PREPARATION OF OUTSIDE SHOULDERS FOR M.O.T.  
 CONSTRUCT TEMPORARY RAMP 2 FOR M.O.T.
- STAGE 1B  
 ROUTE 1-40 E.B. & W.B. TRAFFIC TO OUTSIDE LANE AND SHOULDER.  
 PLACE P.C.C.B. WALL.  
 CONSTRUCT APPROACH AND PORTION OF BRIDGE IN MEDIAN.
- STAGE 2  
 RELOCATE P.C.C.B. WALL.  
 CONSTRUCT PORTION OF APPROACH ON OFF END OF SHELL LAKE BRIDGE PRIOR TO SHIFTING OF TRAFFIC.  
 ROUTE 1-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
 CONSTRUCT APPROACH AND E.B. PORTION OF BRIDGE.  
 INSTALL GUARDRAIL.  
 PLACE PORTION OF PAVEMENT TRANSITION ON E.B. LANES UTILIZING ONE LANE OF TRAFFIC.
- STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE 1-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED BRIDGE AND EXISTING E.B. LANES.  
 ROUTE 1-40 W.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
 CONSTRUCT APPROACH AND W.B. PORTION OF BRIDGE.  
 INSTALL GUARDRAIL.
- STAGE 4A  
 ROUTE 1-40 E.B. AND 1-40 W.B. TO EXISTING LANES.  
 REFER TO MAINTENANCE OF TRAFFIC HWY. 149 INTERCHANGE RAMP RECONSTRUCTION SHEETS.
- STAGE 4B  
 REMOVE TEMPORARY PAVEMENT IN MEDIAN.  
 CONSTRUCT INSIDE SHOULDER.
- STAGE 5  
 MILL AND INLAY & FINAL LIFT OF INSIDE LANES.  
 PLACE FINAL INSIDE LANE EDGE STRIPING.  
 MILL AND INLAY & FINAL LIFT OF OUTSIDE LANES.  
 PLACE FINAL SKIP & OUTSIDE LANE EDGE STRIPING.



STA. 5126+00 INSTALL  
 18" X 10" TEMPORARY CULV'T.  
 STA. 5131+00.00  
 END JOB BBO112  
 LOG MILE 260.25

MAINTENANCE OF TRAFFIC  
 BRIDGE CONSTRUCTION  
 STAGE IB - SHELL LAKE

12/9/2014 3:33:18 PM ...:\04mot bridge construction.dgn T:\job\WL\M2600 AHTD On-Call\2011Task Order\_B003\ShellLake\700 CADD Files\777 Roadway\Drawings\04mot bridge construction.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	26	130	

② MAINTENANCE OF TRAFFIC





STAGE 2  
 REMOVABLE CONSTRUCTION PAVEMENT MARKINGS  
 YELLOW 4" CONTINUOUS = 2362 LIN. FT.  
 WHITE 4" CONTINUOUS = 2362 LIN. FT.  
 WHITE 4" SKIP = 590 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 YELLOW 4" CONTINUOUS = 1200 LIN. FT.  
 WHITE 4" CONTINUOUS = 1200 LIN. FT.  
 WHITE 4" SKIP = 300 LIN. FT.  
 FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER = 2680 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 2583 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH  
 TEMPORARY IMPACT ATTENUATION BARRIER (RELOCATION) = 1 EACH

STA. 5085+00.00  
 BEGIN JOB BBO112  
 LOG MILE 259.38

SEQUENCE OF CONSTRUCTION FOR BRIDGE CONSTRUCTION

- STAGE 1A  
 INSTALL ADVANCE WARNING SIGNS.  
 PLACE TEMPORARY TRAFFIC CONTROL DEVICES.  
 ROUTE 1-40 TRAFFIC TO INSIDE LANE OF W.B. AND E.B. LANES.  
 TRENCH AND SHOULDER PREPARATION OF OUTSIDE SHOULDERS FOR M.O.T.  
 CONSTRUCT TEMPORARY RAMP 2 FOR M.O.T.
- STAGE 1B  
 ROUTE 1-40 E.B. & W.B. TRAFFIC TO OUTSIDE LANE AND SHOULDER.  
 PLACE P.C.C.B. WALL.  
 CONSTRUCT APPROACH AND PORTION OF BRIDGE IN MEDIAN.
- STAGE 2  
 RELOCATE P.C.C.B. WALL.  
 CONSTRUCT PORTION OF APPROACH ON OFF END OF SHELL LAKE BRIDGE PRIOR TO SHIFTING OF TRAFFIC.  
 ROUTE 1-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
 CONSTRUCT APPROACH AND E.B. PORTION OF BRIDGE.  
 INSTALL GUARDRAIL.  
 PLACE PORTION OF PAVEMENT TRANSITION ON E.B. LANES UTILIZING ONE LANE OF TRAFFIC.
- STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE 1-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED BRIDGE AND EXISTING E.B. LANES.  
 ROUTE 1-40 W.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
 CONSTRUCT APPROACH AND W.B. PORTION OF BRIDGE.  
 INSTALL GUARDRAIL.
- STAGE 4A  
 ROUTE 1-40 E.B. AND 1-40 W.B. TO EXISTING LANES.  
 REFER TO MAINTENANCE OF TRAFFIC HWY. 149 INTERCHANGE RAMP RECONSTRUCTION SHEETS.
- STAGE 4B  
 REMOVE TEMPORARY PAVEMENT IN MEDIAN.  
 CONSTRUCT INSIDE SHOULDER.
- STAGE 5  
 MILL AND INLAY & FINAL LIFT OF INSIDE LANES.  
 PLACE FINAL INSIDE LANE EDGE STRIPING.  
 MILL AND INLAY & FINAL LIFT OF OUTSIDE LANES.  
 PLACE FINAL SKIP & OUTSIDE LANE EDGE STRIPING.



CURVE DATA

① PI = 5095+50.28 Δ = 10°00'00" LT. D = 5'15'00" T = 112.94' L = 225.08' PC = 5094+42.68 PT = 5096+57.18	② PI = 5098+21.70 Δ = 10°00'00" RT. D = 5'15'00" T = 97.24' L = 193.97' PC = 5097+24.46 PT = 5099+18.43	③ PI = 5111+86.09 Δ = 12°00'00" RT. D = 5'15'00" T = 114.68' L = 228.56' PC = 5110+73.16 PCC = 5113+01.72	④ PI = 5114+16.40 Δ = 12°00'00" LT. D = 5'15'00" T = 114.68' L = 228.56' PC = 5113+01.72 PT = 5115+30.28
--	---	---	--

STA. 5131+00.00  
 END JOB BBO112  
 LOG MILE 260.25



MAINTENANCE OF TRAFFIC  
 BRIDGE CONSTRUCTION  
 STAGE 2 - SHELL LAKE  
 JACOBS

12/9/2014 3:33:33 PM ...\\04mot\bridge\construction.dgn

STAGE 3  
 REMOVABLE CONSTRUCTION PAVEMENT MARKINGS  
 YELLOW 4' CONTINUOUS = 4070 LIN. FT.  
 WHITE 4' CONTINUOUS = 3751 LIN. FT.  
 WHITE 4' SKIP = 920 LIN. FT.  
 WHITE 4' DOT 234 = LIN. FT.  
 CONSTRUCTION PAVEMENT MARKINGS  
 YELLOW 4' CONTINUOUS = 3230 LIN. FT.  
 WHITE 4' CONTINUOUS = 3230 LIN. FT.  
 WHITE 4' SKIP = 1620 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 YELLOW 4' CONTINUOUS = 1200 LIN. FT.  
 WHITE 4' CONTINUOUS = 1200 LIN. FT.  
 WHITE 4' SKIP = 300 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 5486 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 2 EACH

STA. 5085+00.00  
 BEGIN JOB BBO112  
 LOG MILE 259.38

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BBO113	27
						② MAINTENANCE OF TRAFFIC		



SEQUENCE OF CONSTRUCTION FOR BRIDGE CONSTRUCTION

- STAGE 1A  
 INSTALL ADVANCE WARNING SIGNS.  
 PLACE TEMPORARY TRAFFIC CONTROL DEVICES.  
 ROUTE I-40 TRAFFIC TO INSIDE LANE OF W.B. AND E.B. LANES.  
 TRENCH AND SHOULDER PREPARATION OF OUTSIDE SHOULDERS FOR M. O. T.  
 CONSTRUCT TEMPORARY RAMP 2 FOR M. O. T.
- STAGE 1B  
 ROUTE I-40 E.B. & W.B. TRAFFIC TO OUTSIDE LANE AND SHOULDER.  
 PLACE P.C.C.B. WALL.  
 CONSTRUCT APPROACH AND PORTION OF BRIDGE IN MEDIAN.
- STAGE 2  
 RELOCATE P.C.C.B. WALL.  
 CONSTRUCT PORTION OF APPROACH ON OFF END OF SHELL LAKE BRIDGE PRIOR TO SHIFTING OF TRAFFIC.  
 ROUTE I-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
 CONSTRUCT APPROACH AND E.B. PORTION OF BRIDGE.  
 INSTALL GUARDRAIL.  
 PLACE PORTION OF PAVEMENT TRANSITION ON E.B. LANES UTILIZING ONE LANE OF TRAFFIC.
- STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE I-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED BRIDGE AND EXISTING E.B. LANES.  
 ROUTE I-40 W.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
 CONSTRUCT APPROACH AND W.B. PORTION OF BRIDGE.  
 INSTALL GUARDRAIL.
- STAGE 4A  
 ROUTE I-40 E.B. AND I-40 W.B. TO EXISTING LANES.  
 REFER TO MAINTENANCE OF TRAFFIC HWY. 149 INTERCHANGE RAMP RECONSTRUCTION SHEETS.
- STAGE 4B  
 REMOVE TEMPORARY PAVEMENT IN MEDIAN.  
 CONSTRUCT INSIDE SHOULDER.
- STAGE 5  
 MILL AND INLAY & FINAL LIFT OF INSIDE LANES.  
 PLACE FINAL INSIDE LANE EDGE STRIPING.  
 MILL AND INLAY & FINAL LIFT OF OUTSIDE LANES.  
 PLACE FINAL SKIP & OUTSIDE LANE EDGE STRIPING.

CURVE DATA

① PI = 5096+73.96 Δ = 10°00'00" RT. D = 5'15'00" T = 95.48' L = 190.48' PC = 5095+78.48 PT = 5097+68.96	② PI = 5100+30.52 Δ = 10°00'00" LT. D = 5'15'00" T = 95.48' L = 190.48' PC = 5099+35.04 PT = 5101+25.52	③ PI = 5121+92.42 Δ = 7°30'00" RT. D = 3'00'00" T = 125.18' L = 250.00' PC = 5120+67.24 PT = 5123+17.24	④ PI = 5126+62.89 Δ = 7°30'00" RT. D = 3'00'00" T = 125.18' L = 250.00' PC = 5125+37.71 PT = 5127+87.71	⑤ PI = 5121+44.49 Δ = 58°42'52" LT. D = 200.00' T = 112.50' L = 204.95' PC = 5120+31.99 PT = 5122+36.94
---	---	---	---	---


STA. 5131+00.00  
 END JOB BBO112  
 LOG MILE 260.25

MAINTENANCE OF TRAFFIC  
 BRIDGE CONSTRUCTION  
 STAGE 3 - SHELL LAKE

12/9/2014 3:13:52 PM T:\Job\WLM2600\_AHTD\_Or-Call\2011Task\_Or-der\_B003\ShellLake\700\_CADD\_Files\1777\_Roadway\Drawings\104mot\_brdge\_construction.dgn

STAGE 4B  
REMOVABLE CONSTRUCTION PAVEMENT MARKINGS  
WHITE 4" CONTINUOUS = 646 LIN. FT.  
WHITE 4" SKIP = 160 LIN. FT.  
CONSTRUCTION PAVEMENT MARKINGS  
WHITE 4" CONTINUOUS = 2584 LIN. FT.  
WHITE 4" SKIP = 650 LIN. FT.  
WHITE 4" DOT = 234 LIN. FT.  
RELOCATING PRECAST CONCRETE BARRIER = 7226 LIN. FT.  
TEMPORARY IMPACT ATTENUATION BARRIER (RELOCATION) = 2 EACH

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BBO113	28	130
				② MAINTENANCE OF TRAFFIC				




STA. 5085+00.00  
BEGIN JOB BBO112  
LOG MILE 259.38

SEQUENCE OF CONSTRUCTION FOR BRIDGE CONSTRUCTION

- STAGE 1A  
INSTALL ADVANCE WARNING SIGNS.  
PLACE TEMPORARY TRAFFIC CONTROL DEVICES.  
ROUTE 1-40 TRAFFIC TO INSIDE LANE OF W.B. AND E.B. LANES.  
TRENCH AND SHOULDER PREPARATION OF OUTSIDE SHOULDERS FOR M.O.T.  
CONSTRUCT TEMPORARY RAMP 2 FOR M.O.T.
- STAGE 1B  
ROUTE 1-40 E.B. & W.B. TRAFFIC TO OUTSIDE LANE AND SHOULDER.  
PLACE P.C.C.B. WALL.  
CONSTRUCT APPROACH AND PORTION OF BRIDGE IN MEDIAN.
- STAGE 2  
RELOCATE P.C.C.B. WALL.  
CONSTRUCT PORTION OF APPROACH ON OFF END OF SHELL LAKE BRIDGE PRIOR TO SHIFTING OF TRAFFIC.  
ROUTE 1-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
CONSTRUCT APPROACH AND E.B. PORTION OF BRIDGE.  
INSTALL GUARDRAIL.  
PLACE PORTION OF PAVEMENT TRANSITION ON E.B. LANES UTILIZING ONE LANE OF TRAFFIC.
- STAGE 3  
RELOCATE P.C.C.B. WALL.  
ROUTE 1-40 E.B. TRAFFIC TO NEWLY CONSTRUCTED BRIDGE AND EXISTING E.B. LANES.  
ROUTE 1-40 W.B. TRAFFIC TO NEWLY CONSTRUCTED APPROACH AND BRIDGE IN MEDIAN.  
CONSTRUCT APPROACH AND W.B. PORTION OF BRIDGE.  
INSTALL GUARDRAIL.
- STAGE 4A  
ROUTE 1-40 E.B. AND 1-40 W.B. TO EXISTING LANES.  
REFER TO MAINTENANCE OF TRAFFIC HWY. 149 INTERCHANGE RAMP RECONSTRUCTION SHEETS.
- STAGE 4B  
REMOVE TEMPORARY PAVEMENT IN MEDIAN.  
CONSTRUCT INSIDE SHOULDER.
- STAGE 5  
MILL AND INLAY & FINAL LIFT OF INSIDE LANES.  
PLACE FINAL INSIDE LANE EDGE STRIPING.  
MILL AND INLAY & FINAL LIFT OF OUTSIDE LANES.  
PLACE FINAL SKIP & OUTSIDE LANE EDGE STRIPING.

SPEED LIMIT 60

SPEED LIMIT 60



STA. 5131+00.00  
END JOB BBO112  
LOG MILE 260.25






MAINTENANCE OF TRAFFIC  
BRIDGE CONSTRUCTION  
STAGE 4B - SHELL LAKE

I:\Job\WLM2600\_AHTD On-Call\2011Task\_Order\_8003\ShellLake\700\_CADD Files\777\_Roadway\Drawings\04mot\_ramps.dgn 12/9/2014 3:42:27 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
							JOB NO.	BBO13
							29	130
② MAINTENANCE OF TRAFFIC								

STAGE 1A  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 5023 LIN. FT.  
 YELLOW 4" CONTINUOUS = 4234 LIN. FT.  
 WHITE 8" CONTINUOUS = 1333 LIN. FT.  
 R. P. M. TYPE 11 (CLEAR/RED) = 106 EACH  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 5023 LIN. FT.  
 YELLOW 4" CONTINUOUS = 4234 LIN. FT.  
 WHITE 8" CONTINUOUS = 1333 LIN. FT.  
 R. P. M. TYPE 11 (CLEAR/RED) = 53 EACH

SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION  
 STAGE 1A  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
 PLACE P. C. C. B. WALL ALONG RAMP 2 & 3.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 2 & 3.  
 STAGE 1B  
 ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 PLACE P. C. C. B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 1 & 4.  
 STAGE 2A  
 ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 RECONSTRUCT RAMP 1 & 4.  
 STAGE 2B  
 ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMP.  
 RECONSTRUCT RAMP 2 & 3.  
 REMOVE TEMPORARY RAMP 2.  
 STAGE 3  
 RELOCATE P. C. C. B. WALL.  
 ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMP.  
 REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMP 1, 2, 3, & 4.  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.  
 STAGE 4  
 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.



MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 1A





STAGE 1A  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4' CONTINUOUS = 1818 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4' CONTINUOUS = 1818 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 2095 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH

DENOTES PAVEMENT TO BE  
 CONSTRUCTED

SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION

- STAGE 1A  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
 PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.
- STAGE 1B  
 ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.
- STAGE 2A  
 ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 RECONSTRUCT RAMPS 1 & 4.
- STAGE 2B  
 ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
 RECONSTRUCT RAMPS 2 & 3.  
 REMOVE TEMPORARY RAMP 2.
- STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
 REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.
- STAGE 4  
 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BBO113	30
						MAINTENANCE OF TRAFFIC		



12/19/2014 3:44:39 PM T:\Job\WL\XM2600\_AHTD On-Call\2011 Task Order\_B003\Shell\Task\_0001\Drawings\04mot\_ramps.dgn


MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 1A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	31	130	
MAINTENANCE OF TRAFFIC								



DENOTES PAVEMENT TO BE CONSTRUCTED


BEGIN TEMP. P.C.C.B. WALL STA. 5111+65  
 TEMP. IMPACT ATTENUATION BARRIER



RAMP 3 STA. 5121+00  
 EXTEND EXISTING PIPE WITH 24" x 30" TEMPORARY PIPE

**STAGE 1A**  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1596 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1596 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 1634 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH

- SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION**
- STAGE 1A**  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
PLACE P.C.C.B. WALL ALONG RAMP 2 & 3.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 2 & 3.
  - STAGE 1B**  
ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 1 & 4.
  - STAGE 2A**  
ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
RECONSTRUCT RAMP 1 & 4.
  - STAGE 2B**  
ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMP.  
RECONSTRUCT RAMP 2 & 3.  
REMOVE TEMPORARY RAMP 2.
  - STAGE 3**  
RELOCATE P.C.C.B. WALL.  
ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMP.  
REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMP 1, 2, 3, & 4.  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.
  - STAGE 4**  
REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.




MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 1A

I:\Job\WLM2600\_AHTD\_On-Call\2011Task\_Order\B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04mot\_ramps.dgn  
 ...Drawings\04mot\_ramps.dgn  
 12/9/2014 3:54:55 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	32	130	

② MAINTENANCE OF TRAFFIC





DENOTES PAVEMENT TO BE CONSTRUCTED

**STAGE 1B**  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 645 LIN. FT.  
 YELLOW 4" CONTINUOUS = 546 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 645 LIN. FT.  
 YELLOW 4" CONTINUOUS = 546 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 530 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH

**SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION**

- STAGE 1A**  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.
- STAGE 1B**  
ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
PLACE P.C.C.B. WALL ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.
- STAGE 2A**  
ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
RECONSTRUCT RAMPS 1 & 4.
- STAGE 2B**  
ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
RECONSTRUCT RAMPS 2 & 3.  
REMOVE TEMPORARY RAMP 2.
- STAGE 3**  
RELOCATE P.C.C.B. WALL.  
ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.
- STAGE 4**  
REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.



MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 1B



T:\Job\W\XP2600\_AHTD\_On-Call\Task\_Order\_8003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\104mot\_ramps.dgn  
 12/9/2014 3:45:31 PM

 DENOTES PAVEMENT TO BE CONSTRUCTED

STAGE 1B  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1200 LIN. FT.  
 YELLOW 4" CONTINUOUS = 1000 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1200 LIN. FT.  
 YELLOW 4" CONTINUOUS = 1000 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 1484 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH

SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION

STAGE 1A  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
 PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.

STAGE 1B  
 ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.





STAGE 2A  
 ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 RECONSTRUCT RAMPS 1 & 4.

STAGE 2B  
 ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
 RECONSTRUCT RAMPS 2 & 3.  
 REMOVE TEMPORARY RAMP 2.

STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
 REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.

STAGE 4  
 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113		33	130
				② MAINTENANCE OF TRAFFIC				






MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 1B

T:\Job\WL\2600 AHTD On-Call\2011 Task Order\B003\Shell Lake\700 CADD Files\777 Roadway\Drawings\104mot\_ramps.dgn 12/9/2014 3:15:46 PM


XXXXXX DENOTES PAVEMENT TO BE CONSTRUCTED

STAGE 1B  
CONSTRUCTION PAVEMENT MARKINGS  
WHITE 4" CONTINUOUS = 1148 LIN. FT.  
YELLOW 4" CONTINUOUS = 765 LIN. FT.  
REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
WHITE 4" CONTINUOUS = 1596 LIN. FT.  
YELLOW 4" CONTINUOUS = 765 LIN. FT.  
RELOCATING PRECAST CONCRETE BARRIER = 920 LIN. FT.  
TEMPORARY IMPACT ATTENUATION BARRIER = 2 EACH

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0113	34	130
				② MAINTENANCE OF TRAFFIC				




- SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION
- STAGE 1A
    - REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.
    - PLACE P.C.C.B. WALL ALONG RAMP 2 & 3.
    - CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 2 & 3.
  - STAGE 1B
    - ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.
    - PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.
    - CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 1 & 4.
  - STAGE 2A
    - ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.
    - RECONSTRUCT RAMP 1 & 4.
  - STAGE 2B
    - ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMP.
    - RECONSTRUCT RAMP 2 & 3.
    - REMOVE TEMPORARY RAMP 2.
  - STAGE 3
    - RELOCATE P.C.C.B. WALL.
    - ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMP.
    - REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMP 1, 2, 3, & 4.
    - REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.
  - STAGE 4
    - REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.



SECTION A-A

MAINTENANCE OF TRAFFIC  
HWY. 149 INTERCHANGE  
RAMP RECONSTRUCTION  
STAGE 1B

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	35	130	
				② MAINTENANCE OF TRAFFIC				



SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION

STAGE 1A  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
 PLACE P.C.C.B. WALL ALONG RAMP 2 & 3.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 2 & 3.

STAGE 1B  
 ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 1 & 4.


STAGE 2A  
 ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 RECONSTRUCT RAMP 1 & 4.

STAGE 2B  
 ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMP.  
 RECONSTRUCT RAMP 2 & 3.  
 REMOVE TEMPORARY RAMP 2.

STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMP.  
 REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMP 1, 2, 3, & 4.  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.

STAGE 4  
 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.

STAGE 1B  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 597 LIN. FT.  
 YELLOW 4" CONTINUOUS = 645 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 597 LIN. FT.  
 YELLOW 4" CONTINUOUS = 645 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 1391 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 2 EACH





MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 1B

T:\Job\W\XM2600\_AHTD\_0n-Call\2011Task\_Order\_B003\Shell\laka\1700\_CADD\_Files\777\_Roadway\Drawings\104mot\_ramps.dgn  
 12/9/2014 3:16:04 PM




T:\Job\WLM2600\_AHTD\_On-Call\2011Task\_Order\B003\ShellLake\700\_CADD\_Files\777\_Roadway\Drawings\04mot\_ramps.dgn 12/9/2014 3:16:30 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	37	130	
				② MAINTENANCE OF TRAFFIC				



▨ DENOTES PAVEMENT TO BE CONSTRUCTED




SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION

- STAGE 1A  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.
- STAGE 1B  
ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.
- STAGE 2A  
ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
RECONSTRUCT RAMPS 1 & 4.
- STAGE 2B  
ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
RECONSTRUCT RAMPS 2 & 3.  
REMOVE TEMPORARY RAMP 2.
- STAGE 3  
RELOCATE P.C.C.B. WALL.  
ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.
- STAGE 4  
REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.

STAGE 2A  
REMOVAL OF PERMANENT PAVEMENT MARKINGS = 1200 LIN. FT.  
CONSTRUCTION PAVEMENT MARKINGS  
WHITE 4" CONTINUOUS = 1273 LIN. FT.  
YELLOW 4" CONTINUOUS = 1140 LIN. FT.  
REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
WHITE 4" CONTINUOUS = 1273 LIN. FT.  
YELLOW 4" CONTINUOUS = 1140 LIN. FT.  
RELOCATING PRECAST CONCRETE BARRIER = 1502 LIN. FT.  
TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH

TEMP. RAMP 1

PI	= 5125+31.21
Δ	= 55°11'13" LT.
D	= 10°00'00"
T	= 299.45'
L	= 551.87'
PC	= 5122+31.76
PT	= 5127+83.63




MAINTENANCE OF TRAFFIC  
HWY. 149 INTERCHANGE  
RAMP RECONSTRUCTION  
STAGE 2A

12/9/2014 3:16:45 PM ... Drawings\104mot1\_ramps.dgn ... Job\WL\XMP200\_AHTD On-Cell 2011 Task Order B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\104mot1\_ramps.dgn


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	38	130	

② MAINTENANCE OF TRAFFIC



STAGE 1A  
 REMOVAL OF PERMANENT PAVEMENT MARKINGS = 425 LIN. FT.  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 382 LIN. FT.  
 YELLOW 4" CONTINUOUS = 350 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 382 LIN. FT.  
 YELLOW 4" CONTINUOUS = 350 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 382 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH

☒ DENOTES PAVEMENT TO BE CONSTRUCTED



SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION

STAGE 1A  
 REMOVE AND PLACE PAVEMENT MARKINGS I-40 EB. & WB. LANES.  
 PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.



STAGE 1B  
 ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 PLACE P.C.C.B. ALONG I-40 EB. & WB. OUTSIDE SHOULDER.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.

STAGE 2A  
 ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 RECONSTRUCT RAMPS 1 & 4.

STAGE 2B  
 ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
 RECONSTRUCT RAMPS 2 & 3.  
 REMOVE TEMPORARY RAMP 2.


STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
 REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
 REMOVE AND PLACE PAVEMENT MARKINGS I-40 EB & WB LANES.

STAGE 4  
 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.




MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 2A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BBO113							39	130
② MAINTENANCE OF TRAFFIC								



STAGE 1A  
 REMOVAL OF PERMANENT PAVEMENT MARKINGS = 250 LIN. FT.  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 850 LIN. FT.  
 YELLOW 4" CONTINUOUS = 725 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 850 LIN. FT.  
 YELLOW 4" CONTINUOUS = 725 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 1014 LIN. FT.

⊘ DENOTES PAVEMENT TO BE CONSTRUCTED



① TEMP. RAMP 4  
 PI = 5123+67.14  
 $\Delta$  = 52°22'29" RT.  
 D = 8°15'00"  
 T = 341.54'  
 L = 634.85'  
 PC = 5120+25.60  
 PT = 5126+60.45

SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION

STAGE 1A  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
 PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.


STAGE 1B  
 ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.

STAGE 2A  
 ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 RECONSTRUCT RAMPS 1 & 4.


STAGE 2B  
 ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
 RECONSTRUCT RAMPS 2 & 3.  
 REMOVE TEMPORARY RAMP 2.

STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
 REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.

STAGE 4  
 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.



SECTION A-A




MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 2A


T:\Job\149\MP600\_AHTD\_On-Cell\2011Task\_Order\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04mot\_ramps.dgn  
 12/9/2014 3:16:58 PM

I:\Job\W\X\2600\_AHTD\_0n-Call\2011Task\_Order\_B003\Shell\Lake\_700\_CADD\_Files\777\_Roadway\Drawings\04mot\_ramps.dgn  
 I:\Job\W\X\2600\_AHTD\_0n-Call\2011Task\_Order\_B003\Shell\Lake\_700\_CADD\_Files\777\_Roadway\Drawings\04mot\_ramps.dgn  
 12/9/2014 3:17:11 PM


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO13	40	130	
				② MAINTENANCE OF TRAFFIC				



DENOTES PAVEMENT TO BE CONSTRUCTED



STAGE 2B  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 913 LIN. FT.  
 YELLOW 4" CONTINUOUS = 714 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 913 LIN. FT.  
 YELLOW 4" CONTINUOUS = 714 LIN. FT.  
 RELOCATING PRECAST CONCRETE BARRIER = 775 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 1 EACH



SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION

STAGE 1A  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
 PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.


STAGE 1B  
 ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
 CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.

STAGE 2A  
 ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
 RECONSTRUCT RAMPS 1 & 4.

STAGE 2B  
 ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
 RECONSTRUCT RAMPS 2 & 3.  
 REMOVE TEMPORARY RAMP 2.

STAGE 3  
 RELOCATE P.C.C.B. WALL.  
 ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
 REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
 REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.

STAGE 4  
 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.




MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 2B






I:\Job\WLM2600\_AHTD\_0n-Cell\2011Task\_Order\_B003\ShellLake\700\_CADD\_Files\777\_Roadway\Drawings\104mot\_ramps.dgn 3:17:33 PM 12/9/2014

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		41	130
				JOB NO.	BBO113			
				MAINTENANCE OF TRAFFIC				



DENOTES PAVEMENT TO BE CONSTRUCTED




- SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION
- STAGE 1A  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES.  
PLACE P.C.C.B. WALL ALONG RAMP 2 & 3.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 2 & 3.
  - STAGE 1B  
ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMP 1 & 4.
  - STAGE 2A  
ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
RECONSTRUCT RAMP 1 & 4.
  - STAGE 2B  
ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMP.  
RECONSTRUCT RAMP 2 & 3.  
REMOVE TEMPORARY RAMP 2.
  - STAGE 3  
RELOCATE P.C.C.B. WALL.  
ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMP.  
REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMP 1, 2, 3, & 4.  
REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.
  - STAGE 4  
REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.


MAINTENANCE OF TRAFFIC  
HWY. 149 INTERCHANGE  
RAMP RECONSTRUCTION  
STAGE 2B



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	43	130	
② MAINTENANCE OF TRAFFIC								




T:\Job\11427\11427.dwg Order B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\104mot\_ramps.dwg  
 12/9/2014 3:18:01 PM



MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 2B  
**JACOBS**


T:\Job\WLM\MP2600\_AHTD\_On-Call\2011 Task Order\B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\104mot\_ramps.dgn  
 12/9/2014 3:48:19 PM ...Drawings\104mot\_ramps.dgn

 DENOTES PAVEMENT TO BE REMOVED



STAGE 3  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1818 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1818 LIN. FT.  
 FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER = 2575 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 2 EACH

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	44	130	

② MAINTENANCE OF TRAFFIC




- SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION
- STAGE 1A  
REMOVE AND PLACE PAVEMENT MARKINGS I-40 EB. & WB. LANES.  
PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.
  - STAGE 1B  
ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
PLACE P.C.C.B. ALONG I-40 EB. & WB. OUTSIDE SHOULDER.  
CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.
  - STAGE 2A  
ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T.  
RECONSTRUCT RAMPS 1 & 4.
  - STAGE 2B  
ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS.  
RECONSTRUCT RAMPS 2 & 3.  
REMOVE TEMPORARY RAMP 2.
  - STAGE 3  
RELOCATE P.C.C.B. WALL.  
ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS.  
REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4.  
REMOVE AND PLACE PAVEMENT MARKINGS I-40 EB & WB LANES.
  - STAGE 4  
REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.



MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 3

T:\Job\WLM2600\_AHTD\_On-Call\Task\_Order\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\104mot\_ramps.dgn 12/9/2014 3:18:34 PM




 DENOTES PAVEMENT TO BE REMOVED

STAGE 3  
 CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1596 LIN. FT.  
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS  
 WHITE 4" CONTINUOUS = 1596 LIN. FT.  
 FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER = 2336 LIN. FT.  
 TEMPORARY IMPACT ATTENUATION BARRIER = 4 EACH

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	45	130	
② MAINTENANCE OF TRAFFIC								

STATE OF ARKANSAS  
 REGISTERED PROFESSIONAL ENGINEER  
 No. 11427  
 KEVIN G. TOBLESKY  
 12/9/14

- SEQUENCE OF CONSTRUCTION FOR HWY. 149 RAMP RECONSTRUCTION
- STAGE 1A REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB. & WB. LANES. PLACE P.C.C.B. WALL ALONG RAMPS 2 & 3. CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 2 & 3.
  - STAGE 1B ROUTE RAMP 2 & 3 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T. PLACE P.C.C.B. ALONG 1-40 EB. & WB. OUTSIDE SHOULDER. CONSTRUCT TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1 & 4.
  - STAGE 2A ROUTE RAMP 1 & 4 TRAFFIC TO TEMPORARY PAVEMENT FOR M.O.T. RECONSTRUCT RAMPS 1 & 4.
  - STAGE 2B ROUTE RAMP 1 & 4 TRAFFIC TO RECONSTRUCTED RAMPS. RECONSTRUCT RAMPS 2 & 3. REMOVE TEMPORARY RAMP 2.
  - STAGE 3 RELOCATE P.C.C.B. WALL. ROUTE RAMP 2 & 3 TRAFFIC TO RECONSTRUCTED RAMPS. REMOVE TEMPORARY PAVEMENT FOR M.O.T. RAMPS 1, 2, 3, & 4. REMOVE AND PLACE PAVEMENT MARKINGS 1-40 EB & WB LANES.
  - STAGE 4 REFER TO MAINTENANCE OF TRAFFIC BRIDGE CONSTRUCTION SHEETS.




MAINTENANCE OF TRAFFIC  
 HWY. 149 INTERCHANGE  
 RAMP RECONSTRUCTION  
 STAGE 3




T:\Job\WLM2600\_AHTD\_0n-Call\2011Task\_Order\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04pavementmarking03.dgn  
 12/9/2014 3:19:49 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BBO113	47	130
② PERMANENT PAVEMENT MARKING DETAILS								



NOTE: REFER TO STANDARD DRAWING PM-2 FOR ADDITIONAL INFORMATION.



HIGH PERFORMANCE PAVEMENT MARKINGS	QUANTITY
RAMP 1 & RAMP 2	
4" WHITE CONTINUOUS	3900 L.F.
4" YELLOW CONTINUOUS	3789 L.F.
8" WHITE CONTINUOUS	132 L.F.

HIGH PERFORMANCE PAVEMENT MARKINGS	QUANTITY
RAMP 3 & RAMP 4	
4" WHITE CONTINUOUS	2419 L.F.
4" YELLOW CONTINUOUS	2307 L.F.
8" WHITE CONTINUOUS	185 L.F.

HIGH PERFORMANCE PAVEMENT MARKINGS	QUANTITY
I-40 EASTBOUND LANES	
STA. 5114+62 TO STA. 5137+71	
4" WHITE CONTINUOUS	1394 L.F.
8" WHITE CONTINUOUS	517 L.F.
8" WHITE DOT	54 L.F.
RAISED PAVEMENT MARKERS (TYPE II) WHITE/RED	67 EACH

HIGH PERFORMANCE PAVEMENT MARKINGS	QUANTITY
I-40 WESTBOUND LANES	
STA. 5110+12 TO STA. 5132+29	
4" WHITE CONTINUOUS	1363 L.F.
8" WHITE CONTINUOUS	555 L.F.
8" WHITE DOT	81 L.F.
RAISED PAVEMENT MARKERS (TYPE II) WHITE/RED	75 EACH





I:\Job\W\XP2600\_AHTD\_On-Call\2011\Task\_Order\B003\Shell Lake\700\_CADD\_Files\777\_Roadway\_Drawings\04quantities.dgn 12/9/2014 3:22:00 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		49	130
				JOB NO.	BBO113	49	130	
								QUANTITIES



**REMOVAL AND DISPOSAL OF ITEMS**

FROM			TO			REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT	CONCRETE PAVEMENT	CONCRETE PIER PROTECTION	IMPACT ATTENUATION BARRIER	APPROACH SLAB AND GUTTERS	FENCE	CONCRETE PARAPET WALL	GUARDRAIL
STATION	SIDE	LOCATION	STATION	SIDE	LOCATION	SQ. YD.	SQ. YD.	LIN. FT.	EACH	EACH	LIN. FT.	EACH	LIN. FT.
5091+49	MEDIAN	C.L. MEDIAN I-40							2				
5091+26	RIGHT	RIGHT MAIN LANES I-40	5091+54	RIGHT	RIGHT MAIN LANES I-40			28					
5091+45	LEFT	LEFT MAIN LANES I-40	5091+73	LEFT	LEFT MAIN LANES I-40			28					
5089+01	RIGHT	RIGHT MAIN LANES I-40	5091+26	RIGHT	RIGHT MAIN LANES I-40							225	
5091+73	LEFT	LEFT MAIN LANES I-40	5093+98	LEFT	LEFT MAIN LANES I-40							225	
5104+80	RIGHT	RIGHT MAIN LANES I-40										1	
5104+57	LEFT	RIGHT MAIN LANES I-40										1	
5110+35	RIGHT	LEFT MAIN LANES I-40										1	
5110+44	LEFT	LEFT MAIN LANES I-40										1	
5104+63		RIGHT MAIN LANES I-40								1			
5104+16		LEFT MAIN LANES I-40								1			
5104+81	RIGHT	RIGHT MAIN LANES I-40								60			
5104+34	LEFT	LEFT MAIN LANES I-40								60			
5110+77		RIGHT MAIN LANES I-40								1			
5110+30		LEFT MAIN LANES I-40								1			
5110+59	RIGHT	RIGHT MAIN LANES I-40											
5110+12	LEFT	LEFT MAIN LANES I-40								60			
5112+98	MEDIAN	C.L. MEDIAN I-40							2				
5102+67	RIGHT	RIGHT MAIN LANES I-40	5104+67	RIGHT	RIGHT MAIN LANES I-40								200
5102+44	LEFT	RIGHT MAIN LANES I-40	5104+44	LEFT	RIGHT MAIN LANES I-40								200
5110+71	RIGHT	RIGHT MAIN LANES I-40	5112+71	RIGHT	RIGHT MAIN LANES I-40								200
5110+49	LEFT	RIGHT MAIN LANES I-40	5111+74	LEFT	RIGHT MAIN LANES I-40								125
5110+48	RIGHT	LEFT MAIN LANES I-40	5113+73	RIGHT	LEFT MAIN LANES I-40								325
5110+57	LEFT	LEFT MAIN LANES I-40	5112+32	LEFT	LEFT MAIN LANES I-40								175
5112+83	MEDIAN	C.L. MEDIAN I-40	5113+12	MEDIAN	C.L. MEDIAN I-40			58					
5109+35	LEFT	C.L. RAMP 1	5126+60	LEFT	C.L. RAMP 1								1725
5108+75	RIGHT	C.L. RAMP 1	5121+40	RIGHT	C.L. RAMP 1								1265
5114+80	RIGHT	C.L. RAMP 4	5124+05	RIGHT	C.L. RAMP 4								925
5114+20	LEFT	C.L. RAMP 4	5118+85	LEFT	C.L. RAMP 4								465
5109+30		HWY. 149 INTERCHANGE - RAMP 1	5120+88		HWY. 149 INTERCHANGE - RAMP 1	3860							
5120+88		HWY. 149 INTERCHANGE - RAMP 1	5128+35		HWY. 149 INTERCHANGE - RAMP 1	1245							
5120+88		HWY. 149 INTERCHANGE - RAMP 2	5126+88		HWY. 149 INTERCHANGE - RAMP 2	1001							
5118+29		HWY. 149 INTERCHANGE - RAMP 3	5123+78		HWY. 149 INTERCHANGE - RAMP 3	914							
5114+90		HWY. 149 INTERCHANGE - RAMP 4	5118+30		HWY. 149 INTERCHANGE - RAMP 4	1134							
5118+30		HWY. 149 INTERCHANGE - RAMP 4	5127+36		HWY. 149 INTERCHANGE - RAMP 4	1510							
5099+25	MEDIAN	C.L. MEDIAN I-40	5103+66	MEDIAN	C.L. MEDIAN I-40		3346						
5111+23	MEDIAN	C.L. MEDIAN I-40	5114+25	MEDIAN	C.L. MEDIAN I-40		2418						
5114+25	MEDIAN	C.L. MEDIAN I-40	5129+25	MEDIAN	C.L. MEDIAN I-40		6030						
5121+86		TEMP. RAMP 2 FOR SHELL LAKE BRIDGE RECONS.	5122+82		TEMP. RAMP 2 FOR SHELL LAKE BRIDGE RECONS.		264						
5121+85		HWY. 149 - TEMP. RAMP 1	5127+84		HWY. 149 - TEMP. RAMP 1		1505						
5117+51		HWY. 149 - TEMP. RAMP 2	5137+50		HWY. 149 - TEMP. RAMP 2		6434						
5113+14		HWY. 149 - TEMP. RAMP 3	5127+65		HWY. 149 - TEMP. RAMP 3		4333						
5118+81		HWY. 149 - TEMP. RAMP 4	5126+60		HWY. 149 - TEMP. RAMP 4		1984						
<b>TOTALS:</b>						<b>9664</b>	<b>26314</b>	<b>114</b>	<b>4</b>	<b>4</b>	<b>240</b>	<b>4</b>	<b>6055</b>

**IMPACT ATTENUATION BARRIER**

STATION	LOCATION	(TYPE A) EACH
5103+97	C.L. MEDIAN I-40	1
5110+92	C.L. MEDIAN I-40	1
5112+59	C.L. MEDIAN I-40	1
<b>TOTAL:</b>		<b>3</b>

**BENCH MARKS**

STATION	LOCATION	EACH
5110+60	SHELL LAKE BRIDGE - SE. CORNER	1
<b>TOTAL:</b>		<b>1</b>

NOTE: SHOWN FOR INFORMATION ONLY. BENCH MARKS SHALL BE FURNISHED AND PLACED BY STATE FORCES.

**SELECTED PIPE BEDDING**

LOCATION	CU. YD.
ENTIRE PROJECT - TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER.	40
<b>TOTAL:</b>	<b>40</b>

NOTE: QUANTITIES ESTIMATED. SEE SECTION 104.03 OF THE STD. SPECS.

**TRENCHING & SHOULDER PREPARATION**

STATION	STATION	SIDE	LOCATION	STATION
5092+35.00	5104+58.33	RIGHT	RIGHT MAIN LANES I-40	12
5110+93.86	5116+56.62	RIGHT	RIGHT MAIN LANES I-40	7
5118+35.16	5127+40.00	RIGHT	RIGHT MAIN LANES I-40	10
5092+35.00	5103+95.31	LEFT	LEFT MAIN LANES I-40	12
5110+30.36	5121+26.94	LEFT	LEFT MAIN LANES I-40	12
5120+00.00	5128+54.66	LEFT	LEFT MAIN LANES I-40	9
<b>TOTAL:</b>				<b>62</b>

**TOPSOIL FURNISHED AND PLACED**

STATION	STATION	SIDE	LOCATION	CU. YD.
5085+00.00	5091+25.00	RIGHT	RIGHT MAIN LANES I-40	31
5091+75.00	5104+64.72	RIGHT	RIGHT MAIN LANES I-40	64
5111+00.20	5131+00.00	RIGHT	RIGHT MAIN LANES I-40	99
5085+00.00	5091+25.00	LEFT	RIGHT MAIN LANES I-40	47
5091+75.00	5094+75.00	LEFT	RIGHT MAIN LANES I-40	23
5123+80.00	5131+00.00	LEFT	RIGHT MAIN LANES I-40	54
5085+00.00	5091+25.00	LEFT	LEFT MAIN LANES I-40	31
5091+75.00	5103+89.00	LEFT	LEFT MAIN LANES I-40	60
5110+24.48	5131+00.00	LEFT	LEFT MAIN LANES I-40	103
5085+00.00	5091+25.00	RIGHT	LEFT MAIN LANES I-40	47
5091+75.00	5094+75.00	RIGHT	LEFT MAIN LANES I-40	23
5129+20.00	5131+00.00	RIGHT	LEFT MAIN LANES I-40	14
<b>TOTAL:</b>				<b>596</b>

NOTE: QUANTITIES ESTIMATED. SEE SECTION 104.03 OF THE STD. SPECS.

**STRUCTURES**

STATION	SIDE / LOCATION	DESCRIPTION	TEMPORARY CULVERTS	
			18" LIN. FT.	24" LIN. FT.
5126+00	MEDIAN	INSTALL TEMPORARY CULVERT	10	
5126+00	LT. LANES	EXTEND EXISTING PIPE WITH TEMPORARY CULVERT		20
5124+00	RAMP 2	EXTEND EXISTING PIPE WITH TEMPORARY CULVERT		30
5121+00	RAMP 3	EXTEND EXISTING PIPE WITH TEMPORARY CULVERT		30
5125+52	RAMP 1	INSTALL TEMPORARY CULVERT		60
5123+35	RAMP 4	INSTALL TEMPORARY CULVERT		60
<b>TOTALS:</b>			<b>10</b>	<b>200</b>

NOTE: FOR R.C. PIPE CULVERT INSTALLATIONS USE TYPE 3 BEDDING UNLESS OTHERWISE SPECIFIED.  
NOTE: FOR C.M. PIPE CULVERT INSTALLATIONS USE TYPE 2 BEDDING UNLESS OTHERWISE SPECIFIED.

**GUARDRAIL**

STATION	STATION	SIDE	LOCATION	GUARDRAIL (TYPE A)	THRIE BEAM GUARDRAIL TERMINAL	GUARDRAIL TERMINAL (TYPE 2)	TERMINAL ANCHOR POST (TYPE 1)
				LIN. FT.		EACH	
5088+57.85	5091+26.60	RIGHT	RIGHT MAIN LANES I-40	200	1		
5087+49.00	5092+49.00	LEFT	RIGHT MAIN LANES I-40	450		1	1
5090+49.00	5095+49.00	RIGHT	LEFT MAIN LANES I-40	450		1	1
5091+72.40	5094+41.15	LEFT	LEFT MAIN LANES I-40	200	1		
5102+21.91	5104+90.66	RIGHT	RIGHT MAIN LANES I-40	200	1		
5109+98.54	5112+67.29	LEFT	LEFT MAIN LANES I-40	200	1		
5111+22.70	5113+47.70	LEFT	RIGHT MAIN LANES I-40	175		1	1
5111+47.50	5116+72.50	RIGHT	LEFT MAIN LANES I-40	475		1	1
<b>TOTALS:</b>				<b>2350</b>	<b>4</b>	<b>8</b>	<b>4</b>

T:\Job\W\X\2600\_AHTD\_01-Coll\2011 Task Order - B003\Shell Lake\700\_CADD\_Files\777\_Roadway\Drawings\104quantities.dgn 12/16/2014 2:08:48 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		50	130
				JOB NO.		BBO13	50	130

**APPROACH GUTTERS AND SLABS**

STATION	STATION	SIDE	LOCATION	APPROACH GUTTERS	APPROACH SLABS	REINFORCING STEEL RDWY. (GR. 60)	EPOXY COATED REINFORCING STEEL (GRADE 60)	AGGREGATE BASE CRS. (CLASS 7)
				(TYPE C)	(TYPE SPECIAL 2)			
				CU.YD.	CU.YD.	POUND	POUND	TON
5104+26.86	5104+63.36		CENTERLINE I-40		300.55	33494	1188	153.3
		RIGHT	RIGHT MAIN LANES I-40	18.10		995		
		LEFT	LEFT MAIN LANES I-40	18.10		995		
5110+25.84	5110+62.34		CENTERLINE I-40		300.55	33494	1188	153.3
		RIGHT	RIGHT MAIN LANES I-40	18.10		995		
		LEFT	LEFT MAIN LANES I-40	18.10		995		
<b>TOTALS:</b>				<b>72.40</b>	<b>601.10</b>	<b>70968</b>	<b>2376</b>	<b>306.6</b>

**FENCING**

STATION	SIDE	LOCATION	WIRE FENCE	* 16'-0" GATES
			(TYPE A)	
			LIN. FT.	EACH
5105+00	RIGHT	RIGHT MAIN LANES I-40	65	
5104+27	LEFT	LEFT MAIN LANES I-40	45	1
5110+63	RIGHT	RIGHT MAIN LANES I-40	49	1
5109+89	LEFT	LEFT MAIN LANES I-40	61	
<b>TOTALS:</b>			<b>220</b>	<b>2</b>

\* DENOTES ALTERNATE BID ITEM.



**EARTHWORK**

STATION	STATION	LOCATION / DESCRIPTION	*UNCLASSIFIED EXCAVATION	*COMPACTED EMBANKMENT	*SOIL STABILIZATION
			CU. YD.	CU. YD.	TON
5099+25.00	5104+26.86	C.L. MEDIAN I-40 / TEMPORARY MEDIAN PAVEMENT FOR M.O.T.	540	1413	
5110+62.34	5114+25.00	C.L. MEDIAN I-40 / TEMPORARY MEDIAN PAVEMENT FOR M.O.T.	390	1021	
5114+25.00	5129+25.00	C.L. MEDIAN I-40 / TEMPORARY MEDIAN PAVEMENT FOR M.O.T.	1613	4449	
5121+85.55	5122+82.32	TEMPORARY RAMP 2 FOR SHELL LAKE BRIDGE RECONSTRUCTION	52	412	
5121+84.54	5127+83.63	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 1	322	2552	
5117+51.34	5137+49.91	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 2	1075	5922	
5113+14.14	5127+64.64	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 3	780	4298	
5118+80.59	5126+60.45	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 4	419	3322	
ENTIRE PROJECT		EARTHWORK FOR PAVEMENT TRANSITION AT SHELL LAKE BRIDGE		672	
ENTIRE PROJECT		GUARDRAIL INSTALLATION		89	
5099+25.00	5103+66.47	C.L. MEDIAN I-40 / REMOVAL OF TEMPORARY MEDIAN PAVEMENT FOR M.O.T.	1309		
5111+22.73	5114+25.00	C.L. MEDIAN I-40 / REMOVAL OF TEMPORARY MEDIAN PAVEMENT FOR M.O.T.	897		
5114+25.00	5129+25.00	C.L. MEDIAN I-40 / REMOVAL OF TEMPORARY MEDIAN PAVEMENT FOR M.O.T.	2224		
5121+85.55	5122+82.32	REMOVAL OF TEMPORARY RAMP 2 FOR SHELL LAKE BRIDGE RECONSTRUCTION	412		
5121+84.54	5127+83.63	TEMP. RAMP 1 / REMOVAL OF HWY. 149 INTERCHANGE RAMP RECONSTRUCTION	2552		
5117+51.34	5137+49.91	TEMP. RAMP 2 / REMOVAL OF HWY. 149 INTERCHANGE RAMP RECONSTRUCTION	5922		
5113+14.14	5127+64.64	TEMP. RAMP 3 / REMOVAL OF HWY. 149 INTERCHANGE RAMP RECONSTRUCTION	4298		
5118+80.59	5126+60.45	TEMP. RAMP 4 / REMOVAL OF HWY. 149 INTERCHANGE RAMP RECONSTRUCTION	3322		
ENTIRE PROJECT TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER.					100
<b>TOTALS:</b>			<b>26127</b>	<b>24150</b>	<b>100</b>

NOTE: QUANTITIES ESTIMATED.  
SEE SECTION 104.03 OF THE STD. SPECS.

NOTE: EARTHWORK QUANTITIES SHOWN ABOVE SHALL BE PAID AS PLAN QUANTITY.

**COLD MILLING ASPHALT PAVEMENT**

STATION	STATION	LOCATION	LENGTH	AVG. WIDTH	SQ. YD.
			LIN. FT.	FEET	
** 5083+00.00	5085+00.00	RIGHT MAIN LANES I-40	200.00	28.0	622.22
* 5085+00.00	5089+25.00	RIGHT MAIN LANES I-40	425.00	28.0	1322.22
* 5089+25.00	5093+75.00	RIGHT MAIN LANES I-40 & SHOULDERS	450.00	38.0	1900.00
* 5093+75.00	5094+75.00	RIGHT MAIN LANES I-40	100.00	26.0	288.89
* 5094+75.00	5099+16.47	RIGHT MAIN LANES I-40	441.47	28.0	1373.46
* 5115+72.73	5119+87.63	RIGHT MAIN LANES I-40 & EXIT RAMP TURNOUT	414.90	VAR.	2018.35
* 5119+87.63	5123+80.00	RIGHT MAIN LANES I-40	392.37	24.0	1046.32
* 5123+80.00	5127+35.48	RIGHT MAIN LANES I-40	355.48	26.0	1026.94
** 5127+35.48	5129+00.00	RIGHT MAIN LANES I-40 & ACCELERATION LANE	164.52	40.0	731.20
** 5129+00.00	5131+00.00	RIGHT MAIN LANES I-40 & ACCELERATION LANE	200.00	40.0	888.89
** 5083+00.00	5085+00.00	LEFT MAIN LANES I-40	200.00	28.0	622.22
* 5085+00.00	5089+25.00	LEFT MAIN LANES I-40	425.00	28.0	1322.22
* 5089+25.00	5093+75.00	LEFT MAIN LANES I-40 & SHOULDERS	450.00	38.0	1900.00
* 5093+75.00	5094+75.00	LEFT MAIN LANES I-40	100.00	26.0	288.89
* 5094+75.00	5099+16.47	LEFT MAIN LANES I-40	441.47	28.0	1373.46
* 5115+72.73	5120+00.71	LEFT MAIN LANES I-40 & ACCELERATION LANE	427.98	36.0	1711.92
* 5120+00.71	5127+02.42	LEFT MAIN LANES I-40	701.71	24.0	1871.23
* 5127+02.42	5129+00.00	LEFT MAIN LANES I-40 & EXIT RAMP TURNOUT	197.58	VAR.	1133.08
** 5129+00.00	5131+00.00	LEFT MAIN LANES I-40 & EXIT RAMP TURNOUT	200.00	VAR.	566.54
<b>TOTAL:</b>					<b>22008.05</b>

\* NOTE: MILLING DEPTH 2"  
\*\* NOTE: AVERAGE MILLING DEPTH 1"  
NOTE: THE REMOVAL AND DISPOSAL OF PLOWABLE PAVEMENT MARKERS WILL NOT BE PAID FOR DIRECTLY, BUT WILL BE CONSIDERED INCLUDED IN THE PRICE BID FOR "COLD MILLING ASPHALT PAVEMENT."

**TEMPORARY EROSION CONTROL ITEMS AND DEVICES**

STATION	STATION	LOCATION	TEMPORARY SEEDING	MULCH COVER	WATER	SAND BAG DITCH CHECKS	ROCK DITCH CHECKS	DROP INLET SILT FENCE	SILT FENCE	*SEDIMENT REMOVAL & DISPOSAL
			ACRE	ACRE	M. GAL.	(E-5) BAG	(E-6) CU. YD.	(E-7) LIN. FT.	(E-11) LIN. FT.	CU. YD.
ENTIRE	PROJECT	PRIOR TO CONSTRUCTION	7.05	7.05	143.8			80	180	10
		HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - STAGE 1A	2.10	2.10	42.8		12		3056	113
		HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - STAGE 1B	1.53	1.53	31.2		24			
		HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - STAGE 2A	3.21	3.21	65.5				4070	151
		HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - STAGE 2B	0.63	0.63	12.9					
*ENTIRE PROJECT TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER.			3.63	3.63	74.1	110	36	20	1827	68
<b>TOTALS:</b>			<b>18.15</b>	<b>18.15</b>	<b>370.3</b>	<b>110</b>	<b>72</b>	<b>100</b>	<b>9133</b>	<b>342</b>

BASIS OF ESTIMATE:  
WATER.....20.4 M.G. / ACRE OF TEMPORARY SEEDING.  
SAND BAG DITCH CHECKS.....22 BAGS / LOCATION  
ROCK DITCH CHECKS.....3 CU.YD./LOCATION

NOTE: THE TEMPORARY EROSION CONTROL DEVICES SHOWN ABOVE AND ON THE PLANS SHALL BE INSTALLED IN SUCH A SEQUENCE AS TO DETER EROSION AND SEDIMENTATION ON U.S. WATERWAYS AS EXPLAINED BY THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT.

\*QUANTITIES ESTIMATED.  
SEE SECTION 104.03 OF THE STD. SPECS.

**PERMANENT EROSION CONTROL**

STATION	STATION	LOCATION / DESCRIPTION	SEEDING	LIME	MULCH COVER	WATER	SECOND SEEDING APPLICATION
			ACRE	TON	ACRE	M. GAL.	ACRE
ENTIRE	PROJECT	C.L. MEDIAN	7.05	14.10	7.05	719.1	7.05
		HWY. 149 INTERCHANGE RAMP RECONSTRUCTION	5.75	11.50	5.75	586.5	5.75
*ENTIRE PROJECT TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER.			3.20	6.40	3.20	326.4	3.20
<b>TOTALS:</b>			<b>16.00</b>	<b>32.00</b>	<b>16.00</b>	<b>1632.0</b>	<b>16.00</b>

BASIS OF ESTIMATE:  
LIME.....2 TONS / ACRE OF SEEDING  
WATER.....102.0 M.G. / ACRE OF SEEDING

NOTE: THE TEMPORARY EROSION CONTROL DEVICES SHOWN ABOVE AND ON THE PLANS SHALL BE INSTALLED IN SUCH A SEQUENCE AS TO DETER EROSION AND SEDIMENTATION ON U.S. WATERWAYS AS EXPLAINED BY THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT.

\*QUANTITIES ESTIMATED.  
SEE SECTION 104.03 OF THE STD. SPECS.

T:\Job\WLM2600\_AHTD\_0n-Call\2011Task\_Order\_B003\Shell\Lake\700\_CADD\_Files\777\_Roadway\Drawings\04quantities.dgn  
 12/9/2014 3:22:19 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0113	51	130
								② QUANTITIES

**MOBILE SPEED NOTIFICATION SYSTEM**

LOCATION	EACH
ENTIRE PROJECT - IF AND WHERE DIRECTED BY THE ENGINEER.	2
<b>TOTALS:</b>	<b>2</b>

**AUTOMATED WORK ZONE INFORMATION SYSTEM**

LOCATION	*AWIS MOBILIZATION	*AWIS OPERATION	*DEVICE RELOCATION	FURNISH AND INSTALL			
	LUMP SUM	MONTH	EACH	*CLOSED CIRCUIT TELEVISION SYSTEM	*PUBLIC NOTIFICATION SYSTEM	*VARIABLE MESSAGE SIGN	*VEHICLE DETECTION SYSTEM
ENTIRE PROJECT	1.00	21	16	2	2	6	22
<b>TOTALS:</b>	<b>1.00</b>	<b>21</b>	<b>16</b>	<b>2</b>	<b>2</b>	<b>6</b>	<b>22</b>

\* QUANTITY ESTIMATED. SEE SECTION 104.03 OF THE STANDARD SPECIFICATIONS.  
 REFER TO "AUTOMATED WORK ZONE INFORMATION SYSTEM" SPECIAL PROVISION.



12/9/14

**ASPHALT CONCRETE PATCHING FOR MAINTENANCE OF TRAFFIC**

LOCATION	TON	TACK COAT
		GALLON
ENTIRE PROJECT - TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER	25	50
<b>TOTALS:</b>	<b>25</b>	<b>50</b>

NOTE: QUANTITIES ESTIMATED.  
 SEE SECTION 104.03 OF THE STD. SPECS.  
 BASIS OF ESTIMATE: PATCHING 25 TONS PER MILE  
 TACK COAT 50 GAL. PER MILE

**RUMBLE STRIPS**

STATION	STATION	SIDE	LOCATION	IN ASPHALT SHOULDER LIN. FT.
5083+00	5104+52	RIGHT	RIGHT MAIN LANES I-40	2152
5110+98	5131+00	RIGHT	RIGHT MAIN LANES I-40	2002
5083+00	5103+66	LEFT	RIGHT MAIN LANES I-40	2066
5111+22	5131+00	LEFT	RIGHT MAIN LANES I-40	1978
5083+00	5103+66	RIGHT	LEFT MAIN LANES I-40	2066
5111+22	5131+00	RIGHT	LEFT MAIN LANES I-40	1978
5083+00	5103+89	LEFT	LEFT MAIN LANES I-40	2089
5110+24	5131+00	LEFT	LEFT MAIN LANES I-40	2076
<b>TOTAL:</b>				<b>16407</b>

**CONCRETE BARRIER WALL**

STATION	STATION	SIDE	LOCATION	(MEDIAN TYPE SPECIAL)	(PIER PROTECTION TYPE A)
				LIN. FT.	
5091+26	5091+54	RIGHT	RIGHT MAIN LANES I-40		28
5091+45	5091+73	LEFT	LEFT MAIN LANES I-40		28
5108+90	5122+18	RIGHT	HWY. 149 INTERCHANGE RAMP 1	1328	
5114+22	5119+42	LEFT	HWY. 149 INTERCHANGE RAMP 4	520	
<b>TOTALS:</b>				<b>1848</b>	<b>56</b>

**JOINT SUPPORT**

STATION	LOCATION	LENGTH	WIDTH	DEPTH	CLASS "S" CONCRETE - RDWY.
		LIN. FT.	FEET	INCH	CU. YD.
5109+30.00	HWY. 149 INTERCHANGE - RAMP 1	36.00	3.00	12.00	4.00
5109+45.00	HWY. 149 INTERCHANGE - RAMP 1	36.00	3.00	12.00	4.00
5109+60.00	HWY. 149 INTERCHANGE - RAMP 1	36.00	3.00	12.00	4.00
5128+04.88	HWY. 149 INTERCHANGE - RAMP 1	15.00	3.00	12.00	1.67
5128+19.88	HWY. 149 INTERCHANGE - RAMP 1	15.00	3.00	12.00	1.67
5128+34.88	HWY. 149 INTERCHANGE - RAMP 1	15.00	3.00	12.00	1.67
5120+88.20	HWY. 149 INTERCHANGE - RAMP 2	15.00	3.00	12.00	1.67
5121+03.20	HWY. 149 INTERCHANGE - RAMP 2	15.00	3.00	12.00	1.67
5121+18.20	HWY. 149 INTERCHANGE - RAMP 2	15.00	3.00	12.00	1.67
5118+29.38	HWY. 149 INTERCHANGE - RAMP 3	15.00	3.00	12.00	1.67
5118+44.38	HWY. 149 INTERCHANGE - RAMP 3	15.00	3.00	12.00	1.67
5118+59.38	HWY. 149 INTERCHANGE - RAMP 3	15.00	3.00	12.00	1.67
5114+90.00	HWY. 149 INTERCHANGE - RAMP 4	36.00	3.00	12.00	4.00
5115+05.00	HWY. 149 INTERCHANGE - RAMP 4	36.00	3.00	12.00	4.00
5115+20.00	HWY. 149 INTERCHANGE - RAMP 4	36.00	3.00	12.00	4.00
5127+06.17	HWY. 149 INTERCHANGE - RAMP 4	15.00	3.00	12.00	1.67
5127+21.17	HWY. 149 INTERCHANGE - RAMP 4	15.00	3.00	12.00	1.67
5127+36.17	HWY. 149 INTERCHANGE - RAMP 4	15.00	3.00	12.00	1.67
<b>TOTAL:</b>					<b>44.04</b>


**GEOGRID FOR PAVEMENT REINFORCEMENT**

STATION	STATION	LOCATION	LENGTH	AVG. WIDTH	SQ. YD.
			FEET	FEET	
5109+30.00	5120+87.86	HWY. 149 - RAMP 1	1157.86	54.0	6947.2
5120+87.86	5128+34.88	HWY. 149 - RAMP 1	747.02	33.0	2739.1
5120+88.20	5126+88.45	HWY. 149 - RAMP 2	600.25	33.0	2200.9
5118+29.38	5123+77.93	HWY. 149 - RAMP 3	548.55	33.0	2011.4
5114+90.00	5118+30.20	HWY. 149 - RAMP 4	340.20	54.0	2041.2
5118+30.20	5127+36.17	HWY. 149 - RAMP 4	905.97	33.0	3321.9
<b>TOTAL:</b>					<b>19261.7</b>

3/2/2015 12:00:00 PM ...Drawings\104quantities.dgn T:\Job\W.XM2600 AHTD On-Call\2011Task Order B003\Shell Lake\700\_CADD Files\777 Roadway\Drawings\104quantities.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
3-2-2015				6	ARK.		52	130
				JOB NO.	BBOI13			

② QUANTITIES



**BASE AND SURFACING - MAINTENANCE OF TRAFFIC**

STATION	STATION	LOCATION	LENGTH FEET	AGGREGATE BASE COURSE (CL. 7)		CEMENT STABILIZED CRUSHED STONE BASE COURSE (6" COMP'D. DEPTH)				ACHM SURFACE COURSE (3/8") 110 LBS. PER SQ. YD.			TACK COAT 0.03 GAL. PER SQ. YD.			TEMPORARY PORTLAND CEMENT CONCRETE PAVEMENT	
				TONS PER STA.	TON	AVG. WID. FEET	PROCESSING SQ. YD.	CEMENT TON	AGGREGATE TON	AVG. WID. FEET	SQ. YD.	(PG 64-22) TON	AVG. WID. FEET	SQ. YD.	GAL.	AVG. WID. FEET	10" U.T. SQ. YD.
5094+75.00	5104+26.86	C.L. MEDIAN I-40	951.86			60.00	6345.73	133.26	2087.75	60.00	6345.73	349.02	60.00	6345.73	190.37	60.00	6345.73
5110+62.34	5123+80.00	C.L. MEDIAN I-40	1317.66			60.00	8784.40	184.47	2890.07	60.00	8784.40	483.14	60.00	8784.40	263.53	60.00	8784.40
5123+80.00	5129+25.00	C.L. MEDIAN I-40	545.00			VAR.	1377.56	28.93	453.22	VAR.	1377.56	75.77	VAR.	1377.56	41.33	VAR.	1377.56
5123+80.00	5129+25.00	C.L. MEDIAN I-40 - SHOULDER	545.00	25.25	137.61												
5121+85.55	5122+82.32	TEMPORARY RAMP 2 FOR SHELL LAKE BRIDGE RECONSTRUCTION	96.77			29.00	311.81	6.55	102.59	29.00	311.81	17.15	29.00	311.81	9.35	25.00	268.81
5121+85.55	5122+82.32	TEMPORARY RAMP 2 FOR SHELL LAKE BRIDGE RECONSTRUCTION - RT. SHOULDER	96.77	25.25	24.43												
5121+85.55	5122+82.32	TEMPORARY RAMP 2 FOR SHELL LAKE BRIDGE RECONSTRUCTION - LT. SHOULDER	96.77	25.25	24.43												
5121+84.54	5127+83.63	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 1	509.70			VAR.	1792.20	37.64	589.63	VAR.	1792.20	98.57	VAR.	1792.20	53.77	VAR.	1504.70
5121+84.54	5127+83.63	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 1 - RT. SHOULDER	509.70	25.25	128.70												
5121+84.54	5127+83.63	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 1 - LT. SHOULDER	509.70	25.25	128.70												
5117+51.34	5137+49.91	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 2	1826.00			VAR.	6889.20	144.67	2266.55	VAR.	6889.20	378.91	VAR.	6889.20	206.68	VAR.	6434.10
5117+51.34	5137+49.91	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 2 - LT. SHOULDER	1826.00	25.25	461.07												
5113+14.14	5127+64.64	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 3	1279.50			VAR.	4666.20	97.99	1535.18	VAR.	4666.20	256.64	VAR.	4666.20	139.99	VAR.	4333.30
5113+14.14	5127+64.64	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 3 - RT. SHOULDER	1279.50	25.25	323.07												
5118+80.59	5126+60.45	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 4	678.80			VAR.	2377.90	49.94	782.33	VAR.	2377.90	130.78	VAR.	2377.90	71.34	VAR.	1984.20
5118+80.59	5126+60.45	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 4 - RT. SHOULDER	678.80	25.25	171.40												
5118+80.59	5126+60.45	HWY. 149 INTERCHANGE RAMP RECONSTRUCTION - TEMP. RAMP 4 - LT. SHOULDER	678.80	25.25	171.40												
<b>TOTALS:</b>					1570.81		32545.00	683.45	10707.32		32545.00	1789.98		32545.00	976.36		31032.80

BASIS OF ESTIMATE:  
 ACHM SURFACE COURSE (3/8").....94.3% MIN. AGGR.....5.7% ASPHALT BINDER  
 MAXIMUM NUMBER OF GYRATIONS = 115 FOR PG 64-22  
 CEMENT STABILIZED CRUSHED STONE BASE COURSE = 94.0% AGGR. 6.0% CEMENT

**BASE AND SURFACING - HWY. 149 RAMPS**

STATION	STATION	LOCATION	LENGTH FEET	AGGREGATE BASE COURSE (CL. 7)		CEMENT STABILIZED CRUSHED STONE BASE COURSE (6" COMP'D. DEPTH)				ACHM SURFACE COURSE (3/8") 110 LBS. PER SQ. YD.			TACK COAT 0.03 GAL. PER SQ. YD.			PORTLAND CEMENT CONCRETE PAVEMENT	
				TONS PER STA.	TON	AVG. WID. FEET	PROCESSING SQ. YD.	CEMENT TON	AGGREGATE TON	AVG. WID. FEET	SQ. YD.	(PG 64-22) TON	AVG. WID. FEET	SQ. YD.	GAL.	AVG. WID. FEET	9" U.T. SQ. YD.
5109+30.00	5120+87.86	HWY. 149 INTERCHANGE - RAMP 1	1157.86			52.00	6689.86	140.49	2200.96	52.00	6689.86	367.94	52.00	6689.86	200.70	42.00	5403.35
5109+30.00	5120+87.86	HWY. 149 INTERCHANGE - RAMP 1 - RT. SHOULDER	1157.86	26.50	306.83												
5109+30.00	5120+87.86	HWY. 149 INTERCHANGE - RAMP 1 - LT. SHOULDER	1157.86	44.75	518.14												
5120+87.86	5128+34.88	HWY. 149 INTERCHANGE - RAMP 1	747.02			29.00	2407.06	50.55	791.92	29.00	2407.06	132.39	29.00	2407.06	72.21	25.00	2075.06
5120+87.86	5128+34.88	HWY. 149 INTERCHANGE - RAMP 1 - RT. SHOULDER	747.02	30.50	227.84												
5120+87.86	5128+34.88	HWY. 149 INTERCHANGE - RAMP 1 - LT. SHOULDER	747.02	26.50	197.96												
5120+88.20	5126+88.45	HWY. 149 INTERCHANGE - RAMP 2	600.25			29.00	1934.14	40.62	636.33	29.00	1934.14	106.38	29.00	1934.14	58.02	25.00	1667.36
5120+88.20	5126+88.45	HWY. 149 INTERCHANGE - RAMP 2 - RT. SHOULDER	600.25	30.50	183.08												
5120+88.20	5126+88.45	HWY. 149 INTERCHANGE - RAMP 2 - LT. SHOULDER	600.25	26.50	159.07												
5118+29.38	5123+77.93	HWY. 149 INTERCHANGE - RAMP 3	548.55			29.00	1767.55	37.12	581.52	29.00	1767.55	97.22	29.00	1767.55	53.03	25.00	1523.75
5118+29.38	5123+77.93	HWY. 149 INTERCHANGE - RAMP 3 - RT. SHOULDER	548.55	26.50	145.37												
5118+29.38	5123+77.93	HWY. 149 INTERCHANGE - RAMP 3 - LT. SHOULDER	548.55	30.50	167.31												
5114+90.00	5118+30.20	HWY. 149 INTERCHANGE - RAMP 4	340.20			52.00	1965.60	41.28	646.68	52.00	1965.60	108.11	52.00	1965.60	58.97	42.00	1587.60
5114+90.00	5118+30.20	HWY. 149 INTERCHANGE - RAMP 4 - RT. SHOULDER	340.20	44.75	152.24												
5114+90.00	5118+30.20	HWY. 149 INTERCHANGE - RAMP 4 - LT. SHOULDER	340.20	26.50	90.15												
5118+30.20	5127+36.17	HWY. 149 INTERCHANGE - RAMP 4	905.97			29.00	2919.24	61.30	960.43	29.00	2919.24	160.56	29.00	2919.24	87.58	25.00	2516.58
5118+30.20	5127+36.17	HWY. 149 INTERCHANGE - RAMP 4 - RT. SHOULDER	905.97	26.50	240.08												
5118+30.20	5127+36.17	HWY. 149 INTERCHANGE - RAMP 4 - LT. SHOULDER	905.97	30.50	276.32												
<b>TOTALS:</b>					2664.39		17683.45	371.36	5817.84		17683.45	972.60		17683.45	530.51		14773.70

BASIS OF ESTIMATE:  
 ACHM SURFACE COURSE (3/8").....94.3% MIN. AGGR.....5.7% ASPHALT BINDER  
 MAXIMUM NUMBER OF GYRATIONS = 115 FOR PG 64-22  
 CEMENT STABILIZED CRUSHED STONE BASE COURSE = 94.0% AGGR. 6.0% CEMENT

QUANTITIES



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113		54	130
				① 06939 - QUANTITIES - 55891A				

SCHEDULE OF BRIDGE QUANTITIES - JOB NO. BB0113

BRIDGE NUMBER CODE NUMBER BRIDGE NAME PLATE TITLE	UNIT OF STRUCTURE	ITEM NO.	205	801	801	802	802	802	803	804	804	805	805	805	805	805	807	808	809	812	
			ITEM	REMOVAL OF EXISTING BRIDGE STRUCTURE	UNCLASSIFIED EXCAVATION FOR STRUCTURES - BRIDGE	COFFERDAM	CLASS S CONCRETE - BRIDGE	CLASS S(AE) CONCRETE - BRIDGE	SEAL CONCRETE - BRIDGE	CLASS 1 PROTECTIVE SURFACE TREATMENT	REINFORCING STEEL - BRIDGE (GRADE 60)	EPOXY COATED REINFORCING STEEL (GRADE 60)	STEEL SHELL PILING (16" DIA.)	TEST PILE (16" DIA.)	STEEL SHELL PILING (18" DIA.)	TEST PILE (18" DIA.)	STEEL SHELL PILING (24" DIA.)	STRUCTURAL STEEL IN BEAM SPANS (M270, GR. 50W)	ELASTOMERIC BEARINGS	ARMORED JOINT WITH NEOPRENE STRIP SEAL	BRIDGE NAME PLATE (TYPE D)
		UNIT	LUMP SUM	CU. YD.	EACH	CU. YD.	CU. YD.	CU. YD.	GAL.	LB.	LB.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LB.	CU. INCH	LIN. FT.	EACH	
06939 X071 SHELL LAKE	BENT NO. 1			385		184.11			0.5	30,657	1,189					780	1,157	12,941.3	150		
	BENT NO. 2			1,040	6	335.86			344.44	52,608		2,100	420					13,005.2			
	BENT NO. 3			1,194	6	350.97			631.89	70,809				2,400	480			7,395.0			
	BENT NO. 4			1,053	6	365.16			631.89	62,153				2,400	480			7,395.0			
	BENT NO. 5			1,053	6	365.16			631.89	62,153				2,400	480			7,395.0			
	BENT NO. 6			1,194	6	365.16			631.89	62,153				2,400	480			7,395.0			
	BENT NO. 7			1,106	6	347.84			526.56	69,374				2,400	480			7,395.0			
	BENT NO. 8			1,040	6	333.23			344.44	51,681		2,100	420					13,005.2			
	BENT NO. 9			408		184.11				0.5	30,657	1,189				1,300	1,157	12,941.3	150		
		560'-0" CONT. COMP. W-BEAM UNIT						2,084.70		177.6	9,495	542,072						1,780,526			1
		EXIST. BR. NO. A3900 (Site No. 1)		0.5																	
		EXIST. BR. NO. B3900 (Site No. 1)		0.5																	
	TOTALS FOR JOB NO. BB0113			1	8,473	42	2,831.60	2,084.70	3,743.00	178.6	501,740	544,450	4,200	840	12,000	2,400	2,080	1,782,840	88,868.0	300	1

T:\Job\WLM2600\_AHTD On-Call 2011 Task Order\_B003\Shell Lake\700\_CADD Files\709\_Structural Files\Drawings\B006Quantities01.dgn 4:48:21 PM 12/9/2014



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

DRAWN BY: LHG DATE: 4/27/14 FILENAME: bb0113x1\_qx1.dgn  
 CHECKED BY: CGW DATE: 5/1/14  
 DESIGNED BY: CMF DATE: 4/27/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55891A

SCHEDULE OF BRIDGE QUANTITIES  
 SHELL LAKE STR. & APPRS. (S)  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS


SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	TOTAL QUANTITY	UNIT
202	REMOVAL AND DISPOSAL OF FENCE	240	LIN. FT.
202	REMOVAL AND DISPOSAL OF CONCRETE PARAPET WALL	4	EACH
SP & 202	REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT	9664	SQ. YD.
202	REMOVAL AND DISPOSAL OF CONCRETE PAVEMENT	26314	SQ. YD.
202	REMOVAL AND DISPOSAL OF APPROACH SLAB AND GUTTERS	4	EACH
202	REMOVAL AND DISPOSAL OF IMPACT ATTENUATION BARRIER	4	EACH
SP & 202	REMOVAL AND DISPOSAL OF CONCRETE PIER PROTECTION	114	LIN. FT.
210	REMOVAL AND DISPOSAL OF GUARDRAIL	6055	LIN. FT.
210	UNCLASSIFIED EXCAVATION	26127	CU. YD.
SP & 210	COMPACTED EMBANKMENT	24150	CU. YD.
SP	SOIL STABILIZATION	100	TON
SP	GEORGD FOR PAVEMENT REINFORCEMENT	19262	SQ. YD.
SP & 215	TRENCHING AND SHOULDER PREPARATION	62	STATION
303	AGGREGATE BASE COURSE (CLASS 7)	10141	TON
308	AGGREGATE IN CEMENT STABILIZED CRUSHED STONE BASE COURSE	16525	TON
308	CEMENT IN CEMENT STABILIZED CRUSHED STONE BASE COURSE	1055	TON
308	PROCESSING CEMENT STABILIZED CRUSHED STONE BASE COURSE	50228	SQ. YD.
401	TACK COAT	5349	GAL.
SP & 405	MINERAL AGGREGATE IN ACHM BASE COURSE (1 1/2")	1901	TON
SP & 405	ASPHALT BINDER (PG 76-22) IN ACHM BASE COURSE (1 1/2")	77	TON
SP SS & 406	MINERAL AGGREGATE IN ACHM BINDER COURSE (1")	2498	TON
SP SS & 406	ASPHALT BINDER (PG 76-22) IN ACHM BINDER COURSE (1")	112	TON
SP SS & 407	MINERAL AGGREGATE IN ACHM SURFACE COURSE (3/8")	2606	TON
SP SS & 407	ASPHALT BINDER (PG 64-22) IN ACHM SURFACE COURSE (3/8")	157	TON
SP SS & 407	MINERAL AGGREGATE IN ACHM SURFACE COURSE (1/2")	8771	TON
SP SS & 407	ASPHALT BINDER (PG 64-22) IN ACHM SURFACE COURSE (1/2")	52	TON
SP SS & 407	ASPHALT BINDER (PG 76-22) IN ACHM SURFACE COURSE (1/2")	478	TON
412	COLD MILLING ASPHALT PAVEMENT	22008	SQ. YD.
SP & 414	ASPHALT CONCRETE PATCHING FOR MAINTENANCE OF TRAFFIC	25	TON
501	PORTLAND CEMENT CONCRETE PAVEMENT (9" UNIFORM THICKNESS)	14774	SQ. YD.
SP & 501	TEMPORARY PORTLAND CEMENT CONCRETE PAVEMENT (10" UNIFORM THICKNESS)	31033	SQ. YD.
504	APPROACH SLABS	60110	CU. YD.
504	APPROACH GUTTERS	7240	CU. YD.
601	MOBILIZATION	1.00	LUMP SUM
SP & 602	FURNISHING FIELD OFFICE	1	EACH
SP & 603	MAINTENANCE OF TRAFFIC	1.00	LUMP SUM
603	TRAFFIC CONTROL SUPERVISOR	1.00	LUMP SUM
603	18" TEMPORARY CULVERT	10	LIN. FT.
603	24" TEMPORARY CULVERT	200	LIN. FT.
SS & 604	SIGNS	1772	SQ. FT.
SS & 604	TRAFFIC DRUMS	80	LIN. FT.
SS & 604	BARRICADES	152	EACH
604	FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER	8406	LIN. FT.
SP	MOBILE SPEED NOTIFICATION SYSTEM	2	EACH
604	RELOCATING PRECAST CONCRETE BARRIER	30643	LIN. FT.
604	CONSTRUCTION PAVEMENT MARKINGS	39817	LIN. FT.
604	REMOVABLE CONSTRUCTION PAVEMENT MARKINGS	25685	LIN. FT.
604	REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS	22536	LIN. FT.
604	REMOVAL OF PERMANENT PAVEMENT MARKINGS	11273	LIN. FT.
604	ADVANCE WARNING ARROW PANEL	2560	DAY
SP & 604	PORTABLE CHANGEABLE MESSAGE SIGN	240	WEEK
SS & 604	VERTICAL PANELS	8	EACH
SP	MODULAR GLARE SHIELD	1195	LIN. FT.
SP	PORTABLE CONSTRUCTION LIGHTING	2100	DAY
606	SELECTED PIPE BEDDING	40	CU. YD.
617	GUARDRAIL (TYPE A)	2350	LIN. FT.
617	TERMINAL ANCHOR POSTS (TYPE 1)	4	EACH
617	GUARDRAIL TERMINAL (TYPE 2)	8	EACH
617	THREE BEAM GUARDRAIL TERMINAL	4	EACH
619	WIRE FENCE (TYPE A)	220	LIN. FT.
619	16" STEEL GATES	2	EACH
619	16" ALUMINUM GATES	2	EACH
620	LIME	32	TON
SS & 620	MULCH COVER	16.00	ACRE
620	WATER	34.15	ACRE
621	TEMPORARY SEEDING	2002.3	M.GAL.
621	SILT FENCE	18.15	ACRE
621	SAND BAG DITCH CHECKS	9133	LIN. FT.
621	DROP INLET SILT FENCE	110	BAG
621	SEDIMENT REMOVAL AND DISPOSAL	100	LIN. FT.
621	ROCK DITCH CHECKS	342	CU. YD.
623	SECOND SEEDING APPLICATION	72	CU. YD.
628	TOPSOIL FURNISHED AND PLACED	16.00	ACRE
631	CONCRETE BARRIER WALL (MEDIAN TYPE SPECIAL)	596	CU. YD.
631	CONCRETE BARRIER WALL (PIER PROTECTION TYPE A)	1948	LIN. FT.
SP & 635	ROADWAY CONSTRUCTION CONTROL	56	LIN. FT.
642	RUMBLE STRIPS IN ASPHALT SHOULDERS	1.00	LUMP SUM
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING WHITE (4")	16407	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE WHITE (4")	16396	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING (SKIP LINE) WHITE (4")	16396	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE (SKIP LINE) WHITE (4")	2080	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING WHITE (8")	2080	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE WHITE (8")	1524	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING YELLOW (4")	1524	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE YELLOW (4")	15696	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC CONTRAST PAVEMENT MARKING WHITE (4")	15696	LIN. FT.
SP	HIGH PERFORMANCE CONTRAST MARKING TAPE WHITE (4")	320	LIN. FT.
721	RAISED PAVEMENT MARKERS (TYPE II)	315	EACH
731	IMPACT ATTENUATION BARRIER (TYPE A)	3	EACH
731	TEMPORARY IMPACT ATTENUATION BARRIER	4	EACH
731	TEMPORARY IMPACT ATTENUATION BARRIER (REPAIR)	28	EACH
731	TEMPORARY IMPACT ATTENUATION BARRIER (RELOCATION)	18	EACH
802	CLASS S CONCRETE - ROADWAY	44.04	CU. YD.
804	REINFORCING STEEL-ROADWAY (GRADE 60)	70968	POUND
SP	EPOXY COATED REINFORCING STEEL (GRADE 60)	2376	POUND
SP	AWIS MOBILIZATION	1.00	LUMP SUM
SP	AWIS OPERATION	21	MONTH
SP	DEVICE RELOCATION	16	EACH
SP	FURNISH AND INSTALL CLOSED CIRCUIT TELEVISION SYSTEM	2	EACH
SP	FURNISH AND INSTALL PUBLIC NOTIFICATION SYSTEM	2	EACH
SP	FURNISH AND INSTALL VARIABLE MESSAGE SIGN	6	EACH
SP	FURNISH AND INSTALL VEHICLE DETECTION SYSTEM	22	EACH
STRUCTURES OVER 20' SPAN			
205	REMOVAL OF EXISTING BRIDGE STRUCTURE (SITE NO. 1)	1.00	LUMP SUM
SP & 636	BRIDGE CONSTRUCTION CONTROL	1.00	LUMP SUM
801	UNCLASSIFIED EXCAVATION FOR STRUCTURES-BRIDGE	8473	CU. YD.
801	COFFERDAM	42	EACH
802	CLASS S CONCRETE - BRIDGE	2831.60	CU. YD.
802	SEAL CONCRETE - BRIDGE	2084.70	CU. YD.
803	CLASS T PROTECTIVE SURFACE TREATMENT	3743.00	CU. YD.
804	REINFORCING STEEL-BRIDGE (GRADE 60)	178.8	GAL.
804	EPOXY COATED REINFORCING STEEL (GRADE 60)	501740	POUND
805	STEEL SHELL PILING (16" DIAMETER)	544450	POUND
805	STEEL SHELL PILING (18" DIAMETER)	4200	LIN. FT.
805	STEEL SHELL PILING (24" DIAMETER)	12000	LIN. FT.
805	TEST PILE (16" DIAMETER)	2080	LIN. FT.
805	TEST PILE (18" DIAMETER)	840	LIN. FT.
807	STRUCTURAL STEEL IN BEAM SPANS (M270-GR50W)	2400	LIN. FT.
808	ELASTOMERIC BEARINGS	1782840	POUND
809	ARMORED JOINT WITH NEOPRENE STRIP SEAL	88868.0	CU. IN.
812	BRIDGE NAME PLATE (TYPE D)	300	LIN. FT.
		1	EACH

\* DENOTES ALTERNATE BID ITEMS

REVISIONS

DATE	REVISION	SHEET NUMBER
2/19/2015	DELETED SP "ELECTRONIC SUBMISSION OF ASPHALT CONCRETE HOT MIX ACCEPTANCE TEST RESULTS" AND ADDED SP "SUBMISSION OF ASPHALT CONCRETE HOT MIX ACCEPTANCE TEST RESULTS"	3, 55
3/2/2015	REVISED QUANTITY "TEMPORARY PORTLAND CEMENT CONCRETE PAVEMENT (10" UNIFORM THICKNESS)"	52, 55




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
2-19-2015				6	ARK.		55	130
3-2-2015								

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB013	56	130	

PLAN SHEET - STA. 5065+00 TO STA. 5125+00




CONCRETE BARRIER WALL (PIER PROTECTION TYPE A)  
 STA. 5091+26 TO STA. 5091+54 RT. OF R.M.L. = 28 LIN. FT.  
 STA. 5091+45 TO STA. 5091+73 LT. OF L.M.L. = 28 LIN. FT.



SHELL LAKE - FOR THE CONSTRUCTION OF TEMPORARY WORK RAMPS OR HAUL ROADS, THIS STREAM IS CLASSIFIED AS A 5 CFS STREAM. THE STREAM BANK ELEVATIONS ARE 195.0 FT. SEE SUBSECTION 110.06 (C) FOR THE STANDARD SPECIFICATIONS REGARDING CONSTRUCTION OF TEMPORARY FILLS WITHIN 5 CFS STREAM LIMITS.

STA. 5088+00 IN PLACE TYPE H DROP INLET IN MEDIAN (2 OPENINGS) (4' - 0" X 4' - 0" X 4' - 8") 24" X 96" R.C. PIPE CULVERT RETAIN

XXXX DENOTES: PAVEMENT TRANSITION





GUARDRAIL INSTALLATION	GUARDRAIL (TYPE A)	THREE BEAM GUARDRAIL TERMINAL	GUARDRAIL TERMINAL (TYPE 2)	TERMINAL ANCHOR POST (TYPE 1)
STA. 5088+57.85 TO STA. 5091+26.60 RT. OF R.M.L.	200 LIN. FT.	1 EACH	1 EACH	
STA. 5087+49.00 TO STA. 5092+49.00 LT. OF R.M.L.	450 LIN. FT.		1 EACH	1 EACH
STA. 5090+49.00 TO STA. 5095+49.00 RT. OF L.M.L.	450 LIN. FT.		1 EACH	1 EACH
STA. 5091+72.40 TO STA. 5094+41.15 LT. OF L.M.L.	200 LIN. FT.	1 EACH	1 EACH	
STA. 5102+21.91 TO STA. 5104+90.66 RT. OF R.M.L.	200 LIN. FT.	1 EACH	1 EACH	
STA. 5109+98.54 TO STA. 5112+67.29 LT. OF L.M.L.	200 LIN. FT.	1 EACH	1 EACH	
STA. 5111+22.70 TO STA. 5113+47.70 LT. OF R.M.L.	175 LIN. FT.		1 EACH	1 EACH
STA. 5111+47.50 TO STA. 5116+72.50 RT. OF L.M.L.	475 LIN. FT.		1 EACH	1 EACH

REMOVAL AND DISPOSAL OF IMPACT ATTENUATION BARRIERS  
 STA. 5091+49 MEDIAN = 2 EACH

REMOVAL AND DISPOSAL OF CONCRETE PIER PROTECTION  
 STA. 5091+26 TO STA. 5091+54 RT. OF R.M.L. = 28 LIN. FT.  
 STA. 5091+45 TO STA. 5091+73 LT. OF L.M.L. = 28 LIN. FT.

REMOVAL & DISPOSAL OF GUARDRAIL  
 STA. 5089+01 TO STA. 5091+26 RT. OF R.M.L. = 225 LIN. FT.  
 STA. 5091+73 TO STA. 5093+98 LT. OF L.M.L. = 225 LIN. FT.

NOTE: THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THAT THE MINIMUM 16'-0" VERTICAL CLEARANCE IS OBTAINED BETWEEN THE FINAL PAVEMENT GRADE AND THE BOTTOM OF THE STRUCTURE.



STA. 5099+00 IN PLACE TYPE H DROP INLET IN MEDIAN (2 OPENINGS) (4' - 0" X 4' - 0" X 3' - 5") 24" X 90" R.C. PIPE CULVERT RETAIN

STA. 5112+00 IN PLACE TYPE H DROP INLET IN MEDIAN (2 OPENINGS) (4' - 0" X 4' - 0" X 4' - 5") 24" X 92" R.C. PIPE CULVERT RETAIN

NOTE: THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THAT THE MINIMUM 16'-0" VERTICAL CLEARANCE IS OBTAINED BETWEEN THE FINAL PAVEMENT GRADE AND THE BOTTOM OF THE STRUCTURE.

STA. 5117+00 IN PLACE TYPE H DROP INLET IN MEDIAN (2 OPENINGS) (4' - 0" X 4' - 0" X 6' - 9") 24" X 108" R.C. PIPE CULVERT RETAIN

STA. 5104+63.36 - STA. 5110+25.84 CONSTRUCT 562' - 5 7/8" X 2 @ 63' - 0" CLEAR ROADWAY BRIDGE NO. 06939 560' - 0" CONTINUOUS COMPOSITE STEEL W-BEAM UNIT

STA. 5104+33.92 - STA. 5110+12.08 IN PLACE LEFT MAIN LANES 578' - 2" X 28' - 0" CLEAR ROADWAY BRIDGE CONSISTING OF TWELVE 48' - 0" COMPOSITE I-BEAM SPANS WITH 18" OCTAGONAL CONCRETE TRUSSEL PILE BENTS WITH CONCRETE STRUT REMOVE AS EXISTING BRIDGE STRUCTURE = 1.00 LUMP SUM

REMOVAL AND DISPOSAL OF IMPACT ATTENUATION BARRIERS  
 STA. 5112+98 MEDIAN = 2 EACH

SHELL LAKE  
 EXIST. B.E. 5110+12.08

EXIST. R/W & C OF A WIRE FENCE (TYPE A)	16' - 0" GATE
STA. 5105+00 RT. OF R.M.L.	65 LIN. FT.
STA. 5104+27 LT. OF L.M.L.	45 LIN. FT.
STA. 5110+63 RT. OF R.M.L.	49 LIN. FT.
STA. 5109+89 LT. OF L.M.L.	61 LIN. FT.

REMOVAL & DISPOSAL OF APPROACH SLAB & GUTTERS  
 STA. 5104+63 R.M.L. = 1 EACH  
 STA. 5104+16 L.M.L. = 1 EACH  
 STA. 5110+77 R.M.L. = 1 EACH  
 STA. 5110+30 L.M.L. = 1 EACH

REMOVAL & DISPOSAL OF CONCRETE PARAPET WALL  
 STA. 5104+80 RT. OF R.M.L. = 1 EACH  
 STA. 5104+57 LT. OF R.M.L. = 1 EACH  
 STA. 5110+35 RT. OF L.M.L. = 1 EACH  
 STA. 5110+44 LT. OF L.M.L. = 1 EACH

REMOVAL AND DISPOSAL OF FENCE  
 STA. 5104+81 RT. OF R.M.L. = 60 LIN. FT.  
 STA. 5104+34 LT. OF L.M.L. = 60 LIN. FT.  
 STA. 5110+59 RT. OF R.M.L. = 60 LIN. FT.  
 STA. 5110+12 LT. OF L.M.L. = 680 LIN. FT.

REMOVAL & DISPOSAL OF GUARDRAIL  
 STA. 5102+67 TO STA. 5104+67 RT. OF R.M.L. = 200 LIN. FT.  
 STA. 5102+44 TO STA. 5104+44 LT. OF R.M.L. = 200 LIN. FT.  
 STA. 5110+71 TO STA. 5112+71 RT. OF R.M.L. = 200 LIN. FT.  
 STA. 5110+49 TO STA. 5111+74 LT. OF R.M.L. = 125 LIN. FT.  
 STA. 5110+48 TO STA. 5113+73 RT. OF L.M.L. = 325 LIN. FT.  
 STA. 5110+57 TO STA. 5112+32 LT. OF L.M.L. = 175 LIN. FT.

XXXX DENOTES: PAVEMENT TRANSITION

REMOVAL AND DISPOSAL OF CONCRETE PIER PROTECTION  
 STA. 5112+83 TO STA. 5113+12 MEDIAN = 58 LIN. FT.

IMPACT ATTENUATION BARRIER  
 STA. 5103+97 CENTERLINE MAIN LANES = 1 EACH  
 STA. 5110+92 CENTERLINE MAIN LANES = 1 EACH  
 STA. 5112+59 CENTERLINE MAIN LANES = 1 EACH

REFER TO SHEET 58 FOR ADDITIONAL RAMP INFORMATION

T:\Job\WLM2600\_AHTD On-Call\2011 Task Order\_B003\ShellLake\700\_CADD Files\777\_Roadway\Drawings\04\p1n1.dgn  
 12/9/2014 3:59:39 PM




T:\Job\WLM2600\_AHTD\_On-Call\Task\_Order\B003\Shell\Lake\_700\_CADD\_Files\777\_Roadway\Drawings\04\pin2.dgn  
12/9/2014 3:19:55 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BBO113	57	130

PLAN SHEET- STA. 5125+00 TO STA. 5185+00



12/9/14



STA. 5131+00.00  
END JOB BBO113  
LOG MILE 260.25

RETAIN - APPROACH SLAB & GUTTERS


- STA. 5131+31 R.M.L. = 1 EACH
- STA. 5131+39 L.M.L. = 1 EACH
- STA. 5132+41 R.M.L. = 1 EACH
- STA. 5132+49 L.M.L. = 1 EACH

RETAIN - GUARDRAIL

- STA. 5129+24 TO STA. 5131+49 RT. OF R.M.L. = 225 LIN. FT.
- STA. 5129+24 TO STA. 5131+49 LT. OF R.M.L. = 225 LIN. FT.
- STA. 5132+32 TO STA. 5134+57 RT. OF L.M.L. = 225 LIN. FT.
- STA. 5132+32 TO STA. 5134+57 LT. OF L.M.L. = 225 LIN. FT.

STA. 5139+00 IN PLACE  
TYPE H DROP INLET IN  
MEDIAN (2 OPENINGS)  
(4' -0" X4' -0" X3' -10")  
24" X94" R.C. PIPE CULVERT  
RETAIN

STA. 5151+00 IN PLACE  
TYPE H DROP INLET IN  
MEDIAN (2 OPENINGS)  
(4' -0" X4' -0" X2' -10")  
24" X88" R.C. PIPE CULVERT  
RETAIN



STA. 5163+00 IN PLACE  
TYPE H DROP INLET IN  
MEDIAN (2 OPENINGS)  
(4' -0" X4' -0" X2' -10")  
24" X88" R.C. PIPE CULVERT  
RETAIN

STA. 5184+00 IN PLACE  
TYPE H DROP INLET IN  
MEDIAN (2 OPENINGS)  
(4' -0" X4' -0" X2' -10")  
24" X86" R.C. PIPE CULVERT  
RETAIN

T:\Job\W\12600\_AHTD\_On-Call\2011Task\_Order\_B003\ShellLake\700\_CADD\_Files\777\_Roadway\Drawings\04\Initial.dgn 12/9/2014 3:20:33 PM




NOTE: THE HORIZONTAL ALIGNMENT IS BASED ON EXISTING PLANS. THE CONTRACTOR SHALL VERIFY AND SUBMIT FINDINGS TO THE ENGINEER FOR APPROVAL.

RAMP 2  
STA. 5124+00 IN PLACE  
24' X 92' R.C. PIPE CULVERT  
RETAIN

RAMP 1  
STA. 5126+00 IN PLACE  
24' X 92' R.C. PIPE CULVERT  
RETAIN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BB013							58	130

INTERCHANGE LAYOUT - HWY. 149



REMOVAL AND DISPOSAL OF GUARDRAIL  
 STA. 5109+35 TO STA. 5126+60 LT. OF RAMP 1 CL. = 1725 LIN. FT.  
 STA. 5108+75 TO STA. 5121+40 RT. OF RAMP 1 CL. = 1265 LIN. FT.  
 STA. 5114+80 TO STA. 5124+05 RT. OF RAMP 4 CL. = 925 LIN. FT.  
 STA. 5114+20 TO STA. 5118+85 LT. OF RAMP 4 CL. = 465 LIN. FT.

CONCRETE BARRIER WALL (MEDIAN TYPE SPECIAL)  
 RAMP 4 STA. 5114+22 TO STA. 5119+42 LT. OF RAMP 4 = 520 LIN. FT.  
 RAMP 1 STA. 5108+90 TO STA. 5122+18 RT. OF RAMP 2 = 1328 LIN. FT.

GUARDRAIL INSTALLATION		GUARDRAIL (TYPE A)	GUARDRAIL TERMINAL (TYPE 2)	TERMINAL ANCHOR POST (TYPE 1)
STA. 5109+35 TO STA. 5126+60	LT. OF RAMP 1	1675 LIN. FT.	1 EACH	1 EACH
STA. 5114+80 TO STA. 5124+05	RT. OF RAMP 4	875 LIN. FT.	1 EACH	1 EACH

NO.	LOCATION	P. I.	Δ	D	T L		P. C.	P. T.
					FEET	FEET		
1	RAMP 1	5111+15.60	36°00'00" RT.	10°00'00"	186.17	360.00	5109+29.43	5112+89.43
2	RAMP 1	5119+13.20	23°04'00" RT.	6°30'00"	179.87	354.87	5117+33.33	5120+88.20
3	RAMP 1	5126+47.00	25°30'00" LT.	7°00'00"	185.21	364.29	5124+61.79	5128+26.08
4	RAMP 1	5130+29.60	12°00'00" LT.	3°00'00"	200.73	400.00	5128+28.87	5132+28.87
5	RAMP 2	5125+10.50	127°30'00" RT.	28°38'52"	405.56	445.06	5121+04.94	5125+50.00
6	RAMP 2	5126+75.70	15°00'00" RT.	6°00'00"	125.72	250.00	5125+49.98	5127+99.98
7	RAMP 3	5116+62.50	12°00'00" RT.	3°00'00"	200.73	400.00	5114+61.77	5118+61.77
8	RAMP 3	5123+60.50	131°26'00" RT.	25°27'53"	498.71	516.14	5118+61.79	5123+77.93
9	RAMP 4	5117+05.10	15°00'00" LT.	6°00'00"	125.72	250.00	5115+79.38	5118+29.38
10	RAMP 4	5125+89.10	36°34'00" RT.	7°00'00"	270.43	522.38	5123+18.67	5128+41.05

NOTE: FOR EX. STRUCTURES ON MAIN LANES REFER TO MAIN LANE PLAN SHEETS.


RAMP 3  
STA. 5121+00 IN PLACE  
24' X 84' R.C. PIPE CULVERT  
RETAIN

RAMP 4  
STA. 5124+00 IN PLACE  
24' X 92' R.C. PIPE CULVERT  
RETAIN

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0113	59	130
				06939 - LAYOUT -		55929		

The proposed bridge is positioned to avoid interference with the existing piling. The contractor shall verify measurements before driving any piling. Any adjustments necessary to fit the proposed bridge to the existing bridges' locations shall be submitted for the Engineer's approval.

Note: Utility locations as shown are approximate. The contractor shall verify the absence or location of all facilities, structures or utilities within the construction limits of the bridge prior to excavation.



**PLAN**

Note: For R/W Data, See Roadway Drawings.


Total Length of Bridge = 562'-5 7/8" (Measured Along C Bridge)

Note: Stationing is along C Median I-40. Total bridge length and span lengths are measured along C Bridge. All stations and elevations are shown at C Bridge, unless noted otherwise. Elevations shown are at working point.

No work shall be permitted in this area. All construction activities near bridge ends shall be confined to existing embankments and above the original ground line prior to the construction of existing bridge.

Note: Contours as shown are approximate. The contractor shall field verify as needed.

Note: For Boring Legend, Blow Counts, Boring Location Elevation and General Notes, See Drawing No. 55930.



**ELEVATION**

Note: Skew not shown in Elevation for clarity.

SHEET 1 OF 2  
 LAYOUT OF  
 BRIDGE OVER SHELL LAKE  
 SHELL LAKE STR. & APPRS. (S)  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS



BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014  
 DRAWN BY: WEG  
 CHECKED BY: MAA  
 DESIGNED BY: CJC  
 BRIDGE NO. 06939  
 DATE: 9/16/13  
 DATE: 9/17/13  
 DATE: 6/17/13  
 FILENAME: bbb0113x2\_lx1.dgn  
 SCALE: 1" = 30'-0"  
 DRAWING NO. 55929

**GENERAL NOTES**

BENCH MARK: Top of slab at end of existing Bridge No. A3900 14'-0" Lt. of inside face of right curb (looking upstation).  $\odot$  Median I-40 Sta. 5109+63.00, Elev. 210.38

CONSTRUCTION SPECIFICATIONS: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2014 Edition) with applicable supplemental specifications and special provisions. Unless otherwise noted in the plans, section and subsection refer to the Standard Construction Specifications.

DESIGN SPECIFICATIONS: AASHTO Standard Specifications for Highway Bridges (2002 edition) with current interim specifications.

LIVE LOADING: HS20 and Alternate Military Load

METHOD OF DESIGN: Load Factor

SEISMIC PERFORMANCE CATEGORY: C

MATERIALS AND STRENGTHS:  
 Class S(AE) Concrete (superstructure)  $f'_c=4,000$  psi  
 Class S Concrete (substructure)  $f'_c=3,500$  psi  
 Seal Concrete (substructure)  $f'_c=2,100$  psi  
 Reinforcing Steel (AASHTO M31 or M322, Type A, Gr. 60)  $f_y=60,000$  psi  
 Structural Steel (AASHTO M270, Gr. 36)  $f_y=36,000$  psi  
 Structural Steel (AASHTO M270, Gr. 50W)  $f_y=50,000$  psi

BORING LOGS: Boring logs may be obtained from the Programs and Contracts Division.

CONCRETE FILLED STEEL SHELL PILING: Piling in Bents 1 & 9 shall be 24" dia. concrete filled steel shells and shall be driven with an approved air, steam, or diesel hammer to a minimum ultimate bearing capacity of 200 tons per pile and to a tip elevation of 177.50 or lower at Bent 1 and a tip elevation of 157.50 or lower at Bent 9. Piling in end bents shall be driven after embankment to bottom of cap is in place. Test piles are not required at Bents 1 & 9 but may be driven for the contractor's information in accordance with Subsection 805.08(g). Piling in Bents 2 and 8 shall be 16" dia. concrete filled steel shells and shall be driven with an approved air, steam, or diesel hammer to a minimum ultimate bearing capacity of 110 tons per pile and to a tip elevation of 149.00 or lower for Bent 2 and 149.50 or lower for Bent 8. Piling in Bents 3-7 shall be 18" dia. concrete filled steel shells and shall be driven with an approved air, steam, or diesel hammer to a minimum ultimate bearing capacity of 150 tons and to a tip elevation of 138.00 or lower for Bents 3-6 and 141.00 or lower for Bent 7. The first two piles driven in each footing at Bents 2-8, designated as long piles in the Standard Specifications, shall be driven without a follower and shall serve as test piles to determine the established tip elevation. See bent details for test pile locations. Subsequent piles in each footing at Bents 2-8 may be driven with a follower to the established tip elevation. The length of test piles shown on the layout are the estimated lengths of test pile to be left in place. Lengths of piles and test piles shown are assumed for estimating quantities only. Lengths will be determined in the field. Piles and test piles will be measured and paid for as the actual linear feet of accepted piles left in place. There will be no payment for cut-off or build-up of the piles.

PILE DESIGN CAPACITY: Bents 1 & 9 - 73 tons per pile, Bents 2 & 8 - 40 tons per pile, Bents 3 thru 7 - 54 tons per pile.

DRIVING SYSTEM: The driving system approval and the ultimate bearing capacity determination for all piling in Bents 1 & 9 and for test piling in Bents 2-8 shall be based on the requirements of Subsection 805.09(b) "Method B - Wave Equation Analysis (WEAP)" of the Standard Specifications. It is estimated that the minimum required rated energy of the hammer to obtain the minimum ultimate bearing capacity will be 22,000 foot pounds per blow at all bents.

PREBORING/JETTING: For Bents 1 and 9 preboring may be required to obtain the minimum pile penetration requirements. The actual size and depth of preboring shall be determined by the Engineer. All equipment, labor, tools, and incidentals necessary for preboring shall not be paid for directly but shall be considered subsidiary to the item "Steel Shell Piling (24" Dia.)". Jetting will not be allowed to obtain minimum pile penetration requirements for Bents 1 and 9.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113		60	130
				1		06939 - LAYOUT	55930	

For Bents 2 thru 8 preboring or jetting may be required to obtain the minimum pile penetration requirements. The method used to obtain minimum pile penetration shall not be mixed. The actual size and depth of preboring or the depth of jetting shall be determined by the Engineer. The size and depth of preboring or the pressure and depth of jetting used for driving the test piles shall be the same as for driving the production piles. All equipment, labor, tools, and incidentals necessary for preboring or jetting shall not be paid for directly but shall be considered subsidiary to the item "Steel Shell Piling (16" Dia.)" or "Test Pile (16" Dia.)".

For all preboring operations the Contractor shall be responsible for keeping prebored holes free from debris prior to backfilling which may require the use of temporary casing or other methods. All equipment, labor, tools, and incidentals necessary for the cost of keeping the prebored hole free from debris shall not be paid for directly but shall be considered subsidiary to the item "Steel Shell Piling (16" Dia.)", "Test Pile (16" Dia.)", or "Steel Shell Piling (24" Dia.)".

FOOTINGS: The top of the footings for Bents 2-8 shall be a minimum of 2'-0" below the estimated groundline. Any necessary adjustment of footing elevations shall be submitted for the Engineer's approval. Foundation for footings shall be set in accordance with Subsection 801.04 of the Standard Specifications. For dewatering cofferdams, maximum water surface elevation is 192.00.

BRIDGE DECK: The concrete bridge deck shall be given a fine finish as specified for the final finishing in Subsection 802.19 for Class 5 Tined Bridge Roadway Surface Finish.

DETAIL DRAWINGS:	DRAWING NO.
Stage Construction	55931 - 55934
End Bents	55935 - 55940
Intermediate Bents	55941 - 55949
W-Beam Unit	55950 - 55963
Elastomeric Bearings	55964 - 55965
Type Special Approach Slab	55966A - 55968A
Concrete Filled Steel Shell Piling	55021

EXISTING BRIDGE: Existing Bridge No. A3900 (log 259.75) is 34' wide and 578' long and consists of a steel superstructure supported by concrete piles with concrete struts. Existing Bridge No. B3900 (log 259.75) is 34' wide and 578' long and consists of a steel superstructure supported by concrete piles with concrete struts. Half size sheets of existing bridges may be obtained from the Arkansas Highway and Transportation Department. For Bridge A3900 and B3900, see Drawing Nos. 13021 and 13022.

REMOVAL AND SALVAGE: Remove Existing Bridge No. B3900 after Stage 1 Construction is complete and open to traffic. Remove Existing Bridge No. A3900 after Stage 2 Construction is complete and open to traffic. Existing Bridges No. A3900 and B3900 shall be removed in accordance with Section 205 of the Standard Specifications. All material from the existing bridges shall become the property of the Contractor. All work at Bent 1 and 9 shall be confined to existing embankments and above original grade prior to construction of Bridges No. A3900 and B3900.

MAINTENANCE OF TRAFFIC: See Details of Stage Construction (Drawing No. 55931 to 55934). See Roadway Plans for additional details not shown.


HYDRAULICS: Bridge was designed to provide equal or greater waterway opening as the existing bridges.

**BORING BLOW COUNTS**

$\odot$ Median I-40 Sta. 5104+70	$\odot$ Median I-40 Sta. 5106+75	$\odot$ Median I-40 Sta. 5108+50	$\odot$ Median I-40 Sta. 5110+34
0.5-1.5, N-16	4.5-5.5, N-4	4.5-5.5, N-5	24.0-25.0, N-11
24.0-25.0, N-28	9.0-10.0, N-13	9.0-10.0, N-4	29.0-30.0, N-17
29.0-30.0, N-41	14.0-15.0, N-10	14.0-15.0, N-3	34.0-35.0, N-17
34.0-35.0, N-41	19.0-20.0, N-14	19.0-20.0, N-15	39.0-40.0, N-13
39.0-40.0, N-30	24.0-25.0, N-11	24.0-25.0, N-14	44.0-45.0, N-21
44.0-45.0, N-41	29.0-30.0, N-30	29.0-30.0, N-50	49.0-50.0, N-(50/8")
49.0-50.0, N-(50/11")	34.0-35.0, N-36	34.0-35.0, N-50	54.0-55.0, N-(50/10")
54.0-55.0, N-(50/11")	39.0-40.0, N-38	39.0-40.0, N-50	59.0-60.0, N-33
59.0-60.0, N-50	44.0-45.0, N-35	44.0-45.0, N-42	64.0-65.0, N-(50/10")
64.0-65.0, N-50	49.0-50.0, N-50	49.0-50.0, N-33	69.0-70.0, N-(50/10")
69.0-70.0, N-(50/7")	54.0-55.0, N-50	54.0-55.0, N-43	74.0-75.0, N-(50/8")
74.0-75.0, N-(50/8")	59.0-60.0, N-(50/11")	59.0-60.0, N-(50/6")	79.0-80.0, N-(50/10")
79.0-80.0, N-50	64.0-65.0, N-(50/11")	64.0-65.0, N-(50/8")	84.0-85.0, N-(50/9")
84.0-85.0, N-(50/10")	69.0-70.0, N-44	69.0-70.0, N-38	89.0-90.0, N-(50/8")
89.0-90.0, N-(50/7")	74.0-75.0, N-(50/10")	74.0-75.0, N-40	94.0-95.0, N-(50/8")
94.0-95.0, N-(50/7")	79.0-80.0, N-(50/7")	79.0-80.0, N-(50/9")	99.0-100.0, N-(50/7")
99.0-100.0, N-(50/6")	84.0-85.0, N-(50/6")	84.0-85.0, N-(50/7")	
	89.0-90.0, N-(50/7")	89.0-90.0, N-(50/6")	
	94.0-95.0, N-(50/6")	94.0-95.0, N-(50/7")	
	99.0-100.0, N-(50/6")	99.0-100.0, N-(50/6")	

**BORING LEGEND**

- A- Medium dense silty sand w/organics
- B- Firm brown clay w/ferrous stains and sand
- C- Stiff brown and gray sandy clay
- D- Firm brown and gray silty clay w/ferrous stains
- E- Medium dense to dense brown and gray silty sand
- F- Dense gray sandy silt w/gravel
- G- Very dense brown and gray sand w/silt
- H- Very loose gray sandy silt
- I- Soft gray clay w/organics
- J- Medium dense dark gray clayey silt
- K- Very soft gray clay
- L- Medium dense gray sandy silt
- M- Dense brownish gray sand w/organics
- N- Very dense brown and gray sand w/gravel
- O- Very loose to medium dense gray sandy silt w/organics
- P- Dense grayish brown sand w/organics
- Q- Firm brown silty clay w/gravel
- R- Firm brown and gray clay w/ferrous stains
- S - Stiff brown and gray clay w/ferrous stains
- T - Dense to very dense grayish brown sand



**BORING LOCATION ELEVATION**

Note: Skew not shown in Elevation for clarity.




BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014  
 DRAWN BY: WEG  
 CHECKED BY: MAA  
 DESIGNED BY: CJC  
 BRIDGE NO. 06939  
 DATE: 9/16/13  
 DATE: 9/17/13  
 DATE: 6/17/13  
 FILENAME: bbb0113x2\_lx2.dgn  
 SCALE: 1" = 30'-0"  
 DRAWING NO. 55930


SHEET 2 OF 2  
 LAYOUT OF  
 BRIDGE OVER SHELL LAKE  
 SHELL LAKE STR. & APPRS. (S)  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS

DATE REVISED	DATE FILED	DATE REVISED	DATE FILED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113		61	130


06939 - STAGE CONSTRUCTION - 55931



**STAGE 1**  
(Looking Forward)




**STAGE 2**  
(Looking Forward)



**STAGE 3**  
(Looking Forward)

Notes:  
 Details which relate to Maintenance of Traffic are shown on Bridge Plans for information only. See Roadway Plans for Maintenance of Traffic.  
 Outline of Existing Bridges is indicated by dashed lines. Heavy lines indicate new work.  
 ① Temporary Barrier shall be attached to the bridge deck. For details, see Std. Dwg. TC-4.




BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014

SHEET 1 OF 4  
 DETAILS OF STAGE CONSTRUCTION  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS  
 DRAWN BY: WEG DATE: 6/24/13 FILENAME: bbb0113x2\_scl.dgn  
 CHECKED BY: MAA DATE: 6/28/13  
 DESIGNED BY: CJC DATE: 6/17/13 SCALE: 3/16"=1'-0"  
 BRIDGE NO. 06939 DRAWING NO. 55931


4:48:23 PM T:\Job\WL\2600\_AHTD On-Call\2011 Task Order\_B003\Shell Lake\700\_CADD Files\709\_Structural\Drawings\B106\Shell Lake Const\Stage01.dgn  
 12/9/2014

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	62	130	

06939 - STAGE CONSTRUCTION - 55932



**STAGE 4**  
(Looking Forward)



**FINAL**  
(Looking Forward)

Notes:  
 Details which relate to Maintenance of Traffic are shown on Bridge Plans for information only. See Roadway Plans for Maintenance of Traffic.  
 ① Temporary Barrier shall be attached to the bridge deck. For details, see Std. Dwg. TC-4.




BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014  
 DRAWN BY: LHG  
 CHECKED BY: MAA  
 DESIGNED BY: CJC  
 BRIDGE NO. 06939  
 DATE: 1/22/14  
 DATE: 1/24/14  
 DATE: 6/17/13  
 SCALE: 3/16"=1'-0"  
 DRAWING NO. 55932  
 FILENAME: bbb0113x2\_sc2.dgn

SHEET 2 OF 4  
 DETAILS OF STAGE CONSTRUCTION  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113		63	130

① 06939 - STAGE CONSTRUCTION - 55933



**PLAN**

Note: Dimensions shown are along Centerline of Bearing.



**ELEVATION**  
(Looking Back - End Bent 1)  
(Looking Forward - End Bent 9)



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 3 OF 4  
DETAILS OF STAGE CONSTRUCTION  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS


DRAWN BY: LHG  
CHECKED BY: MAA  
DESIGNED BY: CGW  
BRIDGE NO. 06939

DATE: 02/18/14  
DATE: 05/19/14  
DATE: 02/13/14


FILENAME: bbb0113x2\_sc3.dgn  
SCALE: NO SCALE  
DRAWING NO. 55933

4:48:34 PM T:\Job\WLM2600\_AHTD\_On-Call\2011 Task Order\_B003\ShellLake\700\_CADD\_Files\709\_Structural\Files\Drawings\B106\ShellLakeConst\Stage03.dgn 12/9/2014

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113		64	130
				1 06939 - STAGE CONSTRUCTION - 55934				



PLAN - INTERMEDIATE BENTS



ELEVATION - INTERMEDIATE BENTS  
(Looking Forward)

BENT STATIONING TABLE	
Bent 2	Sta. 5105+28.60
Bent 3	Sta. 5106+00.60
Bent 4	Sta. 5106+72.60
Bent 5	Sta. 5107+44.60
Bent 6	Sta. 5108+16.60
Bent 7	Sta. 5108+88.60
Bent 8	Sta. 5109+60.60



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

CHECKED BY: CGW  
DESIGNED BY: BLB  
BRIDGE NO. 06939

DATE: 3/5/14  
DATE: 4/8/14  
DATE: 2/10/14

FILENAME: bbb0113x2\_sc4.dgn  
SCALE: 1" = 6'-0"  
DRAWING NO. 55934

SHEET 4 OF 4  
DETAILS OF STAGE CONSTRUCTION  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

4:48:34 PM T:\Job\WL\XM2600 AHTD On-Cell Task Order B003\ShellLake\700 CADD Files\709 Structural\Drawings\B106ShellLakeConst\Stage04.dgn 12/9/2014



Note: Class 1 Protective Surface Treatment shall be applied to the top of the backwall.

① See "Rounding Detail" on Dwg. No. 55950.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113		65	130
				① 06939 - END BENT DETAILS - 55935				

**GENERAL NOTES**

All concrete shall be Class "S" with a minimum 28 day compressive strength of  $f'c=3,500$  psi.

Concrete shall be poured in the dry and exposed corners shall be chamfered  $\frac{3}{4}$ " unless otherwise noted.


If anchor bolts are drilled into cap, top reinforcing bars shall be properly placed to avoid damage.

All reinforcing steel shall conform to AASHTO M31 or M322 Type A, Grade 60 ( $f_y = 60,000$  psi). Mill test reports shall be submitted for reinforcing steel.

The backwall above the required constr. joints shall not be poured until the beams are in place. Backwall may be placed prior to placing the adjacent concrete deck only if the optional backwall construction joint is used. See Dwg. No. 55962 for "Expansion Device Installation".


Structural Steel in backwall shall be AASHTO M 270, Gr. 50W and shall be paid for as "Structural Steel in Beam Spans (M 270, Gr. 50W)".

For additional information see layout.




**PLAN - STAGE 1 CONSTRUCTION**  
(No Scale)

\*Dimensions are shown to  $\odot$  Expansion Jt.



**ELEVATION - STAGE 1 CONSTRUCTION**  
(Bent 1 Looking Back Stage 1)  
(Bent 9 Looking Forward Stage 1)  
(No Scale)



**SECTION D-D**  
(No Scale)

Bent	"A"	"B"
No. 1	5104+63.36	5104+49.51
No. 9	5110+25.85	5110+39.69



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014


SHEET 1 OF 6  
DETAILS OF END BENTS 1 & 9  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: LHG DATE: 02/18/14 FILENAME: bbb0113x2\_ax1.dgn  
CHECKED BY: MAA DATE: 05/20/14  
DESIGNED BY: CGW DATE: 02/13/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55935




4:48:35 PM T:\Job\WLMX2600 ARTD On-Call\2011 Task Order B003\ShellLake\700 CADD Files\709 Structural\Drawings\B106ShellLakeEndBent01.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
							66	130
				JOB NO. BB0113				
				1 06939 - END BENT DETAILS - 55936				



**PLAN - STAGE 2 & 3 CONSTRUCTION**  
(No Scale)




**ELEVATION - STAGE 2 & 3 CONSTRUCTION**  
(Bent 1 Looking Back Stage 2)  
(Bent 9 Looking Forward Stage 3)  
(No Scale)

Note: Class 1 Protective Surface Treatment shall be applied to the roadway face and top of the transition rail, and to the top of the backwall.

**GENERAL NOTES**

- All concrete shall be Class "S" with a minimum 28 day compressive strength of f'c=3,500 psi.
- Concrete shall be poured in the dry and exposed corners shall be chamfered 3/4" unless otherwise noted.
- If anchor bolts are drilled into cap, top reinforcing bars shall be properly placed to avoid damage.
- All reinforcing steel shall conform to AASHTO M31 or M322 Type A, Grade 60 (fy = 60,000 psi). Mill test reports shall be submitted for reinforcing steel.
- The backwall above the required constr. joints shall not be poured until the beams are in place. Backwall may be placed prior to placing the adjacent concrete deck only if the optional backwall construction joint is used. See Dwg. No. 55962 for "Expansion Device Installation".
- Structural Steel in backwall shall be AASHTO M 270, Gr. 50W and shall be paid for as "Structural Steel in Beam Spans (M 270, Gr. 50W)".
- For additional information see layout.



SHEET 2 OF 6  
DETAILS OF END BENTS 1 & 9  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS


DRAWN BY: LHG DATE: 02/18/14 FILENAME: bbb0113x2\_ax2.dgn  
 CHECKED BY: MAA DATE: 05/20/14  
 DESIGNED BY: CGW DATE: 02/13/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55936

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	67	130	

06939 - END BENT DETAILS - 55937

Note: Class 1 Protective Surface Treatment shall be applied to the roadway face and top of the transition rail, and to the top of the backwall.

12/19/2014 4:48:35 PM T:\Job\WL\2600\_AHTD On-Call\2011 Task Order\_B003\ShellLake\700\_CADD Files\709\_Structural Files\Drawings\B106ShellLakeEndBent03.dgn



**PLAN - STAGE 2 & 3 CONSTRUCTION**  
(No Scale)

\*Dimensions are shown to C Expansion Jt.

**GENERAL NOTES**

All concrete shall be Class "S" with a minimum 28 day compressive strength of  $f'c=3,500$  psi.

Concrete shall be poured in the dry and exposed corners shall be chamfered  $3/4$ " unless otherwise noted.


If anchor bolts are drilled into cap, top reinforcing bars shall be properly placed to avoid damage.

All reinforcing steel shall conform to AASHTO M31 or M322 Type A, Grade 60 ( $f_y = 60,000$  psi). Mill test reports shall be submitted for reinforcing steel.

The backwall above the required constr. joints shall not be poured until the beams are in place. Backwall may be placed prior to placing the adjacent concrete deck only if the optional backwall construction joint is used. See Dwg. No. 55962 for "Expansion Device Installation".


Structural Steel in backwall shall be AASHTO M 270, Gr. 50W and shall be paid for as "Structural Steel in Beam Spans (M 270, Gr. 50W)".

For additional information see layout.



**ELEVATION - STAGE 2 & 3 CONSTRUCTION**

(Bent 1 Looking Back Stage 3)  
(Bent 9 Looking Forward Stage 2)  
(No Scale)








SHEET 3 OF 6  
DETAILS OF END BENTS 1 & 9  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS


DRAWN BY: LHG DATE: 02/18/14 FILENAME: bbb0113x2\_ax3.dgn  
CHECKED BY: MAA DATE: 05/20/14  
DESIGNED BY: CGW DATE: 02/13/14 SCALE: No Scale  
BRIDGE ENGINEER PRINT DATE: 12/9/2014 BRIDGE NO. 06939 DRAWING NO. 55937

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0113	68	130

1 06939 - END BENT DETAILS - 55938



Note: For additional joint details see Dwg. No. 55962.



Note: Concrete shall be hand packed under the joint armor.




SHEET 4 OF 6  
 DETAILS OF END BENTS 1 & 9  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS


DRAWN BY: LHG DATE: 02/18/14 FILENAME: bbb0113x2\_ox4.dgn  
 CHECKED BY: MAA DATE: 05/20/14  
 DESIGNED BY: CGW DATE: 02/13/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55938

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113		69	130

06939 - END BENT DETAILS - 55939




**DETAIL WING A**  
(No Scale)




**DETAIL WING B**  
(No Scale)


**DETAIL Y**  
(No Scale)  
Note: Parapet enhancements at abutment shall align with enhancement in adjacent span.




**VIEW E-E**  
(No Scale)




**THREE DIMENSIONAL VIEW OF RAIL**  
(No Scale)




**SECTION X-X (WING A)**  
(No Scale)



**SECTION X-X (WING B)**  
(No Scale)




**SECTION F-F**  
(No Scale)



**SECTION B-B**  
(No Scale)

Note: Details shown are typical for all transition rails and wings. Details are opposite hand for rails and wings on opposite side of bridge.



**VIEW D-D**  
(No Scale)


Note: Details shown are typical for all transition rails and wings. Details are opposite hand for rails and wings on opposite side of bridge.

Note: Parapet enhancements shall be made continuous if slip forms are used on Bridge Parapet Rail.


**TABLE OF VARIABLES**

Bt.	Wing	"S"	"T"	"V"
1	Left	8'-4 1/4"	2'-5 3/8"	4'-1 1/8"
	Right	8'-4 1/4"	2'-4 3/4"	4'-1 1/4"
9	Left	8'-4 1/4"	2'-5 3/8"	4'-1 1/8"
	Right	8'-4 1/4"	2'-4 3/4"	4'-1 1/4"


Note: Wing designations are looking ahead.




**SECTION G-G**  
(No Scale)



**SECTION H-H**  
(No Scale)



**STUB WALL DETAIL**  
(No Scale)



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

DRAWN BY: LHG DATE: 02/18/14 FILENAME: bbb0113x2\_ax5.dgn  
 CHECKED BY: MAA DATE: 05/20/14  
 DESIGNED BY: CGW DATE: 02/13/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55939

SHEET 5 OF 6  
 DETAILS OF END BENTS 1 & 9  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0113	70	130
① 06939 - END BENT DETAILS - 55940								

### STAGE 1 CONSTRUCTION BAR LIST

MARK	NO. REQ'D	LENGTH	PIN DIA.
B401	98	18'-3"	2"
B402	36	12'-5"	2"
B403E	82	4'-3"	3"
B404	40	24'-0"	Str.
B406	60	5'-8"	Str.
B407	12	10'-8"	2"
B408	78	7'-3"	2"
B410	30	8'-5"	Str.
B601	166	6'-10"	4 1/2"
B602	40	26'-5"	Str.
B605	72	6'-9"	4 1/2"
B606	72	7'-5"	4 1/2"
B701	166	9'-7"	7 1/2"
B702	48	10'-6"	5 1/4"
B901	32	5'-5"	Str.

Note: All bars designated with an "E" suffix are to be epoxy coated.

Number of bars in bar list are for both End Bents Nos. 1 & 9.

### STAGE 2 CONSTRUCTION BAR LIST

MARK	NO. REQ'D	LENGTH	PIN DIA.
B401	122	18'-3"	2"
B402	54	12'-5"	2"
B403E	106	4'-3"	3"
B405	12	6'-9"	Str.
B406	40	5'-8"	Str.
B407	18	10'-8"	2"
B409	40	28'-6"	Str.
B601	212	6'-10"	4 1/2"
B603	20	52'-9"	Str.
B604	5	9'-0"	4 1/2"
B605	48	6'-9"	4 1/2"
B606	48	7'-8"	4 1/2"
B701	212	9'-7"	7 1/2"
B702	72	10'-6"	5 1/4"
B801	5	13'-11"	6"
B802	5	10'-11"	6"
B902	16	54'-8"	Str.
B903	16	55'-11"	9"
W401E	14	9'-5"	2"
W402E	14	10'-6"	Str.
W403E to W408E	2 ea.	to 6'-8"	2"
W409E to W414E	2 ea.	to 7'-9"	Str.
W415E	26	3'-6"	3"
W601	28	3'-0"	Str.
W701	24	14'-8"	Str.
W702	4	10'-9"	Str.
W703	4	9'-3"	Str.
W704	4	7'-9"	Str.
W705	4	13'-9"	5 1/4"
W801	7	19'-8"	6"
W802	7	16'-10"	6"
R401E	18	3'-11"	2"
R402E	8	4'-0"	2"
R403E	12	14'-8"	Str.
R601E	16	8'-1"	Str.
R602E	6	5'-0"	Str.

Note: All bars designated with an "E" suffix are to be epoxy coated.

Number of bars in bar list are for both End Bents Nos. 1 & 9.



### STAGE 3 CONSTRUCTION BAR LIST

MARK	NO. REQ'D	LENGTH	PIN DIA.
B401	122	18'-3"	2"
B402	54	12'-5"	2"
B403E	106	4'-3"	3"
B405	12	6'-9"	Str.
B406	40	5'-8"	Str.
B407	18	10'-8"	2"
B409	40	28'-6"	Str.
B601	212	6'-10"	4 1/2"
B603	20	52'-9"	Str.
B604	5	9'-0"	4 1/2"
B605	48	6'-9"	4 1/2"
B606	48	7'-8"	4 1/2"
B701	212	9'-7"	7 1/2"
B702	72	10'-6"	5 1/4"
B801	5	13'-11"	6"
B802	5	10'-11"	6"
B902	16	54'-8"	Str.
B903	16	55'-11"	9"
W401E	14	9'-5"	2"
W402E	14	10'-6"	Str.
W403E to W408E	2 ea.	to 6'-8"	2"
W409E to W414E	2 ea.	to 7'-9"	Str.
W415E	26	3'-6"	3"
W601	28	3'-0"	Str.
W701	24	14'-8"	Str.
W702	4	10'-9"	Str.
W703	4	9'-3"	Str.
W704	4	7'-9"	Str.
W705	4	13'-9"	5 1/4"
W801	7	19'-8"	6"
W802	7	16'-10"	6"
R401E	18	3'-11"	2"
R402E	8	4'-0"	2"
R403E	12	14'-8"	Str.
R601E	16	8'-1"	Str.
R602E	6	5'-0"	Str.



Note: All bars designated with an "E" suffix are to be epoxy coated.

Number of bars in bar list are for both End Bents Nos. 1 & 9.

### BENDING DIAGRAMS



**ANCHOR BOLT LAYOUT**  
(No Scale)



**CONSTRUCTION JOINT DETAIL**  
(No Scale)




BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 6 OF 6  
DETAILS OF END BENTS 1 & 9  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS


DRAWN BY: LHG DATE: 02/18/14 FILENAME: bbb0113x2\_ax6.dgn  
CHECKED BY: MAA DATE: 05/20/14  
DESIGNED BY: CGW DATE: 02/13/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55940

4:48:37 PM T:\Job\WL\X2600\_AHTD\_On-Call\2011\Task\_Order\_B003\ShellLake\700\_CADD\_Files\709\_Structural\Files\Drawings\B106ShellLakeEndBentDetails.dgn 12/9/2014


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	71	130	
				06939 - INT. BENT DETAILS - 55941				




**BENTS 2 & 8 - PLAN**  
(STAGE 1 CONSTRUCTION)




**BENTS 2 & 8 - ELEVATION**  
(STAGE 1 CONSTRUCTION, LOOKING AHEAD)




**SECTION B-B**  
(No Scale)




**SECTION C-C**  
(No Scale)



**SECTION E-E**  
(No Scale)




**SECTION D-D**  
(No Scale)



**SECTION A-A**  
(No Scale)

\* Reinforcing bars in top of cap shall be properly placed to avoid interference with anchor bolts or sheet metal sleeves.

Neat lines of seal.  
The inside face of the cofferdam shall be at or outside the seal concrete dimensions shown.  
The plan quantity for seal concrete and structural excavation shall be based on the dimensions shown.




BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 1 OF 3  
DETAILS OF INTERMEDIATE BENTS 2 & 8  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS



DRAWN BY: JWB DATE: 3/5/14 FILENAME: bbb0113x2\_bx1.dgn  
CHECKED BY: CGW DATE: 4/8/14  
DESIGNED BY: BLB DATE: 2/10/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55941

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	72	130	


1 06939 - INT. BENT DETAILS - 55942



**BENTS 2 & 8 - PLAN**  
(STAGES 2 & 3 CONSTRUCTION)



**BENTS 2 & 8 - ELEVATION**  
(STAGE 2 CONSTRUCTION LOOKING BACK, STAGE 3 CONSTRUCTION LOOKING AHEAD)



**SECTION E-E**  
(No Scale)

**SHEET 2 OF 3**  
**DETAILS OF INTERMEDIATE BENTS 2 & 8**  
**BRIDGE OVER SHELL LAKE**  
**ST. FRANCIS COUNTY**  
**ROUTE 40 SECTION 51**  
**ARKANSAS STATE HIGHWAY COMMISSION**  
**LITTLE ROCK, ARKANSAS**

BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

DRAWN BY: JWB DATE: 3/5/14 FILENAME: bbb0113x2\_bx2.dgn  
 CHECKED BY: CGW DATE: 4/8/14  
 DESIGNED BY: BLB DATE: 2/10/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55942

Neat lines of seal.  
The inside face of the cofferdam shall be at or outside the seal concrete dimensions shown.  
The plan quantity for seal concrete and structural excavation shall be based on the dimensions shown.

\*\*\*For seal size shown, maximum water surface elevation shall not exceed 192.0 for dewatered cofferdam.

12/9/2014 4:48:37 PM T:\Job\WL\X2600 AHTD On-Call\2011 Task Order B003\_Shell Lake 700 CADD Files\709 Structural Files\Drawings\B06Shell.cak\IntBent02.dgn




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	73	130	
				① 06939 - INT. BENT DETAILS - 55943				

Bar List - Stage 1 Construction (Per Int. Bent)						
Mark	No. Req'd	Length	A	B	Pin Dia.	
B401	4	11'-10"	4'-2"	1'-7"	2"	
B501	5	24'-10"	---	---	Str.	
B502	57	16'-11"	4'-6 1/2"	3'-8"	2 1/2"	
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"	
B504	24	7'-5 1/2"	2'-0"	3'-8"	2 1/2"	
B505	10	46'-0"	---	---	Str.	
B601	24	8'-8"	3'-9"	1'-4"	4 1/2"	
B1001	9	61'-4"	---	---	Str.	
B1002	9	55'-8"	---	---	Str.	
C501	2	C	2'-6 1/2"	---	3 3/4"	
C502	22	9'-4"	2'-6 1/2"	---	3 3/4"	
C801	36	D	---	---	Str.	
F401	68	7'-6"	7'-0"	4 1/2"	3"	
F601	48	10'-5"	9'-9"	6"	4 1/2"	
F701	82	13'-8"	12'-0"	7"	5 1/4"	
F801	36	E	---	F	6"	
F802	60	18'-4"	16'-6"	8"	6"	

Bar List - Stage 2 Construction (Per Int. Bent)						
Mark	No. Req'd	Length	A	B	Pin Dia.	
B401	6	11'-10"	4'-2"	1'-7"	2"	
B502	43	16'-11"	4'-6 1/2"	3'-8"	2 1/2"	
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"	
B506	10	54'-8"	---	---	Str.	
B507	34	14'-5"	4'-6 1/2"	2'-5"	2 1/2"	
B601	36	8'-8"	3'-9"	1'-4"	4 1/2"	
B1003	9	56'-2"	54'-8"	11 1/2"	10"	
B1004	9	54'-8"	---	---	Str.	
C501	1	C	2'-6 1/2"	---	3 3/4"	
C502	22	9'-4"	2'-6 1/2"	---	3 3/4"	
C503	1	G	2'-6 1/2"	---	3 3/4"	
C802	36	H	---	---	Str.	
F401	68	7'-6"	7'-0"	4 1/2"	3"	
F601	48	10'-5"	9'-9"	6"	4 1/2"	
F701	82	13'-8"	12'-0"	7"	5 1/4"	
F801	36	E	---	F	6"	
F802	60	18'-4"	16'-6"	8"	6"	

Bar List - Stage 3 Construction (Per Int. Bent)						
Mark	No. Req'd	Length	A	B	Pin Dia.	
B401	6	11'-10"	4'-2"	1'-7"	2"	
B502	43	16'-11"	4'-6 1/2"	3'-8"	2 1/2"	
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"	
B506	10	54'-8"	---	---	Str.	
B507	34	14'-5"	4'-6 1/2"	2'-5"	2 1/2"	
B601	36	8'-8"	3'-9"	1'-4"	4 1/2"	
B1003	9	56'-2"	54'-8"	11 1/2"	10"	
B1004	9	54'-8"	---	---	Str.	
C501	1	C	2'-6 1/2"	---	3 3/4"	
C502	22	9'-4"	2'-6 1/2"	---	3 3/4"	
C503	1	G	2'-6 1/2"	---	3 3/4"	
C802	36	H	---	---	Str.	
F401	68	7'-6"	7'-0"	4 1/2"	3"	
F601	48	10'-5"	9'-9"	6"	4 1/2"	
F701	82	13'-8"	12'-0"	7"	5 1/4"	
F801	36	E	---	F	6"	
F802	60	18'-4"	16'-6"	8"	6"	



	Bent 2	Bent 8
C	601'-9"	545'-10"
D	15'-7"	14'-7"
E	15'-9"	14'-9"
F	14'-5"	13'-5"
G	585'-9"	529'-10"
H	15'-4"	14'-4"

**GENERAL NOTES**

All concrete shall be Class "S" with a minimum 28 day compressive strength of  $f'_c = 3,500$  psi.

Concrete shall be poured in the dry and exposed corners shall be chamfered  $3/4"$  unless otherwise noted.

If anchor bolts are drilled into cap, top reinforcing bars shall be properly placed to avoid damage.

All reinforcing steel shall conform to AASHTO M31 or M322, Type A, Grade 60.


Spiral reinforcing shall be plain round or deformed steel bars meeting the requirements of AASHTO M31 or M322, Type A, Grade 60, or shall be cold drawn wire meeting the requirements of AASHTO M32 or M225 (Grade 70) with a minimum diameter of 0.625". Spiral reinforcement shall be paid for at the contract unit price bid per pound for "Reinforcing Steel-Bridge (Grade 60)". No additional payment shall be made for spacers, additional splices, or bracing needed for assembly, shipping, handling, or erecting.

Spiral reinforcement projected into the footing shall be terminated with  $1/2$  turns and a  $135^\circ$  hook with a 10" tail hooked around a vertical bar and projected into the column core. The  $135^\circ$  hook may be field bent.

Spiral reinforcement at lapped splices shall be terminated by a  $135^\circ$  hook with a 10" tail hooked around a vertical bar and projected into the column core. The  $135^\circ$  hook may be field bent. Spiral lap splices shall occur at the mid height of column.


Spiral reinforcement projected into the cap shall be terminated with  $1/2$  turns and a  $135^\circ$  hook with a 24" tail hooked around a vertical bar and projected into cap within the column core. The  $135^\circ$  hook may be field bent.

For additional information see layout.




**OPTIONAL MECHANICAL COUPLER DETAIL**  
(No Scale)


- ① The Mechanical Couplers shall be an approved type in accordance with AHTD Qualified Products List (QPL).  
The cost of Mechanical Couplers shall not be measured for separate payment but shall be considered subsidiary to the item "REINFORCING STEEL - BRIDGE (GRADE 60)".  
Mechanical Couplers shall be developed at least 125% of the specified yield strength of the Reinforcing Steel.
- ② One end of bar shall be threaded to match Mechanical Coupler. Length of bar shall match lap splice length detailed on plans.




**DETAIL A**  
(No Scale)




**ANCHOR BOLT LAYOUT - BENT 2 & 8**  
(No Scale)



**SHEAR BLOCK DETAIL**  
(No Scale)



**VIEW C-C**  
(No Scale)




SHEET 3 OF 3  
DETAILS OF INTERMEDIATE BENTS 2 & 8  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: JWB DATE: 3/5/14 FILENAME: bbb0113x2\_bx3.dgn  
 CHECKED BY: CGW DATE: 4/8/14  
 DESIGNED BY: BLB DATE: 2/10/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55943


12/19/2014 4:48:38 PM T:\Job\WLM2600 AHTD On-Call\2011 Task Order B003\ShellLake\700 CADD Files\709 Structural Files\Drawings\B06ShellBent03.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0113	74	130


06939 - INT. BENT DETAILS - 55944




**BENTS 3 & 7 - PLAN**  
(STAGE 1 CONSTRUCTION)




**SECTION B-B**  
(No Scale)




**SECTION C-C**  
(No Scale)




**BENTS 3 & 7 - ELEVATION**  
(STAGE 1 CONSTRUCTION, LOOKING AHEAD)



**SECTION E-E**  
(No Scale)



**SECTION D-D**  
(No Scale)



**SECTION A-A**  
(No Scale)

\* Reinforcing bars in top of cap shall be properly placed to avoid interference with anchor bolts or sheet metal sleeves.



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 1 OF 3  
DETAILS OF INTERMEDIATE BENTS 3 & 7  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: JWB DATE: 3/5/14  
CHECKED BY: CGW DATE: 4/8/14  
DESIGNED BY: BLB DATE: 2/10/14  
BRIDGE NO. 06939 DRAWING NO. 55944


\*\*\*For seal size shown, maximum water surface elevation shall not exceed 192.0 for dewatered cofferdam.

Neat lines of seal.  
The inside face of the cofferdam shall be at or outside the seal concrete dimensions shown.  
The plan quantity for seal concrete and structural excavation shall be based on the dimensions shown.


12/9/2014 4:48:38 PM T:\Job\WLM2600\_AHTD\_On-Call\2011 Task Order\_B003\ShellLake\700\_CADD\_Files\709\_Structural\Drawings\B106ShellLakeBent04.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BBO113	75	130


06939 - INT. BENT DETAILS - 55945



**BENTS 3 & 7 - PLAN**  
(STAGES 2 & 3 CONSTRUCTION)



	Bent 3	Bent 7
A	93	86
B	95	88



**BENTS 3 & 7 - ELEVATION**

(STAGE 2 CONSTRUCTION LOOKING BACK, STAGE 3 CONSTRUCTION LOOKING AHEAD)

\*\*\*For seal size shown, maximum water surface elevation shall not exceed 192.0 for dewatered cofferdam.

Neat lines of seal.  
The inside face of the cofferdam shall be at or outside the seal concrete dimensions shown.  
The plan quantity for seal concrete and structural excavation shall be based on the dimensions shown.

BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

STATE OF ARKANSAS  
REGISTERED PROFESSIONAL ENGINEER  
CHARLES J. BERRY  
BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

**SHEET 2 OF 3**  
**DETAILS OF INTERMEDIATE BENTS 3 & 7**  
**BRIDGE OVER SHELL LAKE**  
**ST. FRANCIS COUNTY**  
**ROUTE 40 SECTION 51**  
**ARKANSAS STATE HIGHWAY COMMISSION**  
**LITTLE ROCK, ARKANSAS**

12/9/2014 4:48:38 PM T:\web\WLMX2600 AHTD On-Call\2011 Task Order B003\_ShellLake\_700\_CADD\_Files\709\_StructuralFiles\Drawings\B106ShellLakIntBent05.dgn


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	76	130	

06939 - INT. BENT DETAILS - 55946

Bar List - Stage 1 Construction (Per Int. Bent)					
Mark	No. Req'd	Length	A	B	Pin Dia.
B401	4	11'-10"	4'-2"	1'-7"	2"
B501	5	24'-10"	---	---	Str.
B502	57	16'-11"	4'-6 1/2"	3'-8"	2 1/2"
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"
B504	24	7'-5 1/2"	2'-0"	3'-8"	2 1/2"
B505	10	46'-0"	---	---	Str.
B601	24	8'-8"	3'-9"	1'-4"	4 1/2"
B1001	9	61'-4"	---	---	Str.
B1002	9	55'-8"	---	---	Str.
C501	2	C	2'-6 1/2"	---	3 3/4"
C502	32	9'-4"	2'-6 1/2"	---	3 3/4"
C1001	42	D	---	---	Str.
F501	68	7'-11"	7'-4"	5"	3 3/4"
F601	48	10'-6"	9'-10"	6"	4 1/2"
F701	82	13'-10"	12'-2"	7"	5 1/4"
F901	60	19'-2"	16'-8"	10"	9"
F1001	42	E	---	F	10"

Bar List - Stage 2 Construction (Per Int. Bent)					
Mark	No. Req'd	Length	A	B	Pin Dia.
B401	6	11'-10"	4'-2"	1'-7"	2"
B502	43	16'-11"	4'-6 1/2"	3'-8"	2 1/2"
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"
B506	10	54'-8"	---	---	Str.
B507	34	14'-5"	4'-6 1/2"	2'-5"	2 1/2"
B601	36	8'-8"	3'-9"	1'-4"	4 1/2"
B1003	9	56'-2"	54'-8"	11 1/2"	10"
B1004	9	54'-8"	---	---	Str.
C501	1	C	2'-6 1/2"	---	3 3/4"
C502	32	9'-4"	2'-6 1/2"	---	3 3/4"
C503	1	G	2'-6 1/2"	---	3 3/4"
C1002	42	H	---	---	Str.
F501	68	7'-11"	7'-4"	5"	3 3/4"
F601	48	10'-6"	9'-10"	6"	4 1/2"
F701	82	13'-10"	12'-2"	7"	5 1/4"
F901	60	19'-2"	16'-8"	10"	9"
F1001	42	E	---	F	10"

Bar List - Stage 3 Construction (Per Int. Bent)					
Mark	No. Req'd	Length	A	B	Pin Dia.
B401	6	11'-10"	4'-2"	1'-7"	2"
B502	43	16'-11"	4'-6 1/2"	3'-8"	2 1/2"
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"
B506	10	54'-8"	---	---	Str.
B507	34	14'-5"	4'-6 1/2"	2'-5"	2 1/2"
B601	36	8'-8"	3'-9"	1'-4"	4 1/2"
B1003	9	56'-2"	54'-8"	11 1/2"	10"
B1004	9	54'-8"	---	---	Str.
C501	1	C	2'-6 1/2"	---	3 3/4"
C502	32	9'-4"	2'-6 1/2"	---	3 3/4"
C503	1	G	2'-6 1/2"	---	3 3/4"
C1002	42	H	---	---	Str.
F501	68	7'-11"	7'-4"	5"	3 3/4"
F601	48	10'-6"	9'-10"	6"	4 1/2"
F701	82	13'-10"	12'-2"	7"	5 1/4"
F901	60	19'-2"	16'-8"	10"	9"
F1001	42	E	---	F	10"



\*10" @ Footing and Splices  
\*24" @ Cap.

**GENERAL NOTES**

All concrete shall be Class "S" with a minimum 28 day compressive strength of f'c = 3,500 psi.

Concrete shall be poured in the dry and exposed corners shall be chamfered 3/4" unless otherwise noted.

If anchor bolts are drilled into cap, top reinforcing bars shall be properly placed to avoid damage.

All reinforcing steel shall conform to AASHTO M31 or M322, Type A, Grade 60.

Spiral reinforcing shall be plain round or deformed steel bars meeting the requirements of AASHTO M31 or M322, Type A, Grade 60, or shall be cold drawn wire meeting the requirements of AASHTO M32 or M225 (Grade 70) with a minimum diameter of 0.625". Spiral reinforcement shall be paid for at the contract unit price bid per pound for "Reinforcing Steel-Bridge (Grade 60)". No additional payment shall be made for spacers, additional splices, or bracing needed for assembly, shipping, handling, or erecting.


Spiral reinforcement projected into the footing shall be terminated with 1/2 turns and a 135° hook with a 10" tailhooked around a vertical bar and projected into the column core. The 135° hook may be field bent.

Spiral reinforcement at lapped splices shall be terminated by a 135° hook with a 10" tailhooked around a vertical bar and projected into the column core. The 135° hook may be field bent. Spiral lap splices shall occur at the mid height of column.


Spiral reinforcement projected into the cap shall be terminated with 1/2 turns and a 135° hook with a 24" tailhooked around a vertical bar and projected into cap within the column core. The 135° hook may be field bent.

For additional information see layout.


	Bent 3	Bent 7
C	785'-5"	729'-6"
D	20'-10"	19'-10"
E	20'-1"	19'-1"
F	18'-6"	17'-6"
G	769'-5"	713'-6"
H	20'-6"	19'-6"




**DETAIL A**  
(No Scale)




**ANCHOR BOLT LAYOUT - BENT 3 & 7**  
(No Scale)



**SHEAR BLOCK DETAIL**  
(No Scale)




**VIEW C-C**  
(No Scale)



**OPTIONAL MECHANICAL COUPLER DETAIL**  
(No Scale)

1 The Mechanical Couplers shall be an approved type in accordance with AHTD Qualified Products List (QPL).  
The cost of Mechanical Couplers shall not be measured for separate payment but shall be considered subsidiary to the item "REINFORCING STEEL - BRIDGE (GRADE 60)".  
Mechanical Couplers shall be developed at least 125% of the specified yield strength of the Reinforcing Steel.

2 One end of bar shall be threaded to match Mechanical Coupler. Length of bar shall match lap splice length detailed on plans.



SHEET 3 OF 3  
DETAILS OF INTERMEDIATE BENTS 3 & 7  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS


DRAWN BY: JWB DATE: 3/5/14 FILENAME: bbb0113x2\_bx6.dgn  
CHECKED BY: CGW DATE: 4/8/14  
DESIGNED BY: BLB DATE: 2/10/14 SCALE: 1" = 2'-0"  
BRIDGE NO. 06939 DRAWING NO. 55946

12/9/2014 4:48:39 PM T:\Job\WLM2600 AHTD On-Call\2011 Task Order B003\ShellLake\700 CADD Files\709 Structural Files\Drawings\B06ShellLake\Bent06.dgn




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	78	130	


06939 - INT. BENT DETAILS - 55948





**BENTS 4 THRU 6 - PLAN**  
(STAGE 2 & 3 CONSTRUCTION)



**SECTION D-D**  
(No Scale)




**SECTION E-E**  
(No Scale)



**BENTS 4 THRU 6 - ELEVATION**  
(STAGE 2 CONSTRUCTION LOOKING BACK, STAGE 3 CONSTRUCTION LOOKING AHEAD)

SHEET 2 OF 3  
DETAILS OF INTERMEDIATE BENTS 4 THRU 6  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS



DRAWN BY: JWB DATE: 3/5/14 FILENAME: bbb0113x2\_bx8.dgn  
CHECKED BY: CGW DATE: 4/8/14  
DESIGNED BY: BLB DATE: 2/10/14 SCALE: 1" = 3'-0"  
BRIDGE NO. 06939 BRIDGE ENGINEER PRINT DATE: 12/9/2014 DRAWING NO. 55948

\*\*\*For sealsize shown, maximum water surface elevation shall not exceed 192.0 for dewatered cofferdam.

Neat lines of seal.  
The inside face of the cofferdam shall be at or outside the seal concrete dimensions shown.  
The plan quantity for seal concrete and structural excavation shall be based on the dimensions shown.

12/9/2014 4:48:40 PM T:\Job\WL\XM2600\_AHTD On-Call\2011 Task Order\_B003\ShellLake\700 CADD Files\709 Structural\Drawings\Bent\Bent08.dgn


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	79	130	

① 06939 - INT. BENT DETAILS - 55949

Bar List - Stage 1 Construction (Per Int. Bent)					
Mark	No. Req'd	Length	A	B	Pin Dia.
B401	4	11'-10"	4'-2"	1'-7"	2"
B501	5	24'-10"	---	---	Str.
B502	58	16'-11"	4'-6 1/2"	3'-8"	2 1/2"
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"
B504	22	7'-5 1/2"	2'-0"	3'-8"	2 1/2"
B505	10	46'-0"	---	---	Str.
B601	24	8'-8"	3'-9"	1'-4"	4 1/2"
B1001	9	6'-4"	---	---	Str.
B1002	9	55'-8"	---	---	Str.
C501	2	939'-4"	3'-0 1/2"	---	3 3/4"
C502	22	10'-11"	3'-0 1/2"	---	3 3/4"
C503	1	920'-3"	3'-0 1/2"	---	3 3/4"
C801	42	18'-10"	---	---	Str.
F501	68	7'-11"	7'-4"	5"	3 3/4"
F601	48	10'-6"	9'-10"	6"	4 1/2"
F701	82	13'-10"	12'-2"	7"	5 1/4"
F801	42	19'-0"	---	17'-8"	6"
F901	60	19'-2"	16'-8"	10"	9"

Bar List - Stage 2 Construction (Per Int. Bent)					
Mark	No. Req'd	Length	A	B	Pin Dia.
B401	6	11'-10"	4'-2"	1'-7"	2"
B502	47	16'-11"	4'-6 1/2"	3'-8"	2 1/2"
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"
B506	10	54'-8"	---	---	Str.
B507	28	14'-5"	4'-6 1/2"	2'-5"	2 1/2"
B601	36	8'-8"	3'-9"	1'-4"	4 1/2"
B1003	9	56'-2"	54'-8"	11 1/2"	10"
B1004	9	54'-8"	---	---	Str.
C501	1	939'-4"	3'-0 1/2"	---	3 3/4"
C502	22	10'-11"	3'-0 1/2"	---	3 3/4"
C503	1	920'-3"	3'-0 1/2"	---	3 3/4"
C802	42	18'-7"	---	---	Str.
F501	68	7'-11"	7'-4"	5"	3 3/4"
F601	48	10'-6"	9'-10"	6"	4 1/2"
F701	82	13'-10"	12'-2"	7"	5 1/4"
F801	42	19'-0"	---	17'-8"	6"
F901	60	19'-2"	16'-8"	10"	9"

Bar List - Stage 3 Construction (Per Int. Bent)					
Mark	No. Req'd	Length	A	B	Pin Dia.
B401	6	11'-10"	4'-2"	1'-7"	2"
B502	47	16'-11"	4'-6 1/2"	3'-8"	2 1/2"
B503	8	12'-6 1/2"	4'-6 1/2"	3'-8"	2 1/2"
B506	10	54'-8"	---	---	Str.
B507	28	14'-5"	4'-6 1/2"	2'-5"	2 1/2"
B601	36	8'-8"	3'-9"	1'-4"	4 1/2"
B1003	9	56'-2"	54'-8"	11 1/2"	10"
B1004	9	54'-8"	---	---	Str.
C501	1	939'-4"	3'-0 1/2"	---	3 3/4"
C502	22	10'-11"	3'-0 1/2"	---	3 3/4"
C503	1	920'-3"	3'-0 1/2"	---	3 3/4"
C802	42	18'-7"	---	---	Str.
F501	68	7'-11"	7'-4"	5"	3 3/4"
F601	48	10'-6"	9'-10"	6"	4 1/2"
F701	82	13'-10"	12'-2"	7"	5 1/4"
F801	42	19'-0"	---	17'-8"	6"
F901	60	19'-2"	16'-8"	10"	9"



\*10" @ Footing and Splices  
\*24" @ Cap.

**GENERAL NOTES**

All concrete shall be Class "S" with a minimum 28 day compressive strength of  $f'c = 3,500$  psi.

Concrete shall be poured in the dry and exposed corners shall be chamfered  $3/4"$  unless otherwise noted.

If anchor bolts are drilled into cap, top reinforcing bars shall be properly placed to avoid damage.

All reinforcing steel shall conform to AASHTO M31 or M322, Type A, Grade 60.

Spiral reinforcing shall be plain round or deformed steel bars meeting the requirements of AASHTO M31 or M322, Type A, Grade 60, or shall be cold drawn wire meeting the requirements of AASHTO M32 or M225 (Grade 70) with a minimum diameter of 0.625". Spiral reinforcing shall be paid for at the contract unit price bid per pound for "Reinforcing Steel-Bridge (Grade 60)". No additional payment shall be made for spacers, additional splices, or bracing needed for assembly, shipping, handling, or erecting.


Spiral reinforcement projected into the footing shall be terminated with  $1/2$  turns and a  $135^\circ$  hook with a 10" tailhooked around a vertical bar and projected into the column core. The  $135^\circ$  hook may be field bent.

Spiral reinforcement at lapped splices shall be terminated by a  $135^\circ$  hook with a 10" tailhooked around a vertical bar and projected into the column core. The  $135^\circ$  hook may be field bent. Spiral lap splices shall occur at the mid height of column.


Spiral reinforcement projected into the cap shall be terminated with  $1/2$  turns and a  $135^\circ$  hook with a 24" tailhooked around a vertical bar and projected into cap within the column core. The  $135^\circ$  hook may be field bent.

For additional information see layout.


4:48:40 PM T:\Job\WLM2600\_AHTD On-Call\2011 Task Order\_B003\ShellLake\700 CADD Files\709 Structural\Drawings\Bent\Bent09.dgn 12/9/2014




**DETAIL A**  
(No Scale)




**ANCHOR BOLT LAYOUT - BENT 4 THRU 6**  
(No Scale)



**SHEAR BLOCK DETAIL**  
(No Scale)




**VIEW C-C**  
(No Scale)



**OPTIONAL MECHANICAL COUPLER DETAIL**  
(No Scale)

① The Mechanical Couplers shall be an approved type in accordance with AHTD Qualified Products List (QPL).  
The cost of Mechanical Couplers shall not be measured for separate payment but shall be considered subsidiary to the item "REINFORCING STEEL - BRIDGE (GRADE 60)".  
Mechanical Couplers shall be developed at least 125% of the specified yield strength of the Reinforcing Steel.

② One end of bar shall be threaded to match Mechanical Coupler. Length of bar shall match lap splice length detailed on plans.



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 3 OF 3  
DETAILS OF INTERMEDIATE BENTS 4 THRU 6  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: JWB DATE: 3/5/14 FILENAME: bbb0113x2\_bx9.dgn  
CHECKED BY: CGW DATE: 4/8/14  
DESIGNED BY: BLB DATE: 2/10/14 SCALE: 1" = 2'-0"  
BRIDGE NO. 06939 DRAWING NO. 55949







DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0113	81	130
06939 - SPAN DETAILS - 55951								

Note:  
At the Contractor's option, one Epoxy coated #5 Bar in the Top and one Epoxy Coated #5 Bar in the Bottom may be substituted for each Bar S504E. Payment will be based on the weight of Bar S504E.

**SLAB REINFORCING (Stage 2 Construction)**  
 Transverse - S503E @ 12" Centers in Top & Bottom  
 S504E @ 12" Centers bent up over Beams  
 S602E @ 6" Centers in Top of Overhang  
 Longitudinal - S401E spaced as shown (Top)  
 S501E spaced as shown (Bottom)  
 S601E spaced as shown over Int. Bents (Top)




**PARTIAL TYPICAL SECTION**  
(No Scale)



**VIEW AT C.L. JOINT**  
(No Scale)

Note:  
See Drawing No. 55959 for Section A-A.  
See Drawing No. 55957 for Section C-C.

- TOLERANCE**
- Minus - 1/4"
  - Plus = Equal to amount of Slab Thickening used to meet Slab Thickness Tolerance - See "ADJUSTMENT FOR SLAB THICKNESS TOLERANCE WHEN REMOVABLE DECK FORMING IS USED" Detail.
  - See "ADJUSTMENT FOR SLAB THICKNESS TOLERANCE WHEN REMOVABLE DECK FORMING IS USED" Detail.
  - Before the Stage 3 deck pour, loosely install as many bolts as possible on both ends of the diaphragm in this bay to the satisfaction of the Engineer. Install remaining bolts and fully tighten all bolts in diaphragms between Beams 6 and 7 only after all deck pours for Stage 3 Construction are complete.
  - Before the Stage 2 deck pour, loosely install as many bolts as possible on both ends of the diaphragm in this bay to the satisfaction of the Engineer. Install remaining bolts and fully tighten bolts in diaphragms between Beams 11 and 12 only after all deck pours for Stage 2 Construction are complete.
  - 2' wide Median Barrier (Stage 4 Construction).
  - Threaded inserts shall be cast in place in Stage 1 Construction to accommodate the connection of temporary barrier. See Standard Drawing TC-4 for additional details.
  - Measured to Working Point - See Rounding Detail on Drawing No. 55950.
  - Tolerance when removable deck forming is used is +1/2", -1/4". Haunch forming is required and shall be adjusted to maintain slab thickness tolerance.



**EXTERIOR BEAM**

**INTERIOR BEAM**

Note: ts = Slab Thickness shown in "TYPICAL SECTION".

**ADJUSTMENT FOR SLAB THICKNESS TOLERANCE WHEN REMOVABLE DECK FORMING IS USED**  
(No Scale)


**LEGEND**  
U.N.O. - Unless Noted Otherwise

SHEET 2 OF 14  
 DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS

BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014

DRAWN BY: LHG DATE: 3/28/14 FILENAME: bbb0113x2\_x12.dgn  
 CHECKED BY: MAA DATE: 4/28/14  
 DESIGNED BY: CJC DATE: 3/20/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55951

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113		82	130
				06939	- SPAN DETAILS -		55952	




**SECTION AT INTERMEDIATE BENT**

(Looking Ahead)  
(Stage 1 Construction)  
(No Scale)


\* For Stage Construction Details, see Drawing Nos. 55931 and 55932.  
\* \* See Details on Drawing No. 55958.

Note:  
See Drawing No. 55959 for "Section B-B".  
See Drawing No. 55957 for "Section D-D".




**SECTION AT INTERMEDIATE BENT**

(Looking Ahead)  
(Stage 2 Construction)  
(Stage 3 Construction Similar)  
(No Scale)



**DETAIL OF WELD LOCATION FOR EXPANSION DEVICE**

- ③ Grind flush 5" from top of deck.
- ④ Weld after Stage 1 Pour & prior to Stage 2 or 3 Pour.




SHEET 3 OF 14  
DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

BRIDGE ENGINEER  
PRINT DATE: 12/9/2014  
DRAWN BY: LHG  
CHECKED BY: MAA  
DESIGNED BY: CJC  
BRIDGE NO. 06939  
DATE: 3/28/14  
DATE: 5/22/14  
DATE: 3/25/14  
SCALE: No Scale  
DRAWING NO. 55952  
FILENAME: bbb0113x2\_x13.dgn

12/9/2014 4:48:41 PM T:\Job\WL\2600\_AHTD\_On-Cell\2011\_Task\_Order\_B003\ShellLake\700\_CADD\_Files\709\_StructuralFiles\Drawings\B0106ShellLakeTypSec03.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0113	83
						06939 - SPAN DETAILS - 55953		



**FRAMING PLAN**  
(No Scale)

- 1 Before the Stage 2 deck pour, loosely install as many bolts as possible on both ends of the diaphragm in this bay to the satisfaction of the Engineer. Install remaining bolts and fully tighten bolts in diaphragms between Beams 11 and 12 only after all deck pours for Stage 2 Construction are complete.
- 2 Before the Stage 3 deck pour, loosely install as many bolts as possible on both ends of the diaphragm in this bay to the satisfaction of the Engineer. Install remaining bolts and fully tighten all bolts in diaphragms between Beams 6 and 7 only after all deck pours for Stage 3 Construction are complete.

Note: Bolts in diaphragm connections shall be properly installed and tightened in accordance with Subsection 807.71 of the Standard Specifications except as noted.

SHEET 4 OF 14  
 DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS



BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014  
 DRAWN BY: LHG  
 CHECKED BY: CGW  
 DESIGNED BY: CJC  
 DATE: 3/21/14  
 DATE: 5/19/14  
 DATE: 3/20/14  
 FILENAME: bbb0113x2\_x14.dgn  
 SCALE: 1" = 10'-0"  
 DRAWING NO. 55953


12/9/2014 4:48:42 PM T:\Job\WLM\2600\_AHTD On-Call\2011 Task Order\_B003\ShellLake\700 CADD Files\709\_Structural\Drawings\B106\ShellLake\Framing\01.DGN



x2 - 7/8" Dia. x 4" shear connectors will be required at about 6" spacing when the bolted field splice is omitted. Payment will be made on the basis of the plan quantities.

Note: Bolted field splices shown may be eliminated or shop welded splices may be substituted with the approval of the Engineer. Payment will be made on the basis of the plan quantities.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BBO113	85	130
06939 - SPAN DETAILS - 55955								




TYPICAL BEAM ELEVATION  
(No Scale)

TABLE FOR WELDS


Material Thickness of Thicker Part Joined (inches)	Minimum Size of Fillet Weld (inches)	Single Pass Weld Must Be Used
To 3/4" inclusive	1/4"	
Over 3/4"	5/16"	

Note: When a fillet weld size, as shown on the plans, is larger than the minimum, the first pass shall be that specified for minimum size of fillet weld.




Stud Shear Connectors shown shall be 7/8" Dia. x 4" long, granular flux filled, solid fluted or equal, and automatically end welded to the beam flange in accordance with the recommendations of the Manufacturer. 3/4" Dia. studs may be used in place of the 7/8" Dia. studs shown at the ratio of 1.36:1. 3/4" Dia. studs will be used as basis for measurement of structural steel in shear connectors. Maximum stud spacing = 2'-0".

SHEAR CONNECTOR DETAIL  
(No Scale)



WEB SPICE  
(No Scale)

- Note:
- All Field Splice Plates shall be AASHTO M270, Gr. 50W.
  - All Field Splice Bolts shall be 7/8" Hi-Str. Bolts.
  - All Field Splice Bolt Holes shall be 15/16" Dia.



FLANGE SPICE  
(No Scale)



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 6 OF 14  
DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: LHG DATE: 1/14/14 FILENAME: bbb0113x2\_x16.dgn  
CHECKED BY: CJC DATE: 5/07/14  
DESIGNED BY: CGW DATE: 1/17/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55955

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0113	86	130


06939 - SPAN DETAILS - 55956

TABLE OF DEAD LOAD DEFLECTIONS (INCHES)

Span	Point	Beams 1 & 17			Beams 2 - 5 & 13 - 16			Beams 6 & 12			Beams 7 & 11			Beams 8 - 10		
		Structural Steel	Structural Steel & Slab	Structural Steel, Slab & Parapet	Structural Steel	Structural Steel & Slab	Structural Steel, Slab & Parapet	Structural Steel	Structural Steel & Slab	Structural Steel, Slab & Parapet	Structural Steel	Structural Steel & Slab	Structural Steel, Slab & Median Barrier	Structural Steel	Structural Steel & Slab	Structural Steel, Slab & Median Barrier
1	1.0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	1.1	0.045	0.202	0.210	0.047	0.225	0.233	0.045	0.259	0.266	0.045	0.189	0.207	0.047	0.225	0.242
	1.2	0.084	0.373	0.389	0.086	0.416	0.430	0.084	0.480	0.493	0.084	0.349	0.384	0.086	0.416	0.448
	1.3	0.111	0.492	0.514	0.114	0.549	0.569	0.111	0.633	0.651	0.111	0.461	0.508	0.114	0.548	0.591
	1.4	0.123	0.546	0.570	0.126	0.609	0.631	0.123	0.702	0.723	0.123	0.511	0.564	0.126	0.608	0.657
	1.5	0.119	0.533	0.556	0.123	0.594	0.616	0.120	0.685	0.706	0.119	0.499	0.550	0.123	0.593	0.641
	1.6	0.103	0.457	0.476	0.105	0.510	0.528	0.103	0.588	0.607	0.102	0.428	0.471	0.105	0.509	0.550
	1.7	0.075	0.336	0.349	0.077	0.375	0.388	0.075	0.433	0.446	0.075	0.315	0.345	0.077	0.375	0.404
	1.8	0.044	0.197	0.205	0.045	0.220	0.227	0.044	0.251	0.258	0.044	0.185	0.202	0.045	0.220	0.236
	1.9	0.015	0.068	0.071	0.016	0.077	0.080	0.015	0.089	0.091	0.015	0.064	0.070	0.016	0.077	0.083
2	2.0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	2.1	0.008	0.034	0.036	0.009	0.039	0.041	0.008	0.044	0.047	0.008	0.032	0.037	0.009	0.039	0.043
	2.2	0.033	0.143	0.151	0.033	0.153	0.159	0.032	0.178	0.185	0.033	0.134	0.151	0.033	0.153	0.166
	2.3	0.059	0.257	0.270	0.061	0.284	0.295	0.060	0.338	0.351	0.059	0.241	0.269	0.061	0.284	0.307
	2.4	0.081	0.356	0.373	0.085	0.398	0.413	0.081	0.455	0.472	0.081	0.333	0.371	0.085	0.397	0.429
	2.5	0.090	0.393	0.412	0.094	0.439	0.456	0.090	0.504	0.522	0.090	0.368	0.409	0.094	0.439	0.475
	2.6	0.083	0.365	0.382	0.087	0.408	0.423	0.083	0.468	0.485	0.083	0.342	0.379	0.087	0.408	0.441
	2.7	0.064	0.280	0.293	0.068	0.317	0.329	0.064	0.362	0.376	0.064	0.262	0.290	0.068	0.316	0.342
	2.8	0.038	0.166	0.174	0.040	0.188	0.195	0.037	0.206	0.214	0.038	0.156	0.173	0.040	0.188	0.203
	2.9	0.011	0.048	0.050	0.012	0.055	0.057	0.011	0.064	0.067	0.011	0.045	0.050	0.012	0.055	0.060
3	3.0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	3.1	0.014	0.061	0.064	0.014	0.069	0.072	0.014	0.079	0.082	0.014	0.057	0.063	0.014	0.068	0.073
	3.2	0.042	0.187	0.196	0.042	0.202	0.209	0.041	0.235	0.242	0.042	0.175	0.194	0.042	0.202	0.217
	3.3	0.070	0.311	0.325	0.072	0.343	0.355	0.072	0.407	0.420	0.070	0.291	0.322	0.072	0.342	0.369
	3.4	0.093	0.411	0.430	0.096	0.458	0.475	0.093	0.526	0.543	0.093	0.385	0.425	0.096	0.458	0.494
	3.5	0.101	0.444	0.464	0.104	0.496	0.514	0.101	0.570	0.589	0.101	0.416	0.459	0.104	0.495	0.533
	3.6	0.093	0.409	0.427	0.096	0.456	0.472	0.093	0.524	0.541	0.093	0.383	0.422	0.096	0.455	0.490
	3.7	0.071	0.313	0.327	0.074	0.353	0.366	0.071	0.404	0.418	0.071	0.293	0.323	0.074	0.353	0.381
	3.8	0.043	0.188	0.196	0.045	0.212	0.220	0.041	0.234	0.242	0.043	0.176	0.194	0.045	0.212	0.229
	3.9	0.013	0.058	0.061	0.014	0.066	0.068	0.014	0.077	0.080	0.013	0.054	0.060	0.014	0.066	0.071
4	4.0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
	4.1	0.012	0.054	0.057	0.013	0.061	0.063	0.012	0.070	0.072	0.012	0.051	0.057	0.013	0.061	0.066
	4.2	0.040	0.176	0.184	0.040	0.190	0.197	0.039	0.220	0.227	0.040	0.164	0.182	0.040	0.189	0.204
	4.3	0.067	0.297	0.311	0.069	0.328	0.340	0.069	0.389	0.402	0.067	0.278	0.308	0.069	0.327	0.353
	4.4	0.090	0.397	0.415	0.094	0.443	0.459	0.090	0.508	0.525	0.090	0.372	0.412	0.094	0.442	0.477
	4.5	0.098	0.431	0.450	0.102	0.482	0.500	0.098	0.554	0.573	0.098	0.404	0.446	0.102	0.481	0.519
	4.6	0.090	0.398	0.416	0.094	0.444	0.460	0.090	0.511	0.528	0.090	0.373	0.412	0.094	0.444	0.479
	4.7	0.069	0.305	0.318	0.073	0.344	0.357	0.070	0.394	0.408	0.069	0.285	0.315	0.073	0.344	0.371
	4.8	0.041	0.183	0.191	0.044	0.207	0.215	0.040	0.227	0.235	0.041	0.171	0.189	0.044	0.206	0.222
	4.9	0.013	0.056	0.059	0.013	0.063	0.065	0.013	0.074	0.077	0.013	0.052	0.058	0.013	0.063	0.068
5.0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	

← @ Unit

Note: This table is symmetrical about @ Unit.



Note: Camber beams for dead load deflection plus vertical curve. Tolerance is  $\pm 1/4"$ . Deflections shown are from a chord extending from @ Bearing to @ Bearing. Vertical curve corrections are not included. Negative sign (-) indicates point above chord.



SHEET 7 OF 14  
 DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS


BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014  
 DRAWN BY: LHG  
 CHECKED BY: CJC  
 DESIGNED BY: CGW  
 BRIDGE NO. 06939  
 DATE: 4/27/14  
 DATE: 5/7/14  
 DATE: 4/1/14  
 FILENAME: bbb0113x2\_x17.dgn  
 SCALE: No Scale  
 DRAWING NO. 55956

4:48:46 PM T:\Job\WLM2600\_AHTD On-Call 2011 Task Order\_B003\Shell Lake\700\_CADD Files\709\_Structural Files\Drawings\B003\Shell Lake\Deflection01.DGN 12/9/2014


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113		87	130
				06939 - SPAN DETAILS - 55957				

Note:  
1/2" Polystyrene shall be used as a bond breaker between the shear block and the concrete diaphragm and may remain in place.


Polystyrene shall be considered subsidiary to "Class S(AE) Concrete - Bridge".




**PARTIAL VIEW OF LONGITUDINAL SHEAR RESTRAINT DEVICES AND SHEAR BLOCK AT INTERMEDIATE BENTS**  
(No Scale)




**VIEW J-J**  
(No Scale)




**SECTION D-D**  
(No Scale)




**SECTION C-C**  
(No Scale)



**VIEW K-K**  
(Typ. at each beam)  
(No Scale)




**PLAN VIEW OF LONGITUDINAL SHEAR RESTRAINT DEVICE**  
(No Scale)



**VIEW G-G**  
(No Scale)

Note: Beam Restrainer Plate and Bumper Bar shall conform to AASHTO M270, Gr. 50W and shall be included in the item "Structural Steel in Beam Spans (M270 - Gr. 50W)".



**SECTION AT END BENT**  
(No Scale)


Note: For Bumper Bar details, See "End Bent Details".  
For Expansion Joint details, See Drawing No. 55962.

		Temperature				
		20°	40°	60°	80°	100°
Bent 2	"G1"	1"	1 5/16"	1 5/8"	1 5/8"	2 1/4"
	"G2"	2 1/4"	1 5/16"	1 5/8"	1 5/8"	1"
Bent 8	"G1"	2 3/16"	1 5/16"	1 5/8"	1 5/8"	1 1/16"
	"G2"	1 1/16"	1 5/16"	1 5/8"	1 5/8"	2 3/16"


**TABLE A**

Note: The temperature used to set "G1" and "G2" shall be the approximate average air temperature during the 24 hour period immediately before the restrainers are welded to the beams.

The Engineer shall establish the temperature. Interpolation of the table may be necessary.




**VIEW H-H**  
(No Scale)



**VIEW M-M**  
(No Scale)

Note: Longitudinal Shear Restraint Devices shall conform to AASHTO M270, Gr. 50W and shall be included in the item "Structural Steel in Beam Spans (M270 - Gr. 50W)".



**VIEW G-G**  
(No Scale)




BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 8 OF 14  
DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: LHG DATE: 4/16/14 FILENAME: bbb0113x2\_x18.dgn  
CHECKED BY: CJC DATE: 5/9/14  
DESIGNED BY: CGW DATE: 4/1/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55957

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0113	88
						1 06939 - SPAN DETAILS - 55958		




Note:  
Required Slab Joints and Pouring Sequence Construction Joints shall align with the Parapet Joints at the Gutterline. Joints in the Median Barrier shall align with joints in the slab.

**SLAB HALF-PLAN**  
(No Scale)


For spacing of parapet bars in Slab see Drawing No. 55960.

For Slab Pouring Sequence and location of Slab Joints, see Drawing No. 55959.

\* S601E placed as shown over Int. Supports. Refer to "Typical Roadway Section".




**DETAIL A**  
(No Scale)




**DETAIL B**  
(No Scale)

Use Type 3 or 4 Joint Sealer. See Subsections 501.02(h) and 501.05(j). Backer Rod filler will not be required. Joint Sealer shall be measured and paid for as Class S(AE) Concrete-Bridge. Slab joints shall extend to the outside edge of the deck slab. Slab joints shall be installed before the parapet railing is poured. If slab joints are to be sawed, they shall be sawed as soon as the concrete has sufficiently set to allow sawing of the joint without damage to the slab. Slab joints shall be placed at all pouring sequence construction joints and required slab joint locations. The joint sealer shall extend across the deck slab (gutterline to gutterline). Slab joints shall align with parapet open joints. Median Barrier joints shall align with joints in the slab.



**SLAB JOINT DETAIL**  
(No Scale)

1/2" x 1" Type 3 or 4 Joint Sealer. See Subsections 501.02 (h) and 501.05 (j). Backer Rod filler will not be required. Joint Sealer shall be measured and paid for as Class S(AE) Concrete-Bridge. This joint shall be formed. Seal must be gray or other color similar to concrete.



**LONGITUDINAL CONSTRUCTION JOINT**  
(No Scale)

SHEET 9 OF 14  
DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS




BRIDGE ENGINEER  
PRINT DATE: 12/9/2014  
DRAWN BY: LHG  
CHECKED BY: MAA  
DESIGNED BY: CMF  
BRIDGE NO. 06939  
DATE: 2/17/14  
DATE: 2/20/14  
DATE: 2/14/14  
SCALE: No Scale  
DRAWING NO. 55958  
FILENAME: bbb0113x2\_x19.dgn

12/9/2014 4:48:46 PM T:\Job\WLM2600\_AHTD\_On-Call\2011 Task Order\_BB03\ShellLake\Drawings\B06\ShellLake\span01.dgn




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BBO113	89
						06939 - SPAN DETAILS - 55959		



Note: At the Contractor's option, the transverse screed may be placed parallel to the skew or perpendicular to  $\phi$  Bridge.

**CONCRETE PLACEMENT PROCEDURE**  
(No Scale)



**SLAB POURING SEQUENCE**  
(No Scale)

Note:  
Pours with the same number may be placed simultaneously or separately. All pours (1) must be placed before any pours (2) can be placed. Forty-Eight (48) hours shall elapse between the end of a pour and the start of the next pour. Seventy-two (72) hours shall elapse between the end of a pour and the start of an adjacent pour, and between the end of a pour and the pouring of the parapet. Any railing pours made before the slab unit has been placed must be approved by the Engineer.

Concrete in bridge superstructure shall be consolidated for the entire pour before any concrete has taken its initial set. This may require the use of a retarding agent. The contractor must obtain approval from the Bridge Engineer for any deviations from the pouring sequence shown.

**BAR LIST (STAGE 1)**

Mark	No. Required	Length	Pin Dia.	Bending Diagrams Dimensions shown are out to out of bars
S401E	370	57'-6"	Str.	
S501E	420	58'-4"	Str.	
S502E	2142	4'-6"	Str.	
S505E to S548E	4 ea.	3'-10" to 4'-1"	Str.	
S549E	4	47'-11"	Str.	
S601E	238	37'-0"	Str.	
D501E	100	7'-7"	2 1/2"	
D502E	12	5'-3"	2 1/2"	
D503E	350	7'-3"	2 1/2"	
D504E	42	5'-4"	2 1/2"	
D505	216	8'-7"	Str.	
D506	144	2'-11"	Str.	
D507	72	5'-9"	Str.	
M407E	1074	2'-1"	2"	




× × Ends threaded for mechanical couplers. Length of vertical leg includes the length of the mechanical coupler. The actual length of vertical leg engagement into the mechanical coupler shall be determined by the mechanical coupler manufacturer. The length of the vertical leg shall be adjusted accordingly.

**BAR LIST (PER STAGE 2 OR 3)**


Mark	No. Required	Length	Pin Dia.	Bending Diagrams Dimensions shown are out to out of bars
P401E	672	6'-3"	3"	

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	90	130	

06939 - SPAN DETAILS - 55960





ELEVATIONS OF TYPICAL PARAPET RAIL  
(As viewed from roadway side of Parapet)




All panels shall be braced as shown to prevent racking. All open joints shall be sawed as soon as practical to a minimum width of 1/4". To control cracking before sawing, all joints must be grooved before the concrete is set. Sawing of the joints must be controlled so it will follow the grooved joint.

The extruded parapet shall conform to the horizontal and vertical lines shown on the plans or as directed by the Engineer and shall present a smooth, uniform appearance and texture. Unless otherwise noted exposed surfaces may be given a light brush finish or a Class 3, Textured Coating Finish in place of the Class 2 Rubbed Finish.


DETAILS OF OPTIONAL SLIPFORMING OF CONCRETE PARAPET RAIL  
(No Scale)




CLOSED PARAPET SECTION A-A  
(No Scale)



OPEN PARAPET @ END POST SECTION B-B  
(No Scale)




OPEN PARAPET @ DRAIN SECTION C-C  
(No Scale)




Note: Parapet studs shall be 5" long, granular flux filled, solid fluxed, or equal, and automatically end welded to the plate. Studs and plate shall meet the requirements of Section 807. Studs and plates shall be measured and paid for as "Structural Steel in Beam Spans (M270, Gr. 50W)".

The surfaces of the 3/8" plates which will not be in contact with concrete shall be painted in accordance with Section 638 or as approved by the Engineer. Only one coat is required and shall be applied in the fabricator's shop. Painting will not be paid for directly, but will be considered subsidiary to "Structural Steel in Beam Spans (M270, Gr. 50W)".



DETAILS OF PARAPET ENHANCEMENT  
(No Scale)



SECTION F-F  
(No Scale)



SHEET 11 OF 14  
DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

BRIDGE ENGINEER  
PRINT DATE: 12/9/2014




DRAWN BY: LHG  
CHECKED BY: CJC  
DESIGNED BY: CGW

DATE: 02/17/14  
DATE: 05/06/14  
DATE: 02/13/14


FILENAME: bbb0113x2\_x1b.dgn  
SCALE: No Scale  
DRAWING NO. 55960

12/9/2014 4:48:47 PM T:\Job\WL\XM2600 AHTD On-Call\2011 Task Order B003\ShellLake\700 CADD Files\709 Structural\Drawings\B106ShellLakeParapet01.dgn



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	91	130	
				06939 - SPAN DETAILS -		55961		



MARK	NO. REQ'D	LENGTH	PIN DIA.	BENDING DIAGRAMS (DIMENSIONS ARE OUT TO OUT OF BARS)
M401E	2150	1'-6"	Str.	
M402E	944	9'-8"	5 3/4", 3"	
M403E	264	10'-4"	9 3/4", 3"	
M404E	192	9'-8"	Str.	
M405E	160	15'-8"	Str.	
M406E	86	5'-6"	Str.	



③ One end threaded for mechanical coupler. Length of bar does not include any additional length for engagement into mechanical coupler. The actual length of bar engagement into the mechanical coupler shall be determined by the mechanical coupler manufacturer, and the length of the bar shall be adjusted accordingly.



**GENERAL NOTES**

CONCRETE: All concrete shall be Class S(AE) with a minimum 28 day compressive strength  $f'_c = 4,000$  psi.

REINFORCING STEEL: All reinforcing steel shall conform to AASHTO M31 or M322 Type A. Mill test reports shall be submitted.

Slider plates shall be AASHTO M270, Gr. 36 or Gr. 50 and shall be paid for as "Structural Steel in Beam Spans (M270, Gr. 50W)". The surfaces of the plates which will not be in contact with the concrete shall be cleaned and painted in accordance with Section 638, or as directed by the Engineer. Only one coat is required and shall be applied in the fabricator's shop. Painting shall not be paid for directly, but will be considered subsidiary to "Structural Steel in Beam Spans (M270, Gr. 50W)".

Details of the Proposed Slider Plate Assembly for the Median Barrier shall be submitted to and approved by the Engineer prior to fabrication of the structural steel at the expansion device.

Note: The Threaded Dowel and Coupler Assembly shall consist of a QPL Approved Mechanical Splice with Protective Cap and Threaded Dowel Bars (M401E and M407E) as shown and shall develop at least 125% of the yield strength of the Dowel Bars. The Threaded Dowel and Coupler Assembly will not be paid for separately but will be considered included in the unit price for "Reinforcing Steel - Bridge (Grade 60)".

Note: M401E and M407E Dowel Bars shall be a minimum 60 ksi Yield Strength and Threaded as required. Threaded Dowel and Coupler Assembly, except mating surfaces, shall be Epoxy Coated in accordance with the requirements of Section 804.



SHEET 12 OF 14  
 DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS

BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014

DESIGNED BY: CGW  
 BRIDGE NO. 06939

DATE: 4/3/14  
 FILENAME: bbb0113x2\_x1c.dgn  
 SCALE: No Scale  
 DRAWING NO. 55961

12/9/2014 4:48:48 PM T:\Job\WL\M2600\_AHTD On-Call\2011 Task Order\_B003\Shell Lake\700\_CADD Files\709\_Structural Files\Drawings\BBO113\Shell\MedBarrier01.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BBO113							92	130

06939 - SPAN DETAILS - 55962


Note:  
Each expansion joint device shall be blocked in the shop by the Fabricator to the dimension "A" @ 60° F and the blocking details shall be shown on the Shop Drawings. Blocking shall be placed within 2'-0" of each end of the device and with a maximum spacing of 8'-0".

- One of two different blocking systems is required depending on the type of finishing machine that is used.
1. For Transverse Strike-off: Plate, angle or other shapes, attach to steel extrusion for blocking.
  2. For Longitudinal Strike-off: Bolt and spacer attached to channel and angle for blocking.

**EXPANSION DEVICE INSTALLATION**


The Contractor may elect to install the expansion device using one of the following two alternatives.

1. The concrete span pour adjacent to joint shall be placed before the end bent backwall is placed. After the end bent backwall forms are in place and the beams erected, the blocked expansion device shall be installed and adjusted for grade. All connection bolts shall be fully tightened prior to placing the deck concrete adjacent to the bent. Immediately prior to pouring the backwall concrete, the blocking shall be removed, the opening adjusted for temperature, and the backwall constructed.
2. The backwall shall be poured to the optional construction joint after beams are erected. The blocked expansion device shall be installed and adjusted for grade. All connection bolts shall be fully tightened prior to placing the deck concrete adjacent to the bent. Immediately prior to pouring the remainder of the backwall concrete, the blocking shall be removed and the opening adjusted for temperature.




**DETAIL A**  
(No Scale)


Note: Concrete shall be hand packed under the joint armor in the backwall and the span.



**STEEL EXTRUSION DETAIL**  
(No Scale)



**DETAILS OF ANCHORS**  
(No Scale)




**DETAILS FOR BLOCKING EXPANSION JOINT DEVICE**  
(No Scale)

**STRIP SEAL JOINT DATA**


Bent No.	Movement Rating	"A" width perpendicular to joint at 24 hour average temperature of:			"B" width perpendicular to joint at 24 hour average temperature of:			"C" width perpendicular to joint at 24 hour average temperature of 60° F
		40° F	60° F	80° F	40° F	60° F	80° F	
1 & 9	4"	2 3/4"	2 3/8"	2"	2 1/4"	1 1/8"	1 1/2"	2 1/2"

Note: The temperature used to set the joint opening shall be the approximate average air temperature during the 24 hour period immediately before the bolts are tightened. The Engineer shall establish the temperature. Interpolation of the table may be necessary. Installation is limited to 40 degrees F min. and 80 degrees F max. The temperature limitations by the lubricant-adhesive manufacturer shall be observed.




**DETAILS OF NEOPRENE SEAL AT PARAPET FACE**  
(No Scale)

Note: Dimension "X" equals the width of the opening in the parapet at the curb to allow for removal or repair of joint.



**SECTION B-B**  
(No Scale)

Note: Details of joint turn-up in parapet are general and show basic design controls only. Method of installation and fabrication shall be determined by the manufacturer. See Section 809 of the Standard Specifications.



**SECTION D-D**  
(No Scale)

Note: Dimension "X" equals the width of the opening in the parapet at the curb to allow for removal or repair of joint.


**GENERAL NOTES**

**EXPANSION NEOPRENE STRIP SEAL:** The expansion device shall provide a movement of 4" as shown in the "STRIP SEAL JOINT DATA" table. The expansion joint shall be capable of sealing the deck surface and parapet area to prevent moisture and other contaminants from descending through the joint.

Details of proposed slider plate assembly shall be submitted to and approved by the Engineer prior to the fabrication of any structural steel at the expansion device.


All Structural Steel shall be AASHTO M270, Grade 36 unless otherwise noted. All exposed surfaces are to be cleaned and painted as directed in Section 638, or as approved by the Engineer. Only one coat is required and shall be applied in the fabricator's shop. Painting will not be paid for directly, but will be considered subsidiary to Structural Steel in Beam Spans (M270, Gr. 50W). Structural steel completely embedded in concrete need not be painted.

All Structural Steel, except for the steel extrusion for the strip seal, shall be paid for as "STRUCTURAL STEEL IN BEAM SPANS (M270, Grade 50W)". The steel extrusion and neoprene strip seal shall be paid for in accordance with Section 809 of the Standard Specifications.



**SECTION THROUGH JOINT AT END BENTS**  
(No Scale)


Note: Detail expansion device 1/8" high and provide 1/4" shims using 2-1/16" plates and 1-1/8" plate. For additional details, see Dwg. Nos. 55950 and 55951.




**SECTION C-C**  
(No Scale)

\*\* The method of attachment of the cover slider plate assembly or similar device must be such that it may be removed in order to provide for future replacement of the neoprene seal.

Anchors will not be paid for directly but will be considered subsidiary to "Structural Steel in Beam Spans (M270, Gr. 50W)".



**TYPICAL CHANNEL CONNECTION DETAIL**  
(No Scale)



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 13 OF 14  
DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION

LITTLE ROCK, ARKANSAS  
DRAWN BY: LHG DATE: 02/17/14 FILENAME: bbb0113x2\_x1d.dgn  
CHECKED BY: CJC DATE: 05/03/14  
DESIGNED BY: CGW DATE: 02/13/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55962

### SUPERSTRUCTURE GENERAL NOTES

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BBO113	93
						1 06939 - SPAN DETAILS - 55963		

**Construction Specifications:**  
Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2014 edition) with applicable supplemental specifications and special provisions.

**Design Specifications:**  
AASHTO Standard Specifications for Highway Bridges (2002 Edition) with current interim specifications.

**Materials and Strengths:**  
 Class S(AE) Concrete (superstructure)      f'c=4,000 psi  
 Reinforcing Steel (AASHTO M31 or M53, Gr. 60)      fy=60,000 psi  
 Structural Steel (AASHTO M270, Gr. 36)      Fy=36,000 psi  
 Structural Steel (AASHTO M270, Gr. 50W)      Fy=50,000 psi

**Structural Steel:**  
All structural steel shall be AASHTO M 270, Gr. 50W unless otherwise noted and shall be paid for as "Structural Steel in Beam Spans (M 270, Gr. 50W)" unless otherwise noted. AASHTO M 270, Gr. 50W steel shall not be painted. All exposed surfaces shall be cleaned in accordance with Subsection 807.84(e) unless otherwise noted. Structural steel completely embedded in concrete may be AASHTO M 270, Gr. 36 unless otherwise noted.

Requests for substitution of structural steel shapes shown with shapes of greater size must be submitted by the Contractor to the Engineer for approval. Steel of equal or greater strengths will be accepted only when shown on the approved shop drawings. Shapes and materials shown in the plans will be the basis of payment and no additional compensation will be made for any adjustments due to substitutions.

Beams and field splice plates are considered main load carrying members and shall meet the Longitudinal Charpy V-Notch Test specified in Subsection 807.05. This work and material will not be paid for directly, but shall be considered subsidiary to the item "Structural Steel in Beams Spans (M 270, Gr. 50W)".

Flange field splice plates shall be cut and fabricated so that the primary direction of rolling is parallel to the direction of main tensile and/or compressive stresses.

All beams shall be blocked in their true position in the shop with the webs horizontal in groups as specified in Subsection 807.54 (b)(2). The camber, length of sections, distance between bearings, and openings of joints shall be measured with the beam in their true position and this information shall become a part of the permanent records of this job. The component parts shall be match marked in this assembly and these marks shall be shown on the erection diagram. All beam dimensions are based on a temperature of 60°F. A tolerance of +/- 1/4" is allowed for camber.

Field connections shall be bolted with high strength bolts. Bolts shall be placed with heads on the outside face of the exterior beam webs and on bottom of beam flanges. Holes for 3/4" high strength bolts in diaphragms and expansion device may be 15/16" diameter if a washer is supplied for use under both the nut and the head of the bolt.

All welding that is to be done during fabrication of structural steel, including temporary welds, shall be detailed on the shop drawings and submitted for approval. If additional welds are required, whether permanent or temporary, a formal request with detailed drawings shall be submitted to the Engineer for approval; however, additional welds used for attaching falsework support devices or screed rail supports to the structural steel that do not exceed the limitations of Subsection 802.13 will not require approval prior to construction. All welding shall conform to Subsection 807.26.

Drawings show general features of design only. Shop drawings shall be made in accordance with the specifications, submitted, and approval secured before fabrication is begun.

Steel diaphragms shall be installed as beams are erected. All bolts in field splices shall be installed and tightened in accordance with Subsection 807.71 of the Standard Specifications prior to pouring of the slab unless otherwise noted. Before the Stage 2 deck pour, loosely install as many bolts as possible on both ends of the diaphragm between Beams 11 and 12 to the satisfaction of the Engineer. Install remaining bolts and fully tighten bolts in diaphragms between Beams 11 and 12 only after all deck pours for Stage 2 Construction are complete. Before the Stage 3 deck pour, loosely install as many bolts as possible on both ends of the diaphragm between Beams 6 and 7 to the satisfaction of the Engineer. Install remaining bolts and fully tighten all bolts in diaphragms between Beams 6 and 7 only after all deck pours for Stage 3 Construction are complete.

All stud shear connectors shall be granular flux filled, solid fluxed, or equal and shall be automatically end welded in accordance with the recommendations of the manufacturer.


**Reinforcing Steel:**  
All reinforcing steel shall conform to AASHTO M31 or M322, Type A, Grade 60 with mill test reports. The reinforcing steel shall be accurately located in the forms and firmly held in place by steel wire supports sufficient in size and number to prevent displacement during the course of construction. The wire supports will not be paid for directly but will be considered subsidiary to the item of "Epoxy Coated Reinforcing Steel (Grade 60)".

**Concrete:**  
All concrete shall be Class S(AE) with a minimum 28 day compressive strength of f'c = 4,000 psi. Concrete shall be poured in the dry and all exposed corners are to be chamfered 3/4" unless noted otherwise.

The superstructure details shown are for use when removable deck forming is used and are the basis for measurement of Class S(AE) Concrete. See Standard Drawing No. 55005 for allowable modifications and for tolerances when Permanent Steel Bridge Deck Forms are used.

Concrete diaphragms shall be poured monolithically with the slab.

Concrete in bridge superstructure shall be placed and consolidated for the entire pour and screeded off before any concrete has taken its initial set. This may require the use of a retarding agent. The concrete bridge deck shall be given a fine finish as specified for final finishing in Subsection 802.19 for a Class 5 tined bridge roadway surface finish. Movement of the finishing machine across the new concrete shall be on planks placed on the surface and shall be prohibited for 72 hours after finishing the pour. Sufficient concrete must be placed ahead of the strike-off to fully load the beam. If a longitudinal strike-off is used, a vertical camber adjustment must be made in the strike-off to account for the future dead load deflection due to the railing. A minimum of 72 hours shall elapse between completion of slab and pouring of the parapet rail.



**LEGEND**

U.N.O. - Unless Noted Otherwise

**PARTIAL PLAN OF CONCRETE DIAPHRAGM REINFORCING**

(No Scale)

Note:  
See Drawing No. 55959 for Sections A-A and B-B.  
See Drawing No. 55957 for Sections C-C and D-D.



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 14 OF 14  
 DETAILS OF 560'-0" CONT. COMP. W-BEAM UNIT  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS


DRAWN BY: LHC      DATE: 5/9/14      FILENAME: bbb0113x2\_x1e.dgn  
 CHECKED BY: MAA      DATE: 5/12/14  
 DESIGNED BY: JRS      DATE: 5/8/14      SCALE: No Scale  
 BRIDGE NO. 06939      DRAWING NO. 55963

T:\Job\WL\X2600\_AHTD On-Call 2011 Task Order\_B003\_ShellLake\700\_CADD Files\709\_StructuralFiles\Drawings\BDD65ShellLakeStabNotes01.DGN


12/9/2014 4:48:49 PM

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113		94	130


06939 - BEARING DETAILS - 55964




- 1 Care shall be taken to ensure that the external load plate is in full and complete contact with the beam flange before welding begins.
- 2  $\phi$  Elastomeric pad shall be aligned with  $\phi$  Beam.



PLAN VIEW (No Scale)



SIDE VIEW (No Scale)




ELASTOMERIC BEARING (No Scale)

TABLE OF FABRICATOR VARIABLES

BRIDGE NO.	LOCATION			BEARING TYPE	NO. of BRGS. EACH BENT	* MAXIMUM DESIGN LOAD (kips)	ELASTOMERIC PAD										EXTERNAL LOAD PLATE										ANCHOR BOLT			
	BENT NO(S).	UNIT	BEAM NO.				G	H	A	B	N	t <sub>i</sub>	t <sub>e</sub>	NO. & THICKNESS OF STEEL LAMINAE	T	C	D	E	F	K	M	T <sub>a</sub>	T <sub>b</sub>	ANCHOR BOLT		PIPE SLEEVE SIZE (Ø x L)	SHEET METAL SLEEVE SIZE (Ø x L)	STEEL WASHER SIZE (O.D.)		
																								Ø x L	GRADE					
06939	1 & 9	560'	All	Exp.	17	85	11 3/4"	8 1/2"	1'-2"	10"	8	1/2"	1/4"	9 @ 12 ga.	5 7/16"	11"	2'-2"	7 7/16"	3 1/8"	1/2"	9 3/4"	2"	2"	2" x 2'-10"	55	2 1/2" x 8 3/4"	4" x 6"	3 3/4"		

\* Maximum Load - Service Load



ANCHOR BOLT DETAIL (No Scale)

NOTE:  
Anchor Bolts may be cast in place or drilled and grouted into place. If Anchor Bolts are to be cast in place, the Galvanized Sheet Metal Sleeves will not be required.  
If Anchor Bolts are to be drilled and grouted in place, the Galvanized Sheet Metal Sleeves shall be cast in place as shown. Sleeves shall be dry packed with styrofoam, urethane foam or approved equal prior to pouring of concrete. After pouring of the cap and prior to erection of Structural Steel, the dry pack shall be removed and holes for the anchor bolts shall be accurately drilled into the masonry. Bolts placed in drilled holes shall be accurately set and fixed using a QPL approved epoxy or non-shrink grout that completely fills the holes. Galvanized Sheet Metal Sleeves will not be paid for directly, but will be considered subsidiary to the item "Structural Steel in Beam Spans, (M 270, Gr. 50W)".

GENERAL NOTES

Elastomeric Bearings shall conform to Section 808 of the Standard Specifications and shall be paid for at the unit price bid for "Elastomeric Bearings".  
External load plates shall conform to AASHTO M 270, Grade 50W and will not be paid for separately, but will be included in the unit price bid for "Elastomeric Bearings". Pipe sleeves shall be ASTM A53, Grade B, and shall be galvanized to conform to AASHTO M 232, Class C or ASTM B695, Class 50.  
External load plates shall be completely fabricated (including bevel, bolt holes and all shop welding) and shall be cleaned before vulcanized to the elastomeric bearing. The surface in contact with the elastomeric bearing shall be cleaned in accordance with Subsection 808.03. Other surfaces shall be blast cleaned in accordance with Subsection 807.84(e) for unpainted Grade 50W steel.  
Anchor Bolts, Washers and Nuts shall conform to Subsection 807.07 of the Standard Specifications. The anchor bolt grade of steel shall be as specified in the "Table of Fabricator Variables". Indentations shall be circular with rounded bottoms and staggered as shown in the details.  
Pipe Sleeves, Anchor Bolts, Washers and Nuts shall be paid for at the unit price bid for "Structural Steel in Beam Spans (M270, Gr. 50W)".  
Bearings shall be seated in accordance with Subsection 808.08. Work and materials shall be considered subsidiary to the item "Elastomeric Bearings" and will not be paid for directly.




SHEET 1 OF 2  
DETAILS OF ELASTOMERIC BEARINGS  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS


BRIDGE ENGINEER  
PRINT DATE: 12/9/2014  
DRAWN BY: LHG  
CHECKED BY: CJC  
DESIGNED BY: CGW  
BRIDGE NO. 06939  
DATE: 02/17/14  
DATE: 05/03/14  
DATE: 01/23/14  
FILENAME: bbb0113x2\_ex1.dgn  
SCALE: No Scale  
DRAWING NO. 55964

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113	95	130	

06939 - BEARING DETAILS - 55965




- 1 Care shall be taken to ensure that the external load plate is in full and complete contact with the beam flange before welding begins.
- 2  $\phi$  Elastomeric pad shall be aligned with  $\phi$  Beam.



FRONT VIEW (No Scale)


PLAN VIEW (No Scale)



Note: The direction of bevel of the External Load Plate may not be accurately depicted with respect to the "T(a)" and "T(b)" values shown in the "Table of Fabricator Variables".

Unless otherwise approved by the Engineer, welding of the top external load plate at expansion bearings to the beam will be allowed only when: 1) the approximate average air temperature during the 24 hour period immediately preceding welding is between 40°F and 80°F; and 2) The slots in the top external load plates are positioned to center on the anchor bolts; and 3) no horizontal deformation of the elastomeric pad is evident. If welding at other temperatures is required, the Engineer will provide adjustment data.

SIDE VIEW (No Scale)




t<sub>j</sub> = thickness of elastomer between steel laminae  
t<sub>e</sub> = thickness of elastomer cover on top and bottom of pad  
N = number of elastomer layers of thickness t<sub>j</sub>

ELASTOMERIC BEARING (No Scale)

TABLE OF FABRICATOR VARIABLES

BRIDGE NO.	LOCATION			BEARING TYPE	NO. of BRGS. EACH BENT	* MAXIMUM DESIGN LOAD (kips)	ELASTOMERIC PAD										EXTERNAL LOAD PLATE										ANCHOR BOLT			
	BENT NO(S).	UNIT	BEAM NO.				G	H	A	B	N	t <sub>j</sub>	t <sub>e</sub>	NO. & THICKNESS OF STEEL LAMINAE	T	C	D	E	F	J	K	M	T <sub>a</sub>	T <sub>b</sub>	ANCHOR BOLT		PIPE SLEEVE SIZE (Ø x L)	SHEET METAL SLEEVE SIZE (Ø x L)	STEEL WASHER SIZE (O.D.)	
																									Ø x L	GRADE				
06939	2 & 8	560'	All	Exp.	17	166	8 5/8"	6 1/8"	1'-3"	1'-0"	6	1/2"	1/4"	7 @ 12 ga.	4 1/4"	1'-1"	2'-8"	5 5/8"	2"	3 5/8"	1/2"	12"	2"	2"	1/4" x 1'-11"	55	1/4" x 6 3/8"	3" x 6"	2 1/2"	
06939	3 - 7	560'	All	Fix	17	163	7 3/4"	4 15/16"	1'-2 1/2"	10"	4	1/2"	1/4"	5 @ 12 ga.	3"	1"	2'-8"	2 1/4"	2 1/4"	2 1/8"	1/2"	12"	2"	2"	1/2" x 2'-1"	55	1/2" x 5 1/4"	3" x 6"	3"	

\* Maximum Load = Service Load



ANCHOR BOLT DETAIL (No Scale)

NOTE: Anchor Bolts may be cast in place or drilled and grouted into place. If Anchor Bolts are to be cast in place, the Galvanized Sheet Metal Sleeves will not be required. If Anchor Bolts are to be drilled and grouted in place, the Galvanized Sheet Metal Sleeves shall be cast in place as shown. Sleeves shall be dry packed with styrofoam, urethane foam or approved equal prior to pouring of concrete. After pouring of the cap and prior to erection of Structural Steel, the dry pack shall be removed and holes for the anchor bolts shall be accurately drilled into the masonry. Bolts placed in drilled holes shall be accurately set and fixed using a QPL approved epoxy or non-shrink grout that completely fills the holes. Galvanized Sheet Metal Sleeves will not be paid for directly, but will be considered subsidiary to the item "Structural Steel in Beam Spans, (M 270, Gr. 50W)".

GENERAL NOTES

Elastomeric Bearings shall conform to Section 808 of the Standard Specifications and shall be paid for at the unit price bid for "Elastomeric Bearings". External load plates and shear blocks shall conform to AASHTO M 270, Grade 50W and will not be paid for separately, but will be included in the unit price bid for "Elastomeric Bearings". Pipe sleeves shall be ASTM A53, Grade B, and shall be galvanized to conform to AASHTO M 232, Class C or ASTM B695, Class 50. External load plates and external load plates with shear blocks shall be completely fabricated (including bevel, bolt holes and all shop welding) and shall be cleaned before vulcanized to the elastomeric bearing. The surface in contact with the elastomeric bearing shall be cleaned in accordance with Subsection 808.03. Other surfaces shall be blast cleaned in accordance with Subsection 807.84(e) for unpainted Grade 50W steel. Anchor Bolts, Washers and Nuts shall conform to Subsection 807.07 of the Standard Specifications. The anchor bolt grade of steel shall be as specified in the "Table of Fabricator Variables". Indentations shall be circular with rounded bottoms and staggered as shown in the details. Pipe Sleeves, Anchor Bolts, Washers and Nuts shall be paid for at the unit price bid for "Structural Steel in Beam Spans (M270, Gr. 50W)". Bearings shall be seated in accordance with Subsection 808.08. Work and materials shall be considered subsidiary to the item "Elastomeric Bearings" and will not be paid for directly.



BRIDGE ENGINEER  
PRINT DATE: 12/9/2014

SHEET 2 OF 2  
DETAILS OF ELASTOMERIC BEARINGS  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: LHG  
CHECKED BY: CJC  
DESIGNED BY: CGW  
BRIDGE NO. 06939

DATE: 02/17/14  
DATE: 05/03/14  
DATE: 01/23/14  
SCALE: No Scale  
DRAWING NO. 55965


FILENAME: bbb0113x2\_ex2.dgn

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	96	130	

06939 - APPROACH SLAB - 55966A


Note:  
Threaded Inserts shall be cast in place in Stage 1 Approach Slab construction to accommodate the connection of Temporary Barrier. See Standard Drawing TC-4 for additional details.

The Surface Finish for Approach Slabs shall match that used on the Bridge Deck.




**PLAN OF APPROACH SLAB**  
(Left-advance skew shown, right-advance skew similar)

x Lap for #4 Bars = 2'-0"




Use 1/2" x 1" Type 3 or 4 Joint Sealer as per Subsection 501.02(h)(2). Backer Rod is not required.


**DETAIL OF SAWED LONGITUDINAL JOINT**  
(No Scale)




**SECTION Z-Z**  
(No Scale)



**DETAIL OF SUPPORT AT END OF SLAB**  
(No Scale)



**DETAIL OF LONGITUDINAL CONSTRUCTION JOINT**  
(No Scale)



**DETAIL OF INTERIOR SLAB SUPPORT**  
(No Scale)

Note:  
For Details of Approach Gutters, see Dwg. No. 55030C.



BRIDGE ENGINEER  
PRINT DATE: 12/10/2014

SHEET 1 OF 3  
DETAILS OF TYPE SPECIAL 1 APPROACH SLABS  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: LHG DATE: 2/17/14 FILENAME: bbb0113x2\_as1.dgn  
CHECKED BY: LHG DATE: 5/28/14  
DESIGNED BY: JRS DATE: 2/13/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55966A






DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AD. PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0113		97	130

06939 - APPROACH SLAB - 55967A


DOWEL SCHEDULE	
Stage No.	"X"
1	20
2	48
3	24



\* Space and orient M408E bars to align mechanical couplers with M401E bars to be installed in Stage 1 Construction. See Median Barrier on Approach Slab Details on Dwg. No. 55968A for spacing and positioning of M401E bars.

**SECTION Y-Y STAGE 1 CONSTRUCTION**  
(No Scale)

① Threaded inserts shall be cast in place in Stage 1 slab construction to accommodate the connection of Temporary Barrier. See Standard Drawing TC-4 for addition details.



**SECTION X-X STAGE 2 & 3 CONSTRUCTION**  
(No Scale)

**BAR LIST FOR ONE STAGE TYPE SPECIAL APPROACH SLAB**

Mark	No.	Length	Pin Dia.	BENDING DIAGRAM
				(Dimensions are shown out to out of bars)
S401	25	35'-8"	Str.	
S402 to S414	1 each	2'-2" to 33'-4"	Str.	
S415 to S438	2 each	19'-2" to 29'-0"	Str.	
S439	"X"	4'-0"	Str.	
S501	37	35'-8"	Str.	
S502 to S521	1 each	1'-4" to 34'-2"	Str.	
F401	104	10'-4"	2"	
F402	1	9'-10"	2"	
F403	1	9'-2"	2"	
F404	1	8'-0"	2"	
F405	1	7'-2"	2"	
F406	10	35'-8"	Str.	
F407	1	34'-2"	Str.	
F408	1	33'-2"	Str.	
S701 to S772	1 each	36'-2" to 56'-8"	Str.	
M408E	92	3'-1"	2"	

- Notes:
- Bars shown are for Stage 1 Construction (one end of bridge). Stages 2 and 3 are similar except as noted in "Dowel Schedule" and do not include M408E bars.
  - Bar Designations Ending with "E" indicated Epoxy Coated Bars.
  - See "Dowel Schedule" for number of bars.
  - Ends Threaded for Mechanical Couplers. Length of vertical legs includes the length of the mechanical coupler. The actual length of vertical bar engagement into the mechanical coupler shall be determined by the mechanical coupler manufacturer, and the length of the vertical legs shall be adjusted accordingly.

**GENERAL NOTES**

Concrete shall be Class S(AE) (f'c = 4,000 psi) and shall be poured in the dry.  
 Reinforcement Steel shall conform to AASHTO M31 or M322, Grade 60 (fy = 60,000 psi), Type A, with mill test reports.  
 Approach Slabs will be measured and paid for in accordance with Section 504 of the Standard Specifications.

**QUANTITIES FOR ONE APPROACH SLAB**

(All Stages, including Median Barrier on one Approach Slab.)

Reinforcing Steel (lbs.)	Epoxy-Coated Reinforcing Steel (lbs.)	Concrete (cubic yds)
33,494	1188	300.55 **

\*\* Includes 8.30 Cu. Yds. for the Median Barrier.  
 For details of Median Barrier, see Drawing No. 55968A.




BRIDGE ENGINEER  
 PRINT DATE: 12/9/2014

SHEET 2 OF 3  
 DETAILS OF TYPE SPECIAL 1 APPROACH SLABS  
 BRIDGE OVER SHELL LAKE  
 ST. FRANCIS COUNTY  
 ROUTE 40 SECTION 51  
 ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARKANSAS

DRAWN BY: LHG DATE: 2/17/14 FILENAME: bbb0113x2\_as2.dgn  
 CHECKED BY: LHG DATE: 5/26/14  
 DESIGNED BY: JRS DATE: 2/13/14 SCALE: No Scale  
 BRIDGE NO. 06939 DRAWING NO. 55967A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO113	98	130	


06939 - APPROACH SLABS - 55968A




**ELEVATION - MEDIAN BARRIER ON APPROACH SLAB**

Stage 4 Construction  
(No Scale)


② Full Depth Median Barrier Joint (1/4" to 1" max.)  
Stop 4" above Top of Approach Slab.



**DETAIL A**  
(No Scale)



**SECTION A-A**  
(No Scale)



**DETAILS OF OPTIONAL SLIPFORMING OF CONCRETE MEDIAN RAIL**  
(No Scale)

**GENERAL NOTES**

**CONCRETE:** All concrete shall be Class S(AE) with a minimum 28 day compressive strength f'c = 4,000 psi.

**REINFORCING STEEL:** All reinforcing steel shall conform to AASHTO M31 or M322 Type A. Mill test reports shall be submitted.

All structural steel for the Median Barrier Slider Plates, Bent Studs, and Slider Plate Anchors shall be AASHTO M270, Gr. 50W unless otherwise noted. Structural steel completely embedded in concrete need not be painted.

All structural steel for the Median Barrier Slider Plates and Bent Studs shall be paid for as "STRUCTURAL STEEL IN BEAM SPANS (M270, Gr. 50W)".

Details of the Proposed Slider Plate Assembly for the Median Barrier shall be submitted to and approved by the Engineer prior to fabrication of the structural steel at the expansion device.


① One end threaded for mechanical coupler. Length of bar does not include any additional length for engagement into mechanical coupler. The actual length of bar engagement into the mechanical coupler shall be determined by the mechanical coupler manufacturer, and the length of the bar shall be adjusted accordingly.

**BAR LIST STAGE 4 CONSTRUCTION**

MARK	NO. REQ'D	LENGTH	PIN DIA.	BENDING DIAGRAMS (DIMENSIONS ARE OUT TO OUT OF BARS)
M401E	184	1'-1"	Str.	
M402E	92	9'-7"	5 3/4", 3"	
M403E	3	10'-4"	9 3/4", 3"	
M409E	6	16'-2"	Str.	
M410E	4	25'-6"	Str.	
M411E	6	19'-8"	Str.	
M412E	3	11'-4"	Str.	
M413E	3	10'-8"	Str.	

Notes:  
Bar designations with "E" indicates epoxy coated bars.

Bars shown are for Stage 4 Construction, Median Barrier on Approach Slabs (one end of Bridge).




SHEET 3 OF 3  
DETAILS OF TYPE SPECIAL 1 APPROACH SLABS  
BRIDGE OVER SHELL LAKE  
ST. FRANCIS COUNTY  
ROUTE 40 SECTION 51  
ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARKANSAS

DRAWN BY: LHG DATE: 02/17/14 FILENAME: bbb0113x2\_as3.dgn  
CHECKED BY: LHC DATE: 05/26/14  
DESIGNED BY: JRS DATE: 02/13/14 SCALE: No Scale  
BRIDGE NO. 06939 DRAWING NO. 55968A


2:00:29T:R:\Mob\WLM2600\_AHTD On-Call 2011 Task Order\_B003\ShellLake\700\_CADD\_Files\709\_Structural\Files\Drawings\BDD6\Backfish-ShellLakeAppMedBarrier01.dgn 12/10/2014

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		99	
							JOB NO.	


① EMBANKMENT & BACKFILL 55000




EMBANKMENT CONSTRUCTION AND FOOTING BACKFILL AT VERTICAL WALL ABUTMENTS




EMBANKMENT CONSTRUCTION AT SPILL-THROUGH PILE END BENTS




EMBANKMENT CONSTRUCTION AND FOOTING BACKFILL AT SPILL-THROUGH END BENTS




VERTICAL WALL ABUTMENTS



SPILL-THROUGH END BENTS WITH STUB WING



SPILL-THROUGH END BENTS WITH TURNBACK WING



SPILL-THROUGH END BENTS WITH TRANSITION WING

METHOD OF DETERMINING FILL SLOPE LOCATION AT BRIDGE ENDS

GENERAL NOTES

The Bridge End Embankment shall be defined as a section of embankment, not less than 20 feet long adjacent to the bridge end, together with the side slopes and slopes under the bridge end including around the end of wingwalls. Embankment adjacent to structures shall be constructed in 6 inch horizontal layers (loose measure) and compacted by the use of mechanical equipment to the satisfaction of the Engineer. Refer to Subsections 210.09, 210.10 and 801.08 for construction requirements.


STANDARD DETAILS FOR EMBANKMENT CONSTRUCTION AND BACKFILL AT BRIDGE ENDS

ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARK.


DRAWN BY: KDH DATE: 2-27-2014 FILENAME: b55000.dgn  
CHECKED BY: BEF DATE: 2-27-2014 SCALE: NO SCALE  
DESIGNED BY: STD. DATE: -

DRAWING NO. 55000


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		100	
JOB NO.							①	
							RIPRAP & EXCAV.	55001




**EXCAVATION FOR STRUCTURES -  
ABUTMENT IN NEW EMBANKMENT  
INTERIOR BENT IN NEW EMBANKMENT  
AND NATURAL GROUND**




**EXCAVATION FOR STRUCTURES - BRIDGE  
LOCATION WITH DESIGNATED CHANNEL CHANGE**




**PLAN OF DUMPED RIPRAP**




**ELEVATION OF RIPRAP  
BERME WITH RIPRAP**




**ELEVATION OF RIPRAP  
BERME WITHOUT RIPRAP**




**EXCAVATION FOR STRUCTURES -  
ABUTMENT IN NATURAL GROUND**




**EXCAVATION FOR STRUCTURES -  
ABUTMENT IN NEW EMBANKMENT  
INTERIOR BENT IN NATURAL GROUND**




**SECTION A-A  
(Toe Excavation in Soil)**




**SECTION B-B**




**SECTION A-A  
(Toe Excavation in Rock)**




**OPEN ABUTMENT WITH  
TURNBACK WINGS**



**EXCAVATION FOR STRUCTURES -  
BENT IN ROADWAY FILL SECTION  
AND NATURAL GROUND**



**EXCAVATION FOR STRUCTURES - ABUTMENT  
IN NATURAL GROUND AND NEW EMBANKMENT**



**DETAIL C**

Note: Use this type of toe when rock is encountered which is in a stable condition.

Note: In lieu of an aggregate filter blanket, a synthetic fiber geotextile fabric complying with the requirements of Subsection 816.02(e) may be used.

Note: Details for computing excavation for structures are included for information as to how plan quantities were calculated and for use when adjusting quantities when changing footing elevation.

**STANDARD DETAILS FOR  
DUMPED RIPRAP AND FILTER BLANKET  
AND COMPUTING  
EXCAVATION FOR STRUCTURES**













**ARKANSAS STATE HIGHWAY COMMISSION**

LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 2-27-2014 FILENAME: b55001.dgn  
 CHECKED BY: BEF DATE: 2-27-2014 SCALE: NO SCALE  
 DESIGNED BY: STD. DATE: \_\_\_\_\_

DRAWING NO. 55001

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		161	
JOB NO.							BRIDGE DECK FORMS 55005	



\*t<sub>s</sub> = slab thickness as shown on superstructure detail drawings.  
GENERAL NOTES

Permanent steel deck forms may be used at the Contractor's option and shall be at no additional cost to the Department. Such use may result in changes to the dead load deflection of the girder. Any cost for adjustments due to a change in the dead load deflection will be borne by the Contractor. Payment for deck concrete and structural steel will not be increased due to use of permanent steel deck forms.

Permanent steel deck forms shall conform to Subsection 802.14(b). Detailed plans, including detailed calculations and manufacturer's technical brochure, shall be submitted to and approved by the Engineer before work of forming the bridge deck is started.

Welding of form supports to the tension flange of steel girders will be permitted only in areas where shear connectors are used. When welding is not allowed, the method of fastening Z or L supports to the flange must be approved by the Engineer.

Form sheets shall be fastened to supporting members and to each other with galvanized metal screws sufficient in size and number to provide a secure attachment. Alternate methods of attachment must be approved by the Engineer.

When the pitch of form corrugations match the reinforcing spacing, transversely align form sheets across the bridge to maintain the correct orientation of continuous reinforcing bars in the corrugations.

Bar support rods, when used, shall be sized and spaced to adequately support the bottom reinforcing mat at the required position.

High chairs shall be sized to support the top mat of reinforcing at the proper position. High chairs shall be placed at locations shown on the detail drawings.

Specifications: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction (2014 Edition), with applicable Supplemental Specifications and Special Provisions.

**STANDARD DETAILS FOR PERMANENT STEEL BRIDGE DECK FORMS FOR STEEL & CONCRETE GIRDER SPANS**

ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 2-27-2014 FILENAME: b55005.dgn  
CHECKED BY: BEF DATE: 2-27-2014 SCALE: NONE  
DESIGNED BY: STD. DATE: \_\_\_\_\_

DRAWING NO. 55005



① Distance from top of slab to bottom of top flange as measured at centerline girder and as shown on superstructure detail drawings. This dimension may vary within the following limits to maintain the grade and slab thickness tolerances: Minimum - occurs when either the top flange or the support angle leg contacts the bottom reinforcing steel; Maximum = t<sub>s</sub> + 1/4" + flange thickness. See Section C-C for slab thickness tolerance between adjacent girder flanges.

② Distance from top of slab to top of girder as measured at centerline girder and as shown on superstructure detail drawings. This dimension may vary within the following limits to maintain the grade and slab thickness tolerances: Minimum - occurs when either the top of girder or the support angle leg contacts the bottom reinforcing steel; Maximum - value shown on the superstructure detail drawings when removable forms are used. See Section C-C for slab thickness tolerance between adjacent girder flanges.

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
12-1-14				6	ARK.		102	
1-14-15								
				JOB NO.				
① TYPE D NAME PLATE								55010

The name of the bridge as shown on the plans shall be placed on Lines 1 - 3 using 1/8" raised letters and numerals 3/8" high.

Line	Example 1	Example 2	Example 3	Example 4
Line 1	Red River	Southern	Saline	Highway 5
Line 2	Relief	Railroad	River	
Line 3		Overpass	Relief	



**GENERAL NOTES**

Specifications: Arkansas State Highway and Transportation Department Standard Specifications for Highway Construction, (2014 Edition) with applicable Supplemental Specifications and Special Provisions.

Name plates shall be cast bronze and shall meet the material requirements as specified in Section 812.

Body of plate shall be 1/4" thick and shall include four tapering cone lugs 3/8" to 5/8" x 2" long. The border and all lettering shall be raised 1/8" above the face of plate and shall be polished.

All lettering shall be plain gothic, square cut and not tapered.

The number of plates required and the location and name on the plate for each bridge shall be as designated on the plans.

Place the design live loading here using 1/8" raised letters and numerals 1/4" high. Examples: HS 20 HL-93

Place the Year in which Contract was awarded here using 1/8" raised numerals 3/8" high. Example: 2001

Place the name of the company awarded the construction contract here using 1/8" raised letters and numerals 3/8" high. Example: ABCD CONSTRUCTION, INC.

Place the Bridge number here using 1/8" raised letters and numerals 1/4" high. Examples: A1234 05432


- ▲ Revised Chair and Vice Chair Added New Commissioner  
1-14-15 KDH Checked By: CRE
- ▲ Revised Deputy Director/Chief Engineer Added Deputy Director/Chief Operating Officer  
12-1-14 KDH Checked By: CRE

TYPICAL BRIDGE NAME PLATE

STANDARD DETAILS FOR TYPE D BRIDGE NAME PLATE


ARKANSAS STATE HIGHWAY COMMISSION  
LITTLE ROCK, ARK.  
DRAWN BY: KDH DATE: 2-27-2014 FILENAME: b55010.dgn  
CHECKED BY: BEF DATE: 2-27-2014 SCALE: NO SCALE  
DESIGNED BY: STD. DATE: \_\_\_\_\_  
DRAWING NO. 55010

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		103	
				JOB NO.		STEEL SHELL PILES		55021




**CONCRETE FILLED STEEL SHELL PILE**

- ① Pile anchorage shall be placed to minimize interference with anchor bolts and reinforcing in cap or footing.
- ② Welding shall comply with ANSI/AWS D1.4 Structural Welding Code-Reinforcing Steel and applicable portions of ANSI/AWS D1.5 Bridge Welding Code.




**GENERAL NOTES FOR CONCRETE FILLED STEEL SHELL PILES:**

Steel shells shall conform ASTM A252, Grade 3 (Fy = 45,000 psi).  
 Concrete used for filling of steel shell shall be Class S with a minimum 28-day compressive strength, f'c = 3,500 psi. and shall be poured in the dry.  
 Steel shell piling that extends above the ground and is not protected by pile encasement shall be painted in accordance with Subsection 805.02.  
 See Bridge Layout for size and estimated length of steel shell piles and for driving information.  
 Concrete, structural steel, reinforcing steel (including welding), and painting shall not be paid for directly, but shall be considered subsidiary to the item "Steel Shell Piling".



**ALTERNATE PILE ANCHORAGE DETAIL**

Note: Hooked bars shall be oriented to provide the required concrete clearances shown in the plans.




PART SECTION

ELEVATION

**ALTERNATE FLAT TIP DETAIL**

Note: The alternate flat tip detail shall not be used on steel shell piling to be driven through embankments constructed with internal geosynthetic reinforcement.




PART SECTION

ELEVATION

VIEW H-H


**ALTERNATE VANED TIP DETAIL**



TYPICAL SPLICE DETAILS

**TABLE OF VARIABLES**


OUTSIDE DIAMETER "D"	NOMINAL SHELL THICKNESS "T"	PLATE THICKNESS "X"	NO. OF HOOKED BARS FOR ALTERNATE PILE ANCHORAGE
14"	0.50"	3/4"	5
16"	0.50"	1"	5
18"	0.50"	1 1/4"	6
20"	0.50"	1 1/2"	6
24"	0.50"	1 3/4"	8



HOOKED BAR DETAIL

**GENERAL NOTES FOR PILE ENCASEMENTS:**


See Bridge Layout for additional notes and required location of pile encasements.  
 Concrete shall be Class S with a minimum 28-day compressive strength, f'c = 3,500 psi. If concrete cannot be placed in the dry, Seal Concrete may be used from top to bottom of encasement.  
 Reinforcing steel shall be Grade 60 conforming to AASHTO M 31 or M 322, Type A.  
 Welded wire fabric shall conform to AASHTO M 55 or M 221.  
 Concrete, welded wire fabric or reinforcing steel, and galvanized pipe shall not be paid for directly, but shall be considered subsidiary to the item "Pile Encasement".



**PILE ENCASEMENT DETAIL FOR STEEL SHELL PILES**

⑤ (Shown with Encasement to Bottom of Cap)


- ③ Unless otherwise noted on Bridge Layout.
- ④ See Bridge Layout for height of pile encasement (3'-0" Minimum).
- ⑤ Pile encasement, when not extended to bottom of cap, shall have 2" concrete taper for water runoff as shown in the detail for partial height encasement.
- ⑥ Alternate pile encasement may not be allowed. See Bridge Layout.



**ALTERNATE PILE ENCASEMENT DETAIL FOR STEEL SHELL PILES**

(Shown with Partial Height Encasement)

This document was originally issued and sealed by Carl J. Fuseller, PE No. 7510, on February 27, 2014. This copy is not a signed and sealed document.



**STANDARD DETAILS FOR CONCRETE FILLED STEEL SHELL PILES AND PILE ENCASEMENTS**


ARKANSAS STATE HIGHWAY COMMISSION  
 LITTLE ROCK, ARK.

DRAWN BY: A.M.S. DATE: 2/27/2014 FILENAME: b55021.dgn  
 CHECKED BY: B.E.F. DATE: 2/27/2014 SCALE: NO SCALE  
 DESIGNED BY: STD. DATE: —

DRAWING NO. 55021









LONGITUDINAL JOINT

NOTE: THE TIE BAR SUPPORT SHOWN ABOVE MAY BE ELIMINATED IF OTHER APPROVED METHODS FOR PLACING AND SUPPORTING THE TIE BARS ARE PROVIDED. TIE BARS SHALL BE 15' FROM TRANSVERSE JOINTS.




NOTE: EACH DOWEL TO BE COATED ACCORDING TO SECTION 502 OF THE STANDARD SPECIFICATIONS.




ONE-HALF 24' PAVEMENT 12 DOWELS PLAN

NOTE: FOR 20' PAVEMENT USE 20 DOWELS @ 12' CTRS. WITH 6' SPACING FROM C.L. AND EDGE OF SLAB TO FIRST BAR. FOR 15' PAVEMENT USE 15 DOWELS @ 12' CTRS. WITH 6' SPACING FROM C.L. AND EDGE OF SLAB TO FIRST BAR. FOR 26' PAVEMENT USE 26 DOWELS @ 12' CTRS. WITH 6' SPACING FROM C.L. AND EDGE OF SLAB TO FIRST BAR. FOR PAVEMENT WIDTHS OTHER THAN THOSE SHOWN ABOVE, USE DOWELS AT 12' CTRS. WITH 6' MAX. SPACING FROM C.L. TO FIRST BAR. DISTANCE FROM EDGE OF SLAB TO FIRST BAR SHALL BE ADJUSTED TO MAINTAIN 12' DOWEL BAR SPACING

CONTRACTION JOINT DETAILS



DETAIL OF SAWED CONTRACTION JOINT




DETAIL OF EXPANSION JOINT

JOINT CONFIGURATION FOR TYPE 3 OR 4 JOINT SEALANT


JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/4	3/8	1/2
3/8	1/4	1/2	1/2
1/2	1/4	5/8	1/2
5/8	3/8	3/4	3/4
3/4	3/8	7/8	3/4
1 1/2	3/4	2	1 1/4

JOINT CONFIGURATION FOR TYPE 5 JOINT SEALANT

JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/2	3/8	3/4
3/8	3/4	1/2	1




PLAN SHOWING EXPANSION JOINTS AT BRIDGE APPROACH SLABS




ELEVATION

NOTE: ALL DOWEL BARS SHALL CONFORM TO THE DETAILS FOR CONTRACTION JOINTS.





DETAIL OF SAWED LONGITUDINAL JOINT AND LONGITUDINAL CONSTRUCTION JOINT

\*NOTE: T/3 SAW CUT NOT REQUIRED FOR LONGITUDINAL CONSTRUCTION JOINT.




DETAIL OF JOINT SUPPORT FOR EXPANSION JOINTS

REINFORCING SHALL BE GRADE 40 OR GRADE 60 DEFORMED BARS.



LONGITUDINAL CONSTRUCTION JOINT



TRANSVERSE CONSTRUCTION JOINT



- GENERAL NOTES
- \*T DENOTES THICKNESS OF SLAB.
  - DOWEL BARS SHALL BE PLACED IN ACCORDANCE WITH THE DIMENSIONS SHOWN. A TOLERANCE OF PLUS OR MINUS ONE INCH WILL BE ALLOWED FOR THE VERTICAL AND LATERAL PLACEMENT AND A TOLERANCE OF PLUS OR MINUS 1/4" WILL BE ALLOWED FOR THE TILT AND SKEW. DOWEL BARS SHALL BE FIELD COATED FOR A MINIMUM DISTANCE OF 2' GREATER THAN HALF THE LENGTH OF THE BAR WITH AN APPROVED GREASE AS A BOND BREAKER JUST PRIOR TO PLACEMENT OF CONCRETE.
  - THE EXPANSION JOINT SUPPORT MAY BE CONSTRUCTED WITH CLASS 'A', 'S' OR PAVING CONCRETE. PAYMENT FOR THE JOINT SUPPORT SHALL BE FOR THE CONTRACT UNIT PRICE BID FOR THE CLASS OF CONCRETE SPECIFIED IN THE PLANS. PAYMENT FOR ALL OTHER WORK AND MATERIALS REQUIRED FOR THE CONSTRUCTION OF THE JOINT SUPPORT SHALL BE INCLUDED IN THE PRICE BID FOR THE ABOVE ITEMS.
  - CONTRACTION JOINTS SHALL BE CONSTRUCTED ON 15' CENTERS.
  - TOOLING NOT REQUIRED FOR SELF-LEVELING SILICONE.
  - UNLESS OTHERWISE SPECIFIED IN THE PLANS, CONCRETE SHOULDERS SHALL BE CONSTRUCTED ACCORDING TO THE DETAILS SHOWN HEREON. CONTRACTION JOINTS SHALL MATCH CONTRACTION JOINTS IN THE LANES.
  - TIE WIRES IN DOWEL BAR ASSEMBLIES SHALL NOT BE CUT PRIOR TO PLACEMENT OF PAVING CONCRETE.

ARKANSAS STATE HIGHWAY COMMISSION

TRANSVERSE & LONGITUDINAL JOINTS FOR CONCRETE PAVEMENT (NON-REINFORCED)


STANDARD DRAWING CPTJ - 6A

DATE	REVISION	DATE FILMED
5-25-06	ADDED GENERAL NOTE 7	
10-9-03	REMOVED TIE BAR COATING & REVISED GENERAL NOTES	
11-16-01	ADDED TOOL SEALANT AND NOTE 5; REVISED NOTE 3	
4-26-96	REVISED CONTRACTION JOINT NOTE	
11-3-94	ADDED NOTE RE: REINF. BARS	
4-1-93	REVISED DOWEL BARS & GEN. NOTES	4-1-93
10-1-92	REVISED DOWEL SPACING	10-1-92
8-15-91	ADDED SPAC FOR CONTR JTS & DEL KEYWAY	
05-24-90	REVISED TIE BAR, DOWEL & JOINT SIZE	
01-25-90	ADDED EXPANSION JOINT	01-25-90
11-30-89	CHANGED T/4+1 TO T/3+1	11-30-89
03-23-89	ALTERED SAWED JOINT & ADDED NOTE	512-03-23-89
07-15-88	REVISED AND REDRAWN	632-07-15-88




DETAILS OF W-BEAM GUARD RAIL


RAIL SECTION OF CLOSELY SIMILAR DIMENSIONS AND COMPARABLE STRENGTH MAY BE SUBSTITUTED IF APPROVED BY THE ENGINEER.




SPLICE BOLT  
POST BOLT - SAME EXCEPT LENGTH




CUT STEEL WASHER



NUT




WOOD BLOCKOUT (W-BEAM)




PLASTIC BLOCKOUT (W-BEAM)

NOTES:  
1. SIMILAR SHAPED PLASTIC BLOCKOUTS MAY BE USED AS LONG AS THEY MEET NCHRP-350 TEST LEVEL 3 SPECIFICATIONS OR REQUIREMENTS FOR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH).  
2. DIMENSIONS ARE SUBJECT TO MANUFACTURERS TOLERANCES.




STEEL POST




DETAILS OF STEEL LINE POST CONNECTIONS (W-BEAM)

-GENERAL NOTES-

ALL BOLTS SHALL BE SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND NO MORE THAN 3/4" BEYOND IT.  
WHERE W-BEAM GUARD RAIL CONTIGUES, THE INTERMEDIATE SECTIONS SHALL HAVE A POST SPACING OF 6'-3" UNLESS OTHERWISE NOTED.  
W-BEAM GUARD RAIL REPRESENTING INTERMEDIATE SECTIONS WILL BE MEASURED ALONG THE ROADWAY FACE FROM CENTERLINE OF POST TO CENTERLINE OF POST.  
USE W-BEAM GUARD RAIL COMPONENTS OF SAME MATERIAL FOR ENTIRE JOB. FOR EXTENSIONS OR MODIFICATION OF EXISTING GUARD RAIL, W-BEAM GUARD RAIL COMPONENTS OF THE SAME TYPE AS THOSE EXISTING SHALL BE USED.  
ANY BACKFILLING UNDER OR AROUND POST SHALL BE DAMP SAND THOROUGHLY TAMPED IN PLACE.  
WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER 9.7f (1400 f) OR NO. 1 1350 f SOUTHERN PINE.  
CONTRACTOR SHALL HAVE THE OPTION OF USING WOOD BLOCKOUTS FOR W-BEAM GUARD RAIL OR PLASTIC BLOCKOUTS, AS LONG AS BLOCKOUT USED MEETS NCHRP-350 TEST LEVEL 3 SPECIFICATIONS OR REQUIREMENTS FOR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) FOR W-BEAM GUARD RAIL.



WOOD BLOCKOUT CONNECTIONS  
PLASTIC BLOCKOUT CONNECTIONS  
DETAILS OF STEEL LINE POST CONNECTIONS (W-BEAM)




WOOD BLOCKOUT CONNECTIONS  
PLASTIC BLOCKOUT CONNECTIONS  
DETAILS OF WOOD LINE POST CONNECTIONS (W-BEAM)

7-4-10	RAISED HEIGHT OF GUARD RAIL 1"	
0-15-09	ADDED REFERENCE TO MASH	
4-10-03	REVISED GENERAL NOTES	
8-22-02	REVISED DIMENSION ON WOOD & PLASTIC BLOCKOUT CONNECTIONS & ON STEEL POST	
11-16-01	REVISED WOOD BLOCKOUT & DETAILS OF WOOD LINE POST CONNECTIONS	
3-30-00	REMOVED GUARD RAIL AT BRIDGE ENDS	
11-2-00	ADDED PLASTIC BLOCKOUT	
8-12-98	REV. BLOCKOUTS TO WOOD, DELETED CONC. POST & REV. GENERAL NOTE, DELETED DET. OF GUARD RAIL REPLACE, BEHIND CURB DET. OF POST PLACE IN SOLID ROCK, & ADDED DETAILS OF STEEL LINE POST CONN. REMOVED BACK-UP PLATE, REVISED HOLES IN STEEL POLES	
4-3-97	REMOVED "LAP IN DIRECTION OF TRAFFIC" NOTE & PLACED ARROWS ON WASHERS	
10-18-96	REVISED WOOD POST NOTE	
6-2-94	ADDED AT 1. STEEL POST SIZE	
8-5-93	REVISED STEEL POST SIZE	8-5-93
10-1-92	REDRAWN & REVISED	10-1-92
8-15-91	REVISED WASHER NOTE	8-5-91
8-2-90	REV. GEN. NOTE & DEPTH OF ANC. POST IN ROCK	8-2-90
7-15-88	REVISED SECTION 3 & GENERAL NOTES	
3-4-88	REV. ANCHOR POST, ELEV. NOTES & POST IN ROCK	780-3-4-88
10-30-87	REV. WOOD LINE POST DETAIL	546-10-30-87
0-9-87	REDRAWN & REVISED	802-10-9-87
DATE	REVISION	DATE FILM


ARKANSAS STATE HIGHWAY COMMISSION

GUARD RAIL DETAILS

STANDARD DRAWING GR-8




Note: Bolts, nuts, washers and plates shall be galvanized in accordance with Section 807 of the Standard Specifications.




**DETAIL OF GUARD RAIL PLACEMENT BEHIND CURB (W-BEAM)**

FOR DESIGN SPEEDS OF 50 MPH OR LESS ALL CURB FACES, AS SHOWN ON STD. DRWG. CG-1, MAY BE USED. FOR DESIGN SPEEDS OF 55 MPH OR MORE TYPE "E" CURB FACE SHALL BE USED.




**Plan View Steel Posts**

Either hole configuration acceptable



**Plan View Wood Posts**

Either hole configuration acceptable



Notes: For overlying soil depths (A) ranging from 0 to 18", the depth of required drilling (B) is equal to 24".


Zone A: Backfill according to Section 617.03(a).

Zone B: Backfill hole in 6" lifts with material meeting the requirements of Section 802.02(c) - Alternate gradation. Compact to 95% maximum dry density per ASTM D-698.


Notes: For overlying soil depths (A) ranging from 18" to 44", the depth of required drilling (B) is equal to either 12" or 44" minus the depth of soil whichever is less.

Zone A & B: Backfill according to Section 617.03(a).


**DETAIL OF POST PLACEMENT IN SOLID ROCK (W-BEAM)**



SECTION A-A



DETAIL OF CONNECTION



PLAN LAYOUT OF TYPE A GUARD RAIL AT LOW-FILL CULVERTS

NOTE: THIS DETAIL IS TO BE USED ONLY WHEN THE COVER OVER THE CULVERT DOES NOT PERMIT FULL EMBEDMENT OF GUARD RAIL POSTS AS SHOWN ON STD. DRWG. GR-8.


NOTE: WHEN POSSIBLE, POSTS SHALL BE SPACED TO AVOID INTERIOR AND EXTERIOR WALLS OF CULVERT. WHEN THIS IS NOT POSSIBLE AND POSTS MUST BE INSTALLED OVER AN INTERIOR OR EXTERIOR WALL, ANCHOR BOLTS SHALL BE INSTALLED BY DRILLING AND EPOXYING USING METHODS AND MATERIALS APPROVED BY THE ENGINEER.

7-14-10	RAISED HEIGHT OF GUARD RAIL 1"	
4-12-07	REVISED DETAIL OF GUARD RAIL PLACEMENT BEHIND CURB	
11-10-05	ADDED GUARD RAIL PLACEMENT BEHIND CURB; REVISED DETAIL OF CONNECTION	
11-18-04	REVISED POST PLACEMENT IN ROCK & CULVERT CONNECTION DETAILS; ADDED DETAIL FOR GUARD RAIL PLACEMENT AT LOW-FILL CULVERTS	
3-30-00	REMOVED CONCRETE INSERT ANCHOR	
8-12-98	CHANGED STEEL SPACER BLOCK TO WOOD BLOCKOUT; ADD. DET. OF GUARD RAIL CONNECTION TO R.C. BOX CULVERT. DELETED DET. OF STEEL LINE POST CONNS. ADDED DET. OF GUARD RAIL PLACE. BEHIND CURB & DET. OF POST PLACE. IN SOLID ROCK	
4-3-96	PLACED ARROWS AT CUT STEEL WASHERS	4-3-96
10-18-96	REV. ASTM REF. TO AASHTO	
1-22-95	ADDED OPTIONAL HOLES	
6-2-94	REVISED ALTERNATE POST SIZE	
8-5-93	REVISED STEEL POST SIZE	
10-1-92	REDRAWN & REVISED	10-1-92
8-2-90	DEL. WASHER ON ANCHOR ASSEMBLY	8-2-90
7-15-88	CONFORMED TO 1988 SPECS	
3-4-88	REVISED ANCHOR NOTE	
10-30-87	REVISED ANCHOR ASSEMBLY	10-30-87
10-30-87	REVISED PLACEMENT BEHIND CURB	547-10-30-87
10-3-87	REDRAWN & REVISED	803-10-9-87
DATE	REVISION	DATE FILM


ARKANSAS STATE HIGHWAY COMMISSION

GUARD RAIL DETAILS


STANDARD DRAWING GR-8A



METHODS OF INSTALLATION OF GUARD RAIL AT LESS THAN FULL SHOULDER WIDTH BRIDGES USING GUARD RAIL TERMINAL (TYPE 2)




METHOD OF INSTALLATION OF GUARD RAIL AT FULL SHOULDER WIDTH BRIDGES USING GUARD RAIL TERMINAL (TYPE 2)




METHOD OF INSTALLATION OF GUARD RAIL USING GUARD RAIL TERMINAL (TYPE 1) (FULL SHOULDER WIDTH OR LESS BRIDGES)


ARKANSAS STATE HIGHWAY COMMISSION		
GUARD RAIL DETAILS		
STANDARD DRAWING GR-9		
4-17-08	REVISED LAYOUTS	
11-10-05	REMOVED GUARD RAIL NOTES AND DETAILS	
11-16-01	DELETED NOTE-METHOD OF INSTALLATION OF GUARD RAIL USING GUARD RAIL TERM. (TY. 1)	
1-12-00	ADDED CONSTRUCTION NOTE	1-12-00
6-26-97	REVISED LAYOUT	
10-1-92	REDRAWN & REVISED	10-1-92
10-9-87	REDRAWN & REVISED	
DATE	REVISION	DATE FILM



NOTE: NORMAL SECTION TO BE WIDENED APPROX. 5'-6" EACH SIDE TO SUPPORT GUARD RAIL.





SECTION A-A




SECTION B-B

DETAILS OF WIDENING FOR GUARD RAIL




DETAILS SHOWING POSITION OF GUARD RAIL ON HIGHWAY




METHOD OF INSTALLATION OF GUARD RAIL AT FIXED OBSTACLE

ARKANSAS STATE HIGHWAY COMMISSION			
GUARD RAIL DETAILS			
4-17-08	MINOR REVISION		
11-10-05	DRAWN		
DATE	REVISION	DATE	FILM
STANDARD DRAWING GR-9A			






THREE BEAM RAIL WITH STEEL TUBING BLOCKOUT AND STEEL POST  
POSTS 1-7




W-BEAM TO THREE BEAM TRANSITION RAIL WITH WOOD OR PLASTIC BLOCKOUT AND STEEL POST  
POST 8


\* NOTE:  
THESE DIMENSIONS WILL NEED TO BE ADJUSTED IN THE FIELD TO MAKE THE TRANSITION FROM 21" MID POINT OF THREE BEAM TO 22" MID POINT OF W-BEAM.



THREE BEAM RAIL WITH WOOD OR PLASTIC BLOCKOUTS & WOOD POSTS  
POSTS 1-6



THREE BEAM RAIL WITH WOOD OR PLASTIC BLOCKOUT & WOOD POST  
POST 7



W-BEAM TO THREE BEAM TRANSITION RAIL WITH WOOD OR PLASTIC BLOCKOUT & WOOD POST  
POST 8

GENERAL NOTES:  
RAIL POSTS SHALL BE SET PERPENDICULAR TO THE ROADWAY PROFILE GRADE AND VERTICALLY IN CROSS SECTION.

WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER 3.7F (1400 F) OR NO. 1 350 F SOUTHERN PINE.

ARKANSAS STATE HIGHWAY COMMISSION


GUARD RAIL DETAILS

STANDARD DRAWING GR-10A


DATE	REVISION	DATE FILM
7-14-10	REVISED POST 8 DIMENSIONS	
11-29-07	ADDED PLASTIC BLOCKOUTS	
8-22-02	REVISED LIP CURB NOTE	
3-30-00	DRAWN & ISSUED	








PLAN - GUARD RAIL TERMINAL (TYPE I)




ELEVATION - GUARD RAIL TERMINAL (TYPE I)

NOTE:  
SECTIONS 1 AND 2 OF GUARD RAIL TERMINAL  
SHALL BE PAID FOR AT THE PRICE BID PER  
LINEAR FOOT OF THE TYPE OF GUARD RAIL SPECIFIED.



SECTION 1

TERMINAL SECTION




DETAIL OF TERMINAL ANCHOR POST (TYPE I)

NOTE: GALVANIZE UPPER 15" OF ANCHOR POST AND ANCHOR ASSEMBLY


NOTE: RAIL MEMBERS MAY BE BOLTED TO ANGLE AT TERMINAL ANCHOR AND THE TWO ASSEMBLIES POSITIONED TO PROPER ALIGNMENT PRIOR TO PLACING CONCRETE AROUND 8 WF 17 POST IF CONTRACTOR SO DESIRES.

		ARKANSAS STATE HIGHWAY COMMISSION
		GUARD RAIL DETAILS
7-14-10	RAISED HEIGHT OF GUARD RAIL	
6-26-97	REVISED LAP NOTE	
10-18-96	REVISED ASTM REF. TO AASHTO	
11-3-94	DIMENSION TERMINAL DETAIL	
11-11-92	ADDED NOTE FOR PAYMENT	11-11-92
10-1-92	DRAWN & ISSUED	10-1-92
DATE	REVISION	DATE FILM
		STANDARD DRAWING GRT-1




(TYPE C)

BARRIER LENGTH = 27'-6"  
DESIGN IMPACT SPEED = 50 M.P.H. = 73.3 fps




(TYPE B)

BARRIER LENGTH = 34'-6"  
DESIGN IMPACT SPEED = 60 M.P.H. = 88 fps



(TYPE A)


BARRIER LENGTH = 41'-6"  
DESIGN IMPACT SPEED = 70 M.P.H. = 103 fps



METHOD OF INSTALLATION OF IMPACT ATTENUATION BARRIER FOR PIER PROTECTION

GENERAL NOTES


1. DIMENSIONS SHOWN ARE TO TOP OF PLASTIC MODULES.
2. SPACING BETWEEN PLASTIC MODULES SHALL NOT EXCEED 6" AT THE TOP.
3. PLASTIC MODULES SHALL MEET THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH).



APPROXIMATE QUANTITIES PER PAD

TYPE	ALTERNATE #1		ALTERNATE #2
	AGGR. BASE COURSE TONS	A.C.H.M. SURFACE COURSE TONS	P.C. CONC. BASE (4" U.T.) SQ.YDS.
A	9.7	4.6	41.6
B	8.1	3.8	34.9
C	6.6	3.1	28.3

NOTE: APPROXIMATE QUANTITIES SHOWN ARE FOR INFORMATIONAL PURPOSES ONLY. PAYMENT TO BE INCLUDED IN UNIT PRICE BID FOR IMPACT ATTENUATION BARRIER.



DETAIL OF BARRIER PAD

NOTE: BARRIER PAD TO BE SKEWED TOWARD ONCOMING TRAFFIC A MAXIMUM OF 6:1 WITH 6:1 BEING NORMAL

DATE	REVISION	DATE FILMED
10-15-09	ADDED REFERENCE TO MASH	
11-29-07	REVISED TY. A & TY. C ARRAYS	
11-19-98	REVISED FIXED OBJECT	
11-18-98	REV. NOTES & TYPE A MOD. WTS.	
10-18-96	REDRAWN	
7-15-88	CONFORMED TO 1988 SPECS	
7-29-87	REDRAWN	

ARKANSAS STATE HIGHWAY COMMISSION  
**IMPACT ATTENUATION BARRIER**  
STANDARD DRAWING IB-1

REINFORCED CONCRETE ARCH PIPE DIMENSIONS

EQUIV. DIA.	SPAN		RISE	
	AASHTO M 206	AHTD NOMINAL	AASHTO M 206	AHTD NOMINAL
INCHES	INCHES			
15	18	18	11	11
18	22	22	13½	14
21	26	26	15½	16
24	28½	29	18	18
30	36¼	36	22½	23
36	43¾	44	26¾	27
42	51½	51	31¾	31
48	58½	59	36	36
54	65	65	40	40
60	73	73	45	45
72	88	88	54	54
84	102	102	62	62
90	115	115	72	72
96	122	122	77½	77
108	138	138	87½	87
120	154	154	96¾	97
132	168¾	169	106½	107

THE MEASURED SPAN AND RISE SHALL NOT VARY MORE THAN ± 2 PERCENT FROM THE VALUES SPECIFIED BY AASHTO M206.

REINFORCED CONCRETE HORIZONTAL ELLIPTICAL PIPE DIMENSIONS

EQUIV. DIA.	AASHTO M 207	
	SPAN	RISE
INCHES	INCHES	
18	23	14
24	30	19
27	34	22
30	38	24
33	42	27
36	45	29
39	49	32
42	53	34
48	60	38
54	68	43
60	76	48
66	83	53
72	91	58
78	98	63
84	106	68

THE MEASURED SPAN AND RISE SHALL NOT VARY MORE THAN ± 2 PERCENT FROM THE VALUES SPECIFIED BY AASHTO M207.

CONSTRUCTION SEQUENCE

1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. PLACE AND COMPACT THE HAUNCH AREA UP TO THE MIDDLE OF THE PIPE.
5. COMPLETE BACKFILL ACCORDING TO SUBSECTION 606.03.(f)(ii).

NOTE: HAUNCH AND STRUCTURAL BEDDING MATERIAL WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF CONCRETE PIPE.


- LEGEND -

- D<sub>i</sub> = NORMAL INSIDE DIAMETER OF PIPE
- D<sub>o</sub> = OUTSIDE DIAMETER OF PIPE
- H = FILL COVER HEIGHT OVER PIPE (FEET)
- MIN. = MINIMUM
- [Symbol] = UNDISTURBED SOIL

INSTALLATION TYPE	MATERIAL REQUIREMENTS FOR HAUNCH AND STRUCTURAL BEDDING
TYPE 1	AGGREGATE BASE COURSE (CLASS 5 OR CLASS 7)
TYPE 2	SELECTED MATERIALS (CLASS SM-1, SM-2, OR SM-4) OR TYPE 1 INSTALLATION MATERIAL*
TYPE 3**	AASHTO CLASSIFICATION A-1 THRU A-6 SOIL OR TYPE 1 OR 2 INSTALLATION MATERIAL

\*SM-3 WILL NOT BE ALLOWED.

\*\* MATERIALS SHALL NOT INCLUDE ORGANIC MATERIALS OR STONES LARGER THAN 3 INCHES.



EMBANKMENT AND TRENCH INSTALLATIONS

1. MATERIAL IN THE HAUNCH AND OUTER STRUCTURAL BEDDING SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.
2. FOR TRENCHES WITH WALLS OF NATURAL SOIL, THE DENSITY OF THE SOIL IN THE LOWER SIDE ZONE SHALL BE AS FIRM AS THE 95% DENSITY REQUIRED FOR THE HAUNCH. IF THE EXISTING SOIL DOES NOT MEET THIS CRITERIA, IT SHALL BE REMOVED AND RECOMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OF MATERIAL USED.
3. FOR EMBANKMENTS, THE MATERIAL IN THE LOWER SIDE ZONE SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.

GENERAL NOTES

1. CONCRETE PIPE CULVERT CONSTRUCTION SHALL CONFORM TO ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (CURRENT EDITION), WITH APPLICABLE SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS, UNLESS OTHERWISE NOTED IN THE PLANS, SECTION AND SUBSECTION REFER TO THE STANDARD CONSTRUCTION SPECIFICATIONS.
2. CONCRETE PIPE CULVERT DESIGN SHALL CONFORM TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, FIFTH EDITION (2010) WITH 2010 INTERIMS.
3. ALL PIPE SHALL CONFORM TO SECTION 606. CIRCULAR R.C. PIPE CULVERTS SHALL CONFORM TO AASHTO M170, R.C. ARCH PIPE CULVERTS SHALL CONFORM TO AASHTO M206 AND HORIZONTAL ELLIPTICAL PIPE CULVERTS SHALL CONFORM TO AASHTO M207.
4. ALL PIPE SHALL BE PROTECTED DURING CONSTRUCTION BY A COVER SUFFICIENT TO PREVENT DAMAGE FROM PASSAGE OF EQUIPMENT.
5. THE MINIMUM TRENCH WIDTH SHALL BE THE OUTSIDE DIAMETER OF THE PIPE PLUS 24 INCHES. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PRACTICABLE FOR WORKING CONDITIONS.
6. MULTIPLE PIPE CULVERTS SHALL BE INSTALLED WITH A MINIMUM CLEARANCE OF 24 INCHES BETWEEN STRINGS OF PIPE. REFER TO STD. DWG. FES-2 FOR MINIMUM CLEARANCE WHERE FLARED END SECTIONS ARE USED.
7. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
8. NOT MORE THAN ONE LIFTING HOLE MAY BE PROVIDED IN CONCRETE PIPE TO FACILITATE HANDLING. HOLE MAY BE CAST IN PLACE, CUT INTO THE FRESH CONCRETE AFTER FORMS ARE REMOVED, OR DRILLED. THE HOLE SHALL NOT BE MORE THAN TWO INCHES IN DIAMETER OR TWO INCHES SQUARE. CUTTING OR DISPLACEMENT OF REINFORCEMENT WILL NOT BE PERMITTED. SPALLED AREAS AROUND THE HOLE SHALL BE REPAIRED IN A WORKMANLIKE MANNER. LIFTING HOLE SHALL BE FILLED WITH MORTAR, CONCRETE, OR OTHER METHOD AS APPROVED BY THE ENGINEER.
9. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS "STRUCTURAL BEDDING" ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS "SELECTED PIPE BEDDING."
10. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED ABOVE AS THE HAUNCH), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF "SELECTED PIPE BACKFILL."

MINIMUM HEIGHT OF FILL "H" OVER CIRCULAR R.C. PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE			
	CLASS III	CLASS IV	CLASS V	CLASS V
PIPE ID (IN.)	FEET			
12-15	2	2.5	2	1
18-24	2.5	3	2	1
27-33	3	4	2	1
36-42	3.5	5	2	1
48	4.5	5.5	2	1
54-60	5	7	2	1
66-78	6	8	2	1
84-108	7.5	8	2	1

NOTE: FOR MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM OF 12" OF PAVEMENT AND/OR BASE.

MAXIMUM HEIGHT OF FILL "H" OVER CIRCULAR R.C. PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE		
	CLASS III	CLASS IV	CLASS V
TYPE 1	21	32	50
TYPE 2	16	25	39
TYPE 3	12	20	30

NOTE: IF FILL HEIGHT EXCEEDS 50 FEET, A SPECIAL DESIGN CONCRETE PIPE WILL BE REQUIRED USING TYPE 1 INSTALLATION.

MINIMUM HEIGHT OF FILL "H" OVER R.C. ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE	
	CLASS III	CLASS IV
TYPE 2 OR TYPE 3	2.5	1.5

NOTE: TYPE 1 INSTALLATION WILL NOT BE ALLOWED FOR ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS.

NOTE: FOR MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM OF 12" OF PAVEMENT AND/OR BASE.

MAXIMUM HEIGHT OF FILL "H" OVER R.C. ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS

INSTALLATION TYPE	CLASS OF PIPE	
	CLASS III	CLASS IV
TYPE 2	13	21
TYPE 3	10	16

NOTE: TYPE 1 INSTALLATION WILL NOT BE ALLOWED FOR ARCH & HORIZONTAL ELLIPTICAL PIPE CULVERTS.

DATE	REVISION	DATE FILMED
2-27-14	REVISED GENERAL NOTE 1.	
12-15-11	REVISED FOR LRFD DESIGN SPECIFICATIONS	
5-18-00	REVISED TYPE 3 BEDDING & ADDED NOTE	
3-30-00	REVISED INSTALLATIONS	
11-06-97	ISSUED	

ARKANSAS STATE HIGHWAY COMMISSION

CONCRETE PIPE CULVERT  
FILL HEIGHTS & BEDDING

STANDARD DRAWING PCC-1

**CORRUGATED STEEL PIPE (ROUND)**

PIPE DIAMETER (INCHES)	① MINIMUM COVER TOP OF PIPE TO TOP OF GROUND "H" (FEET)	MAX. FILL HEIGHT "H" ABOVE TOP OF PIPE (FEET)				
		METAL THICKNESS (INCHES)				
		0.064	0.079	0.109	0.138	0.168
2 1/2 INCH BY 1/2 INCH CORRUGATION RIVETED, WELDED, OR HELICAL LOCK-SEAM						
12	1	84	91			
15	1	67	73			
18	1	56	61			
24	1	42	46	59		
30	2	34	36	47		
36	2		30	39	41	
42	2		43	67	70	73
48	2		37	58	61	64
② 3 INCH BY 1 INCH OR 5 INCH BY 1 INCH CORRUGATION RIVETED, WELDED, BOLTED, OR HELICAL LOCK-SEAM						
36	1	48	60	88	111	118
42	1	41	51	72	90	102
48	1	36	45	64	77	85
54	2	32	40	59	71	79
60	2	29	36	53	64	71
66	2	26	33	47	58	64
72	2	24	30	44	53	59
78	2		28	41	49	54
84	2		26	38	45	51
90	2		24	35	43	45
96	2		22	33	40	44
102	2			31	38	42
108	2			30	35	39
114	2			28	34	37
120	2			27	32	35

**CONSTRUCTION SEQUENCE**

1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. COMPLETE STRUCTURAL BACKFILL OPERATION BY WORKING FROM SIDE TO SIDE OF THE PIPE. THE SIDE TO SIDE STRUCTURAL BACKFILL DIFFERENTIAL SHALL NOT EXCEED 24 INCHES OR 1/3 THE SIZE OF THE PIPE, WHICHEVER IS LESS.


NOTE: STRUCTURAL BACKFILL AND STRUCTURAL BEDDING WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF METAL PIPE.

INSTALLATION TYPE	MATERIAL REQUIREMENTS FOR STRUCTURAL BACKFILL AND STRUCTURAL BEDDING
TYPE 1	AGGREGATE BASE COURSE (CLASS 4, 5, 6, OR 7)
TYPE 2	SELECTED MATERIALS (CLASS SM-1, SM-2, OR SM-4) OR TYPE 1 INSTALLATION MATERIAL ③

③ SM-3 WILL NOT BE ALLOWED.

**- LEGEND -**

- D<sub>o</sub> = OUTSIDE DIAMETER OF PIPE
- MAX. = MAXIMUM
- MIN. = MINIMUM
- [Symbol] = STRUCTURAL BACKFILL MATERIAL
- [Symbol] = UNDISTURBED SOIL
- EQUIV. DIA. = EQUIVALENT DIAMETER
- H = FILL COVER HEIGHT OVER PIPE (FEET)



**EMBANKMENT AND TRENCH INSTALLATIONS**

1. STRUCTURAL BACKFILL, EMBANKMENT, AND OUTER STRUCTURAL BEDDING MATERIAL SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY ACCORDING TO THE TYPE OR CLASS OF MATERIAL USED.
2. INSTALLATION TYPE 1 OR 2 MAY BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE (ROUND).
3. INSTALLATION TYPE 1 SHALL BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE ARCHES WITH 2 1/2" x 1/2" CORRUGATION.
4. INSTALLATION TYPE 1 OR 2 MAY BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE ARCHES WITH 3" x 1" OR 5" x 1" CORRUGATION.

**CORRUGATED ALUMINUM PIPE (ROUND)**

PIPE DIAMETER (INCHES)	① MINIMUM COVER TOP OF PIPE TO TOP OF GROUND "H" (FEET)	MAX. FILL HEIGHT "H" ABOVE TOP OF PIPE (FEET)				
		METAL THICKNESS IN INCHES				
		0.060	0.075	0.105	0.135	0.164
2 1/2 INCH BY 1/2 INCH CORRUGATION RIVETED OR HELICAL LOCK-SEAM						
12	1	45	45	52		
18	2	30	30	39	41	34
24	2	22	22	31	32	28
30	2		18	26	27	28
36	2.5		15	26	27	28
42	2			43	43	44
48	2			40	41	43
54	2			35	37	38
60	2				33	34
66	2					31
72	2					29

**EQUIVALENT METAL THICKNESSES AND GAUGES**

METAL THICKNESS IN INCHES			GAUGE NUMBER	
STEEL				
ZINC COATED	UNCOATED	ALUMINUM		
0.064	0.0598	0.060		16
0.079	0.0747	0.075		14
0.109	0.1046	0.105		12
0.138	0.1345	0.135		10
0.168	0.1644	0.164		8

**GENERAL NOTES**

1. METAL PIPE CULVERT CONSTRUCTION SHALL CONFORM TO ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (CURRENT EDITION), WITH APPLICABLE SUPPLEMENTAL SPECIFICATIONS AND SPECIAL PROVISIONS. UNLESS OTHERWISE NOTED IN THE PLANS, SECTION AND SUBSECTION REFER TO THE STANDARD CONSTRUCTION SPECIFICATIONS.
2. METAL PIPE CULVERT DESIGN SHALL CONFORM TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, FIFTH EDITION (2010) WITH 2010 INTERIMS.
3. METAL PIPE CULVERT MATERIALS AND INSTALLATIONS SHALL CONFORM TO SECTION 606 AND JOB SPECIAL PROVISION "METAL PIPE".
4. ALL PIPE SHALL BE PROTECTED DURING CONSTRUCTION BY A COVER SUFFICIENT TO PREVENT DAMAGE FROM PASSAGE OF EQUIPMENT.
5. THE MINIMUM TRENCH WIDTH SHALL BE THE OUTSIDE DIAMETER OF THE PIPE PLUS 24 INCHES. THE MAXIMUM ALLOWABLE TRENCH WIDTH SHALL BE THE MINIMUM WIDTH PRACTICABLE FOR WORKING CONDITIONS.
6. MULTIPLE PIPE CULVERTS SHALL BE INSTALLED WITH A MINIMUM CLEARANCE OF 24 INCHES BETWEEN STRINGS OF PIPE. REFER TO STD. DWG. FES-2 FOR MINIMUM CLEARANCE WHERE FLARED END SECTIONS ARE USED.
7. IMPERVIOUS MATERIAL SHOULD BE PLACED AS DIRECTED BY THE ENGINEER AT THE ENDS OF THE CULVERT TO PREVENT LOSS OF STRUCTURAL BEDDING WHEN PERVIOUS MATERIAL IS USED FOR STRUCTURAL BEDDING AND/OR BACKFILL.
8. WHEN DIRECTED BY THE ENGINEER, UNSUITABLE MATERIAL THAT IS ENCOUNTERED AT THE BOTTOM OF THE EXCAVATED TRENCH (BELOW THE AREA IDENTIFIED AS "STRUCTURAL BEDDING" ABOVE) WILL BE EXCAVATED AND REPLACED WITH SELECTED PIPE BEDDING. THE QUANTITY OF MATERIAL REQUIRED TO BACKFILL THE UNDERCUT AREA UP TO THE SELECTED PIPE BEDDING PAY LIMIT DESIGNATED ABOVE WILL BE MEASURED AND PAID FOR AS "SELECTED PIPE BEDDING."
9. WHEN THE EXISTING MATERIAL EXCAVATED FOR THE PIPE TRENCH IS DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING THE PIPE (ABOVE THE AREA IDENTIFIED AS STRUCTURAL BACKFILL), BORROW MATERIAL OR MATERIAL FROM THE ROADWAY EXCAVATION WILL BE USED TO BACKFILL THE PIPE. IF SUITABLE MATERIAL IS NOT AVAILABLE, THE ENGINEER MAY AUTHORIZE THE USE OF "SELECTED PIPE BACKFILL."

**CORRUGATED METAL PIPE ARCHES**

EQUIV. DIA. (INCHES)	PIPE DIMENSION SPAN X RISE (INCHES)	MINIMUM CORNER RADIUS (INCHES)	STEEL				ALUMINUM			
			MIN. THICKNESS REQUIRED INCHES	① MIN. HEIGHT OF FILL, "H" (FT.)		MIN. THICKNESS REQUIRED INCHES	① MIN. HEIGHT OF FILL, "H" (FT.)			
				INSTALLATION			INSTALLATION			
				TYPE 1	TYPE 1		TYPE 1	TYPE 1		
2 1/2 INCH BY 1/2 INCH CORRUGATION RIVETED, WELDED, OR HELICAL LOCK-SEAM										
15	17x13	3	0.064	2	15	0.060	2	15		
18	21x15	3	0.064	2	15	0.060	2	15		
21	24x18	3	0.064	2,25	15	0.060	2,25	15		
24	28x20	3	0.064	2,5	15	0.075	2,5	15		
30	35x24	3	0.079	3	12	0.075	3	12		
36	42x29	3 1/2	0.079	3	12	0.105	3	12		
42	49x33	4	0.079	3	12	0.105	3	12		
48	57x38	5	0.109	3	13	0.135	3	13		
54	64x43	6	0.109	3	14	0.135	3	14		
60	71x47	7	0.138	3	15	0.135	3	14		
66	77x52	8	0.168	3	15					
72	83x57	9	0.168	3	15	0.164	3	15		
② 3 INCH BY 1 INCH OR 5 INCH BY 1 INCH CORRUGATION RIVETED, WELDED, OR HELICAL LOCK-SEAM										
			INSTALLATION		INSTALLATION					
			TYPE 2	TYPE 1	TYPE 2	TYPE 1				
36	40x31	5	0.079	3	2	12	15			
42	46x36	6	0.079	3	2	13	15			
48	53x41	7	0.079	3	2	13	15			
54	60x46	8	0.079	3	2	13	15			
60	66x51	9	0.079	3	2	13	15			
66	73x55	12	0.079	3	2	15	15			
72	81x59	14	0.079	3	2	15	15			
78	87x63	14	0.079	3	2	15	15			
84	95x67	16	0.109	3	2	15	15			
90	103x71	16	0.109	3	2	15	15			
96	112x75	18	0.109	3	2	15	15			
102	117x79	18	0.109	3	2	15	15			
108	128x83	18	0.138	3	2	15	15			

① FOR MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM 12" OF PAVEMENT AND/OR BASE.



② WHERE THE STANDARD 2 2/3" x 1/2" CORRUGATION AND GAUGE IS SPECIFIED FOR A GIVEN DIAMETER, A PIPE OF THE SAME DIAMETER WITH A 3" x 1" OR 5" x 1" CORRUGATION MAY BE SUBSTITUTED, PROVIDING IT IS GAUGED FOR A FILL HEIGHT CONDITION EQUAL TO OR GREATER THAN THE MAXIMUM FILL HEIGHT CONDITION FOR THE SPECIFIED GAUGE AND CORRUGATION.

DATE	REVISION	DATE FILMED
2-27-14	REVISED GENERAL NOTE 1	
12-15-11	REVISED FOR LRFD DESIGN SPECS	
3-30-00	REVISED INSTALLATIONS	
11-06-97	ISSUED	


ARKANSAS STATE HIGHWAY COMMISSION

**METAL PIPE CULVERT  
FILL HEIGHTS & BEDDING**


STANDARD DRAWING PCM-1




BROKEN LINE STRIPING




SOLID LINE STRIPING ON CONCRETE PAVEMENT



SOLID LINE STRIPING ON ASPHALT PAVEMENT




ASPHALT PAVEMENT



CONCRETE PAVEMENT

STRIPING AT ADJACENT NO PASSING LANES




CROSSWALK AND STOPBAR DETAILS


NOTES:

1. ALL LINES SHALL HAVE A WIDTH OF 4 INCHES.
2. THE THICKNESS AND RATE OF PAINT APPLICATION SHALL BE AS SPECIFIED IN SECTION 718 OF THE STANDARD SPECIFICATIONS.
3. THIS DRAWING SHALL BE USED IN CONJUNCTION WITH THE LATEST REVISED ADDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
4. RAISED PAVEMENT MARKERS SHALL BE CENTERED BETWEEN SKIP LINES ON 40 FEET SPACING UNLESS OTHERWISE SHOWN ON THE PLANS.


2" FOR ASPHALT OR CONCRETE PAVEMENT  
6" FOR BITUMINOUS SURFACE TREATMENT



PAVEMENT EDGE LINE MARKING



NOTE:  
THE RED LENS OF THE TYPE II R.P.M. SHALL FACE THE INCORRECT TRAFFIC MOVEMENT.



DETAIL OF STANDARD RAISED PAVEMENT MARKERS

GENERAL NOTES:  
THIS DRAWING SHOULD BE CONSIDERED AS TYPICAL ONLY AND THE FINAL LOCATION OF THE STRIPING AND RAISED PAVEMENT MARKERS SHALL BE DETERMINED BY THE ENGINEER.

THIS DRAWING SHOULD BE USED IN CONJUNCTION WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", LATEST REVISION.

NOTE:  
DIMENSIONS SHOWN FOR RAISED PAVEMENT MARKERS ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR MARKERS WITH THE APPROVAL OF THE ENGINEER. REQUESTING APPROVAL FOR SIMILAR MARKERS MAY BE MADE BY REFERRING TO THE AHTD QUALIFIED PRODUCTS LIST.

9-12-13	REVISED DETAIL OF STANDARD RAISED PAVEMENT MARKERS	
11-17-10	REVISED GENERAL NOTES & REMOVED FLOWABLE PAVT MRKRS	
11-18-04	REVISED NOTE 2 & GENERAL NOTES	
8-22-02	ADDED CROSSWALK & STOPBAR DTLS.	
7-02-98	ADDED DETAILS OF STD. RAISED PAVT. MARKERS	
4-26-96	REV. NOTES 3&4; ADDED R.P.M.	
9-30-80	DRAWN	1-9-30-80
DATE	REVISION	FILMED


ARKANSAS STATE HIGHWAY COMMISSION

PAVEMENT MARKING DETAILS


STANDARD DRAWING PM-1

ENTRANCE RAMP  
8" WHITE = 228 LIN. FT.  
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 38 EACH


EXIT RAMP  
4" WHITE = 280 LIN. FT.  
8" WHITE = 655 LIN. FT.  
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 38 EACH  
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 46 EACH  
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 38 EACH



ENTRANCE RAMPS




EXIT RAMPS



DETAIL OF STANDARD RAISED PAVEMENT MARKERS

NOTE:  
THE RED LENS OF THE TYPE II R.P.M. SHALL FACE THE INCORRECT TRAFFIC MOVEMENT.



(19) STANDARD TYPE II R.P.M.

DIRECTIONAL ARROWS

GENERAL NOTES:  
THIS DRAWING SHOULD BE CONSIDERED AS TYPICAL ONLY AND THE FINAL LOCATION OF THE STRIPING AND PAVEMENT MARKERS SHALL BE DETERMINED BY THE ENGINEER.

THIS DRAWING SHOULD BE USED IN CONJUNCTION WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", LATEST REVISION.

NOTE:  
DIMENSIONS SHOWN FOR RAISED PAVEMENT MARKERS ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR MARKERS WITH THE APPROVAL OF THE ENGINEER. REQUESTING APPROVAL FOR SIMILAR MARKERS MAY BE MADE BY REFERRING TO THE AHTD QUALIFIED PRODUCTS LIST.

DATE	REVISION	FILMED
9-12-13	REVISED DETAIL OF STANDARD RAISED PAVEMENT MARKERS	
7-26-12	REVISED RPM NOTATION	
12-15-11	REVISED RPMs ACCORDING TO LATEST POLICY	
11-17-10	REMOVED PLOWABLE PAVEMENT MARKERS	
6-3-10	REVISED PER 2009 MUTCD	
11-18-04	REVISED NOTES	
8-22-02	ADDED & REVISED NOTES; REV. ENTRANCE & EXIT RAMPS	
5-18-00	REMOVED HASHMARKS	
7-02-98	CHANGED TYPES TO ROMAN NUMERALS	
4-26-96	ADDED DIMENSIONS & QUANTITIES; REVISED LANE WIDTH ON EXIT RAMP	
2-2-95	PLACED IN USE	2-2-95

ARKANSAS STATE HIGHWAY COMMISSION  
PERMANENT PAVEMENT MARKING  
ON ACCESS CONTROLLED ROADWAYS



ADVANCE DISTANCES (XXXX)

500 FT	1/2 MILE
1000 FT	3/4 MILE
1500 FT	1 MILE AHEAD














































GENERAL NOTES:

- ALL TRAFFIC CONTROL DEVICES USED ON ROAD CONSTRUCTION SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION, AND TO THE STANDARD HIGHWAY SIGNS, LATEST EDITION, OR AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION.
- TRAFFIC CONTROL DEVICES SHALL BE SET UP JUST BEFORE THE START OF CONSTRUCTION OPERATIONS AND SHALL BE PROPERLY MAINTAINED DURING THE TIME SUCH CONDITIONS EXIST. THEY SHALL REMAIN IN PLACE ONLY AS LONG AS NEEDED AND REMOVED THEREAFTER.
- EXISTING SIGNS AND CONSTRUCTION SIGNS SHALL BE KEPT IN PROPER POSITION, AND BE CLEAN AND LEGIBLE AT ALL TIMES. SIGNS THAT DO NOT APPLY TO EXISTING CONDITIONS SHALL BE REMOVED. SIGNS THAT ARE DAMAGED, DEFACED, OR THAT ACCUMULATE DIRT DURING CONSTRUCTION SHALL BE CLEANED, REPAIRED, OR REPLACED.
- SIGNS ARE USUALLY MOUNTED ON A SINGLE POST, ALTHOUGH THOSE WIDER THAN 36" OR LARGER THAN 10 SQ. FT. SHALL BE MOUNTED ON TWO POSTS OR ABOVE A TYPE III BARRICADE.
- SIGN POSTS DIRECT BURIED IN SOIL SHALL BE 2 LB. MINIMUM CHANNEL POST OR 4"x4" WOOD POSTS. CHANNEL POSTS SHALL BE PAINTED GREEN. WOOD POSTS SHALL BE PAINTED WHITE. ALL POSTS SHALL BE NEATLY CONSTRUCTED, AND SHALL BE REPLUMBED, CLEANED, OR REPAIRED AS NEEDED FOR THE DURATION OF THE JOB. THERE SHALL NOT BE MORE THAN 2 POSTS IN A 7' PATH FOR WOOD OR CHANNEL POSTS. ANY CHANNEL POST SPLICE SHALL BE IN ACCORDANCE WITH STANDARD DRAWING TC-3.
- POST MOUNTED SIGNS IN RURAL AREAS SHALL BE CONSTRUCTED WITH THE NEAR EDGE OF THE SIGN FROM 6 TO 12 FEET FROM THE PAVEMENT EDGE. SIGNS IN URBAN AREAS AND BARRICADE MOUNTED SIGNS SHALL BE MOUNTED A MINIMUM OF 2 FEET FROM THE PAVEMENT EDGE.
- ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN URBAN AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE. ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN RURAL AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE, EXCEPT A MINIMUM OF 6' SHALL BE USED WHEN MOUNTING AN ADVISORY SIGN BELOW A WARNING SIGN. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR INTERMEDIATE TERM STATIONARY WORK CONDITIONS. THE SIGNS MINIMUM MOUNTING HEIGHT SHALL BE 5'. RETROREFLECTIVE DEVICES SHALL BE USED. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR SHORT-TERM, SHORT DURATION, AND MOBILE CONDITIONS. THEY SHALL BE NO LESS THAN ONE (1) FOOT ABOVE THE TRAVELED WAY. LONG-TERM STATIONARY SIGNS SHALL BE DIRECT BURIED IN SOIL, UNLESS CONDITIONS NECESSITATE THE USE OF PORTABLE SIGNS, OR AS APPROVED BY THE ENGINEER. CONCRETE PADS, CONCRETE OR ROCK BALLAST, OR OTHER SOLID MATERIALS SHALL NOT BE UTILIZED WITH PORTABLE SIGN SUPPORTS.
- FLAGGERS SHALL USE REFLECTORIZED STOP-SLOW PADDLES. FLAGS MAY BE USED ONLY FOR EMERGENCY SITUATIONS.
- MOST OF THE SIGNS SHOWN ARE ORIENTED TO THE RIGHT. HOWEVER, THIS DOES NOT PRECLUDE THE USE OF MIRROR IMAGES OF THESE SIGNS WHERE THE REVERSE ORIENTATION MIGHT BETTER CONVEY TO MOTORISTS THE PROPER DIRECTION OF MOVEMENT.
- R55-1 SIGNS SHALL BE PLACED AT LEAST 1500' BUT NOT MORE THAN 1 MILE IN ADVANCE OF THE WORK ZONE. IF A SPEED LIMIT REDUCTION IS IN EFFECT, THE SIGN SHALL BE PLACED A MINIMUM OF 500' IN ADVANCE OF THE "REDUCED SPEED AHEAD" SIGN.


NOTE: SUPPORTS FOR SIGNS, BARRICADES, AND VERTICAL PANELS THAT ARE DIFFERENT FROM THE REQUIREMENTS SHOWN IN NOTES 4 & 5, BUT MEET THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH), WILL BE ACCEPTED. COMPLIANCE WITH THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) IS REQUIRED FOR ALL PROJECTS.

12-15-11	REVISED W24-1	
11-17-10	DELETED W8-9a & ADDED W8-9	
10-15-09	ADDED REFERENCE TO MASH & ADDED SIGN W24-1	
4-17-08	REVISED SIGN DESIGNATIONS	
11-18-04	REVISED NOTES	
10-9-03	REVISED NOTE 1	
11-16-01	REVISED NOTE 7	
9-28-00	REVISED NOTE	
11-18-98	ADDED NOTE	
6-26-97	REVISED NOTE 5	
4-03-97	REVISED NOTE 5	
10-18-96	ADDED CONTROLLED ACCESS HWY. SIGN & TO NOTE 7	
10-12-95	ADDED R55-1	
6-8-95	REVISED TO CORRECT SIGN ILLUSTRATIONS	6-8-95
2-2-95	REVISED PER PART VI, MUTCD SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	
DATE	REVISION	FILMED


ARKANSAS STATE HIGHWAY COMMISSION  
STANDARD TRAFFIC CONTROLS  
FOR HIGHWAY CONSTRUCTION  
STANDARD DRAWING TC-1

<p>RI-1</p>  <p>STANDARD 30"x30" EXPRESSWAY 36"x36" SPECIAL 48"x48"</p>	<p>RI-2</p>  <p>STD. 36"x36"x36" EXPWY. 48"x48"x48" FWY. 60"x60"x60"</p>	<p>R2-1</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R2-5A</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R2-5C</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R4-1</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R4-2</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>
<p>R5-1</p>  <p>STD. 30"x30" EXPWY. 36"x36" SPECIAL 48"x48"</p>	<p>R11-2</p>  <p>48"x30"</p>	<p>R11-3A</p>  <p>60"x30"</p>	<p>R11-4</p>  <p>60"x30"</p>	<p>RSP-1</p>  <p>48"x30"</p>	<p>W1-1</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W1-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>
<p>W1-3</p>  <p>STD. 48"x48"</p>	<p>W1-4</p>  <p>STD. 48"x48"</p>	<p>W1-6</p>  <p>STD. 48"x24" SPECIAL 60"x30"</p>	<p>W1-8</p>  <p>STD. 18"x24" SPECIAL 24"x30" EXPWY. 30"x36" FWY. 36"x48"</p>	<p>W3-1</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W3-2</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W4-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>
<p>W5-1</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W6-3</p>  <p>EXPWY. 36"x36" SPECIAL 48"x48"</p>	<p>W8-7</p>  <p>EXPWY. 36"x36" FWY. 48"x48"</p>	<p>W9-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W13-1</p>  <p>STD. 24"x24"</p>	<p>W20-1</p>  <p>STD. 48"x48"</p>	<p>W20-2</p>  <p>STD. 48"x48"</p>
<p>W20-3</p>  <p>STD. 48"x48"</p>	<p>W20-4</p>  <p>STD. 48"x48"</p>	<p>W20-5</p>  <p>STD. 48"x48"</p>	<p>W20-7a</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W21-2</p>  <p>STD. 30"x30" SPECIAL 36"x36"</p>	<p>W21-5</p>  <p>STD. 30"x30" SPECIAL 36"x36"</p>	<p>W24-1</p>  <p>STD. 36"x36"</p>
<p>W1-4b</p>  <p>STD. 48"x48"</p>	<p>R56-1</p>  <p>STD. 18"x18"</p>	<p>W8-11</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W8-9</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>G20-1</p>  <p>60"x24"</p>	<p>G20-2</p>  <p>48"x24"</p>	<p>OM-3L OM-3R</p>  <p>12"x36"</p>
<p>M4-9</p>  <p>STD. 30"x24" SPECIAL 48"x36" SPECIAL 60"x48"</p>	<p>M4-10</p>  <p>48"x18"</p>	<p>R55-1</p>  <p>36"x60" * USE 6" C LETTERS ** USE 4" D LETTERS</p>				







(A) TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES ON A 2-LANE HIGHWAY WHERE THE ENTIRE ROADWAY IS CLOSED AND A BYPASS DETOUR IS PROVIDED.




(B) TYPICAL APPLICATION - 4-LANE DIVIDED ROADWAY WHERE ONE ROADWAY IS CLOSED.




(C) TYPICAL APPLICATION - 4-LANE UNDIVIDED ROADWAY WHERE HALF OF THE ROADWAY IS CLOSED.




(D) TYPICAL APPLICATION - ROADWAY CLOSED BEYOND DETOUR POINT.



(E) TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES ON 2-LANE HIGHWAY WHERE ONE LANE IS CLOSED AND FLAGGING IS PROVIDED.



(F) TYPICAL APPLICATION - 4-LANE UNDIVIDED ROADWAY WITH INSIDE LANE CLOSED.




TYPICAL ADVANCE WARNING SIGN PLACEMENT

TAPER FORMULAE:  
 $L = SXW$  FOR SPEEDS OF 45MPH OR MORE.  
 $L = \frac{WS^2}{60}$  FOR SPEEDS OF 40MPH OR LESS.  
 WHERE:  
 L = MINIMUM LENGTH OF TAPER.  
 S = NUMERICAL VALUE OF POSTED SPEED LIMIT PRIOR TO WORK OR 85TH PERCENTILE SPEED.  
 W = WIDTH OF OFFSET.


- GENERAL NOTES:
- ADVISORY SPEED POSTED ON W1-3 OR W1-4 CURVE WARNING SIGNS TO BE DETERMINED AT SITE. USE W1-4 WHEN SPEED IS GREATER THAN 30MPH AND W1-3 WHEN 30MPH OR LESS.
  - WHEN THE EXISTING SPEED LIMIT IS 55MPH AND THE PLANS REQUIRE A SPEED LIMIT OF 45MPH, THE R2-N55) SHALL BE OMITTED AND THE R2-5A SHALL BE INSTALLED AT THAT LOCATION. ADDITIONAL R2-145MPH SPEED LIMIT SIGNS SHALL BE INSTALLED AT A MAXIMUM OF 1MILE INTERVALS. AT THE END OF THE WORK AREA A R2-1XX) SHALL BE INSTALLED TO MATCH ORIGINAL SPEED LIMIT.
  - WHEN THE EXISTING SPEED LIMIT IS 65MPH AND THE PLANS REQUIRE A SPEED LIMIT OF 55MPH, THE R2-N45) SHALL BE OMITTED. ADDITIONAL R2-155MPH SPEED LIMIT SIGNS SHALL BE INSTALLED AT A MAXIMUM OF 1MILE INTERVALS. AT THE END OF THE WORK AREA A R2-1XX) SHALL BE INSTALLED TO MATCH ORIGINAL SPEED LIMIT.
  - THE MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES IN A TAPER SHOULD BE APPROXIMATELY EQUAL IN FEET TO THE SPEED LIMIT. BEYOND THE TAPER, MAXIMUM SPACING SHALL BE TWO TIMES THE SPEED LIMIT, OR AS DIRECTED BY THE ENGINEER.
  - WARNING LIGHTS AND/OR FLAGS MAY BE MOUNTED TO SIGNS OR CHANNELIZING DEVICES AT NIGHT AS NEEDED.
  - PAVEMENT MARKINGS NO LONGER APPLICABLE WHICH MIGHT CREATE CONFUSION IN THE MINDS OF VEHICLE OPERATORS SHALL BE REMOVED OR OBLITERATED AS SOON AS PRACTICABLE.
  - TRAILER MOUNTED DEVICES SUCH AS ARROW PANELS AND PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE DELINEATED BY AFFIXING CONSPICUOUS MATERIAL IN A CONTINUOUS LINE ON THE FACE OF THE TRAILER. WHEN PLACED ON OR ADJACENT TO THE SHOULDER AND NOT BEHIND A POSITIVE BARRIER, THESE DEVICES SHALL BE DELINEATED BY PLACING FIVE (5) TRAFFIC DRUMS, EQUALLY SPACED ALONG THE TRAFFIC SIDE OF THE DEVICE.

9-12-13	REVISED DETAIL OF RAISED PAVEMENT MARKERS	
3-11-10	ADDED (AFAD)	
11-20-08	REVISED SIGN DESIGNATIONS	
11-18-04	ADDED GENERAL NOTE	
10-18-96	ADDED R55-1	
4-26-96	CORRECTED (a) BEHIND G20-2	
6-8-95	CORRECTED SIGN IDENT. ON W1-4A	6-8-95
2-2-95	REVISED PER PART VI, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	
DATE	REVISION	FILMED

ARKANSAS STATE HIGHWAY COMMISSION  
 STANDARD TRAFFIC CONTROLS  
 FOR HIGHWAY CONSTRUCTION  
 STANDARD DRAWING TC-2




(A) Typical application - daytime maintenance operations of short duration on a 4-lane divided roadway where half of the roadway is closed.



(B) Typical application - 3-lane oneway roadway where center lane is closed.



Channelizing devices






TRAFFIC CONTROL DEVICES FOR VERTICAL PAVEMENT DIFFERENTIALS

VERTICAL DIFFERENTIAL	LOCATIONS	TRAFFIC CONTROL
1" to 3"	Centerline, lane lines	W8-11
1" to 3"	Edge of shoulder	W8-9
Greater than 3"	Lane lines	Standard lane closure required
Greater than 3"	Edge of traveled lane	*RSP-1 and vertical panels, drums or concrete barrier
Greater than 3"	Edge of shoulder	*Vertical panels, drums or concrete barrier


\* When shown on the plans concrete barrier will be used.  
When the shoulder area is used as part of the traveled lane and there is insufficient width to place drums on the remaining shoulder width, then vertical panels shall be used.



VERTICAL PANEL PLACEMENT




NOTES: USE SPLICES ONLY WHEN NECESSARY FOR INSTALLATION. TYPICAL INSTALLATION SHOULD HAVE NO SPLICES (SEE STD. DRAWING NO. SHS-2). NORMAL INSTALLATIONS WILL REQUIRE 1/4" DIA. BOLTS TO MOUNT SIGNS TO POST AND 5/16" DIA. BOLTS TO ASSEMBLE THE VARIOUS POST SUPPORTS. EACH OF THESE BOLTS SHALL BE CARRIAGE BOLTS. SIGN POSTS SHALL BE PAINTED GREEN; SIGNS SHALL NOT BE PAINTED, AND ALL SIGN POSTS SHALL BE PLUMB.



- KEY:
- Arrow Panel (if Required)
  - Channelizing Device
  - Traffic drum

GENERAL NOTES:

- A speed limit reduction may be implemented ONLY when designated in the plan or when recommended by the Roadway Design Division.
- When the existing speed limit is 55mph and the plans require a speed limit of 45mph, the R2-1(55) shall be omitted and the R2-5A shall be installed at that location. Additional R2-1 45mph speed limit signs shall be installed at a maximum of 1 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
- When the existing speed limit is 65mph and the plans require a speed limit of 55mph, the R2-1(65) shall be omitted. Additional R2-1 55mph speed limit signs shall be installed at a maximum of 1 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
- The maximum spacing between channelizing devices in a taper should be approximately equal in feet to the speed limit. Beyond the taper, maximum spacing shall be two times the speed limit or as directed by the Engineer.
- Warning lights and/or flags may be mounted to signs or channelizing devices at night as needed.
- Pavement markings no longer applicable which might create confusion in the minds of vehicle operators shall be removed or obliterated as soon as practicable.
- The G20-1 sign will be required on jobs of over two miles in length. When the lane closure is not at the beginning of the project, the G20-1 sign shall be erected 125' in advance of the job limit. Additional W20-1 (1 MILE) signs are not required in advance of lane closures that begin inside the project limits.
- Flaggers shall use STOP/SLOW paddles for controlling traffic through work zones. Flags may be used only for emergency situations.
- All plastic drums and cones shall meet the requirements of NCHRP-350 or Manual for Assessing Safety Hardware (MASH).
- Trailer mounted devices such as arrow panels and portable changeable message signs shall be delineated by affixing conspicuity material in a continuous line on the face of the trailer. When placed on or adjacent to the shoulder and not behind a positive barrier, these devices shall be delineated by placing five (5) traffic drums, equally spaced along the traffic side of the device.










(C) Typical application - construction operations of intermediate to long term duration on a 4-lane divided roadway where half of the roadway is closed.

(D) Typical application - closing multiple lanes of a multilane highway.





DATE	REVISION	FILMED
10-15-09	ADDED REFERENCE TO MASH	
11-20-08	REVISED SIGN DESIGNATIONS	
11-18-04	ADDED NOTE	
10-1-98	ADDED NOTE	
4-03-97	ADDED (SP) TO W6-1 & REVISED TRAFFIC CONTROL DEVICES NOTE	
10-18-96	ADDED R55-1	
10-12-95	MOVED UPPER SPLICE	
6-8-95	REVISED SPLICE DETAIL, TEXT	6-8-95
2-2-95	REVISED PER PART VI, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	

ARKANSAS STATE HIGHWAY COMMISSION  
STANDARD TRAFFIC CONTROLS  
FOR HIGHWAY CONSTRUCTION  
STANDARD DRAWING TC-3

REINFORCING BAR TABLE PER BARRIER UNIT			
MARK	LOCATION	BAR SIZE	(NO. BARS)
H-1	HORIZONTAL IN BARRIER TIED INSIDE V-1 BARS	#5	(6)
H-2	CENTERED ABOVE DRAIN SLOTS LONG. & TRANSVERSELY	#5	(6)
H-3	TIED ABOVE H-1 BARS TO SUPPORT H-2, TIED TO V-1	#4	(2)
S-1	OVER LIFT HOLES	#4	(2)
S-2	HORIZ. AROUND SLOTS BETWEEN V-1'S & DRAIN SLOTS	#4	(2)
V-1	VERTICAL IN BARRIER (3) EACH END & (2) AT EACH DRAIN SLOTS	#5	(16)




- General Notes**
- The contractor shall furnish the Precast Concrete Barrier Units and shall be responsible for the manufacture, shipment, storage, placement and removal. At the completion of the project, the precast units will remain the property of the contractor.
  - Materials shall meet the following minimum requirements:  
 Concrete: 2500 psi compressive strength at 28 days.  
 Reinforcing Steel: AASHTO M 31 or M 53, Grade 60  
 Structural Steel: AASHTO-M270 Grade 36 shall be used for the Connection Pin, Connection Loops, and Stabilization Pins. A One Piece Pin with a 3" rounded top may be used in place of the detailed Connection Pin.  
 Delineators: Delineators shall be mounted at 10' spacing on top of precast barrier.  
  
 In applications where barrier walls within 6 feet of a traffic lane, additional delineators shall be placed on the barrier at 10' spacing approximately one (1) foot from the top of the barrier. Delineators shall be on the AHTD Qualified Products List for Construction Concrete Barrier Markers. Delineator color shall be in accordance with the Manual on Uniform Traffic Control Devices.  
 Payment for delineators shall be considered included in the price bid per Ln. Ft. for "Furnishing and installing Precast Concrete Barrier". The contractor shall certify to the Engineer that the material and the design used in the precast barrier units meets the requirements as shown on this standard drawing.
  - Other Precast Concrete Barriers that have been crash tested and approved by the Federal Highway Administration to meet the requirements of NCHRP-350 test level 3 or Manual For Assessing Safety Hardware (MASH) will be accepted in lieu of the barrier shown. Drain slots shall be provided as needed or as directed by the Engineer. The Contractor shall furnish a certification of NCHRP Report 350 or Manual For Assessing Safety Hardware (MASH) compliance for any other types of precast barrier to be used. The certification shall state that the precast concrete barrier meets the requirements of NCHRP Report 350 or Manual For Assessing Safety Hardware (MASH) and include a copy of the Federal Highway Administration's (FHWA) approval letter with all attachments. Precast concrete barrier units shall be fabricated and installed in accordance with crash testing and documentation provided in the FHWA approval letter. Mixing of shapes will not be allowed in a continuous line of units.
  - Dowel holes in pavement or bridge slabs that are to remain in place shall be filled. Holes in concrete pavement and bridge slabs shall be filled with an approved non-shrink epoxy grout. Holes in asphalt pavement shall be filled with an approved asphalt joint filler. Payment for drilling and filling holes to be included in the price for various barrier items.
  - Attach Units To Roadway Surface with Stabilization Pins and to Deck Slabs using bolts when required.
  - A 4" White PVC Sleeve may be used to form the Lifting Hole and if used the Sleeve is to be left in place.



DATE	REVISION	FILMED
2-27-14	REVISED BARRIER STABILIZATION DETAIL	
10-15-09	ADDED REFERENCE TO MASH	
8-5-09	REV. NOTE 3 CONCERNING DRAIN SLOTS	
11-29-07	REVISED NOTE 3	
5-25-06	DELETED GENERAL NOTE 7	
11-18-04	REVISED BARRIER STABILIZATION DETAIL BRIDGE DECKS	
4-10-03	REVISED GENERAL NOTE 2	
8-22-02	ISSUED NEW DRAWING	

ARKANSAS STATE HIGHWAY COMMISSION  
 STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION - TEMPORARY PRECAST BARRIER  
 STANDARD DRAWING TC-4


(A) 4 feet or greater preferred. If less than 4 feet, Precast Units shall be connected to slab (SEE BARRIER STABILIZATION DETAIL-BRIDGE DECKS STD. DRWG. TC-4)



BARRIER PLACEMENT ALONG BRIDGE WITH OFFSET


No Scale

\*\* Offset Distance for Two Way Traffic Only



SECTION J-J

No Scale



BARRIER PLACEMENT ALONG ROADWAY WITH OFFSET

No Scale


\* Offset Distance (See Table)

\*\* Offset Distance for Two Way Traffic Only

Offset Distance Table

Speed (MPH)	Offset Distance (FT.)
≤ 45	12
> 45	18

If offset distance is not attainable, then see 'Barrier Placement With Attenuator' Detail shown below.




SPECIAL END UNIT

No Scale

General Notes

When shown on the Plans, the ends of the Temporary Precast Concrete Barrier shall be protected with an NCHRP-350 or Manual For Assessing Safety Hardware (MASH) approved Crash Cushion. Payment for Crash Cushions shall be made under the item of "Temporary Impact Attenuation Barrier."










BARRIER PLACEMENT WITH ATTENUATOR

No Scale


\*\* Offset Distance for Two Way Traffic Only

\*\*\*Min. 3'-0" From Edge of Travel Lane to Nearest Edge of Attenuator


			ARKANSAS STATE HIGHWAY COMMISSION
			STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION - TEMPORARY PRECAST BARRIER
10-15-09	ADDED REFERENCE TO MASH		STANDARD DRAWING TC-5
5-25-06	REVISED BARRIER PLACEMENT		
8-22-02	ISSUED NEW DRAWING		
DATE	REVISION	FILMED	




12-15-11	DELETED BALED STRAW DITCH CHECK & ADDED WATTLE DITCH CHECK		ARKANSAS STATE HIGHWAY COMMISSION
11-18-98	ADDED NOTES		
7-02-98	ADDED BALED STRAW FILTER BARRIER (E-2)		
7-20-95	REVISED SILT FENCE E-4 AND E-11	7-20-95	TEMPORARY EROSION CONTROL DEVICES
7-15-94	REV. E-4 & E-11 MIN. 13" BURIED END OF FABRIC		
6-2-94	REVISED E-1, 4, 7 & 11; DELETED E-2 & 3	6-2-94	
4-1-93	REDRAWN		
10-1-92	REDRAWN		
8-2-76	ISSUED R.D.M.	298-7-28-76	STANDARD DRAWING TEC-1
DATE	REVISION	FILMED	




SEDIMENT BASIN WITH RIPRAP OUTLET (E-9)




SEDIMENT BASIN WITH PIPE OUTLET (E-10)



DIVERSION DITCH (E-8)



SLOPE DRAIN (E-12)



SEDIMENT BASIN (E-14)


DATE	REVISION	FILMED
6-2-94	Revised E-8 & E-12; Added E-14 & Deleted E-13	
4-1-93	ISSUED	

ARKANSAS STATE HIGHWAY COMMISSION  
 TEMPORARY EROSION CONTROL DEVICES  
 STANDARD DRAWING TEC-2

### CLEARING AND GRUBBING

- CONSTRUCTION SEQUENCE
1. PLACE PERIMETER CONTROLS (I.E. SILT FENCES , DIVERSION DITCHES, SEDIMENT BASINS, ETC.)
  2. PERFORM CLEARING AND GRUBBING OPERATION.

### EXCAVATION



NOTE:  
NUMBER OF PHASES WILL VARY.  
THREE PHASES SHOWN FOR  
ILLUSTRATION.


GENERAL NOTE

ALL CUT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE EXCAVATED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.

CONSTRUCTION SEQUENCE

1. EXCAVATE AND STABILIZE INTERCEPTOR AND/OR DIVERSION DITCHES.
2. PERFORM PHASE 1 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
3. PERFORM PHASE 2 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
4. PERFORM FINAL PHASE OF EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING. STABILIZE DITCHES. CONSTRUCT DITCH CHECKS, DIVERSION DITCHES, SEDIMENT BASINS, OR OTHER EROSION CONTROL DEVICES AS REQUIRED.

### EMBANKMENT



NOTE:  
NUMBER OF PHASES WILL VARY.  
THREE PHASES SHOWN FOR  
ILLUSTRATION.


GENERAL NOTE

ALL EMBANKMENT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE CONSTRUCTED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.

CONSTRUCTION SEQUENCE


1. CONSTRUCT DIVERSION DITCHES, DITCH CHECKS, SEDIMENT BASINS, SILT FENCES, OR OTHER EROSION CONTROL DEVICES AS SPECIFIED.
2. PLACE PHASE 1 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
3. PLACE PHASE 2 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
4. PLACE FINAL PHASE OF EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PLACE DIVERSION DITCHES AND SLOPE DRAINS AND MAINTAIN UNTIL ENTIRE SLOPE IS STABILIZED.

		ARKANSAS STATE HIGHWAY COMMISSION	
		TEMPORARY EROSION CONTROL DEVICES	
11-23-94	CORRECTED SPELLING		
6-2-94	Drawn & Issued	6-2-94	
DATE	REVISION	FILMED	
		STANDARD DRAWING TEC-3	



ENTRANCE RAMP


NOTE: JOINT SPACING ON THE MAIN LANES SHALL BE ADJUSTED AS NECESSARY TO CONFORM TO THESE JOINT LAYOUTS. THE MAIN LANE JOINT SPACING MAY BE REDUCED TO A 12' MINIMUM.




EXIT RAMP

EXIT RAMP

DESIGN SPEED V	Y	NOSE OFFSET C	LENGTH NOSE TAPER Z	RETURN RADIUS R	ADDITIONAL SURFACING SQ. YDS.
40	300.0	8.0	96.0	580.0	602.43
50	320.0	10.0	120.0	725.0	687.29
60	340.0	12.0	168.0	1182.0	790.55
70	360.0	14.0	210.0	1582.0	902.27



DETAIL "A"



DETAIL OF EXPANSION JOINT & JOINT SUPPORT

NOTE: THE EXPANSION JOINTS SHALL BE MEASURED AND PAID FOR AS P.C.C. PAVEMENT (RAMP THICKNESS), WHEN RAMP PAVING IS ASPHALT, EXPANSION JOINT IS NOT REQUIRED. THE JOINT SUPPORT MAY BE CONSTRUCTED WITH CLASS "A", "S", OR PAVING CONCRETE. PAYMENT FOR THE JOINT SUPPORT SHALL BE FOR THE CONTRACT UNIT PRICE BID FOR THE CLASS OF CONCRETE USED. ALL OTHER WORK AND MATERIALS REQUIRED FOR THE CONSTRUCTION OF THE JOINT SUPPORT SHALL BE INCLUDED IN THE PRICE BID FOR THE ABOVE ITEMS.

DATE	REVISION	DATE FILM'D
8-22-02	DELETED NOTE	
11-16-01	CORRECTED SPELLING ON ENTRANCE RAMP NOTE	
5-13-99	ADDED, EDITED AND DELETED NOTES	
11-03-94	ADDED NOTE RE: REINF. BARS	
10-1-92	ADDED DETAIL A & OTHER MINOR CHANGES	10-1-92
1-25-90	REVISED EXPANSION JOINT	1-25-90
7-15-88	CONFORM D TO 1988 SPECIFICATIONS	65C-7-15-88
3-2-81	ISSUED	511-10-2-72

ARKANSAS STATE HIGHWAY COMMISSION

DETAILS OF STANDARD TURNOUT

FOR

ENTRANCE & EXIT RAMPS (NON-REINFORCED)

STANDARD DRAWING TR-1A



GENERAL NOTES:

STEEL LINE POSTS SHALL BE GALVANIZED, 7 FT. IN LENGTH.

TUBULAR END, CORNER, PULL, OR DIAGONAL BRACES MUST CONFORM TO THE DIMENSIONS AND WEIGHTS SPECIFIED ON STANDARD DRAWING WF-3 (CHAIN LINK).


THE CONTRACTOR SHALL FURNISH AT LEAST 25% OF WOOD LINE POSTS OF 7' LENGTHS IN ORDER TO PROVIDE SUFFICIENT SET IN SOFT GROUND OR SMALL DEPRESSIONS.

GATE HINGES AND LATCHES WITH LOCKS TO BE OF A TYPE APPROVED BY THE ENGINEER. DRIVEWAY GATES, EITHER SINGLE 12' OR 16' OR DOUBLE 6' TO 8' OPENINGS OF THE SAME TYPE AS THE PEDESTRIAN GATE, SHALL BE INSTALLED ON THE RIGHT SIDE OF EACH THROUGH LANE ROAD AT LARGE CULVERTS OR BRIDGE CROSS FENCE FOR USE BY MAINTENANCE EQUIPMENT. LOCATION OF GATES TO BE SHOWN ON THE PLANS OR AS DESIGNATED BY THE ENGINEER.



AT STREAM CROSSINGS THE FENCE SHALL NOT BE CONSTRUCTED ACROSS LARGE STREAMS, WHERE CLEARANCE IS SUFFICIENT FROM THE TOP OF BANK TO THE BRIDGE STRUCTURE, A CROSS CONNECTION SHALL BE CONSTRUCTED BETWEEN THE FENCE ON EACH SIDE OF THE ROAD, WHERE THE CLEARANCE IS NOT SUFFICIENT, THE FENCE SHALL BE TERMINATED WITH CROSS CONNECTIONS AND END POSTS ADJACENT TO THE BRIDGE ABUTMENTS OR CULVERT WINGWALLS.

SPLICE FOR WOVEN WIRE BETWEEN PULL POST SHALL BE BY THE "WESTERN UNION METHOD" AS DESCRIBED AS FOLLOWS: THE VERTICAL WIRES FOR EACH END OF THE FENCE FABRIC SHALL BE PLACED SIDE BY SIDE AND THE PROJECTING HORIZONTAL WIRES SHALL BE WRAPPED A MINIMUM OF 4 TIMES AROUND THE HORIZONTAL WIRES OF THE FIRST WEB.



SPLICE FOR BARBED WIRE BETWEEN PULL POST ASSEMBLY SHALL BE BY THE "EYE METHOD": AS DESCRIBED AS FOLLOWS: THE ENDS OF THE BARBED WIRE SHALL BE BENT TO FORM A LOOP. THE LOOPS SHALL BE CONNECTED. AFTER THE LOOPS ARE CONNECTED THE ENDS OF THE WIRE SHALL BE WRAPPED AROUND THE PROJECTING WIRE A MINIMUM OF 4 TIMES FOR EACH WIRE LOOP.




NOTE: STAPLE AT LEAST TOP, BOTTOM AND ALTERNATE WIRES OF WOVEN FABRIC FOR WOOD LINE POSTS.



TYPE A FENCE (WOOD POSTS)




TYPE A FENCE (STEEL POSTS)



NOTE: RIGHT-OF-WAY MONUMENTS SHALL NOT BE DISTURBED BY FENCE CONSTRUCTION. CORNER POSTS SHALL BE CONSTRUCTED 2' FROM THE RIGHT-OF-WAY MONUMENT OR AS DIRECTED BY THE ENGINEER.


△ - R/W MONUMENTS  
○ - FENCE POSTS

RIGHT-OF-WAY FENCE LOCATION





WHERE EXISTING PRIVATE FENCE CONSISTS OF STEEL POSTS, USE END POST ASSEMBLY AS SHOWN WITH TYPE A FENCE OR OTHER END POST ASSEMBLY AS APPROVED BY THE ENGINEER.

PRIVATE FENCE TERMINAL INSTALLATION



SPACING AND SIZE OF POSTS FOR TYPE B FENCE SHALL BE THE SAME AS TYPE A FENCE.

TYPE B FENCE




DETAIL OF FENCE CONSTRUCTION AT LARGE CULVERTS (5' IN HEIGHT AND OVER)

DATE	REVISION	DATE FILMED
8-22-02	REVISED GENERAL NOTES	
10-18-96	REVISED ASTM REF. TO AASHTO	
11-22-95	REVISED R-O-W LOCATION DETAIL	
6-2-94	ADDED CORNER POST NOTE	6-2-94
8-5-93	REVISED R-O-W LOCATION DETAIL	8-5-93
10-1-92	ADDED STAPLE NOTE	
8-2-90	REV'D PULL POST LENGTH	
11-30-89	DELETED CLASS CONC.	
7-15-88	ADDED SPLICE NOTES	
7-15-88	ADDED HEIGHT DIMENSION	
4-3-87	REVISED VARIOUS NOTES	
	AND GENERAL NOTES	
11-1-84	MAX. POST SPACING	
1-4-83	MIN. DIA. LINE POST	
10-2-72	REVISED & REDRAWN	

ARKANSAS STATE HIGHWAY COMMISSION

WIRE FENCE  
TYPE A AND B


STANDARD DRAWING WF-1



LINE POST  
3" MIN. DIA. 6'-3" LENGTH  
MAX. SPACING TO BE 10'-0"


LINE BRACE ASSEMBLY  
MAX. SPACING TO BE 330"

TYPE C FENCE (WOOD POSTS)




NOTE: STEEL LINE POSTS SHALL BE 6'-6" MINIMUM LENGTH.

TYPE C FENCE (STEEL POSTS)




NOTE: SPACING AND SIZE (EXCEPT LENGTH) OF POSTS, APPROACH SPANS, PULL POST ASSEMBLIES, AND CORNER BRACING FOR TYPE D FENCE SHALL CONFORM TO TYPE C FENCE. USE GALVANIZED STAPLES ON WOOD POSTS AND APPROVED FASTENERS ON STEEL POSTS.



NOTE: RIGHT-OF-WAY MONUMENTS SHALL NOT BE DISTURBED BY FENCE CONSTRUCTION. CORNER POSTS SHALL BE CONSTRUCTED 2' FROM THE RIGHT-OF-WAY MONUMENT OR AS DIRECTED BY THE ENGINEER.

RIGHT-OF-WAY FENCE LOCATION



PRIVATE FENCE TERMINAL INSTALLATION  
WHERE EXISTING FENCE CONSISTS OF STEEL POSTS, USE END POST ASSEMBLY AS SHOWN IN TYPE C FENCE OR OTHER END POST ASSEMBLY AS APPROVED BY THE ENGINEER.


GENERAL NOTES:  
STEEL LINE POSTS SHALL BE PAINTED OR GALVANIZED. TUBULAR END, CORNER, PULL, OR DIAGONAL BRACES MUST CONFORM TO THE DIMENSIONS AND WEIGHTS SPECIFIED ON STANDARD DRAWING WF-3 (CHAIN LINK). APPROVED ALTERNATES ARE ACCEPTABLE. AN ACCEPTABLE TOLERANCE IN LENGTH OF TUBULAR OR WOODEN POSTS SHALL BE - 1" TO +2". TUBULAR POSTS MUST BE PAINTED OR GALVANIZED.

THE CONTRACTOR SHALL FURNISH AT LEAST 25% OF TIMBER LINE POSTS OF 7 FOOT LENGTHS IN ORDER TO PROVIDE SUFFICIENT SET IN SOFT GROUND OR SMALL DEPRESSIONS.

DRIVEWAY GATES, EITHER SINGLE 12' TO 16' OR DOUBLE 6' TO 8' OPENING OF THE SAME TYPE AS THE PEDESTRIAN GATE, SHALL BE INSTALLED ON THE RIGHT SIDE OF EACH THROUGH LANE ROAD AT LARGE CULVERTS OR BRIDGE CROSS FENCE, FOR USE OF MAINTENANCE EQUIPMENT. LOCATION OF GATES TO BE SHOWN ON PLANS OR AS DESIGNATED BY THE ENGINEER.

AT STREAM CROSSINGS, THE FENCE SHALL NOT BE CONSTRUCTED ACROSS LARGE STREAMS, WHERE CLEARANCE IS SUFFICIENT FROM THE TOP OF THE BANK TO THE BRIDGE STRUCTURE A CROSS CONNECTION SHALL BE CONSTRUCTED BETWEEN THE FENCE ON EACH SIDE OF THE ROAD, WHERE THE CLEARANCE IS NOT SUFFICIENT, THE FENCE SHALL BE TERMINATED WITH CROSS CONNECTIONS AND END POSTS ADJACENT TO BRIDGE ABUTMENTS OR CULVERT WINGWALLS.

NOTE: USE 3/8" x 1 1/2" LAG BOLT & SHIELD OR AS APPROVED BY THE ENGINEER.




DETAIL OF FENCE CONSTRUCTION AT LARGE CULVERTS (5' IN HEIGHT AND OVER)

SPLICE FOR BARBED WIRE BETWEEN PULL POST ASSEMBLY SHALL BE BY THE 'EYE METHOD' AS DESCRIBED AS FOLLOWS: THE ENDS OF THE BARBED WIRE SHALL BE BENT TO FORM A LOOP, THE LOOPS SHALL BE CONNECTED. AFTER THE LOOPS ARE CONNECTED THE ENDS OF THE WIRE SHALL BE WRAPPED AROUND THE PROJECTING WIRES A MINIMUM OF 4 TIMES FOR EACH WIRE LOOP.

SPLICE FOR WOVEN WIRE BETWEEN PULL POST SHALL BE BY THE 'WESTERN UNION METHOD' AS DESCRIBED AS FOLLOWS: THE VERTICAL WIRES FOR EACH END OF THE FENCE FABRIC SHALL BE PLACED SIDE BY SIDE AND THE PROJECTING HORIZONTAL WIRES SHALL BE WRAPPED A MINIMUM OF 4 TIMES AROUND THE HORIZONTAL WIRES OF THE FIRST WEB.

STAPLE AT LEAST TOP, BOTTOM AND ALTERNATE WIRES OF WOVEN FABRIC FOR WOOD LINE POSTS.



OTHER STYLE VEHICULAR GATES MAY BE USED WITH THE APPROVAL OF THE ENGINEER. THE METHOD OF SECURING GATE (LATCH AND/OR LOCK) SHALL MEET THE APPROVAL OF THE ENGINEER.

TYPICAL VEHICULAR GATES (ALTERNATE TYPE)

8-22-02	REVISED GENERAL NOTES	
10-18-96	REVISED AASHTO	
11-22-95	REVISED R-O-W LOCATION DETAIL	
6-2-94	REVISED BARB WIRE AND ADDED CORNER POST NOTES	6-2-94
8-5-93	REVISED R/W INSTALLATION FENCE	8-5-93
10-1-92	ADDED STAPLE NOTE	10-1-92
8-15-91	ADDED TYPE D-2 FENCE	8-15-91
11-30-89	DELETED CLASS CONCRETE	11-30-89
7-15-88	ADDED SPLICE NOTE	700-7-15-88
10-30-87	GENERAL REVISIONS	549-10-30-87
11-1-84	MAX. POST SPACING MIN. WIRE GAUGE	507-11-1-84
1-4-83	MIN. DIA. LINE POST	648-1-4-83
3-2-81	TOLERANCE FOR POST LENGTH	722-3-2-81
12-1-72	ADDED D-1 & FENCE INSTALLATION	564-12-1-72
10-2-72	REVISED AND REDRAWN	540-10-2-72
DATE	REVISION	FILMED

ARKANSAS STATE HIGHWAY COMMISSION

WIRE FENCE  
TYPE C AND D

STANDARD DRAWING WF-4