


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO. BB0202	I	235
								HWY. 104-HWY. 65B (F)

"A FULLY CONTROLLED ACCESS FACILITY"
 ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT
 CONSTRUCTION PLANS FOR STATE HIGHWAY


HWY. 104-HWY. 65B (F)

JEFFERSON COUNTY
 ROUTE 530 SECTION 5
 FED. AID PROJ. BIM-B530(202) &
 BIM-HSIP-B530(202)

JOB BB0202




ARK. HWY. DIST. NO. 2



PROJECT LOCATION

NOT TO SCALE



RIIW
 RIOW

STA. 175+14.73
 BEGIN JOB BB0202
 LOG MILE 34.99

STA. 447+70.79
 END JOB BB0202
 LOG MILE 29.89

STA. 346+80.17
 END EXCEPTION

STA. 245+17.70
 END EXCEPTION

BRIDGE DATA (FOR INFORMATION ONLY)

- 1 STA. 243+18.26 BRIDGE END
 BRIDGE NO. A5500 IN PLACE
 226'-0" CONTINUOUS PLATE GIRDER UNITS
 39' CLEAR ROADWAY
 228'-8 3/16" BRIDGE LENGTH
 STA. 245+46.95 BRIDGE END
 RETAIN
- 2 STA. 242+59.76 BRIDGE END
 BRIDGE NO. B5500 IN PLACE
 226'-0" CONTINUOUS PLATE GIRDER UNITS
 39' CLEAR ROADWAY
 228'-8 3/16" BRIDGE LENGTH
 STA. 244+88.44 BRIDGE END
 RETAIN
- 3 STA. 345+29.22 BRIDGE END
 BRIDGE NO. A5501 IN PLACE
 168'-0" CONTINUOUS COMPOSITE W-BEAM UNITS
 39' CLEAR ROADWAY
 170'-5 1/4" BRIDGE LENGTH
 STA. 346+99.58 BRIDGE END
 RETAIN
- 4 STA. 344+90.40 BRIDGE END
 BRIDGE NO. B5501 IN PLACE
 168'-0" CONTINUOUS COMPOSITE W-BEAM UNITS
 39' CLEAR ROADWAY
 170'-5 1/4" BRIDGE LENGTH
 STA. 346+60.76 BRIDGE END
 RETAIN
- 5 STA. 447+89.13 BRIDGE END
 BR. NO. A5611 IN PLACE
 242'-0" CONTINUOUS GIRDER UNITS
 39'-0" CLEAR ROADWAY
 245'-1 1/8" BRIDGE LENGTH
 STA. 450+34.22 BRIDGE END
 RETAIN
- 6 STA. 448+73.18 BRIDGE END
 BR. NO. B5611 IN PLACE
 242'-0" CONTINUOUS PLATE GIRDER UNITS
 39'-0" CLEAR ROADWAY
 245'-1 1/8" BRIDGE LENGTH
 STA. 451+18.27 BRIDGE END
 RETAIN

STRUCTURES OVER 20'-0" SPAN
 (FOR INFORMATION ONLY)

- 1 STA. 417+05
 IN PLACE TRIP. 8'X6'X25'
 R.C. BOX CULVERT 45° LT. FWD. SKEW
 L.M. 30.59
 SPAN = 37.71'
 RETAIN

STA. 345+09.81
 BEGIN EXCEPTION

STA. 242+89.01
 BEGIN EXCEPTION

LENGTH MEASURE ALONG C.L. MEDIAN (FOR INFORMATION ONLY)

	GROSS LENGTH OF	PROJECT	27256.06	FEET OR	5.162	MILES
NET	"	ROADWAY	26857.02	"	5.087	"
NET	"	BRIDGES	0.00	"	0.00	"
NET	"	PROJECT	26857.02	"	5.087	"

P.E. JOB BB0202

DESIGN TRAFFIC DATA

DESIGN YEAR	2036
2016 ADT	23,500
2036 ADT	33,000
2036 DHV	3,630
DIRECTIONAL DISTRIBUTION	0.60
TRUCKS	11%
DESIGN SPEED	70 MPH




6-24-2016

INDEX OF SHEETS

SHEET NO.	TITLE	BRIDGE NO.	DRWG. NO.	DATE
1	TITLE SHEET			
2	INDEX OF SHEETS			
3	GOVERNING SPECIFICATIONS AND GENERAL NOTES			
4 - 8	TYPICAL SECTIONS OF IMPROVEMENT			
9 - 19	SPECIAL DETAILS			
20 - 82	TEMPORARY EROSION CONTROL DETAILS			
83 - 141	MAINTENANCE OF TRAFFIC			
142	PERMANENT PAVEMENT MARKING DETAILS			
143 - 152	SIGN LAYOUT SHEETS			
153 - 169	SIGN PLACEMENT SHEETS			
170 - 172	SIGN QUANTITIES SHEETS			
173 - 182	QUANTITIES			
183	SUMMARY OF QUANTITIES AND REVISIONS			
184 - 204	PLAN SHEETS			
205	LAYOUT OF BRIDGES OVER HWY. 270 - FOR INFORMATION ONLY	5500 A&B		
206	LAYOUT OF BRIDGES OVER HOLLAND STREET - FOR INFORMATION ONLY	5501 A&B		
207	STANDARD DETAILS FOR TYPE 'AT' APPROACH GUTTERS (BRIDGES WITH 6" CURB WIDTH & TYPE A RAILING)		55036	9-02-15
208	STANDARD DETAILS FOR TYPE C1 APPROACH SLAB		55040C1	2-27-14
209	CONCRETE DITCH PAVING		CDP-1	11-17-10
210	TRANSVERSE & LONGITUDINAL JOINTS FOR CONCRETE PAVEMENT (NON-REINFORCED)		CPTJ-6A	5-25-06
211	DETAILS OF DROP INLETS & JUNCTION BOXES		FPC-9	11-16-01
212	DETAILS OF DROP INLETS		FPC-9D	8-22-02
213	DETAILS OF DROP INLETS AND SPILLWAY OUTLET		FPC-9N	7-02-98
214	GUARD RAIL DETAILS		GR-8	7-14-10
215	GUARD RAIL DETAILS		GR-8A	7-14-10
216	GUARD RAIL DETAILS		GR-9	4-17-08
217	GUARD RAIL DETAILS		GR-9A	4-17-08
218	GUARD RAIL DETAILS		GR-10	7-14-10
219	GUARD RAIL DETAILS		GR-10A	7-14-10
220	GUARD RAIL DETAILS		GRT-1	7-14-10
221	METAL PIPE CULVERT FILL HEIGHTS & BEDDING		PCM-1	2-27-14
222	PAVEMENT MARKING DETAILS		PM-1	5-12-16
223	PERMANENT PAVEMENT MARKING ON ACCESS CONTROLLED ROADWAYS		PM-2	9-12-13
224	DETAILS OF PIPE UNDERDRAIN		PU-1	4-10-03
225	TABLES AND METHOD OF SUPERELEVATION FOR ONE-WAY TRAFFIC		SE-1	1-09-87
226	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-1	9-02-15
227	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-2	9-02-15
228	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION		TC-3	9-02-15
229	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION-TEMPORARY PRECAST BARRIER		TC-4	2-27-14
230	STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION-TEMPORARY PRECAST BARRIER		TC-5	10-15-09
231	TEMPORARY EROSION CONTROL DEVICES		TEC-1	12-15-11
232	TEMPORARY EROSION CONTROL DEVICES		TEC-2	6-02-94
233	TEMPORARY EROSION CONTROL DEVICES		TEC-3	11-03-94
234	TEMPORARY EROSION CONTROL DEVICES		TEC-4	7-26-12
235	DETAILS OF STANDARD TURNOUT FOR ENTRANCE & EXIT RAMPS (NON-REINFORCED)		TR-1A	8-22-02

Leonard.Speed 6/21/2016 10:44:04 AM
 WORKSPACE: Leonard.Speed
 T:\Projects\141010885_1\530_Hwy\04-Hwy\655\Deliverables\ROADWAY\Drawings\BB0202_02_IND_MAIN_01.dgn



Michael Baker INTERNATIONAL				DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
								2	ARK.			
								JOB NO.	BB0202		3	235
								2 GOV. SPECS. & GEN. NOTES				


GOVERNING SPECIFICATIONS

ARKANSAS STATE HIGHWAY COMMISSION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EDITION OF 2014, THE FOLLOWING SPECIAL PROVISIONS AND SUPPLEMENTAL SPECIFICATIONS:

NUMBER	TITLE
ERRATA	ERRATA FOR THE BOOK OF STANDARD SPECIFICATIONS
FHWA-1273	REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - NOTICE TO CONTRACTORS
FHWA-1273	SUPPLEMENT - SPECIFIC EQUAL EMPLOYMENT OPPORTUNITY RESPONSIBILITIES (23 U.S.C. 140)
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - GOALS AND TIMETABLES
FHWA-1273	SUPPLEMENT - EQUAL EMPLOYMENT OPPORTUNITY - FEDERAL STANDARDS
FHWA-1273	SUPPLEMENT - TRAINING PROGRAM - JOB BB0202
FHWA-1273	SUPPLEMENT - POSTERS AND NOTICES REQUIRED FOR FEDERAL-AID PROJECTS
FHWA-1273	SUPPLEMENT - WAGE RATE DETERMINATION
100-3	CONTRACTOR'S LICENSE
108-1	LIQUIDATED DAMAGES
108-2	WORK ALLOWED PRIOR TO ISSUANCE OF WORK ORDER
303-1	AGGREGATE BASE COURSE
400-1	TACK COATS
410-1	CONSTRUCTION REQUIREMENTS AND ACCEPTANCE OF ASPHALT CONCRETE PLANT MIX COURSES
604-1	RETROREFLECTIVE SHEETING FOR TRAFFIC CONTROL DEVICES IN CONSTRUCTION ZONES
620-1	MULCH COVER
JOB BB0202	AUTOMATED WORK ZONE INFORMATION SYSTEM
JOB BB0202	BIDDING REQUIREMENTS AND CONDITIONS
JOB BB0202	BORROW
JOB BB0202	BROADBAND INTERNET SERVICE FOR ASPHALT CONCRETE PLANT
JOB BB0202	BROADBAND INTERNET SERVICE FOR FIELD OFFICE
JOB BB0202	CARGO PREFERENCE ACT REQUIREMENTS
JOB BB0202	CHANNEL POST SIGN SUPPORT
JOB BB0202	CONCRETE DITCH PAVING
JOB BB0202	COORDINATION OF WORK
JOB BB0202	CULVERT CLEAN OUT
JOB BB0202	DISADVANTAGED BUSINESS ENTERPRISE BIDDER'S RESPONSIBILITIES
JOB BB0202	EMPLOYMENT REPORTING
JOB BB0202	FURNISH AND OPERATION OF MOBILE SPEED NOTIFICATION SYSTEM
JOB BB0202	GOALS FOR DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION
JOB BB0202	HIGH PERFORMANCE PAVEMENT MARKING
JOB BB0202	ISSUANCE OF PROPOSALS
JOB BB0202	MAINTENANCE OF TRAFFIC
JOB BB0202	MANDATORY ELECTRONIC CONTRACT
JOB BB0202	MANDATORY ELECTRONIC DOCUMENT SUBMITTAL
JOB BB0202	MODIFYING DROP INLETS
JOB BB0202	MODULAR GLARE SHIELD
JOB BB0202	OMNI-DIRECTIONAL BREAKAWAY SIGN SUPPORT
JOB BB0202	PARTNERING REQUIREMENTS
JOB BB0202	PERCENT WITHIN LIMITS/PAVEMENT SMOOTHNESS
JOB BB0202	PORTABLE CONSTRUCTION LIGHTING
JOB BB0202	PROSECUTION AND PROGRESS - CALENDAR DAY CONTRACT WITH CPM
JOB BB0202	REMOVAL AND DISPOSAL OF GUARDRAIL
JOB BB0202	REMOVAL AND DISPOSAL OF IMPACT ATTENUATION BARRIERS
JOB BB0202	REMOVAL AND DISPOSAL OF WIRE ROPE SAFETY FENCE
JOB BB0202	REMOVING EXISTING PORTLAND CEMENT CONCRETE PAVEMENT
JOB BB0202	ROADWAY CONSTRUCTION CONTROL
JOB BB0202	RUMBLE STRIP REMOVAL
JOB BB0202	SCARIFYING CONCRETE PAVEMENT
JOB BB0202	SEQUENCE OF CONSTRUCTION
JOB BB0202	SITE USE (A+C METHOD) - CALENDAR DAY CONTRACT
JOB BB0202	SOIL STABILIZATION
JOB BB0202	STORM WATER POLLUTION PREVENTION PLAN
JOB BB0202	SUBMISSION OF ASPHALT CONCRETE HOT MIX ACCEPTANCE TEST RESULTS
JOB BB0202	TRAFFIC CONTROL DEVICES IN CONSTRUCTION ZONES
JOB BB0202	TRAFFIC CONTROL SUPERVISOR
JOB BB0202	TRENCHING AND SHOULDER PREPARATION FOR TEMPORARY WIDENING
JOB BB0202	UTILITY ADJUSTMENTS
JOB BB0202	VALUE ENGINEERING
JOB BB0202	WARM MIX ASPHALT
JOB BB0202	WELLHEAD PROTECTION
JOB BB0202	WIRE ROPE SAFETY FENCE END TERMINAL
JOB BB0202	WIRE ROPE SAFETY FENCE (POST REPAIR)
JOB BB0202	WIRE ROPE SAFETY FENCE (WRSF) SPECIFICATIONS


GENERAL NOTES

1. GRADE LINE DENOTES FINISHED GRADE WHERE SHOWN ON PLANS.
2. ALL PIPE LINES, POWER, TELEPHONE, AND TELEGRAPH LINES TO BE MOVED OR LOWERED BY THE RESPECTIVE OWNERS AS PER AGREEMENT WITH SUCH OWNERS.
3. ANY EQUIPMENT OR APPURTENANCE THAT INTERFERES WITH THE PROPOSED CONSTRUCTION AND WHICH MAY BE THE PROPERTY OF UTILITY SERVICE ORGANIZATIONS SHALL BE MOVED BY THE OWNERS UNLESS OTHERWISE PROVIDED.
4. ALL LAND MONUMENTS LOCATED WITHIN THE CONSTRUCTION AREA SHALL BE PROTECTED IN ACCORDANCE WITH SECTION 107.12 OF THE STANDARD SPECIFICATIONS.
5. ALL TREES THAT DO NOT DIRECTLY INTERFERE WITH THE PROPOSED CONSTRUCTION SHALL BE SPARED AS DIRECTED BY THE ENGINEER. CARE AND DISCRETION SHALL BE USED TO INSURE THAT ALL TREES NOT TO BE REMOVED SHALL BE HARMED AS LITTLE AS POSSIBLE DURING THE CONSTRUCTION OPERATIONS.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A FENCE TO CONTROL LIVESTOCK IN AREAS WHERE PASTURES ARE SEVERED. WIRE FENCE MAY BE CONSTRUCTED INITIALLY, OR IN LIEU THEREOF, THE CONTRACTOR AT HIS OWN EXPENSE, MAY ELECT TO PROVIDE TEMPORARY FENCING SUITABLE TO CONTAIN LIVESTOCK.
7. ALL FLEXIBLE BASE AND ASPHALTIC PAVEMENTS REMOVED SHALL BE PAID FOR UNDER THE ITEM NO. 210 - UNCLASSIFIED EXCAVATION.
8. THE EXISTING ASPHALT PAVEMENT TO BE REMOVED FROM THE REMAINING PAVEMENT SHALL BE SEPARATED BY SAWING ALONG A NEAT LINE. AFTER SAWING, THE PAVEMENT TO BE REMOVED SHALL BE CAREFULLY REMOVED IN A MANNER THAT WILL NOT DAMAGE THE PAVEMENT THAT IS TO REMAIN. ANY DAMAGE OF THE ASPHALT PAVEMENT THAT IS TO REMAIN IN PLACE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	4	235

2 TYPICAL SECTIONS OF IMPROVEMENT




FULL-DEPTH RECONSTRUCTION - TANGENT SECTION

(SHOWN IN DIRECTION OF TRAFFIC)

STA. 175+90.50 TO 181+80.04 LT.	STA. 175+90.50 TO 181+80.04 RT.
STA. 231+73.40 TO 242+73.40 LT.	STA. 231+14.91 TO 242+14.91 RT.
STA. 245+91.81 TO 250+73.89 LT.	STA. 245+33.30 TO 250+73.89 RT.
STA. 333+87.17 TO 344+87.14 LT.	STA. 333+48.36 TO 344+48.36 RT.
STA. 347+41.62 TO 358+41.62 LT.	STA. 347+02.80 TO 358+08.81 RT.
STA. 437+40.77 TO 447+40.77 LT.	STA. 438+24.82 TO 448+24.82 RT.

- NOTES:
1. AGGREGATE BASE COURSE (CLASS II) SHALL BE UNIFORMLY COMPACTED, STABLE, AND FREE OF SEGREGATED AREAS. THE DENSITY REQUIREMENTS OF SECTION 303 ARE WAIVED.
 2. THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.
 3. THE THICKNESS OF AGGREGATE BASE COURSE SHALL BE WITHIN PLUS OR MINUS ONE INCH OF THE PLAN THICKNESS SHOWN. THE CONTRACTOR WILL CORRECT ANY DEFICIENT THICKNESS THAT DOES NOT MEET TOLERANCE INDICATED. PAYMENT WILL NOT BE MADE FOR MATERIAL PLACED IN EXCESS OF THE TOLERANCE INDICATED.


*** ON ALL SUPERELEVATED CURVES AND THROUGH SUPERELEVATION TRANSITIONS, THE ALGEBRAIC DIFFERENCE BETWEEN PAVEMENT SLOPE AND SHOULDER SLOPE SHALL NOT EXCEED 0.08'/'.



FULL-DEPTH RECONSTRUCTION - SUPERELEVATED SECTION


STA. 175+14.73 TO 175+90.50 LT.	STA. 175+14.73 TO 175+90.50 RT.
STA. 181+80.04 TO 186+14.73 LT.	STA. 181+80.04 TO 186+14.73 RT.
STA. 250+73.89 TO 256+91.81 LT.	STA. 250+73.89 TO 256+33.30 RT.

TYPICAL SECTIONS OF IMPROVEMENT



6/20/2016 12:06:23 PM
 LEONARD SPEED
 WORKSPACE: C:\Users\leonard.s\Documents\Projects\BBO202\04_TS_MAIN_01.dgn
 Y:\Projects\BBO202\04_TS_MAIN_01.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	5
						TYPICAL SECTIONS OF IMPROVEMENT		



STA. 211+49.38 TO 231+73.40 LT. STA. 211+49.38 TO 231+14.91 RT.

STA. 267+25.57 TO 333+87.14 LT. STA. 267+25.57 TO 333+48.36 RT.


STA. 358+41.62 TO 358+48.43 LT. STA. 358+08.81 TO 358+48.43 RT.

STA. 377+60.20 TO 437+40.77 LT. STA. 377+60.20 TO 438+24.82 RT.

*LEVELING TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER & TO CORRECT SUPERELEVATION OF CONCRETE BASE LAYER.

***ON ALL SUPERELEVATED CURVES AND THROUGH SUPERELEVATION TRANSITIONS, THE ALGEBRAIC DIFFERENCE BETWEEN PAVEMENT SLOPE AND SHOULDER SLOPE SHALL NOT EXCEED 0.08'/'.
MATCH POINT FOR ACCELERATION LANES (SEE ACCELERATION LANE SECTION).


- NOTES:
- AGGREGATE BASE COURSE (CLASS II) SHALL BE UNIFORMLY COMPACTED, STABLE, AND FREE OF SEGREGATED AREAS. THE DENSITY REQUIREMENTS OF SECTION 303 ARE WAIVED.
 - ASPHALT FOR LEVELING OF EXISTING PAVEMENT SHALL BE PLACED ONLY IF AND WHERE DIRECTED BY THE ENGINEER. CALCULATIONS FOR THE AMOUNT OF LEVELING AND/OR LEVELING OPERATIONS SHALL BE PERFORMED BEFORE CONSTRUCTING NOTCH AND WIDENING. CALCULATIONS WILL NOT BE PAID FOR DIRECTLY, BUT PAYMENT WILL BE CONSIDERED INCLUDED IN THE VARIOUS PAY ITEMS.
 - THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.



STA. 186+14.73 TO 211+49.38 LT. STA. 186+14.73 TO 211+49.38 RT.

STA. 256+91.81 TO 267+25.57 LT. STA. 256+93.30 TO 267+25.57 RT.


STA. 358+48.43 TO 377+60.20 LT. STA. 358+48.43 TO 377+60.20 RT.



Leonard.Speed 6/20/2016 12:06:24 PM
WORKSPACE: Leonard.Speed
I:\Projects\15825\15825_1\30_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_04_TS_MAIN_02.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.		6	235

② TYPICAL SECTIONS OF IMPROVEMENT



**ACCELERATION LANE & TAPER
FULL DEPTH RECONSTRUCTION SECTION**
(SHOWN IN DIRECTION OF TRAFFIC)

STA. 175+78.49 TO STA. 185+78.49
STA. 231+73.40 TO STA. 232+54.01
STA. 256+08.85 TO STA. 256+33.30




**ACCELERATION LANE & TAPER
RUBBLIZE & OVERLAY SECTION**
(SHOWN IN DIRECTION OF TRAFFIC)

STA. 222+54.01 TO STA. 231+73.40
STA. 256+33.30 TO STA. 266+08.85
STA. 322+54.09 TO STA. 332+54.09
STA. 359+12.68 TO STA. 369+12.68
STA. 425+76.51 TO STA. 435+76.51

* LEVELING TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER.

NOTES:


1. AGGREGATE BASE COURSE (CLASS I) SHALL BE UNIFORMLY COMPACTED, STABLE, AND FREE OF SEGREGATED AREAS. THE DENSITY REQUIREMENTS OF SECTION 303 ARE WAIVED.
2. ASPHALT FOR LEVELING OF EXISTING PAVEMENT SHALL BE PLACED ONLY IF AND WHERE DIRECTED BY THE ENGINEER. CALCULATIONS FOR THE AMOUNT OF LEVELING AND/OR LEVELING OPERATIONS SHALL BE PERFORMED BEFORE CONSTRUCTING NOTCH AND WIDENING. CALCULATIONS WILL NOT BE PAID FOR DIRECTLY, BUT PAYMENT WILL BE CONSIDERED INCLUDED IN THE VARIOUS PAY ITEMS.
3. THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.
4. THE THICKNESS OF AGGREGATE BASE COURSE SHALL BE WITHIN PLUS OR MINUS ONE INCH OF THE PLAN THICKNESS SHOWN. THE CONTRACTOR WILL CORRECT ANY DEFICIENT THICKNESS THAT DOES NOT MEET TOLERANCE INDICATED. PAYMENT WILL NOT BE MADE FOR MATERIAL PLACED IN EXCESS OF THE TOLERANCE INDICATED.




Leonard.Speed 6/20/2016 12:06:25 PM
WORKSPACE: Leonard.Speed
Y:\Projects\VAHFD_158215-1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Dr-awings\BBO202_04_TS_MAIN_03.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							7	235


② TYPICAL SECTIONS OF IMPROVEMENT



MAIN LANE TEMP. CROSSOVER FOR MAINTENANCE OF TRAFFIC




TEMPORARY INTERCHANGE RAMPS FOR MAINTENANCE OF TRAFFIC



TRENCH AND SHOULDER PREPARATION FOR MAINTENANCE OF TRAFFIC (SOUTHBOUND MAIN LANES INSIDE SHOULDER)


STA. 172+60.00 TO STA. 242+69.57 RT. - L.M.L.
 STA. 245+71.26 TO STA. 344+84.63 RT. - L.M.L.
 STA. 347+27.99 TO STA. 447+69.33 RT. - L.M.L.

- NOTES:
1. THE FINAL 2" OF SURFACE COURSE IS TO BE PLACED AFTER ALL OTHER COURSES HAVE BEEN LAID. LONGITUDINAL JOINTS SHALL BE AT LANE LINES.
 2. ALL FLEXIBLE BASE AND ASPHALTIC PAVEMENTS REMOVED SHALL BE PAID FOR UNDER ITEM NO. 210 - UNCLASSIFIED EXCAVATION.
 3. THE EXISTING ASPHALT PAVEMENT TO BE REMOVED FROM THE REMAINING PAVEMENT SHALL BE SEPARATED BY SAWING ALONG A NEAT LINE. AFTER SAWING, THE PAVEMENT TO BE REMOVED SHALL BE CAREFULLY REMOVED IN A MANNER THAT WILL NOT DAMAGE THE PAVEMENT THAT IS TO REMAIN. ANY DAMAGE OF THE ASPHALT PAVEMENT THAT IS TO REMAIN IN PLACE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.



Leonard.Speed 6/20/2016 12:06:26 PM
 WORKSPACE: Leonard.Speed
 I:\Projects\158215\1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_04_TS_Main_04.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	8
						TYPICAL SECTIONS OF IMPROVEMENT		




TEMPORARY ACCELERATION LANE FOR MAINTENANCE OF TRAFFIC - LEFT (SB) MAIN LANES

STA. 175+64.09 TO STA. 186+82.41
 STA. 255+82.62 TO STA. 270+14.81
 STA. 359+39.03 TO STA. 372+96.78

TEMPORARY ACCELERATION LANE FOR MAINTENANCE OF TRAFFIC - RIGHT (NB) MAIN LANES

STA. 216+75.00 TO STA. 232+07.91
 STA. 318+79.10 TO STA. 332+18.71
 STA. 422+00.86 TO STA. 435+51.48

- NOTES:
1. CONSTRUCT ACCELERATION LANES TO LIMITS INDICATED IN THE MAINTENANCE OF TRAFFIC PLANS.
 2. CONSTRUCT RUMBLE STRIPS ON NB LANES AFTER TEMPORARY CROSSOVERS AND TEMPORARY RAMPS HAVE BEEN REMOVED.
 3. ALL FLEXIBLE BASE AND ASPHALTIC PAVEMENTS REMOVED SHALL BE PAID FOR UNDER THE ITEM NO. 210 - UNCLASSIFIED EXCAVATION.
 4. ANY EXISTING CONCRETE, GRAVEL, OR ASPHALT PAVEMENT TO BE REMOVED FROM THE REMAINING PAVEMENT SHALL BE SEPARATED BY SAWING ALONG A NEAT LINE. AFTER SAWING, THE PAVEMENT TO BE REMOVED SHALL BE CAREFULLY REMOVED IN A MANNER THAT WILL NOT DAMAGE THE PAVEMENT THAT IS TO REMAIN. ANY DAMAGE OF THE CONCRETE PAVEMENT THAT IS TO REMAIN IN PLACE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.




SHOULDER REHAB. TYPICAL FOR RAMPS




6/20/2016 12:06:27 PM
 Leonar-d.Speed
 WORKSPACE: Leonar-d.Speed
 I:\PROJECTS\AR\10_152625_1\30_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_04_TS_MAIN_05.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							9	235


② SPECIAL DETAILS




TYPICAL SECTION OF IMPROVEMENT FOR WIRE ROPE SAFETY FENCE LEFT OF CENTERLINE




TYPICAL SECTION OF IMPROVEMENT FOR WIRE ROPE SAFETY FENCE RIGHT OF CENTERLINE



SECTION OF APPROACH SLAB






DETAIL FOR THE MAINTENANCE OF EXISTING BREAKAWAY SIGN STRUCTURES



SPECIAL DETAILS


L:\proj\152016 6/20/2016 12:06:28 PM
 L:\proj\152016 6/20/2016 12:06:28 PM
 Y:\Projects\152016\152016-1530-Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_05_SD_MAIN_01.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	IO 235
② SPECIAL DETAILS								





NOTES:

1. ALIGNMENT OF RUMBLE STRIPS SHALL GENERALLY BE STRAIGHT AND OFFSET APPROXIMATELY 4" FROM THE OUTER EDGE OF THE EDGE LINE. THIS OFFSET MAY BE ADJUSTED TO ACCOMMODATE VARIATIONS IN THE EDGE LINE AS WELL AS TO AVOID EXISTING LONGITUDINAL JOINTS.
2. THE 1/2" DEPTH SHALL GENERALLY APPLY FOR THE ENTIRE 16" LENGTH. SOME VARIATION TO SUIT SHOULDER SLOPE BREAKS MAY BE NECESSARY.
3. RUMBLE STRIPS SHALL NOT BE INSTALLED ON BRIDGE DECKS, APPROACH SLABS, OR ACROSS TRANSVERSE JOINTS OF CONCRETE SHOULDERS.



2' STRIP TO BE MILLED & INLAID WITH ACHM SURFACE COURSE (1/2") (PG 76-22) (220 LBS. PER SQ. YD.) & 2'-0" TACK COAT (0.17 GAL. PER SQ. YD.)


ELEVATION VIEW



DETAILS OF RUMBLE STRIPS

LOCATION PLAN OF RUMBLE STRIPS LEFT OR RIGHT SHOULDER

DETAIL OF RUMBLE STRIP REMOVAL IN INSIDE AND OUTSIDE SHOULDERS (ASPHALT)




Leonor d Speed 6/20/2016 12:06:23 PM
 WORKSPACE: Leonor d Speed
 Y:\Projects\BIDD\138215-1-530-Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_05_SD_MAIN_02.dgn



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.		II	235
				JOB NO. BBO202				

② SPECIAL DETAILS




DETAIL OF TRANSITION & FULL DEPTH PAVEMENT REPLACEMENT AT EXISTING BRIDGE ENDS

- (2) STA. 231+73.40 TO STA. 242+73.40 LT.
- (2) STA. 245+91.81 TO STA. 256+91.81 LT.
- (2) STA. 333+87.14 TO STA. 344+87.17 LT.
- (2) STA. 347+41.62 TO STA. 358+41.62 LT.
- (1) STA. 437+40.77 TO STA. 447+40.77 LT.
- (2) STA. 231+14.91 TO STA. 242+14.91 RT.
- (2) STA. 245+33.30 TO STA. 256+33.30 RT.
- (2) STA. 333+48.36 TO STA. 344+48.36 RT.
- (2) STA. 347+08.81 TO STA. 358+08.81 RT.
- (1) STA. 438+24.82 TO STA. 448+24.82 RT.

** THE HWY. 104 MAIN LANE OVERPASS BRIDGES WERE HYDRODEMOLISHED (1/2" SURFACE REMOVAL) AND OVERLAID (1/2" CONCRETE) IN JOB BBO201. THIS WILL RESULT IN A NET GAIN OF ONE INCH ELEVATION AT THE BRIDGE DECK AND APPROACH SLABS, RESULTING CUT DEPTH AND LENGTH WILL BE 3 IN. AND 300 FT., RESPECTIVELY.

	(1) HWY. 104 OVERPASS	(2) HWY. 270 & HOLLAND AVE. OVERPASSES
* LENGTH OF TRANSITION (FT)	1000	1100

Leonard.Speed 6/20/2016 2:29:09 PM
WORKSPACE: Leonard.Speed
I:\Projects\158205\1530-Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05_SD_Main_03.dgn




DETAIL OF TRANSITION TO EXISTING PAVEMENT SECTION AT BEGINNING OF PROJECT

STA. 175+14.73 TO STA. 186+14.73



SPECIAL DETAILS


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							12	235
2 SPECIAL DETAILS								



TRANSITION FROM RUBBLIZE AND OVERLAY TO INTERCHANGE RAMP

HOLLAND AVE. RAMP 2 STA. 353+63.40 TO STA. 359+13.40
 HOLLAND AVE. RAMP 3 STA. 353+30.27 TO STA. 358+80.27
 HOLLAND AVE. RAMP 4 STA. 332+54.25 TO STA. 338+04.25
 HWY. 104 RAMP 4 STA. 435+75.68 TO STA. 441+25.68

NOTE:
 PLACE AGGREGATE BASE COURSE (CLASS 7) TO RAISE THE GRADE OF THE RAMP SHOULDERS IN THE PAVING TRANSITION AREAS.



TRANSITION FROM FULL DEPTH PAVEMENT TO INTERCHANGE RAMP

	"A" (IN.)	"B" (FT.)	"C" (LBS./SQ. YD.)
HWY. 270 RAMP 1 STA. 232+09.90 TO STA. 237+12.60	6.05	202.70	442.97
HWY. 270 RAMP 2 STA. 250+67.11 TO STA. 256+04.89	6.76	237.78	481.55
HWY. 270 RAMP 3 STA. 251+25.45 TO STA. 256+49.50	6.48	224.05	466.46
HWY. 270 RAMP 4 STA. 232+53.30 TO STA. 237+63.00	6.19	209.70	450.66
HOLLAND AVE. RAMP 1 STA. 335+08.82 TO STA. 339+77.53	5.37	168.71	405.58
HWY. 104 RAMP 1 STA. 439+61.27 TO STA. 444+43.24	5.64	181.97	420.17


NOTE:
 PLACE AGGREGATE BASE COURSE (CLASS 7) TO RAISE THE GRADE OF THE RAMP SHOULDERS IN THE PAVING TRANSITION AREAS.



Leonard.Speed 6/20/2016 12:06:31 PM
 WORKSPACE: Leonard.Speed
 I:\Projects\AR\15825\1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05_SD_MAIN_04.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO. BB0202	13	235

2 SPECIAL DETAILS




NOTE:
REFER TO "WIRE ROPE SAFETY FENCE (WRSF) SPECIFICATIONS" SPECIAL PROVISION FOR ADDITIONAL REQUIREMENTS.


THREADED TERMINAL DETAIL



SECTION DETAIL OF SHOULDER WIDENING FOR GUARDRAIL & OVERLAP ENDS OF WIRE ROPE SAFETY FENCE - INSIDE SHOULDER
REFER TO STANDARD DRAWINGS GR-8, GR-9, GR-9A, GR-10, GR-10A FOR ADDITIONAL INFORMATION.



DETAIL FOR SOLID SODDING AROUND DROP INLETS



DETAIL OF WIRE ROPE SAFETY FENCE AT EXISTING BRIDGE ENDS


REFER TO PLANS FOR RELATIVE PLACEMENT OF GUARDRAIL AND WIRE ROPE SAFETY FENCE AT EACH BRIDGE END.



SPECIAL DETAILS

Leonard.Speed 6/20/2016 12:06:31 PM
WORKSPACE: Leonard.Speed
I:\PROJECTS\AR\10158255\1-330_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05_SD_MAIN_05.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							14	235
② SPECIAL DETAILS								



** PARAPET WALL WITH THRIE BEAM GUARDRAIL CONNECTION AT BRIDGE. SEE STD. DWG. GR-10.

GUARDRAIL DETAIL FOR MAIN LANES AT HWY. 104 OVERPASS


NOTE: REFER TO STANDARD DRAWINGS GR-8, GR-8A, GR-9, GR-10 & GR-10A FOR ADDITIONAL INFORMATION.




** PARAPET WALL WITH THRIE BEAM GUARDRAIL CONNECTION AT BRIDGE. SEE STD. DWG. GR-10.

GUARDRAIL DETAIL FOR MAIN LANES AT HWY. 270 AND HOLLAND AVE. OVERPASSES

NOTE: REFER TO STANDARD DRAWINGS GR-8, GR-8A, GR-9, GR-10 & GR-10A FOR ADDITIONAL INFORMATION.




GUARDRAIL DETAIL FOR MAIN LANES AT OVERHEAD SIGN STRUCTURE (STA. 212+20)




WIDENING FOR GUARDRAIL

NOTE: REFER TO STANDARD DRAWINGS GR-8, GR-8A, GR-9, GR-10 & GR-10A FOR ADDITIONAL INFORMATION.




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	15
						SPECIAL DETAILS		

DETAILS OF PIPE UNDERDRAINS




NOTE: GEOTEXTILE FABRIC SHALL MEET THE REQUIREMENTS OF SECTION 625 FOR TYPE I.

IN LIEU OF LAPPING THE GEOTEXTILE FABRIC, THE CONTRACTOR MAY (WITH APPROVAL OF THE ENGINEER) UTILIZE AN ALTERNATE METHOD FOR PROVIDING POSITIVE CLOSURE.




SECTION A-A FULL DEPTH CONSTRUCTION



SECTION A-A RUBBLIZE & OVERLAY

NOTES FOR PIPE UNDERDRAINS


1. GEOTEXTILE FABRIC SHALL MEET THE REQUIREMENTS OF SECTION 625 FOR TYPE I. PAYMENT FOR GEOTEXTILE FABRIC AND GRANULAR FILTER MATERIAL SHALL BE INCLUDED IN THE PRICE BID PER LIN. FT. FOR "4" PIPE UNDERDRAINS" IN ACCORDANCE WITH SECTION 611 OF THE STANDARD SPECIFICATIONS.
2. 4" NON-PERFORATED SCHEDULE 40 PVC PIPE LATERALS WITH OUTLET PROTECTORS SHALL BE INSTALLED AS SHOWN HEREON OR AS ON STD. DWG. PU-1. LATERALS WILL BE MEASURED AND PAID FOR AS "4" PIPE UNDERDRAINS." UNDERDRAIN OUTLET PROTECTORS WILL BE MEASURED AND PAID FOR BY THE UNIT IN ACCORDANCE WITH SECTION 611 OF THE STANDARD SPECIFICATIONS.
3. 4" PIPE UNDERDRAINS SHALL BE PLACED ON THE LOW SIDE OF SUPERELEVATED ROADWAYS AS SHOWN ON THE TYPICAL SECTIONS. 4" PIPE UNDERDRAINS SHALL BE CONNECTED TO MEDIAN DROP INLETS WHERE DIRECTED BY THE ENGINEER. PAYMENT FOR CONNECTING TO DROP INLETS SHALL BE CONSIDERED INCLUDED IN THE PRICE BID FOR "4" PIPE UNDERDRAINS."
4. THE LOCATION OF ALL LATERALS SHALL BE MARKED WITH 4" X 12" PERMANENT PAVEMENT MARKING TAPE (TYPE III WHITE) AT THE OUTSIDE EDGE OF THE SHOULDER, PLACED TRANSVERSE TO TRAFFIC. PAYMENT SHALL BE CONSIDERED INCLUDED IN THE PRICE BID FOR THE VARIOUS CONTRACT ITEMS.
5. THE RODENT SCREEN SHOWN HEREON SHALL BE USED IN LIEU OF THE RODENT SCREEN SHOWN ON STD. DWG. PU-1. PAYMENT FOR THE RODENT SCREEN SHALL BE INCLUDED IN THE PRICE BID PER EACH FOR "UNDERDRAIN OUTLET PROTECTORS."
6. ANY EXISTING UNDERDRAINS THAT INTERFERE WITH INSTALLATION OF THE NEW UNDERDRAIN SYSTEM SHALL BE REMOVED AND DISPOSED OF AS DIRECTED BY THE ENGINEER. PAYMENT FOR LATERALS TO BE REMOVED OR ABANDONED SHALL BE CONSIDERED INCLUDED IN THE PRICE BID FOR THE VARIOUS CONTRACT ITEMS.
7. AT LOCATIONS WHERE A SINGLE LATERAL IS USED, THE CONTRACTOR SHALL HAVE THE FOLLOWING OPTIONS: 1.) INSTALL OUTLET PROTECTOR AS SHOWN ON STANDARD DRAWING PU-1 AND GROUT THE UNUSED HOLE OR 2.) INSTALL AN OUTLET PROTECTOR WITH A SINGLE HOLE. PAYMENT SHALL BE INCLUDED IN THE PRICE BID EACH FOR "UNDERDRAIN OUTLET PROTECTORS."
8. 4" PIPE UNDERDRAIN SHALL BE PLACED SUCH THAT POSITIVE DRAINAGE IS ACHIEVED.



PLAN DETAIL OF PIPE UNDERDRAIN LATERALS


NOTE: PVC PIPE FOR LATERALS SHALL MEET THE REQUIREMENTS OF ASTM D 1785 (LATEST REVISION) FOR SCHEDULE 40 PIPE. UNDERDRAIN OUTLET PROTECTORS SHALL BE INSTALLED ON NEW LATERALS. (REFER TO STD. DWG. PU-1. & NOTE #5.)

FOR WIDTH OF EXISTING SHOULDER, TRENCH FOR LATERALS SHALL BE BACKFILLED WITH GRANULAR MATERIAL OR AGGREGATE BASE COURSE (CLASS 7). PAYMENT SHALL BE INCLUDED IN THE PRICE BID FOR THE VARIOUS CONTRACT ITEMS.





DETAIL OF RODENT SCREEN


Leonard Speed 6/20/2016 12:06:33 PM WORKSPACE: Leon... 1:17:00:18 W:\10152825-1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_05_SD_MAIN_07.dgn




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	16
						2 SPECIAL DETAILS		



DETAILS OF SHOULDER WIDENING FOR GUARDRAIL AND OVERLAPS WITH ENDS OF WIRE ROPE SAFETY FENCE



DETAIL OF NORTHBOUND GUARDRAIL & WIRE ROPE SAFETY FENCE AT OVERHEAD SIGN STRUCTURE (STA. 189+78.00)



DETAIL OF SOUTHBOUND GUARDRAIL AT OVERHEAD SIGN STRUCTURE (STA. 189+78.00)

REFER TO PLANS FOR RELATIVE PLACEMENT OF GUARDRAIL AND WIRE ROPE SAFETY FENCE



Leoner.dSpeed 6/20/2016 12:06:34 PM
 WORKSPACE: c:\prowork\138225\1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_05_SD_MAIN_08.dgn
 Y:\Projects\138225\1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_05_SD_MAIN_08.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BBO202	17	235	

② SPECIAL DETAILS

JOINT CONFIGURATION FOR TYPE 3 & 4 JOINT SEALANT

JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/4	3/8	1/2
3/8	1/4	1/2	1/2
1/2	1/4	5/8	1/2
5/8	5/16	3/4	9/16
3/4	3/8	7/8	7/8
4/8	7/16	1	11/16
1	1/2	1 1/4	3/4
1 TO 1 1/2	1/2	1 1/4*	3/4

NOTE: JOINTS GREATER THAN 1 1/2' IN WIDTH SHALL BE SEALED WITH TYPE 5 JOINT SEALANT.




DETAILS OF TYPE A OR TYPE B JOINT REHABILITATION

* CONTRACTION JOINTS SHALL BE SAWED TO MIN. WIDTH OF 3/8". WARPING & LONGITUDINAL JOINTS SHALL BE SAWED TO MIN. WIDTH OF EXISTING WIDTH + 1/8" (1/16" ON EACH SIDE).

JOINT CONFIGURATION FOR TYPE 5 JOINT SEALANT

JOINT WIDTH	APPROX. WIDTH TO DEPTH RATIO	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES				
1/4	1:2	1/2	3/8	3/4
3/8		3/4	1/2	1
1/2		1	5/8	1 1/4
5/8	1:1.75	1 1/4	3/4	1 1/2
3/4		1 3/8	7/8	1 5/8
7/8	1:1.6	1 1/2	1	1 3/4
1		1 5/8	1 1/4	1 7/8
1 TO 3		1 5/8*	1 1/4*	1 7/8*



** WARPING & LONGITUDINAL JOINTS SHALL BE SAWED TO MIN. WIDTH OF EXISTING WIDTH + 1/8" (1/16" ON EACH SIDE).

NOTE: FOR JOINTS WIDER THAN 1 1/2", THE CONTRACTOR SHALL HAVE THE OPTION OF COMPLETELY FILLING THE JOINT IN LIEU OF USING A BACKER ROD.


DETAILS OF TYPE B JOINT REHABILITATION

REFER TO SECTION 509 OF THE STANDARD SPECIFICATIONS FOR ADDITIONAL INFORMATION.




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							18	235


SPECIAL DETAILS




SECTION A-A
TIED LONGITUDINAL JOINT



SECTION D-D
LOCKED JOINT




PLAN OF PAVEMENT REPAIR
(FULL SLABS)




DETAIL OF SAWED FREE TRANSVERSE &
FREE LONGITUDINAL JOINT

TYPICAL SLAB REPLACEMENT EXAMPLES


SLAB(S) TO BE RECONSTRUCTED	TYPE OF JOINT TO BE CONSTRUCTED					
	JOINT 1	JOINT 2	JOINT 3	JOINT 4	JOINT 5	JOINT 6
A OR D	LOCKED	FREE	LOCKED	LOCKED	FREE	LOCKED
B OR E	FREE	FREE	LOCKED	LOCKED	FREE	LOCKED
A & B OR D & E	LOCKED	CONTRACTION	LOCKED	LOCKED	CONTRACTION	LOCKED
B & C	FREE	FREE	WARPIING	LOCKED	WARPIING	LOCKED
B, C & D	FREE	FREE	WARPIING	WARPIING	FREE	LOCKED
C			LOCKED	LOCKED		




SECTION E-E
FREE TRANSVERSE JOINT




PLAN OF PAVEMENT REPAIR
(PARTIAL SLABS)




DETAIL OF SAWED CONTRACTION JOINT




DETAIL OF SAWED TIED LONGITUDINAL JOINT AND WARPIING JOINT



SECTION B-B
WARPIING JOINT



SECTION C-C
ONE-HALF 24' PAVEMENT
12 DOWELS
PLAN - CONTRACTION JOINT




SECTION F-F
FREE LONGITUDINAL JOINT

JOINT CONFIGURATION FOR TYPE 3 OR 4 JOINT SEALANT

JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/4	3/8	1/2
3/8	1/4	1/2	1/2
1/2	1/4	5/8	1/2

JOINT CONFIGURATION FOR TYPE 5 OR 7 JOINT SEALANT

JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/2	3/8	3/4
3/8	3/4	1/2	1



DETAIL OF EPOXY RETENTION DISK


NOTES FOR PAVEMENT REPAIR

- EXACT SIZE AND LOCATION OF AREA TO BE REPAIRED SHALL BE DETERMINED BY THE ENGINEER. ALL PATCHES SHALL EXTEND ACROSS THE FULL WIDTH OF THE SLAB AS SHOWN IN THESE DETAILS.
- THE FINAL SURFACE FINISH FOR PATCHES SHALL MATCH THAT OF THE EXISTING PAVEMENT.
- WHEN AREA TO BE REPAIRED INCLUDES AN EXISTING JOINT, THE JOINT SHALL BE RECONSTRUCTED TO THE CONFIGURATION SHOWN IN THESE DETAILS.
- ALL REPAIRED AREAS SHALL BE REINFORCED WITH MESH FABRIC AS SHOWN. DEPTH OF MESH PLACEMENT SHALL HAVE A TOLERANCE OF +1 INCH. MESH FABRIC SHALL BE 12 X 12 - W4 X W4 WELDED WIRE FENCE (MINIMUM WIRE SIZE). LAPS SHALL BE MINIMUM 6" IN EACH DIRECTION. MINIMUM COVER AT EDGES SHALL BE 2".
- FORMS FOR PAVEMENT REPAIR SHALL BE METAL UNLESS OTHERWISE APPROVED BY THE ENGINEER.
- CLOSED CELL POLYETHYLENE FOAM SHALL BE SECURED TO SAWED FACE OF EXISTING P.C.C. PAVEMENT WITH ADHESIVE OR ADHESIVE TAPE AS APPROVED BY THE ENGINEER AND TRIMMED FLUSH WITH TOP OF EXISTING SLAB TO PREVENT DISPLACEMENT WHEN THE PATCH IS BEING PLACED.
- WHEN THE PATCH IS PLACED OVER GRANULAR BASE, REMOVE ANY LOOSE BASE MATERIAL. COMPACT REMAINING BASE AS NECESSARY AND PLACE PATCH. WHEN PATCH IS PLACED OVER TREATED BASE, REMOVE ANY LOOSE BASE MATERIAL AND PLACE PATCH.
- 1/4" THICK, COMPRESSIBLE MATERIAL SHALL BE ATTACHED TO THE ENDS OF DOWEL BARS AT ALL FREE TRANSVERSE JOINTS (SEE SECTION E-E). THE MATERIAL SHALL BE THE SAME DIAMETER AS THE DOWEL BAR. A PLASTIC CAP OF OTHER TYPE OF DEVICE MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
- DOWEL BARS SHALL BE PLACED IN ACCORDANCE WITH THE DIMENSIONS SHOWN. A TOLERANCE OF PLUS OR MINUS ONE INCH WILL BE ALLOWED FOR VERTICAL AND LATERAL PLACEMENT AND A TOLERANCE OF PLUS OR MINUS 1/4" WILL BE ALLOWED FOR THE TILT AND SKEW.




DETAILS OF PORTLAND CEMENT
CONCRETE PAVEMENT PATCHING
(MAIN LANES)


Leonard Speed 6/20/2016 12:06:35 PM
WORKSPACE: Leonard.Speed
Y:\Projects\AHTD_138215_1\530 Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05_SD_MAIN.dwg




SECTION B-B
WARPING JOINT



SECTION D-D




PLAN OF PAVEMENT REPAIR
(FULL SLABS)




SECTION E-E
FREE TRANSVERSE JOINT

TYPICAL SLAB REPLACEMENT EXAMPLES


SLAB(S) TO BE RECONSTRUCTED	TYPE OF JOINT TO BE CONSTRUCTED					
	JOINT 1	JOINT 2	JOINT 3	JOINT 4	JOINT 5	JOINT 6
A OR D	LOCKED	FREE	LOCKED	LOCKED	FREE	LOCKED
B OR E	LOCKED	FREE	LOCKED	LOCKED	FREE	LOCKED
A & B OR D & E	LOCKED	CONTRACTION	LOCKED	LOCKED	CONTRACTION	LOCKED
B & C		FREE	WARPING	LOCKED		LOCKED
B, C & D		FREE	WARPING	WARPING	FREE	
C			LOCKED	LOCKED		




DETAIL OF SAWED CONTRACTION JOINT




SECTION C-C




PLAN OF PAVEMENT REPAIR
(PARTIAL SLABS)



DETAIL OF SAWED FREE TRANSVERSE JOINT




DETAIL OF SAWED WARPING JOINT



15' PAVEMENT
15 DOWELS
PLAN - CONTRACTION JOINT

NOTE: FOR 15' PAVEMENT USE 15 DOWELS @ 12' CTRS. WITH 6" SPACING FROM C.L. AND EDGE OF SLAB TO FIRST BAR. FOR PAVEMENT WIDTHS OTHER THAN THOSE SHOWN ABOVE, USE DOWELS AT 12' CTRS. WITH 6" MAX. SPACING FROM C.L. TO FIRST BAR. DISTANCE FROM EDGE OF SLAB TO FIRST BAR SHALL BE ADJUSTED TO MAINTAIN 12" DOWEL BAR SPACING

CONTRACTION JOINT DETAILS



DETAIL OF EPOXY
RETENTION DISK

NOTE: EPOXY RETENTION DISK SHALL BE SLIPPED TIGHTLY OVER TIE BARS AND FIRMLY AGAINST THE SLAB FACE AFTER INSERTING TIE BAR AND EPOXY INTO HOLE

NOTES FOR PAVEMENT REPAIR

- EXACT SIZE AND LOCATION OF AREA TO BE REPAIRED SHALL BE DETERMINED BY THE ENGINEER. ALL PATCHES SHALL EXTEND ACROSS THE FULL WIDTH OF THE SLAB AS SHOWN IN THESE DETAILS.
- THE FINAL SURFACE FINISH FOR PATCHES SHALL MATCH THAT OF THE EXISTING PAVEMENT.
- WHEN AREA TO BE REPAIRED INCLUDES AN EXISTING JOINT, THE JOINT SHALL BE RECONSTRUCTED TO THE CONFIGURATION SHOWN IN THESE DETAILS.
- ALL REPAIRED AREAS SHALL BE REINFORCED WITH MESH FABRIC AS SHOWN. DEPTH OF MESH PLACEMENT SHALL HAVE A TOLERANCE OF +1/4 INCH. MESH FABRIC SHALL BE 12 X 12 - W4 X W4 WELDED WIRE FENCE (MINIMUM WIRE SIZE). LAPS SHALL BE MINIMUM 6" IN EACH DIRECTION. MINIMUM COVER AT EDGES SHALL BE 2". FORMS FOR PAVEMENT REPAIR SHALL BE METAL UNLESS OTHERWISE APPROVED BY THE ENGINEER.
- CLOSED CELL POLYETHYLENE FOAM SHALL BE SECURED TO SAWED FACE OF EXISTING P.C.C. PAVEMENT WITH ADHESIVE OR ADHESIVE TAPE AS APPROVED BY THE ENGINEER AND TRIMMED FLUSH WITH TOP OF EXISTING SLAB TO PREVENT DISPLACEMENT WHEN THE PATCH IS BEING PLACED.
- WHEN THE PATCH IS PLACED OVER GRANULAR BASE, REMOVE ANY LOOSE BASE MATERIAL, COMPACT REMAINING BASE AS NECESSARY AND PLACE PATCH. WHEN PATCH IS PLACED OVER TREATED BASE, REMOVE ANY LOOSE BASE MATERIAL AND PLACE PATCH.
- 1/4" THICK, COMPRESSIBLE MATERIAL SHALL BE ATTACHED TO THE ENDS OF DOWEL BARS AT ALL FREE TRANSVERSE JOINTS (SEE SECTION E-E). THE MATERIAL SHALL BE THE SAME DIAMETER AS THE DOWEL BAR. A PLASTIC CAP OF OTHER TYPE OF DEVICE MAY BE USED WITH THE APPROVAL OF THE ENGINEER.
- DOWEL BARS SHALL BE PLACED IN ACCORDANCE WITH THE DIMENSIONS SHOWN. A TOLERANCE OF PLUS OR MINUS ONE INCH WILL BE ALLOWED FOR VERTICAL AND LATERAL PLACEMENT AND A TOLERANCE OF PLUS OR MINUS 1/4" WILL BE ALLOWED FOR THE TILT AND SKEW.

JOINT CONFIGURATION FOR TYPE 3 OR 4 JOINT SEALANT

JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/4	3/8	1/2
3/8	1/4	1/2	1/2
1/2	1/4	5/8	1/2


JOINT CONFIGURATION FOR TYPE 5 JOINT SEALANT

JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/2	3/8	3/4
3/8	3/4	1/2	1

DETAILS OF PORTLAND CEMENT CONCRETE PAVEMENT PATCHING FOR RAMPS



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
							20	235
② TEMPORARY EROSION CONTROL DETAILS								



STA. 179+50 LT. SEDIMENT BASIN (TYPE E-14) 202 CU. YDS.

STA. 178+40 TO STA. 180+00 LT. 160 L.F. SILT FENCE (TYPE E-11)

STA. 175+60 TO STA. 180+00 RT. 440 L.F. SILT FENCE (TYPE E-11)

STA. 178+50 LEACH SAND BAG DITCH CHECKS IN MEDIAN (TYPE E-5)

STA. 178+50 RT. SEDIMENT BASIN (TYPE E-14) 202 CU. YDS.

STA. 175+14.73
BEGIN JOB BB0202
LOG MILE 34.99


LEGEND

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= SEDIMENT BASIN (TYPE E-14)
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

REVISIONS

DATE OF REVISION	REVISION

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.





TEMPORARY EROSION CONTROL DETAILS - STAGE IA

Leonard.Speed 6/20/2016 2:29:18 PM
WORKSPACE: Leonard.Speed
Y:\Projects\ARB0202\ARB0202_05E-EC-IA-MAN_01.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						BB0202	21	235
②								TEMPORARY EROSION CONTROL DETAILS

STA. 180+00 TO STA. 181+16 LT.
116 L.F. SILT FENCE (TYPE E-II)

STA. 182+00 LT.
SEDIMENT BASIN (TYPE E-14)
911 CU. YDS.









STA. 189+19.90 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 180+00 TO STA. 184+25 RT.
425 L.F. SILT FENCE (TYPE E-II)

STA. 182+00 RT.
SEDIMENT BASIN (TYPE E-14)
911 CU. YDS.

LEGEND

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= SEDIMENT BASIN (TYPE E-14)
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

REVISIONS


DATE OF REVISION	REVISION

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



Leonard.Speed 6/20/2016 2:29:49 PM
W:\SP\ACE\Leonard.Speed\Projects\Roadway\04-Hwy65B-Deliverables\ROADWAY\Drawings\RB0202_05E-EC-IA-MAIN_02.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	22
						TEMPORARY EROSION CONTROL DETAILS		



Leoner.d.Speed 6/20/2016 2:29:20 PM
 Y:\P\06018\18101_152251_1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E.EC.IA-MAIN_03.dgn

REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	235
							BB0202	23
							TEMPORARY EROSION CONTROL DETAILS	

APPROXIMATE 100 YR. FLOODPLAIN LIMITS


STA. 213+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 217+00
1 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)



EXISTING R/W & C/A

EXISTING R/W & C/A



STA. 210+00 TO STA. 215+00
3 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(250' O.C.)

REVISIONS	
DATE OF REVISION	REVISION



LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



LeonardSpeed 6/20/2016 2:29:20 PM
 W:\SP\ACE\16000\Projects\BB0202\Drawings\Roadway\Drawings\BB0202_05E.LC.IA-MAIN_04.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	24	235	
				2 TEMPORARY EROSION CONTROL DETAILS				



STA. 226+00 IEACH SAND BAG DITCH CHECKS IN MEDIAN (TYPE E-5)

STA. 229+50 TO STA. 230+00 2 EACH SAND BAG DITCH CHECKS IN MEDIAN (TYPE E-5) (100' O.C.)


STA. 234+25 TO STA. 235+00 2 EACH SAND BAG DITCH CHECKS IN MEDIAN (TYPE E-5) (75' O.C.)

STA. 236+00 TO STA. 237+00 2 EACH SAND BAG DITCH CHECKS IN MEDIAN (TYPE E-5) (100' O.C.)

REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING



EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



TEMPORARY EROSION CONTROL DETAILS - STAGE IA

Leonard.Speed 6/20/2016 2:29:21PM WORKSPACE: Leonard.Speed 6/20/2016 2:29:21PM T:\Projects\14885_1\330_Hwy104-Hwy655\Deliverables\ROADWAY\Drawings\BB0202_05E-EC-IA-MAIN_05.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							25	235
② TEMPORARY EROSION CONTROL DETAILS								



Leonard.Speed 6/20/2016 2:29:22 PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\VAH10-15825-1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E-EC_IL-MAN_06.dgn


REVISIONS		LEGEND	
DATE OF REVISION	REVISION	Symbol	Description
		(E-5)	= SAND BAG DITCH CHECKS
		(E-7)	= DROP INLET SILT FENCE
		(E-11)	= SILT FENCE
		[Hatched Box]	= CONSTRUCTION AREA

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



TEMPORARY EROSION CONTROL DETAILS - STAGE IA


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
								26
								235
② TEMPORARY EROSION CONTROL DETAILS								



STA. 251+00 TO STA. 252+50
3 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(75' O.C.)

STA. 253+00 TO STA. 253+75
2 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(75' O.C.)

STA. 258+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)




REVISIONS	
DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.

APPROXIMATE 100 YR FLOODPLAIN LIMITS




TEMPORARY EROSION CONTROL DETAILS - STAGE IA

LeonardSpeed 6/20/2016 2:29:22 PM WORKSPACE: LeonardSpeed TRXProjects\AHTD_15825_1-530_Hwy104-Hwy65B-Deliverables\ROADWAY\Drawings\BB0202_08E-EC-IA-MAIN_07.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
							SHEET NO.	27
							TOTAL SHEETS	235


② TEMPORARY EROSION CONTROL DETAILS



STA. 264+40 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 272+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 273+00 TO STA. 279+00 LT.
612 L.F. SILT FENCE (TYPE E-II)



STA. 264+00 LEACH SAND
BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 268+00 LEACH SAND
BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

APPROXIMATE 100 YR.
FLOODPLAIN LIMITS

STA. 276+00 LEACH SAND
BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)


REVISIONS

DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA


EROSION CONTROL MEASURES PLACED IN
STAGE IA SHALL BE RETAINED THROUGHOUT
STAGE IB OR UNTIL FINAL STABILIZATION.



TEMPORARY EROSION CONTROL DETAILS - STAGE IA

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
							SHEET NO.	28
							TOTAL SHEETS	235


② TEMPORARY EROSION CONTROL DETAILS



REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
(E-5)	= SAND BAG DITCH CHECKS
(E-7)	= DROP INLET SILT FENCE
(E-11)	= SILT FENCE
[Hatched Box]	= CONSTRUCTION AREA

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



TEMPORARY EROSION CONTROL DETAILS - STAGE IA

Leonor d. Speed 6/20/2016 2:29:23 PM
 Y:\Projects\2016\06\04\Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_IA-MAIN_09.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	29	235	
(2) TEMPORARY EROSION CONTROL DETAILS								

APPROXIMATE 100 YR. FLOODPLAIN LIMITS

STA. 296+75 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 303+24 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

EXIST. R/W & C/A

EXIST. R/W & C/A

295

300

305

8'x5' BC

N30°53'00"W

E-7

E-5

C.L. I-530

E-7

E-5

E-5

18"

EXIST. R/W & C/A

EXIST. R/W & C/A

STA. 299+00 IEACH SAND BAG
DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 304+00 IEACH SAND BAG
DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 309+00 IEACH SAND BAG
DITCH CHECKS
IN MEDIAN (TYPE E-5)

APPROXIMATE 100 YR. FLOODPLAIN LIMITS

REVISIONS

DATE OF REVISION	REVISION

LEGEND



- (E-5) = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- (E-11) = SILT FENCE
- [Hatched Box] = CONSTRUCTION AREA

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



Leonard Speed 6/20/2016 2:29:24 PM W:\Projects\AR\138215_I-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_OSE_EC_IA-MAIN_ID.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	235
							BB0202	30
							TEMPORARY EROSION CONTROL DETAILS	



REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.




Leonard.Speed 6/20/2016 2:29:25 PM \\projects\ar\10156295\1-330_Hwy04-Hwy65B\Drawings\BB0202_05E_EC_IA-MAIN.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.	BBO202	31	235
				JOB NO. BBO202				
				TEMPORARY EROSION CONTROL DETAILS				

STA. 326+90 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 337+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)




REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING


EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.

STA. 338+00 TO STA. 339+50
2 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(150' O.C.)



Leonard.Speed 6/20/2016 2:29:25 PM
WORKSPACE: Leonard.Speed
Y:\Projects\BBO202\BBO202_05E_EC_IA-MAIN_12.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							32	235
(2) TEMPORARY EROSION CONTROL DETAILS								



STA. 353+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 341+00 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

APPROXIMATE 100 YR.
FLOODPLAIN LIMITS

APPROXIMATE 100 YR.
FLOODPLAIN LIMITS

STA. 348+00 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 350+00 TO STA. 352+00
3 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(100' O.C.)

HOLLAND AVE. STA. 23+50.00 =
RAMP 1 STA. 344+73.49
RAMP 2 STA. 344+19.54

EROSION CONTROL MEASURES PLACED IN
STAGE IA SHALL BE RETAINED THROUGHOUT
STAGE IB OR UNTIL FINAL STABILIZATION.


DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA



Leonard.Speed 6/20/2016 2:29:26 PM
 WORKSPACE: Leonard.Speed
 PROJECT: I:\PROJECTS\148251-1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_IA_MAIN_13.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	TOTAL SHEETS
							BB0202	33 235
② TEMPORARY EROSION CONTROL DETAILS								




REVISIONS

DATE OF REVISION	REVISION

LEGEND


	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



Leonard.Speed 6/20/2016 2:29:27 PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\154170_156215_1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E-EC-IA-MAIN_14.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
JOB NO.							BB0202	34	235
② TEMPORARY EROSION CONTROL DETAILS									



STA. 369+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 375+50 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 380+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)



STA. 368+70 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 375+20 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)


STA. 379+70 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 380+30 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

REVISIONS	
DATE OF REVISION	REVISION


LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.




Leonard Speed 6/20/2016 2:29:27 PM
WORKSPACE: Leonard Speed
Y:\Projects\AHTD_138215_P-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IA-MAIN_15.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	35
						② TEMPORARY EROSION CONTROL DETAILS		



STA. 386+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 393+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)



STA. 385+75 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 392+75 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 395+00 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

REVISIONS	
DATE OF REVISION	REVISION


LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.




Leonard.Speed 6/20/2016 2:29:28 PM
WORKSPACE: Leonard.Speed
I:\Projects\AR\10_1525L_P530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IA-MAN_ILB.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	36
						② TEMPORARY EROSION CONTROL DETAILS		



STA. 397+50 IEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

STA. 402+00 TO STA. 407+00
3 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(250' O.C.)



STA. 400+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)


STA. 406+50 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

REVISIONS

DATE OF REVISION	REVISION


LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



Leonor.d.Speed 6/20/2016 2:29:28 PM
 WORKSPACE: Leonor.d.Speed
 Y:\Projects\NH10152\1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_05E_EC_IA-MAN.IT.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	37
						TEMPORARY EROSION CONTROL DETAILS		




STA. 413+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 420+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 427+50 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 418+35 TO STA. 422+00 LT.
383 L.F. SILT FENCE (TYPE E-11)



REVISIONS	
DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING


EROSION CONTROL MEASURES PLACED IN STAGE 1A SHALL BE RETAINED THROUGHOUT STAGE 1B OR UNTIL FINAL STABILIZATION.



Leonard.Speed 6/20/2016 2:29:29 PM
WORKSPACE: Leonard.Speed
I:\Projects\15\152615_1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_OBE_EC_1A-MAIN_IB.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	38	235

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS

DATE OF REVISION	REVISION

LEGEND

- (E-5) = SAND BAG DITCH CHECKS
- (E-7) = DROP INLET SILT FENCE
- (E-11) = SILT FENCE
- [Hatched Box] = CONSTRUCTION AREA
- [Diagonal Lines Box] = TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE 1A SHALL BE RETAINED THROUGHOUT STAGE 1B OR UNTIL FINAL STABILIZATION.


STATE OF ARKANSAS
 LICENSED PROFESSIONAL ENGINEER
 No. 10887
 SCOTT P. THORNBERY
 6/21/2016

TEMPORARY EROSION CONTROL DETAILS - STAGE 1A

Leander.d.Speed 6/20/2016 2:29:29 PM
 X:\Projects\104-Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_1A-MAIN_B.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BBO202	39	235	

TEMPORARY EROSION CONTROL DETAILS



STA. 447+70.79
END JOB BB0202
LOG MILE 29.90


REVISIONS

DATE OF REVISION	REVISION

LEGEND

- (E-5) = SAND BAG DITCH CHECKS
- (E-7) = DROP INLET SILT FENCE
- (E-11) = SILT FENCE
- [Hatched Box] = CONSTRUCTION AREA
- [Diagonal Lines Box] = TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.





TEMPORARY EROSION CONTROL DETAILS - STAGE IA

Leonor.d.Speed 6/20/2016 2:29:30 PM
 WORKSPACE: Leonor.d.Speed
 Y:\Projects\AHTD_13825_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC-IA-MAIN_20.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	40	235	

2 TEMPORARY EROSION CONTROL DETAILS

STA. 455+50 LEACH SAND BAG DITCH CHECKS IN MEDIAN (TYPE E-5)




STA. 462+50 MEDIAN 20 L.F. DROP INLET SILT FENCE (TYPE E-7)

REVISIONS	
DATE OF REVISION	REVISION

LEGEND


- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.



TEMPORARY EROSION CONTROL DETAILS - STAGE IA

Leonard.Speed 6/20/2016 2:29:31PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\LAHTD_138215_I-530_Hwy104-Hwy65B_Deliverables\ROADWAY\Drawings\RB0202_05E_EC-IA-MAIN.dwg




REVISIONS

DATE OF REVISION	REVISION

LEGEND



- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-II = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonard.Speed 6/20/2016 2:29:31PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_13825_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_01.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	42
						2 TEMPORARY EROSION CONTROL DETAILS		



REVISIONS

DATE OF REVISION	REVISION

LEGEND


	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonard.Speed 6/20/2016 2:29:32 PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD\158215_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBBO202_05E_EC_IB-MIN_02.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	43
						2 TEMPORARY EROSION CONTROL DETAILS		



Leonard.Speed 6/20/2016 2:29:33 PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_138215_I-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_IB-MAIN_03.dgn

REVISIONS


DATE OF REVISION	REVISION

LEGEND

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.

STA. 204+20 RT. & LT. 4 EACH SAND BAG DITCH CHECKS (TYPE E-5)




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	44	235

② TEMPORARY EROSION CONTROL DETAILS



APPROXIMATE 100 YR. FLOODPLAIN LIMITS



Leonard.Speed 6/20/2016 2:29:33 PM
 WORKSPACE: Leonard.Speed
 F:\Projects\AHTD\3525_I-530_Hwy04-Hwy65B\Deliverables\RD\DWG\Drawings\RB0202_05E_EC_IB-MAIN_04.dgn


DATE OF REVISION	REVISION

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	45
						2 TEMPORARY EROSION CONTROL DETAILS		



DATE OF REVISION	REVISION


LEGEND

- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-11 = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

STA. 232+00 LT. AND RT. 3 EACH
SAND BAG DITCH CHECKS (TYPE E-5)

HWY. 270 RAMP 1
STA. 234+02 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)



EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonard.Speed 6/20/2016 2:29:34 PM
WORKSPACE: Leonard.Speed
Y:\Projects\AHTD_158215_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_IB-MAIN_05.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	46	235

2 TEMPORARY EROSION CONTROL DETAILS




REVISIONS

DATE OF REVISION	REVISION

LEGEND

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.




TEMPORARY EROSION CONTROL DETAILS - STAGE IB

Leonard.Speed 6/20/2016 2:29:34 PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_138215_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_06.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	47
						TEMPORARY EROSION CONTROL DETAILS		

② TEMPORARY EROSION CONTROL DETAILS



STA. 249+00 LT. 2 EACH SAND BAG DITCH CHECKS (TYPE E-5)

HWY. 270 RAMP 3
STA. 255+00 TO STA. 257+00
3 EACH SAND BAG DITCH CHECKS ON LT. (TYPE E-5) (100' O.C.)



REVISIONS


DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.


APPROXIMATE 100 YR FLOODPLAIN LIMITS




Leonard.Speed 6/20/2016 2:29:35 PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_13825_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_IB-MAIN_07.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	48	235

② TEMPORARY EROSION CONTROL DETAILS



STA. 264+40 LT. IEACH SAND BAG DITCH CHECKS (TYPE E-5)



STA. 264+40 RT. IEACH SAND BAG DITCH CHECK (TYPE E-5)

REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.





TEMPORARY EROSION CONTROL DETAILS - STAGE IB

Leonor.d.Speed 6/20/2016 2:29:35 PM
 WORKSPACE: Leonor.d.Speed
 Y:\Projects\AHD\13825\1-530-Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_08.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	49	235

② TEMPORARY EROSION CONTROL DETAILS




Leonard.Speed 6/20/2016 2:29:36 PM
 WORKSPACE: Leonard.Speed
 H:\Projects\I-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_IB-MAN_09.dgn

REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE



EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	50	235	

② TEMPORARY EROSION CONTROL DETAILS

APPROXIMATE 100 YR. FLOODPLAIN LIMITS



STA. 303+24 LT. & RT. 4 EACH SAND BAG DITCH CHECKS (TYPE E-5)

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.


REVISIONS

DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE

APPROXIMATE 100 YR. FLOODPLAIN LIMITS



TEMPORARY EROSION CONTROL DETAILS - STAGE IB



Leonard.Speed 6/20/2016 2:29:37 PM
 WORKSPACE: Leonard.Speed
 I:\Projects\14170_1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAN_IG.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	51	235

② TEMPORARY EROSION CONTROL DETAILS




Leonor G. Speed 6/20/2016 2:29:37 PM
 Y:\Projects\AR\BB0202\Drawings\Roadway\Drawings\BB0202_05E_EC_IB_MAIN.dgn


DATE OF REVISION	REVISION

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	52
						TEMPORARY EROSION CONTROL DETAILS		



STA. 327+60 LT. 2 EACH
SAND BAG DITCH CHECKS (TYPE E-5)

STA. 326+60 RT. 2 EACH
SAND BAG DITCH CHECKS (TYPE E-5)



REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonora.Speed 6/20/2016 2:29:38 PM
WORKSPACE: Leonora.Speed
I:\Projects\AR\101530.Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202.05E_EC_IB-MAN.rvt.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	53	235

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS	
DATE OF REVISION	REVISION

LEGEND

- (E-5) = SAND BAG DITCH CHECKS
- (E-7) = DROP INLET SILT FENCE
- (E-11) = SILT FENCE
- [Hatched Box] = CONSTRUCTION AREA
- [Diagonal Lines Box] = TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.





TEMPORARY EROSION CONTROL DETAILS - STAGE IB

Leonard.Speed 6/20/2016 2:29:38 PM
 WORKSPACE: Leonard.Speed
 I:\Projects\14170_15215_1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_15.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	54
						TEMPORARY EROSION CONTROL DETAILS		

② TEMPORARY EROSION CONTROL DETAILS




REVISIONS

DATE OF REVISION	REVISION

LEGEND

- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-II = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.




Leonard Speed 6/20/2006 2:29:39 PM
 Y:\Projects\ARB0202\Drawings\ROADWAY\Drawings\ARB0202_05E_EC_IB_MAIN.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
JOB NO.							BB0202	55	235

② TEMPORARY EROSION CONTROL DETAILS



STA. 380+00 LT. 2 EACH
SAND BAG DITCH CHECKS (TYPE E-5)



REVISIONS

DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.





TEMPORARY EROSION CONTROL DETAILS - STAGE IB

Leonard.Speed 6/20/2016 2:29:39 PM
WORKSPACE: Leonard.Speed
I:\Projects\AR\10_15251_1530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_15.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
JOB NO.							BB0202	56	235

② TEMPORARY EROSION CONTROL DETAILS




Leonard Speed 6/20/2016 2:29:40 PM
 WORKSPACE\Projects\1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_16.dgn

DATE OF REVISION	REVISION


	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	57
						TEMPORARY EROSION CONTROL DETAILS		

APPROXIMATE 100 YR. FLOODPLAIN LIMITS



STA. 400+00 LT. 1 EACH
SAND BAG DITCH CHECKS (TYPE E-5)

STA. 409+60 LT. & RT. 4 EACH
SAND BAG DITCH CHECKS (TYPE E-5)



LeonardSpeed 6/20/2016 2:29:40 PM
WORKSPACE: LeonardSpeed
Y:\Projects\AHTD_138215_1-530_Hwy104-Hwy658\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN.IT.dgn


REVISIONS

DATE OF REVISION	REVISION

LEGEND



	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	58	235

② TEMPORARY EROSION CONTROL DETAILS




REVISIONS

DATE OF REVISION	REVISION

LEGEND

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonard.Speed 6/20/2016 2:29:41PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD\15825_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_IB.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	59	235

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS

DATE OF REVISION	REVISION


LEGEND

- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-11 = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.


STA. 440+80 RT. 2 EACH SAND BAG DITCH CHECKS (TYPE E-5)

APPROXIMATE 100 YR. FLOODPLAIN LIMITS



Leonor.d.Speed 6/20/2016 2:29:41 PM
 WORKSPACE: Leonor.d.Speed
 Y:\Projects\AHTD_138215_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_IB-MAIN_IB.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							60	235
② TEMPORARY EROSION CONTROL DETAILS								




STA. 447+70.79
END JOB BB0202
LOG MILE 29.90

REVISIONS

DATE OF REVISION	REVISION

LEGEND



	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING



Leonard.Speed 6/20/2016 2:29:42 PM
 WORKSPACE: Leonard.Speed
 I:\Projects\AR\152151\1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_IB-MAIN_20.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	61	235


② TEMPORARY EROSION CONTROL DETAILS



6/20/2016 2:29:43 PM
 Leonor.d.Speed
 WORKSPACE: Leonor.d.Speed
 Y:\Projects\AR10_138215_1-530_Hwy104-Hwy658\Deliverables\ROADWAY\Drawings\RBBO202_05E_EC_IB-MAIN_21.dgn


REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							62	235

② TEMPORARY EROSION CONTROL DETAILS



STA. STA. 258+50
EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)



REVISIONS


DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES PLACED IN STAGE IA SHALL BE RETAINED THROUGHOUT STAGE IB OR UNTIL FINAL STABILIZATION.

APPROXIMATE 100 YR FLOODPLAIN LIMITS




Leonor J. Speed 6/20/2016 2:29:43 PM
 WORKSPACE: Leonor J. Speed
 P:\Projects\153025\15300_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_2B-MAN.dwg

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	63	235

② TEMPORARY EROSION CONTROL DETAILS

STA. 330+45 TO STA. 331+84
REMOVE 139 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN




REVISIONS

DATE OF REVISION	REVISION

LEGEND

- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-II = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING



EROSION CONTROL MEASURES PLACED IN STAGE 1A SHALL BE RETAINED THROUGHOUT STAGE 1B OR UNTIL FINAL STABILIZATION.



LeonardSpeed 6/20/2016 2:29:44 PM
WORKSPACE: LeonardSpeed
Y:\Projects\AR\108215_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBBO202_05E_EC_2B-MAIN_02.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	64
						2 TEMPORARY EROSION CONTROL DETAILS		

STA. 361+26 TO STA. 361+89
REMOVE 63 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN



REVISIONS

DATE OF REVISION	REVISION

LEGEND


	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING



Leonard.Speed 6/20/2016 2:29:44 PM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_15225_1-530_Hwy104-Hwy658\Deliverables\ROADWAY\Drawings\RBB0202_05E_EC_2B-MAIN_03.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	65	235

② TEMPORARY EROSION CONTROL DETAILS



**STA. 175+14.73
BEGIN JOB BBO202
LOG MILE 34.99**

STA. 172+00 TO STA. 174+21
REMOVE 231 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN


STA. 173+80 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)

STA. 176+80 TO 177+59
REMOVE 79 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
(E-5)	= SAND BAG DITCH CHECKS
(E-7)	= DROP INLET SILT FENCE
(E-II)	= SILT FENCE
[Hatched Box]	= CONSTRUCTION AREA
[Diagonal Lines Box]	= TEMPORARY SEEDING



LeonardSpeed 6/20/2016 2:29:45 PM
 WORKSPACE: LeonardSpeed
 Y:\Projects\AHTD\138215_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_3A-MAIN_01.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	66
						2 TEMPORARY EROSION CONTROL DETAILS		



STA. 253+81 TO STA. 255+37
REMOVE 156 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

STA. 254+50 TO STA. 255+00
2 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(50' O.C.)


REVISIONS	
DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.

APPROXIMATE 100 YR FLOODPLAIN LIMITS



LeonardSpeed 6/20/2016 2:29:46 PM
WORKSPACE: LeonardSpeed
Y:\Projects\AR\10_13825_I-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_3A-MAIN_02.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	67
						TEMPORARY EROSION CONTROL DETAILS		



REVISIONS


DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

STA. 357+51 TO STA. 357+91
REMOVE 40 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



LeonardSpeed 6/20/2016 2:29:46 PM
 WORKSPACE: LeonardSpeed
 Y:\Projects\AMTD\138215_1-530_Hwy04-Hwy65\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_3A-MAIN_03.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	68	235

② TEMPORARY EROSION CONTROL DETAILS




REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.

APPROXIMATE 100 YR. FLOODPLAIN LIMITS



STA. 440+00 TO STA. 441+00
2 EACH SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)
(100' O.C.)



TEMPORARY EROSION CONTROL DETAILS - STAGE 3A

Leonor.d.Speed 6/20/2016 2:29:47 PM
 WORKSPACE: Leonor.d.Speed
 T:\Projects\AHTD\15625_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_3A-MAIN_04.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	69
						2 TEMPORARY EROSION CONTROL DETAILS		



APPROXIMATE 100 YR FLOODPLAIN LIMITS

STA. 184+65 TO STA. 187+70
REMOVE 305 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

STA. 186+25 LEACH
SAND BAG DITCH CHECKS
IN MEDIAN (TYPE E-5)

REVISIONS

DATE OF REVISION	REVISION

LEGEND

- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-II = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonard.Speed 6/20/2016 2:29:47 PM
 WORKSPACE: Leonard.Speed
 T:\Projects\AR\1013825_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E.LC_3B-MAIN_01.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	70	235

② TEMPORARY EROSION CONTROL DETAILS




STA. 226+42 TO 229+21
REMOVE 279 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

REVISIONS	
DATE OF REVISION	REVISION

LEGEND

- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-11 = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.





TEMPORARY EROSION CONTROL DETAILS - STAGE 3B

LeonardSpeed 6/20/2016 2:29:48 PM
WORKSPACE: LeonardSpeed
Y:\Projects\AHTD\3625_I-530_Hwy04-Hwy65B\Drawings\RB0202_05E_EC_3B-MAIN_02.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	71	235

② TEMPORARY EROSION CONTROL DETAILS




STA. 260+00 LEACH SAND BAG DITCH CHECKS IN MEDIAN (TYPE E-5)

REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING



EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.

APPROXIMATE 100 YR FLOODPLAIN LIMITS



LeonardSpeed 6/20/2016 2:29:49 PM WORKSPACE: LeonardSpeed Y:\Projects\AR\1013825_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_3B-MAIN_03.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	72
						② TEMPORARY EROSION CONTROL DETAILS		



STA. 328+00 TO STA. 330+45
REMOVE 245 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

REVISIONS	
DATE OF REVISION	REVISION

LEGEND


- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-11 = SILT FENCE
- = CONSTRUCTION AREA
- = TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonard.Speed 6/20/2016 2:29:49 PM
WORKSPACE: Leonard.Speed
T:\Projects\AR\1015825_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_3B-MAN_04.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	73	235	
② TEMPORARY EROSION CONTROL DETAILS								



REVISIONS

DATE OF REVISION	REVISION


LEGEND

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

STA. 361+89 TO STA. 364+18
REMOVE 229 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

STA. 363+00 MEDIAN
20 L.F. DROP INLET
SILT FENCE (TYPE E-7)


EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



LeonardSpeed 6/20/2016 2:29:50 PM
WORKSPACE: LeonardSpeed
T:\Projects\NH1013825_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E.EC_3B-MAIN_05.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	74	235

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS


DATE OF REVISION	REVISION

LEGEND

	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= CONSTRUCTION AREA
	= TEMPORARY SEEDING

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.


APPROXIMATE 100 YR. FLOODPLAIN LIMITS



TEMPORARY EROSION CONTROL DETAILS - STAGE 3B

Leonard.Speed 6/20/2016 2:29:50 PM
WORKSPACE: Leonard.Speed 6/20/2016 2:29:50 PM
T:\Projects\AR\10118885_1\50_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E_EC_3B-MAIN_05.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BB0202	75	235
② TEMPORARY EROSION CONTROL DETAILS								



STA. 174+21 TO STA. 177+59
REMOVE 338 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

RAMP A65 STA. 176+52 RT.
REMOVE 17 LIN. FT. OF
TEMP. PIPE CULVERT

TEMP. RAMP A65 A STA. 33+92
REMOVE 142 LIN. FT. OF
TEMP. PIPE CULVERT

RAMP D65 STA. 169+60 LT.
REMOVE 12 LIN. FT. OF
TEMP. PIPE CULVERT

TEMP. RAMP D65 STA. 24+94
REMOVE 224 LIN. FT. OF
TEMP. PIPE CULVERT

STA. 175+14.73
BEGIN JOB BB0202
LOG MILE 34.99

REVISIONS	
DATE OF REVISION	REVISION


LEGEND

- (E-5) = SAND BAG DITCH CHECKS
- (E-7) = DROP INLET SILT FENCE
- (E-11) = SILT FENCE
- [Hatched Box] = OBLITERATION
- [Diagonal Lines Box] = PERMANENT SEEDING

EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.


EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonard.Speed 6/20/2016 2:29:45PM WORKSPACE: Leonard.Speed T:\Projects\AR\RD_15825_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_4A&B-MAIN_01.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	76
						2 TEMPORARY EROSION CONTROL DETAILS		



Leonor.d.Speed 6/20/2016 2:29:52 PM
 WORKSPACE: Leonor.d.Speed
 Y:\Projects\AHTD_13825_1-530 Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\RB0202_05E.EC-4&B-MAN_02.dgn


REVISIONS

DATE OF REVISION	REVISION

LEGEND


	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= OBLITERATION
	= PERMANENT SEEDING

EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.
 EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.
 EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	77	235

② TEMPORARY EROSION CONTROL DETAILS



HWY. 270 TEMP. RAMP 4 STA. 84+83
REMOVE 129 LIN. FT. OF
TEMP. PIPE CULVERT

STA. 230+90 TO STA. 234+09
REMOVE 319 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= OBLITERATION
	= PERMANENT SEEDING


EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.
EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.
EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.

TEMPORARY EROSION CONTROL DETAILS - STAGE 4 A&B




Leonor d. Speed 6/20/2016 2:25:52 PM
 WORKSPACE: Leonor d. Speed
 Y:\Projects\AHTD\3825\1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_4A&B-MAIN_03.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BB0202	78
						TEMPORARY EROSION CONTROL DETAILS		



HWY. 270 TEMP. RAMP 3A STA. 112+89
REMOVE 195 LIN. FT. OF
TEMP. PIPE CULVERT

STA. 255+37 TO STA. 257+98
REMOVE 261 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN



REVISIONS

DATE OF REVISION	REVISION

LEGEND


- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = OBLITERATION
- = PERMANENT SEEDING

EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.

EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES, THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.


APPROXIMATE 100 YR FLOODPLAIN LIMITS




Leonor C. Speed 6/20/2016 2:29:53 PM
 WORKSPACE: Leonor C. Speed
 I:\Projects\AR\1013825_1\530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E_EC_4A&B-MAN_04.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	79	235

② TEMPORARY EROSION CONTROL DETAILS



HOLLAND AVE. TEMP. RAMP 4B
STA. 165+33 REMOVE 230 LIN. FT. OF
TEMP. PIPE CULVERT



STA. 332+00 TO STA. 334+50
REMOVE 250 LIN. FT. OF
TEMP. PIPE CULVERT IN MEDIAN

HOLLAND AVE. TEMP. RAMP 1B
STA. 144+76 REMOVE 185 LIN. FT. OF
TEMP. PIPE CULVERT

REVISIONS	
DATE OF REVISION	REVISION

LEGEND


- E-5 = SAND BAG DITCH CHECKS
- E-7 = DROP INLET SILT FENCE
- E-11 = SILT FENCE
- = OBLITERATION
- = PERMANENT SEEDING

EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.

EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



TEMPORARY EROSION CONTROL DETAILS - STAGE 4 A&B



Leonard.Speed 6/20/2016 2:29:54 PM
WORKSPACE: Leonard.Speed
T:\Projects\ARHTD\5865_I-550_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC_4A&B-MAN_05.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	80	235	

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS

DATE OF REVISION	REVISION

LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = OBLITERATION
- = PERMANENT SEEDING

EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.

EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.


TEMPORARY EROSION CONTROL DETAILS - STAGE 4 A&B



6/20/2016 2:29:54 PM
 LEONARD SPEED
 Y:\Projects\AR\10136625_1350_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_05E.EC_4A&B-MAIN_06.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	81	235

② TEMPORARY EROSION CONTROL DETAILS



REVISIONS	
DATE OF REVISION	REVISION

LEGEND	
	= SAND BAG DITCH CHECKS
	= DROP INLET SILT FENCE
	= SILT FENCE
	= OBLITERATION
	= PERMANENT SEEDING

EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.

EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



TEMPORARY EROSION CONTROL DETAILS - STAGE 4 A&B



LeonardSpeed 6/20/2016 2:29:55 PM WORKSPACE: LeonardSpeed Y:\Projects\AR1013825-1-530_Hwy104-Hwy65B\Drawings\BBO202_05E.EC-4A&B-Main_07.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BBO202	82	235	

2 TEMPORARY EROSION CONTROL DETAILS



REVISIONS	
DATE OF REVISION	REVISION


LEGEND

- = SAND BAG DITCH CHECKS
- = DROP INLET SILT FENCE
- = SILT FENCE
- = OBLITERATION
- = PERMANENT SEEDING

EROSION CONTROL MEASURES IN MEDIAN TO BE PLACED DURING STAGE 4A.

EROSION CONTROL MEASURE IN GORE AREA TO BE PLACED DURING STAGE 4B.

EROSION CONTROL MEASURES TO BE PLACED DURING APPROPRIATE STAGES. THESE DEVICES SHALL BE LEFT IN PLACE AS LONG AS REQUIRED TO CONTROL EROSION.



Leonor.d.Speed 6/20/2016 2:29:55 PM
 WORKSPACE: Leonor.d.Speed
 Y:\Projects\AHTD_1822E_LJ-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_05E_EC-4A&B-MAIN_08.dgn

SUMMARY OF SEQUENCE OF CONSTRUCTION

STAGE 1A OPERATIONS:

INSTALL ADVANCE WARNING SIGNS.
CLOSE INSIDE LANE ON MAIN LANES.
REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.

STAGE 1B OPERATIONS:

CLOSE OUTSIDE LANE ON MAIN LANES.
GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
PAVE TEMPORARY RAMPS AS SHOWN.

STAGE 2A OPERATIONS:

INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
MODIFY MEDIAN RAMPS AS INDICATED.
NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.

STAGE 2B OPERATIONS:

UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO ALTERNATE TEMPORARY RAMPS.
MODIFY MEDIAN RAMPS AS INDICATED.
RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.

STAGE 3A OPERATIONS:

RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
MODIFY MEDIAN RAMPS AS INDICATED.
NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.

STAGE 3B OPERATIONS:

UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO ALTERNATE TEMPORARY RAMPS.
MODIFY MEDIAN RAMPS AS INDICATED.
RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.

STAGE 4A OPERATIONS:


SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
CONSTRUCT FINAL GRADING IN MEDIAN AREA.
PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
PLACE FINAL STRIPING ON INSIDE LANES.

STAGE 4B OPERATIONS:


SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	83	235

② MAINTENANCE OF TRAFFIC



NOTE THAT THESE SIGNS MAY BE TEMPORARILY REPLACED BY SOME OF THE ADVANCE SIGNS FOR LANE CLOSURES WHILE WORK IS UNDERWAY IN THESE AREAS.



NOTE THAT THESE SIGNS MAY BE TEMPORARILY REPLACED BY SOME OF THE ADVANCE SIGNS FOR LANE CLOSURES WHILE WORK IS UNDERWAY IN THESE AREAS.

ADVANCE WARNING SIGNS AT BEGINNING AND END OF JOB

SUMMARY OF SEQUENCE OF CONSTRUCTION

STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.

STAGE 1B OPERATIONS:
 CLOSE OUTSIDE LANE ON MAIN LANES.
 GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PAVE TEMPORARY RAMPS AS SHOWN.

STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.

STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.

STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.


STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.

STAGE 4A OPERATIONS:
 SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
 RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
 REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
 CONSTRUCT FINAL GRADING IN MEDIAN AREA.
 PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
 CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
 INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
 PLACE FINAL STRIPING ON INSIDE LANES.

STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. BB0202	84	235
② MAINTENANCE OF TRAFFIC								






DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	85	235

② MAINTENANCE OF TRAFFIC



C. Jumper
6/20/2016



SIGN TYPE	DESCRIPTION	SIGN SIZE	MAXIMUM NUMBER REQUIRED	SIGN AREA
				SQ. FT.
M1-5	HWY 65	(24" x 24")	2	8
M1-5	HWY 104	(30" x 24")	2	10
M3-1	NORTH	(24" x 12")	2	4
M3-3	SOUTH	(24" x 12")	2	4
M4-5	TO	(24" x 12")	4	8
M6-3	STRAIGHT AHEAD ARROW	(21" x 15")	4	8.8
S-1	WIDE LOAD DETOUR & ALT. ROUTE EXIT NEXT RIGHT USE HWY 104 TO HWY 365	(9.5' x 3')	1	28.5
S-2	WIDE LOAD DETOUR & ALT. ROUTE EXIT NEXT RIGHT USE HWY 65 TO HWY 365	(9.5' x 3')	1	28.5
S-3	WIDE LOAD DETOUR & ALT. ROUTE TAKE HWY 365 TO HWY 65	(9.5' x 3')	1	28.5
S-4	WIDE LOAD DETOUR & ALT. ROUTE TAKE HWY 365 TO HWY 104	(9.5' x 3')	1	28.5
S-5	WIDE LOAD DETOUR & ALT. ROUTE TAKE HWY 65 TO IH-530	(9.5' x 3')	1	28.5
S-6	WIDE LOAD DETOUR & ALT. ROUTE TAKE HWY 365 TO HWY 104	(9.5' x 3')	1	28.5
S-7	WIDE LOAD DETOUR & ALT. ROUTE	(9.5' x 3')	1	28.5
S-8	WIDE LOAD DETOUR & ALT. ROUTE	(9.5' x 3')	1	28.5
S-9	WIDE LOAD DETOUR & ALT. ROUTE	(9.5' x 3')	1	28.5
TOTALS FOR JOB BB0202				299.3

- NOTES:
- SPECIAL SIGNS SHALL BE CONSTRUCTED USING (WHITE) TYPE III BACKGROUND WITH (BLACK) TYPE V LEGEND AND BORDER.
 - PAYMENT FOR MOUNTING THE GUIDE SIGNS ON TEMPORARY SUPPORTS, RELOCATING THE SIGNS AS REQUIRED DURING VARIOUS PHASES OF CONSTRUCTION, AND REMOVING AND DISPOSING OF THE SIGNS WHEN THE PROJECT IS COMPLETED SHALL BE SUBSIDIARY TO SECTION 604, STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 2014 EDITION.
 - EXACT PLACEMENT OF SIGNS SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.

WIDE LOAD DETOUR AND ALT ROUTE AND TEMPORARY SIGNS


MAINTENANCE OF TRAFFIC

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
							JOB NO.	235
							BB0202	86
							② MAINTENANCE OF TRAFFIC	




Clinton D. Jumper
6/20/2016


STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.



- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
 TRAFFIC DRUMS (100' O.C.): 287 EACH + 32 ADDITIONAL DRUMS
 STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES
 TRAFFIC DRUMS (100' O.C.): 287 EACH + 46 ADDITIONAL DRUMS



MAINTENANCE OF TRAFFIC
 STAGE 1A



STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO
 PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.



Clinton D. Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	87
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 1A



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	88
						② MAINTENANCE OF TRAFFIC		



CDJ
6/20/2016


STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
STAGE 1A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BBO202	89	235





Clinton D. Jumper
6/20/2016

STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.


② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
STAGE 1A


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
							JOB NO.	BB0202
							SHEET NO.	90
							TOTAL SHEETS	235



Clinton D. Juniper
6/20/2016




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.

② MAINTENANCE OF TRAFFIC




MAINTENANCE OF TRAFFIC
STAGE 1A






STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO
 PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.




Clinton D. Juniper
 6/20/2016




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. BB0202	91	235

-  RAMP OBLITERATION
-  RAMP CONST. THIS STAGE
-  RAMP CONST. PREVIOUS STAGE
-  MAIN LANE CONST.
-  CONST. GRADING



② MAINTENANCE OF TRAFFIC




MAINTENANCE OF TRAFFIC
 STAGE 1A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	92
						② MAINTENANCE OF TRAFFIC		



STAGE 1A OPERATIONS:
 INSTALL ADVANCE WARNING SIGNS.
 CLOSE INSIDE LANE ON MAIN LANES.
 REMOVE WIRE ROPE SAFETY FENCE AND MEDIAN GUARDRAILS IN CONSTRUCTION AREAS.
 GRADE IN CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES IN MEDIAN AREA.
 PAVE CROSSOVERS, TEMPORARY RAMPS, AND ACCELERATION LANES AS SHOWN.
 TRENCH & SHOULDER PREPARATION OF THE INSIDE SOUTHBOUND SHOULDER OF THE SB I-530 LANES TO PROPOSED LIMITS SHOWN ON ROADWAY TYPICALS.



CDJ
6/20/2016




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
STAGE 1A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	93	235
② MAINTENANCE OF TRAFFIC								



Clinton D. Jumper
6/20/2016


STAGE 1B OPERATIONS:
CLOSE OUTSIDE LANE ON MAIN LANES.
GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
PAVE TEMPORARY RAMPS AS SHOWN.



- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
TRAFFIC DRUMS (100' O.C.): 289 EACH + 356 ADDITIONAL DRUMS
STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES
TRAFFIC DRUMS (100' O.C.): 258 EACH + 388 ADDITIONAL DRUMS
NB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 1,200 LF WITH 3 TIABS
SB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 1,900 LF WITH 5 TIABS



MAINTENANCE OF TRAFFIC
STAGE 1B


STAGE 1B OPERATIONS:
 CLOSE OUTSIDE LANE ON MAIN LANES.
 GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PAVE TEMPORARY RAMPS AS SHOWN.



Clinton D. Juniper
 6/20/2016


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	94
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 1B



STAGE 1B OPERATIONS:
 CLOSE OUTSIDE LANE ON MAIN LANES.
 GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PAVE TEMPORARY RAMPS AS SHOWN.



Cl Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	95
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 1B

STAGE 1B OPERATIONS:
 CLOSE OUTSIDE LANE ON MAIN LANES.
 GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PAVE TEMPORARY RAMPS AS SHOWN.





Cl Jumper
 6/20/2016




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	96
						② MAINTENANCE OF TRAFFIC		


- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	97	235



Clinton D. Jumper
6/20/2016




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 1B OPERATIONS:
CLOSE OUTSIDE LANE ON MAIN LANES.
GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
PAVE TEMPORARY RAMPS AS SHOWN.

② MAINTENANCE OF TRAFFIC




MAINTENANCE OF TRAFFIC
STAGE 1B

STAGE 1B OPERATIONS:
 CLOSE OUTSIDE LANE ON MAIN LANES.
 GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PAVE TEMPORARY RAMPS AS SHOWN.





Clinton D. Jumper
 6/10/16




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BB0202							98	235
② MAINTENANCE OF TRAFFIC								

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 1B

STAGE 1B OPERATIONS:
 CLOSE OUTSIDE LANE ON MAIN LANES.
 GRADE IN TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PAVE TEMPORARY RAMPS AS SHOWN.





Clinton D. Jumper
 6/20/2016



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	99	235
② MAINTENANCE OF TRAFFIC								


- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



STA. 461+95.06 END WORK ZONE
 SEE DETAILS SHEET 84

MAINTENANCE OF TRAFFIC
 STAGE 1B


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BB0202	100	235	




Clinton D. Jumper
6/20/2016

② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.



LOCATION OF TEMPORARY PRECAST CONCRETE BARRIER WALL FOR MAINTENANCE OF TRAFFIC - SOUTHBOUND MAIN LANES (STA. 172+60.00 TO STA. 461+95.06)

- STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES VERTICAL PANELS (100' O.C.): 294 EACH
- STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES REMOVAL OF PERMANENT PAVEMENT MARKINGS: 56,580 LF
- STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES CONSTRUCTION PAVEMENT MARKINGS: 101,440 LF
- NB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 553 LF
- SB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 30,640 LF WITH 5 TIABS
- REMOVAL OF PLOWABLE PAVEMENT MARKINGS SUBSIDIARY TO REMOVAL OF EXIST ASPHALT OVERLAY.
- STA. 170+39.48 - STA. 461+95.06 MAIN LANES TRAFFIC DRUMS: 322 EACH
- MODULAR GLARE SHIELD ON BARRIER STA. 173+60 - STA. 177+60 - 400 LF



MAINTENANCE OF TRAFFIC
STAGE 2A

STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.

NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.





Cl D Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	101	235

② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 2A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	102	235




C.D. Jumper
6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.

② MAINTENANCE OF TRAFFIC




MAINTENANCE OF TRAFFIC
STAGE 2A


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	103
						② MAINTENANCE OF TRAFFIC		




Clinton D. Jumper
6/20/2016




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	104
						② MAINTENANCE OF TRAFFIC		




Cl J
6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.




MAINTENANCE OF TRAFFIC
 STAGE 2A






DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BB0202							105	235
② MAINTENANCE OF TRAFFIC								



STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.



Cl D Jumper
 6/20/2016




-  RAMP OBLITERATION
-  RAMP CONST. THIS STAGE
-  RAMP CONST. PREVIOUS STAGE
-  MAIN LANE CONST.
-  CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 2A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
							JOB NO.	BB0202
							SHEET NO.	106
							TOTAL SHEETS	235





Clinton D. Jumper
6/20/2016

② MAINTENANCE OF TRAFFIC


STAGE 2A OPERATIONS:
 INSTALL PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 ROUTE NB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF SB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT NB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
STAGE 2A


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	107	235




CDJ
6/20/2016

② MAINTENANCE OF TRAFFIC

STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.



- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES
 VERTICAL PANELS (100' O.C.): 294 EACH

NB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 553 LF
 SB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 30,640 LF WITH 5 TIABS

STA. 170+39.48 - STA. 461+95.06 MAIN LANES
 TRAFFIC DRUMS: 236 EACH


MODULAR GLARE SHIELD ON BARRIER
 STA. 173+60 - STA. 177+60 - 400 LF



MARTHA MITCHELL EXPY.

MAINTENANCE OF TRAFFIC
 STAGE 2B



STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.



Clinton D. Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	108
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 2B

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	109
						② MAINTENANCE OF TRAFFIC		


STATE OF ARKANSAS
 REGISTERED PROFESSIONAL ENGINEER
 No. 16728
 CLINTON D. JUMPER

Cl D Jumper
 6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.




MAINTENANCE OF TRAFFIC
 STAGE 2B


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0202	110	235



Ch Jumper
6/20/2016




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.

② MAINTENANCE OF TRAFFIC



END ROAD WORK
G20-2
(48"x24")

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. BB0202	111	235





Clinton D. Jumper
6/20/2016

STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.

② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
STAGE 2B



STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.



CD Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS		
				6	ARK.					
							JOB NO.	BB0202	112	235
									② MAINTENANCE OF TRAFFIC	


- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 2B


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BB0202							113	235

② MAINTENANCE OF TRAFFIC




Clinton D. Jumper
6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 2B OPERATIONS:
 UTILIZE STAGE 2A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.



MAINTENANCE OF TRAFFIC
 STAGE 2B


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BB0202							114	235




6/20/2016

② MAINTENANCE OF TRAFFIC

STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



- STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
VERTICAL PANELS (100' O.C.): 294 EACH
- STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
REMOVAL OF PERMANENT PAVEMENT MARKINGS: 5,360 LF
- STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
CONSTRUCTION PAVEMENT MARKINGS: 135,440 LF
- NB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 31,200 LF
WITH 7 TIABS
- REMOVAL OF PLOWABLE PAVEMENT MARKINGS SUBSIDIARY
TO REMOVAL OF ASPHALT OVERLAY.
- STA. 170+39.48 - STA. 461+95.06 MAIN LANES
TRAFFIC DRUMS: 376 EACH
- MODULAR GLARE SHIELD ON BARRIER
STA. 454+80 - STA. 458+80 - 400 LF


LOCATION OF TEMPORARY PRECAST CONCRETE BARRIER WALL FOR MAINTENANCE OF TRAFFIC - NORTHBOUND MAIN LANES (STA. 170+39.48 TO STA. 461+48.71)

TEMP. RELOCATE "EXIT" SIGN FROM NORMAL GORE AREA




MAINTENANCE OF TRAFFIC
STAGE 3A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	115
						② MAINTENANCE OF TRAFFIC		




Cl D Jumper
6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.



MAINTENANCE OF TRAFFIC
STAGE 3A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0202	116	235





Clinton D. Jumper
6/20/2016

STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.

② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
STAGE 3A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0202	117	235



② MAINTENANCE OF TRAFFIC

STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.




Clinton D. Jumper
 6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 3A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BBO202	118
						② MAINTENANCE OF TRAFFIC		




Clinton D. Juniper
6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.



MAINTENANCE OF TRAFFIC
STAGE 3A



STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BBO202	119	235

(2) MAINTENANCE OF TRAFFIC


- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 3A

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	120
						② MAINTENANCE OF TRAFFIC		



STAGE 3A OPERATIONS:
 RELOCATE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER TO NB LANES.
 ROUTE SB I-530 TRAFFIC THROUGH CROSSOVERS ONTO INSIDE LANE OF NB MAIN LANES.
 REMOVE MAIN LANE GUARDRAILS WHERE ILLUSTRATED.
 RECONSTRUCT SB LANES, APPROACH GUTTERS & SLABS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 NOTE: MODIFICATIONS SHOWN FOR ILLUSTRATIVE PURPOSES ONLY AND DO NOT INDICATE CONSTRUCTION LIMITS.



Clinton D. Jumper
 6/20/2016




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 3A


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO. BB0202							121	235
② MAINTENANCE OF TRAFFIC								



STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



LOCATION OF TEMPORARY PRECAST CONCRETE BARRIER WALL FOR MAINTENANCE OF TRAFFIC - NORTHBOUND MAIN LANES (STA. 170+39.48 TO STA. 461+48.71)

STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
 VERTICAL PANELS (100' O.C.): 294 EACH
 NB MAIN LANES TEMPORARY PRECAST CONCRETE BARRIER: 31,200 LF WITH 7 TIABS
 STA. 170+39.48 - STA. 461+95.06 MAIN LANES
 TRAFFIC DRUMS: 222 EACH
 MODULAR GLARE SHIELD ON BARRIER
 STA. 454+80 - STA. 458+80 - 400 LF



MAINTENANCE OF TRAFFIC
 STAGE 3B



STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.



Clinton D. Jumper
 6/20/2016


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	122
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 3B

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	123 235





W. J. Jumper
6/20/2016

STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.


② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
STAGE 3B

STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.





Clinton D. Jumper
 6/20/2016



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	124
						② MAINTENANCE OF TRAFFIC		


- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 3B

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. BB0202	125	235


② MAINTENANCE OF TRAFFIC




Cl D Jumper
6/20/2016



- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.




MAINTENANCE OF TRAFFIC
 STAGE 3B

STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.









Cl Jumper
 6/20/2016



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	126 235

② MAINTENANCE OF TRAFFIC

-  RAMP OBLITERATION
-  RAMP CONST. THIS STAGE
-  RAMP CONST. PREVIOUS STAGE
-  MAIN LANE CONST.
-  CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 3B

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. BB0202	127	235



② MAINTENANCE OF TRAFFIC

STAGE 3B OPERATIONS:
 UTILIZE STAGE 3A TRAFFIC PATH FOR NB I-530 TRAFFIC.
 SHIFT EXIT AND ENTRANCE RAMP TRAFFIC TO
 ALTERNATE TEMPORARY RAMPS.
 MODIFY MEDIAN RAMPS AS INDICATED.
 RECONSTRUCT REMAINING SECTIONS OF I-530 NORTHBOUND LANES.

STATE OF ARKANSAS
 REGISTERED PROFESSIONAL ENGINEER
 No. 16728
 CLINTON D. JUMPER

Cl Jumper
 6/20/2016

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 3B


STAGE 4A OPERATIONS:

- SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
- RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
- REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
- OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
- CONSTRUCT FINAL GRADING IN MEDIAN AREA.
- PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
- CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
- INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.




Cl Jumper
2/28/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
7-28-2016				6	ARK.			
						JOB NO.	BB0202	128
						② MAINTENANCE OF TRAFFIC		




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



LOCATION OF TRAFFIC DRUMS FOR MAINTENANCE OF TRAFFIC (SOUTHBOUND MAIN LANES)
(TRANSITIONS AT STA. 171+60.00 TO STA. 172+60.00 AND STA. 461+95.06 TO STA. 462+95.06)

LOCATION OF TRAFFIC DRUMS FOR MAINTENANCE OF TRAFFIC (NORTHBOUND MAIN LANES)
(TRANSITIONS AT STA. 169+39.48 TO STA. 170+39.48 AND STA. 461+48.71 TO STA. 462+48.71)

- STA. STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES TRAFFIC DRUMS (100' O.C.): 292 EACH + 61 ADDITIONAL DRUMS
- STA. STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES TRAFFIC DRUMS (100' O.C.): 290 EACH + 60 ADDITIONAL DRUMS
- STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES REMOVAL OF PERMANENT PAVEMENT MARKINGS: 2,740 LF
- STA. STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES CONSTRUCTION PAVEMENT MARKINGS: 61,760 LF
- STA. STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS: 55,100 LF
- STA. STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS: 2,120 LF
- NB MAIN LANES RELOCATE TEMPORARY PRECAST CONCRETE BARRIER: 1,240 LF WITH 3 TIABS
- SB MAIN LANES RELOCATE TEMPORARY PRECAST CONCRETE BARRIER: 1,120 LF WITH 4 TIABS



MAINTENANCE OF TRAFFIC
STAGE 4A

STAGE 4A OPERATIONS:

- SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
- RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
- REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
- OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
- CONSTRUCT FINAL GRADING IN MEDIAN AREA.
- PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
- CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
- INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
- PLACE FINAL STRIPING ON INSIDE LANES.





Clinton D. Jumper
6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	129	235

② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
STAGE 4A

STAGE 4A OPERATIONS:
 SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
 RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
 REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
 CONSTRUCT FINAL GRADING IN MEDIAN AREA.
 PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
 CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
 INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
 PLACE FINAL STRIPING ON INSIDE LANES.





Clinton D. Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
						JOB NO.	BB0202	130	235

② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 4A

STAGE 4A OPERATIONS:
 SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
 RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
 REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
 CONSTRUCT FINAL GRADING IN MEDIAN AREA.
 PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
 CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
 INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
 PLACE FINAL STRIPING ON INSIDE LANES.





CD Jumper
 6/20/2016



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BBO202	131	235
② MAINTENANCE OF TRAFFIC								

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 4A



STAGE 4A OPERATIONS:
 SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
 RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
 REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
 CONSTRUCT FINAL GRADING IN MEDIAN AREA.
 PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
 CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
 INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
 PLACE FINAL STRIPING ON INSIDE LANES.



Cr Jumper
 6/20/2016


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
						JOB NO.	BB0202	132	235
② MAINTENANCE OF TRAFFIC									

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 4A



STAGE 4A OPERATIONS:
 SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
 RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
 REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
 CONSTRUCT FINAL GRADING IN MEDIAN AREA.
 PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
 CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
 INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
 PLACE FINAL STRIPING ON INSIDE LANES.



CD Jumper
 6/20/2016


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0202	133	235
② MAINTENANCE OF TRAFFIC								

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 4A


STAGE 4A OPERATIONS:
 SHIFT SB TRAFFIC TO OUTSIDE SB LANE.
 RETAIN NB TRAFFIC IN OUTSIDE NB LANE.
 REMOVE PRIMARY MAIN LANE PRECAST CONCRETE BARRIER.
 OBLITERATE REMAINING CROSSOVERS AND TEMPORARY RAMPS IN MEDIAN AREA.
 CONSTRUCT FINAL GRADING IN MEDIAN AREA.
 PLACE FINAL LIFT OF SURFACE ON INSIDE LANE AND SHOULDER.
 CONSTRUCT WRSF AND GUARDRAIL ON MEDIAN SIDE OF MAIN LANES.
 INSTALL RUMBLE STRIPS ON INSIDE SHOULDERS.
 PLACE FINAL STRIPING ON INSIDE LANES.



Cl D Jumper
 6/20/2016


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	134
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 4A


STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).




Clinton D. Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	135	235

② MAINTENANCE OF TRAFFIC




- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
 TRAFFIC DRUMS (100' O.C.): 263 EACH + 285 ADDITIONAL DRUMS
 STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES
 TRAFFIC DRUMS (100' O.C.): 259 EACH + 292 ADDITIONAL DRUMS

STA. 170+39.48 - STA. 461+95.06 NB MAIN LANES
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS: 56,171 LF
 STA. 170+39.48 - STA. 461+95.06 SB MAIN LANES
 REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS: 55,269 LF



MAINTENANCE OF TRAFFIC
 STAGE 4B



STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).



CD Jumper
 6/20/2016


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
						JOB NO.	BB0202	136	235
② MAINTENANCE OF TRAFFIC									

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 4B



STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).



Clinton D. Jumper
 6/20/2016


DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	137
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 4B

STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).





Clinton D. Juniper
 6/20/2016




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	138
						② MAINTENANCE OF TRAFFIC		

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 4B

STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).





Clinton D. Jumper
 6/20/2016




DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BBO202	139	235
② MAINTENANCE OF TRAFFIC								

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING



MAINTENANCE OF TRAFFIC
 STAGE 4B



STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).



Clinton D. Jumper
 6/20/2016

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
JOB NO.						BB0202	140	235
② MAINTENANCE OF TRAFFIC								

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




MAINTENANCE OF TRAFFIC
 STAGE 4B

STAGE 4B OPERATIONS:
 SHIFT TRAFFIC TO INSIDE LANES OF NB & SB LANES.
 OBLITERATE TEMPORARY RAMPS BETWEEN MAIN LANES AND RAMPS.
 PLACE FINAL LIFT OF SURFACE ON OUTSIDE LANES, SHOULDERS, AND RAMPS.
 CONSTRUCT GUARDRAIL ON OUTSIDE SHOULDER OF MAIN LANES.
 PLACE FINAL STRIPING (SEE PERMANENT PAVEMENT MARKING DETAILS).





Clinton D. Jumper
 6/20/2016



DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	141	235

② MAINTENANCE OF TRAFFIC

- RAMP OBLITERATION
- RAMP CONST. THIS STAGE
- RAMP CONST. PREVIOUS STAGE
- MAIN LANE CONST.
- CONST. GRADING




→ STA. 461+95.06 END WORK ZONE → SEE DETAILS SHEET 84

MAINTENANCE OF TRAFFIC
 STAGE 4B

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO.						BBO202	142	235
② PERMANENT PAVEMENT MARKING DETAILS								


ASPHALT ROADWAY

HIGH PERFORMANCE PAVEMENT MARKINGS:
 SKIP LINE - INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING (SKIP LINE) WHITE (4") ALT. NO. 1
 OR HIGH PERFORMANCE MARKING (SKIP LINE) WHITE (4") TAPE ALT. NO. 2
 EDGE LINES - INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING ALT. NO. 1
 OR HIGH PERFORMANCE MARKING TAPE ALT. NO. 2
 REFER TO SPECIAL PROVISION - HIGH PERFORMANCE PAVEMENT MARKING



CONCRETE APPROACH SLAB & BRIDGE DECK

HIGH PERFORMANCE PAVEMENT MARKINGS:
 SKIP LINE - INVERTED PROFILE THERMOPLASTIC CONTRAST PAVEMENT MARKING WHITE (4") ALT. NO. 1
 OR HIGH PERFORMANCE CONTRAST MARKING TAPE (WHITE) (4") ALT. NO. 2
 EDGE LINES - INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING ALT. NO. 1
 OR HIGH PERFORMANCE MARKING TAPE ALT. NO. 2
 REFER TO SPECIAL PROVISION - HIGH PERFORMANCE PAVEMENT MARKING



NOTES:
 1. REFER TO PM-2 FOR PERMANENT PAVEMENT MARKINGS AT INTERCHANGE.
 2. NO PERMANENT PAVEMENT MARKINGS SHALL BE PLACED UNTIL A MINIMUM OF THREE DAYS AFTER ALL MAIN LANE PAVING HAS BEEN COMPLETED. IN ADDITION, NO PERMANENT PAVEMENT MARKINGS SHALL BE PLACED WITHIN THE PERIOD FROM DECEMBER 21 TO MARCH 15, INCLUSIVE.

PERMANENT PAVEMENT MARKING DETAILS


Leonard.Speed 6/21/2016 10:17:45 AM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD\158215-1-530_Hwy104-Hwy688\Deliverables\ROADWAY\Drawings\BBO202-07_PAV.MARK_01.dgn




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
JOB NO.							BBO202	143	235

② SIGN LAYOUT SHEET


MAINTAIN
OVERHEAD SIGN STRUCTURE
REPLACE OVERHEAD SIGNS




OH-530-189+90SB-A
OH-530-189+90SB-B




OH-530-35-189+90SB-B; 6.0" Radius, 2.0" Border, White on Green;
[S OUTH] ClearviewHwy-5-W-R; [Dumas] E Mod 2K; [McGehee] E Mod 2K;
[Lake Village] E Mod 2K;




OH-530-62-415+00SB-B;
6.0" Radius, 2.0" Border, White on Green;
[EXIT] E Mod 2K; [35] E Mod 2K;
12.0" Radius, 2.0" Border, White on Green;
[S] E Mod 2K [] ClearviewHwy-5-W [OUTH] E Mod 2K; [Martha Mitchell] E Mod 2K; [Expressway] E Mod 2K;
Standard Arrow Custom 33.4" X 20.3" 45°;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO.	BB0202	144
						SIGN LAYOUT SHEET		




GM-530-205+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [35] E Mod 2K;
 12.0" Radius, 2.0" Border, White on Green;
 [SOUTH] E Mod 2K; [Martha Mitchell] E Mod 2K; [Expressway] E Mod 2K; [1/2 MILE] E Mod 2K;




GM-530-251+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [35] E Mod 2K;
 12.0" Radius, 2.0" Border, White on Green;
 [SOUTH] E Mod 2K; [Martha Mitchell] E Mod 2K; [Expressway] E Mod 2K; [1 MILE] E Mod 2K;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
JOB NO.							BB0202	145	235
SIGN LAYOUT SHEET									



GM-530-198+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [University of Arkansas] E Mod; [Pine Bluff] E Mod; [Natural State Golf] E Mod; [Trail] E Mod; [EXIT 35] E Mod;



GM-530-240+00SB; 6.0" Radius, 2.0" Border, White on Brown;
 [Governor] E Mod 2K; [Mike Huckabee] E Mod 2K; [Delta Rivers] E Mod 2K;
 [Nature Center] E Mod 2K; [EXIT 35] E Mod 2K;




GM-530-246+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [Pine Bluff] E Mod 2K; [NEXT 8 EXITS] E Mod 2K;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. NO. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.		BB0202	146	235


② SIGN LAYOUT SHEET



GM-530-278+00SB; 3.0" Radius, 2.0" Border, 0.5" Indent, White on Green;
 [EXIT] E Mod 2K; [34] E Mod 2K 105% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; [Sheridan] E Mod 2K; [¾ MILE] E Mod 2K;



GM-530-317+00SB; 3.0" Radius, 2.0" Border, 0.5" Indent, White on Green;
 [EXIT] E Mod 2K; [34] E Mod 2K 105% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; [Sheridan] E Mod 2K; [1 MILE] E Mod 2K;




GM-530-265+00SB; 6.0" Radius, 2.0" Border, 0.5" Indent, White on Green;
 [EXIT] E Mod 2K 102% spacing; [34] E Mod 2K;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; [Sheridan] E Mod 2K; Standard Arrow Custom 0.0" X 20.3" 45°;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						BBO202	147	235


② SIGN LAYOUT SHEET



GM-530-227+00NB; 6.0" Radius, 2.0" Border, 0.5" Indent, White on Green;
 [EXIT] E Mod 2K 102% spacing; [34] E Mod 2K;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; [Sheridan] E Mod 2K; Standard Arrow Custom 0.0" X 20.3" 45°;




GM-530-364+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [32] E Mod 2K 108% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; Standard Arrow Custom 33.4" X 20.3" 45°;




GM-530-330+00NB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [32] E Mod 2K 108% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; Standard Arrow Custom 33.4" X 20.3" 45°;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO202	I48	235	
② SIGN LAYOUT SHEET								




GM-530-434+90NB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K 105% spacing;
 [30] E Mod 2K 105% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 Standard Arrow Custom 33.4" X 20.3" 45°;



GM-530-390+00NB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K;
 [30] E Mod 2K 105% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 [1] E Mod 2K; [MILE] E Mod 2K;




GM-530-278+00NB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [32] E Mod 2K 108% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; [1 MILE] E Mod 2K;




GM-530-413+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [32] E Mod 2K 108% spacing;
 6.0" Radius, 2.0" Border, White on Green;
 [White Hall] E Mod 2K; [1 MILE] E Mod 2K;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. BBO202	149	235



LL-530-195+00NB; 6.0" Radius, 2.0" Border, White on Blue;
[LODGING-EXIT 34] C 2K;




LF-530-203+00NB; 6.0" Radius, 2.0" Border, White on Blue;
[FOOD-EXIT 34] C 2K;




LG-530-211+00NB; 6.0" Radius, 2.0" Border, White on Blue;
[GAS-EXIT 34] C 2K;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						BB0202	150	235
							(2)	SIGN LAYOUT SHEET




LG-530-292+00SB; 6.0" Radius, 2.0" Border, White on Blue;
[GAS-EXIT 34] C 2K;



LF-530-299+00SB; 6.0" Radius, 2.0" Border, White on Blue;
[FOOD-EXIT 34] C 2K;




LL-530-306+00NB; 6.0" Radius, 2.0" Border, White on Blue;
[LODGING-EXIT 34] C 2K;




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						BBO202	151	235


② SIGN LAYOUT SHEET



LGF-530-285+00NB; 6.0" Radius, 2.0" Border, White on Blue;
 [GAS-EXIT 32] C 2K; [FOOD-EXIT 32] C 2K;





LGF-530-404+00NB; 6.0" Radius, 2.0" Border, White on Blue;
 [GAS-EXIT 32] C 2K; [FOOD-EXIT 32] C 2K;





DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				6	ARK.				
JOB NO.							BBO202	152	235
SIGN LAYOUT SHEET									


STANDARD SIGNS

G-2

 M3-1 30"X15"
 MI-1 45"X36"
 SS-530-268+00NB
 SS-530-372+00NB


G-2

 M3-3 30"X15"
 MI-1 45"X36"
 SS-530-221+00SB
 SS-530-322+00SB
 SS-530-423+00SB

G-2

 R2-1 48"X60"
 SS-530-212+IOSB
 SS-530-274+00NB
 SS-530-313+00SB
 SS-530-383+00NB
 SS-530-416+00SB


G-2

 R4-3 48"X60"
 SS-530-217+50SB
 SS-530-271+00NB
 SS-530-319+00SB
 SS-530-377+00NB
 SS-530-420+00SB





EX-530-179+50SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [35] E Mod 2K;
 Arrow Custom - 29.0" 45°;




EX-530-233+00NB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [34] E Mod 2K;
 Arrow Custom - 29.0" 45°;


G-2

 WI3-3 48"X60"
 SS-530-182+00SB
 SS-530-231+00NB
 SS-530-260+00SB
 SS-530-3321+00NB
 SS-530-436+00NB

G-2

 W4-IR 48"X48"
 SS-530-171+00NB
 SS-530-237+00SB
 SS-530-252+00NB
 SS-530-336+00SB
 SS-530-354+00NB
 SS-530-441+00SB



G-2

 W8-13 48"X48"
 SS-530-235+00NB
 SS-530-253+00SB
 SS-530-239+00NB
 SS-530-354+00SB
 SS-530-442+00NB




EX-530-255+90SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [34] E Mod 2K;
 Arrow Custom - 29.0" 45°;





EX-530-335+60NB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [32] E Mod 2K;
 Arrow Custom - 29.0" 45°;

OM-3L 12"X36"
 UI-1
 OM-3R 12"X36"




- SS 530-242+50NB-A
- SS 530-242+50NB-B
- SS 530-245+50SB-A
- SS 530-245+50SB-B
- SS 530-344+50NB-A
- SS 530-344+50NB-B
- SS 530-347+00SB-A
- SS 530-347+00SB-B
- SS-530-448+IONB-A
- SS-530-448+IONB-B

G-2

 WI3-3 48"X60"
 SS-530-362+00SB

G-2

 WI-2RT 48"X48"
 SS-530-178+00SB-A
 SS-530-178+00SB-B




EX-530-358+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [32] E Mod 2K;
 Arrow Custom - 29.0" 45°;



EX-530-358+00SB;
 6.0" Radius, 2.0" Border, White on Green;
 [EXIT] E Mod 2K; [30] E Mod 2K;
 Arrow Custom - 29.0" 45°;



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BBO202							153	235
② SIGN PLACEMENT SHEET								



REPLACE
SS-530-178+00SB-A
SS-530-178+00SB-B

REPLACE
EX-530-179+50SB




REPLACE
SS-530-171+00NB

STA. 175+14.73
BEGIN JOB BBO202
L.M. 34.90

STA. 165+00 TO STA. 180+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	154	235	

2 SIGN PLACEMENT SHEET





NOTE: EXISTING VERTICAL CLEARANCE UNDER SIGN AT STA. 189+78 IS 19'-2"; A MINIMUM 17'-0" VERTICAL CLEARANCE IS REQUIRED FOR FINISHED ROADWAY.


STA. 180+00 TO STA. 195+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.		BBO202	155	235


2 SIGN PLACEMENT SHEET



INSTALL
GM-530-198+00SB
REMOVE EXISTING SIGNS




REPLACE
GM-530-205+00SB




TRIP. 4'X3' BC




C.L. I-530



INSTALL
LF-530-203+00NB
REMOVE EXISTING



INSTALL
LL-530-195+00NB
REMOVE EXISTING




STA. 195+00 TO STA. 209+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
JOB NO.							BBO202	156	235
②								SIGN PLACEMENT SHEET	



MAINTAIN
OVERHEAD SIGN & SIGN STRUCTURE
VMS-530-212+IOSB



INSTALL
SS-530-212+IOSB



INSTALL
SS-530-217+50SB



INSTALL
SS-530-221+00SB



300' TAPER





INSTALL
LG-530-211+00NB

NOTE: EXISTING VERTICAL CLEARANCE OF OVERHEAD SIGN STRUCTURE AT STA. 212+20 IS 18'-3". A MINIMUM 17'-0" VERTICAL CLEARANCE IS REQUIRED FOR FINISHED ROADWAY.

STA. 209+00 TO STA. 224+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BBO202	157	235	
SIGN PLACEMENT SHEET								



REPLACE
GM-530-227+00NB

White Hall
Sheridan

EXIT 34

REPLACE
SS-530-231+00NB

EXIT 40

REPLACE
EX-530-233+00NB

EXIT 34



INSTALL
SS-530-235+00NB

BRIDGE
ICES BEFORE
ROAD

REPLACE
SS-530-237+00SB






DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.		158	235
				JOB NO.		BB0202	158	235
				SIGN PLACEMENT SHEET				




STA. 240+00 TO STA. 250+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
				JOB NO.	BB0202	159	235		
								2	SIGN PLACEMENT SHEET





STA. 250+00 TO STA. 264+00



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
								160
								235
SIGN PLACEMENT SHEET								



INSTALL
GM-530-265+00SB



INSTALL
LG-530-292+00SB
REMOVE EXISTING




STA. 264+00 TO STA. 294+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BBO202							161	235



② SIGN PLACEMENT SHEET



INSTALL
LF-530-299+00SB
REMOVE EXISTING




INSTALL
LL-530-306+00SB
REMOVE EXISTING



INSTALL
SS-530-313+00SB




INSTALL
GM-530-317+00SB



INSTALL
SS-530-319+00SB






INSTALL
SS-530-322+00SB




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
JOB NO.							BBO202	162	235

② SIGN PLACEMENT SHEET



STA. 325+00 TO STA. 340+00



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.		BB0202	163	235
				SIGN PLACEMENT SHEET				



STA. 340+00 TO STA. 354+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BB0202	164	235	


2 SIGN PLACEMENT SHEET



STA. 354+00 TO STA. 367+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BBO202							165	235

2 SIGN PLACEMENT SHEET



INSTALL
SS-530-372+00NB
REMOVE EXISTING

INSTALL
SS-530-377+00NB
REMOVE EXISTING

INSTALL
SS-530-383+00NB
REMOVE EXISTING

INSTALL
SS-530-390+00NB




STA. 367+00 TO STA. 397+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
							JOB NO. BBO202	166	235

② SIGN PLACEMENT SHEET



INSTALL
LFG-530-404+00SB
REMOVE EXISTING



INSTALL
GM-530-413+00SB
REMOVE EXISTING

REPLACE
SS-530-416+00SB




TRIP 8'x6' BC

REPLACE
SS-530-420+00SB





REPLACE
SS-530-423+00SB





STA. 397+00 TO STA. 427+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BBO202	167	235	
② SIGN PLACEMENT SHEET								






STA. 427+00 TO STA. 443+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
								168
								235
								(2) SIGN PLACEMENT SHEET



STA. 443+00 TO STA. 455+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
								169
								235
②								SIGN PLACEMENT SHEET



STA. 455+00 TO STA. 467+00

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						JOB NO. BBO202	170	235
② SIGNING QUANTITIES SHEET								

SIGNING SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	TOTAL	UNIT
725	GUIDE SIGN - OVERHEAD MOUNTED (DEMOUNTABLE LEGEND)	448	SQ. FT.
725	GUIDE SIGN - ROADSIDE MOUNTED (DEMOUNTABLE LEGEND)	3682	SQ. FT.
726	STANDARD SIGN	574	SQ. FT.
727	EXIT NUMBER PANEL (TYPE A)	260	SQ. FT.
SP	OMNI-DIRECTIONAL BREAKAWAY SIGN SUPPORTS (TYPE G-2)	34	EACH
SP & 729	CHANNEL POST SIGN SUPPORT (TYPE U-1)	10	EACH
730	BREAKAWAY SIGN SUPPORT (TYPE G-2)	22889	POUND

NOTES:

ALL EXISTING GUIDE SIGNS SHALL BE MAINTAINED IN SUCH A MANNER THAT THE SIGNS ARE FULLY VISIBLE, INTACT, AND ERECT FOR THE DURATION OF THE PROJECT, AND SHALL BE REMOVED WHEN THEIR USE IS NO LONGER REQUIRED. REMOVAL AND DISPOSAL OF ROADSIDE MOUNTED SIGNS, SUPPORTS SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED SUBSIDIARY TO OTHER ITEMS IN THE CONTRACT.

THE EXISTING SIGNS AND POSTS SHALL BECOME THE PROPERTY OF THE CONTRACTOR. THE EXISTING FOOTINGS SHALL BE REMOVED AND THE HOLES FILLED WITH A SUITABLE MATERIAL AND COMPACTED.

EXISTING LOGOS WILL BE RELOCATED TO THE NEW LOGO SIGN BY THE CONTRACTOR. THE LOGO INSTALLATION SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED SUBSIDIARY TO OTHER ITEMS IN THE CONTRACT.

NOTE:

BREAKAWAY SIGN SUPPORT TOTAL IS CALAULATED BY TAKING THE LENGTH OF H1, H2, H3 AND THE STUB POST AND MULTIPLYING BY THE BEAM WEIGHT (LBS).




DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
				JOB NO.	BBO202	171	235	

② SIGNING QUANTITIES SHEET

MAIN LANES SIGNING QUANTITIES

SIGN NO./ LOCATION	STRUCTURE TYPE					BREAKAWAY SIGN SUPPORT													EXIT NUMBER PANEL					
	ST	CL	OH	BM	G-2	GUIDE SIGN		STEEL SECT.		SIGN POST LENGTH			STUB POST			FOOTINGS			SIGN POST AND STUB POUND	LEGEND	TYPE			
						Length	Height	SQ. Ft.	A-572		H - 1	H - 2	H - 3	H - 1	H - 2	H - 3	DIA.	DEPTH			EMBED.	A	B	C
									BEAM	LBS														
EXIT 30																								
EX-530-440+40NB					1	6.00	5.00	30.00	W6	9	12.00	13.00		2.33	2.33		1.50	3.00	2.00	266.94				
GM-530-434+90NB					1	10.50	5.00	52.50	W8	18	12.00	13.00		3.99	3.99		2.50	5.50	3.66	593.64	32	20.00		
GM-530-390+00NB					1	8.00	7.00	56.00	W8	18	14.00	15.00		3.99	3.99		2.50	5.50	3.66	665.64	32	20.00		
EXIT 32																								
EX-530-358+00SB					1	6.00	5.00	30.00	W6	9	12.00	13.00		3.99	3.99		2.00	5.50	3.66	296.82				
EX-530-335+60NB					1	6.00	5.00	30.00	W6	9	12.00	13.00		3.99	3.99		2.00	5.50	3.66	296.82				
GM-530-413+00SB					1	13.00	9.50	123.50	W8	21	16.50	17.50		4.99	4.99		2.50	7.00	4.66	923.58	32	20.00		
GM-530-330+00NB					1	16.50	7.60	125.40	W8	21	14.50	15.50		4.99	4.99		2.50	7.00	4.66	839.58	32	20.00		
GM-530-278+00NB					1	13.00	9.50	123.50	W8	21	16.50	17.50		4.99	4.99		2.50	7.00	4.66	923.58	32	20.00		
GM-530-364+00SB					1	16.50	7.60	125.40	W8	21	14.50	15.50		4.99	4.99		2.50	7.00	4.66	839.58	32	20.00		
LFG-530-404+00SB					1	12.00	16.00	192.00	W10	22	23.00	24.00		3.99	3.99		2.50	5.50	3.66	1209.56				
LFG-530-285+00NB					1	12.00	16.00	192.00	W10	22	23.00	24.00		3.99	3.99		2.50	5.50	3.66	1209.56				
EXIT 34																								
EX-530-255+90SB					1	6.00	5.00	30.00	W6	9	12.00	13.00		2.33	2.33		1.50	3.00	2.00	266.94				
EX-530-233+00NB					1	6.00	5.00	30.00	W6	9	12.00	13.00		2.33	2.33		1.50	3.00	2.00	266.94				
GM-530-317+00SB					1	13.00	12.00	156.00	W8	21	19.00	20.00		3.99	3.99		2.50	5.50	3.66	986.58	34	20.00		
GM-530-278+00SB					1	13.00	12.00	156.00	W8	21	19.00	20.00		3.99	3.99		2.50	5.50	3.66	986.58	34	20.00		
GM-530-265+00SB					1	16.00	10.00	160.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58	34	20.00		
GM-530-227+00NB					1	16.00	10.00	160.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58	34	20.00		
LG-530-292+00SB					1	12.00	13.50	162.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58				
LF-530-299+00SB					1	12.00	13.50	162.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58				
LL-530-306+00SB					1	12.00	13.50	162.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58				
LL-530-195+00NB					1	12.00	13.50	162.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58				
LF-530-203+00NB					1	12.00	13.50	162.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58				
LG-530-211+00NB					1	12.00	13.50	162.00	W8	21	17.00	18.00		3.99	3.99		2.50	5.50	3.66	902.58				
EXIT 35																								
EX-530-179+50SB					1	6.00	5.00	30.00	W6	9	12.00	13.00		2.33	2.33		1.50	3.00	2.00	266.94				
GM-530-251+00SB					1	18.50	12.00	222.00	W12	26	19.00	20.00		4.99	4.99		3.00	7.00	3.66	1273.48	35	20.00		
GM-530-205+00SB					1	18.50	12.00	222.00	W12	26	19.00	20.00		4.99	4.99		3.00	7.00	3.66	1273.48	35	20.00		
GM-530-198+00SB					1	22.50	11.50	258.75	W12	26	18.50	19.50		4.99	4.99		3.00	7.00	3.66	1247.48				
GM-530-246+00SB					1	10.50	4.50	47.25	W6	9	11.50	12.50		2.33	2.33		1.50	3.00	2.00	257.94				
GM-530-240+00SB					1	15.00	10.50	157.50	W8	21	14.00	15.00		3.99	3.99		2.50	5.50	3.66	776.58				
OH-530-189+90SB-A			1			20.00	13.00	260.00													35	20.00		
OH-530-189+90SB-B			1			15.00	12.50	187.50																
GUIDE SIGNS ROADSIDE MOUNTED TOTALS;								3,681.80																
GUIDE SIGNS OVERHEAD MOUNTED TOTALS; (SIGNS ONLY)								447.50																
TOTALS:								4,129.30																
																		22,888.88						



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.			
						BBO20I	172	235

② SIGNING QUANTITIES SHEET

STANDARD SIGNS FLAT SHEET													
OMNI-DIRECTIONAL BREAKAWAY SIGN SUPPORTS													
SIGN NO./	TYPE												STANDARD
	G1	G2	G2-1	G2-2	G2-3	G2-4	G2-5	G2-6	G2-7	G2-8	G2-9	G2-10	
LOCATION	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	SQ. FT.
SS-530-268+00NB		1											3.13
SS-530-372+00NB		1											3.13
SS-530-221+00SB		1											3.13
SS-530-322+00SB		1											3.13
SS-530-423+00SB		1											3.13
SS-530-212+10SB		1											20.00
SS-530-274+00NB		1											20.00
SS-530-313+00SB		1											20.00
SS-530-383+00NB		1											20.00
SS-530-416+00SB		1											20.00
SS-530-217+50SB		1											20.00
SS-530-271+00NB		1											20.00
SS-530-319+00SB		1											20.00
SS-530-377+00NB		1											20.00
SS-530-420+00SB		1											20.00
SS-530-182+00SB		1											20.00
SS-530-231+00NB		1											20.00
SS-530-260+00SB		1											20.00
SS-530-3321+00NB		1											20.00
SS-530-436+00NB		1											20.00
SS-530-171+00NB		1											16.00
SS-530-237+00SB		1											16.00
SS-530-252+00NB		1											16.00
SS-530-336+00SB		1											16.00
SS-530-354+00NB		1											16.00
SS-530-441+00SB		1											16.00
SS-530-235+00NB		1											16.00
SS-530-253+00SB		1											16.00
SS-530-239+00NB		1											16.00
SS-530-354+00SB		1											16.00
SS-530-442+00NB		1											16.00
SS-530-178+00SB-A		1											16.00
SS-530-178+00SB-B		1											16.00
SS-530-362+00SB		1											20.00
TOTALS:		34											543.65

STANDARD SIGNS FLAT SHEET													
CHANNEL POST SIGN SUPPORTS													
SIGN NO./	TYPE												STANDARD
	U1	U2	U2-1	U2-2	U2-3	U2-4	U2-5	U2-6	U2-7	U2-8	U2-9	U2-10	
LOCATION	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	SQ. FT.
SS 530-242+50NB-A	1												3.00
SS 530-242+50NB-B	1												3.00
SS 530-245+50SB-A	1												3.00
SS 530-245+50SB-B	1												3.00
SS 530-344+50NB-A	1												3.00
SS 530-344+50NB-B	1												3.00
SS 530-347+00SB-A	1												3.00
SS 530-347+00SB-B	1												3.00
SS-530-448+10NB-A	1												3.00
SS-530-448+10NB-B	1												3.00
TOTALS:	10												30.00



MAINTENANCE OF TRAFFIC ITEMS

STATION	STATION	LOCATION	MOBILE SPEED NOTIFICATION SYSTEM	TRAFFIC CONTROL SUPERVISOR	PORTABLE CONSTRUCTION LIGHTING		ADVANCE WARNING ARROW PANEL		PORTABLE CHANGEABLE MESSAGE SIGN	MODULAR GLARE SHIELD
			EACH	LUMP SUM	TOTAL NO.	DAY	SIGNS	DAY		
							WEEK	LIN. FT.		
ENTIRE PROJECT IF AND WHERE DIRECTED BY ENGINEER			2	1.00						400
ENTIRE PROJECT - CROSSOVER LOCATIONS					4	800				
WIDE LOAD DETOUR (REFER TO PLAN SHEET 85) BEG & END OF PROJECT							2	110		
TOTALS:			2	1.00	4	800	2	250		400

NOTE: THIS IS A HIGH TRAFFIC VOLUME ROAD AS DEFINED IN SECTION 604.03 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 2014 EDITION.

AUTOMATED WORK ZONE INFORMATION SYSTEM

LOCATION	FURNISH AND INSTALL VEHICLE DETECTION SYSTEM	FURNISH AND INSTALL CLOSED CIRCUIT TELEVISION SYSTEM	FURNISH AND INSTALL VARIABLE MESSAGE SIGN	FURNISH AND INSTALL PUBLIC NOTIFICATION SYSTEM	* AWIS OPERATION	AWIS MOBILIZATION	* DEVICE RELOCATION
	EACH	EACH	EACH	EACH	MONTH	LUMP SUM	EACH
1/2 MILE BEFORE & AFTER PROJECT; 1 MI SPACING WITHIN JOB LIMITS	16						
ONE @ EXITS 30, 32, 34, AND 35		4					
NB - IN ADVANCE OF EXITS 39, 37, 36, 35, 34, & 32			10				
SB - IN ADVANCE OF EXITS 34, 32, 30, & 27				2			
1 @ MI MARKER 28 & 1 @ EXIT 37					16		
ESTIMATED QUANTITY: IF AND WHERE DIRECTED BY THE ENGINEER						1.00	16
TOTALS:	16	4	10	2	16	1.00	16

* QUANTITIES ESTIMATED. REFER TO SECTION 104.03 OF THE STANDARD SPECIFICATIONS

ADVANCE WARNING SIGNS AND DEVICES


SIGN NUMBER	DESCRIPTION	SIGN SIZE	ADVANCED WARNING BEGINNING	ADVANCED LANE CONTINUES	STAGE 1A	STAGE 1B	STAGE 2A	STAGE 2B	STAGE 3A	STAGE 3B	STAGE 4A	STAGE 4B	MAXIMUM NUMBER REQUIRED	TOTAL SIGNS REQUIRED		VERTICAL PANELS	TRAFFIC DRUMS	BARRICADES (TYPE III)		FURNISHING & INSTALLING PRECAST CONC. BARRIER	RELOCATING PRECAST CONCRETE BARRIER	TEMPORARY IMPACT ATTENUATION BARRIER	TEMP. IMPACT ATTEN. BARR. (REPAIR)	TEMP. IMPACT ATTEN. BARR. (RELOCATION)
														NO.	SQ. FT.			RIGHT	LEFT					
W20-1	ROAD WORK AHEAD	48"x48"		4		3	3	3	3	3	3	3	7	7	112.0									
W3-5	REDUCED SPEED AHEAD	48"x48"		4									4	4	64.0									
W20-1	ROAD WORK 1 MILE	48"x48"	4										4	4	64.0									
W20-1	ROAD WORK 1/2 MILE	48"x48"	4										4	4	64.0									
W20-1	ROAD WORK 1500 FT.	48"x48"	4			1							5	5	80.0									
W20-1	ROAD WORK 1000 FT.	48"x48"				1							1	1	16.0									
W20-1	ROAD WORK 500 FT.	48"x48"				5	3	3	3	3	3	3	5	5	80.0									
W20-5	RIGHT LANE CLOSED 1 MILE	48"x48"		4									4	4	64.0									
W20-5	RIGHT LANE CLOSED 1/2 MILE	48"x48"		4									4	4	64.0									
W20-5	RIGHT LANE CLOSED 1500 FT.	48"x48"		4									4	4	64.0									
G20-2	END ROAD WORK	48"x24"	4			7	7	7	7	7	7	7	11	11	88.0									
G20-1	ROAD WORK NEXT xx MILES	60"x24"	2	2									2	2	20.0									
W1-2R	CURVE RT.	48"x48"					3	3	3	3			3	3	48.0									
W13-1	SPEED LIMIT (ADVISORY)	24"x24"					3	3	3	3			3	3	12.0									
R11-2	ROAD CLOSED	48"x30"			26	38	32	33	35	27	20	12	38	38	380.0									
W1-6	LARGE ARROW	60"x30"		6									6	6	75.0									
W1-8	CHEVRONS	36"x48"						21	21	18	18		21	21	252.0									
R2-1	SPEED LIMIT	48"x60"		8									8	8	160.0									
R2-2	SPEED LIMIT TRUCKS	48"x48"		4									4	4	64.0									
R4-1	DO NOT PASS	48"x60"		8									8	8	160.0									
R55-1	FINES DOUBLE	36"x60"	4										4	4	60.0									
W4-2R	RIGHT LANE CLOSED	48"x48"		4	6	6	6	6	6	6	6	6	10	10	160.0									
SPECIAL	MERGE NOW	48"x48"		2									2	2	32.0									
	WIDE LOAD & ALT. ROUTE DETOUR SIGNS														299.3									
RSP-1	SHOULDER CLOSED (IF & WHERE DIRECTED)	48"x30"																						
	VERTICAL PANELS						294	294	294	294			294			294								
	TRAFFIC DRUMS				652	1291	322	235	376	222	703	1099	1291				1291							
	TYPE III BARRICADE-RT. (16')					6	20	23	21	19	7	6	23					368						
	TYPE III BARRICADE-LT. (16')				26	32	12	10	14	8	13	6	32						512					
	FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER					3120	28080						31200							31200				
	RELOCATING PRECAST CONCRETE BARRIER					3120					1080		35400								35400			
	TEMPORARY IMPACT ATTENUATION BARRIER					8	5		7		7		8								8			
	TEMPORARY IMPACT ATTENUATION BARRIER (REPAIR)					8	5		7		7		8									8		
	TEMPORARY IMPACT ATTENUATION BARRIER (RELOCATION)						5		7		4		16											16
TOTALS:														2482.3	294	1291	368	512		31200	35400	8	8	16

NOTES: THIS IS A HIGH TRAFFIC VOLUME ROAD AS DEFINED IN SECTION 604.03, STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
 THE QUANTITY OF TRAFFIC DRUMS PROVIDED IS FOR BOTH SIDES OF THE ROADWAY FOR THE FULL LENGTH OF THE JOB. HOWEVER,
 THE INSTALLATION OF TRAFFIC DRUMS SHALL NEVER EXCEED THE ACTUAL WORK AREA BY MORE THAN 1/4 MILE, UNLESS APPROVED BY THE ENGINEER.

CONSTRUCTION PAVEMENT MARKINGS AND PERMANENT PAVEMENT MARKINGS

DESCRIPTION	STAGE 1A	STAGE 1B	STAGE 2A	STAGE 2B	STAGE 3A	STAGE 3B	STAGE 4A	STAGE 4B	REMOVAL OF PERMANENT PAVEMENT MARKINGS	CONSTRUCTION PAVEMENT MARKINGS	REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS	RAISED PAVEMENT MARKERS	HIGH PERFORMANCE CONTRAST PAVEMENT MARKING	HIGH PERFORMANCE PAVEMENT MARKING										
	LIN. FT. - EACH													LIN. FT.	LIN. FT.	LIN. FT.								
														EACH	EACH									
REMOVAL OF PERMANENT PAVEMENT MARKINGS								2740		64680														
CONSTRUCTION PAVEMENT MARKINGS			56580		135440			63360		300240														
REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS								57220	111440		168660													
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED)												1333												
HIGH PERFORMANCE CONTRAST PAVEMENT MARKING WHITE (4")													286											
HIGH PERFORMANCE PAVEMENT MARKING WHITE (4")														57931										
HIGH PERFORMANCE MARKING TAPE (SKIP LINE) WHITE (4")																13348								
HIGH PERFORMANCE PAVEMENT MARKING YELLOW (4")																					59011			
HIGH PERFORMANCE PAVEMENT MARKING WHITE (8")																								3532
TOTALS:									64680	300240	168660	1333	286	57931	13348	59011								3532

NOTES: THIS IS A HIGH TRAFFIC VOLUME ROAD AS DEFINED IN SECTION 604.03, STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
 NO PERMANENT PAVEMENT MARKINGS SHALL BE PLACED UNTIL A MINIMUM OF THREE DAYS AFTER MAIN LANE PAVING HAS BEEN COMPLETED. IN ADDITION, NO PERMANENT PAVEMENT MARKINGS SHALL BE PLACED DURING THE TIME PERIOD FROM DECEMBER 21 TO MARCH 15, INCLUSIVE.



QUANTITIES

Scott Thornsberry/V 2016 11:20 AM
 WORKSPACE: A:\ITD...38205...530...Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_06_001_MAIN_01.dwg

DATE, DATE FILMED, DATE REVISED, DATE FILMED, FED. RD. DIST. NO., STATE, FED. AID PROJ. NO., SHEET NO., TOTAL SHEETS

EROSION CONTROL

Table with columns: STATION, LOCATION, SEEDING, LIME, MULCH COVER, WATER, SECOND SEEDING APPLICATION, TEMPORARY SEEDING, MULCH COVER, WATER, SAND BAG DITCH CHECKS, DROP INLET SILT FENCE, SILT FENCE, SEDIMENT BASIN, OBLITERATION OF SEDIMENT BASIN, *SEDIMENT REMOVAL & DISPOSAL

BASIS OF ESTIMATE: LIME 2 TONS / ACRE OF SEEDING, WATER 102.0 M.G. / ACRE OF SEEDING, WATER 20.4 M.G. / ACRE OF TEMPORARY SEEDING, WATER 12.6 GAL. / SQ. YD. OF SOLID SODDING, SAND BAG DITCH CHECKS 22 BAGS / LOCATION

NOTE: THE TEMPORARY EROSION CONTROL DEVICES SHOWN ABOVE AND ON THE PLANS SHALL BE INSTALLED IN SUCH A SEQUENCE AS TO DETER EROSION AND SEDIMENTATION ON U.S. WATERWAYS AS EXPLAINED BY THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT.

REMOVAL AND DISPOSAL OF PIPE UNDERDRAINS

Table with columns: STATION, LOCATION, PIPE UNDERDRAINS, UNDERDRAIN OUTLET PROTECTORS

NOTE: QUANTITIES ESTIMATED. SEE SECTION 104.03 OF THE STD. SPECS.

REMOVAL AND DISPOSAL OF ITEMS

Table with columns: STATION, LOCATION, CONCRETE DITCH PAVING, RUMBLE STRIPS, IMPACT ATTEN. BARRIER, WIRE ROPE SAFETY FENCE, GUARDRAIL, APPROACH SLAB & GUTTERS

NOTE: THE PAY ITEM FOR REMOVAL AND DISPOSAL OF GUARDRAIL SHALL INCLUDE THE REMOVAL OF ANY TERMINAL ANCHOR POSTS.

CLEARING AND GRUBBING

Table with columns: STATION, LOCATION, CLEARING, GRUBBING

*CLEARING AND GRUBBING WILL BE PERFORMED TO A MINIMUM OF 50 FEET FROM INSIDE AND OUTSIDE SHOULDER EDGES. TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER. SEE SECTION 201 OF THE STANDARD SPECIFICATIONS.

GUARDRAIL


Table with columns: STATION, LOCATION, GUARDRAIL (TYPE A), THRIE BEAM GUARDRAIL TERMINAL, GUARDRAIL TERMINAL (TYPE 2), TERMINAL ANCHOR POST (TYPE 1)

* LOCATION SHALL BE IF AND WHERE DIRECTED BY THE ENGINEER.

EARTHWORK

Table with columns: STATION, LOCATION / DESCRIPTION, UNCLASSIFIED EXCAVATION, COMPACTED EMBANKMENT

NOTE: EARTHWORK QUANTITIES SHOWN ABOVE SHALL BE PAID AS PLAN QUANTITY.



Leonard.Speed 6/21/2016 10:52:28 AM WORKSPACE: Leonard.Speed T:\Projects\NH02_1530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_06_OUT_MAIN_02.dgn

RUBBLIZING & REMOVAL OF PORTLAND AND ASPHALT CEMENT CONCRETE PAVEMENTS

STATION	STATION	** LOCATION	LENGTH LIN. FT.	REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT		RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT		* REMOVAL OF EXISTING P.C. STABILIZED BASE (6" U.T.)		*** SOIL STABILIZATION TON
				WIDTH FEET	SQ. YD.	WIDTH FEET	SQ. YD.	WIDTH FEET	CU. YD.	
175+14.73	186+14.73	FULL DEPTH MAIN LANE LT & SHOULDERS	1100.00	24.00	2933.33			38.00	774.07	193.60
175+14.73	186+14.73	FULL DEPTH MAIN LANE RT & SHOULDERS	1100.00	24.00	2933.33			38.00	774.07	193.60
186+14.73	231+73.40	RUBBLIZE & OVERLAY MAIN LANE LT	4558.67			24.00	12156.45			
186+14.73	231+14.91	RUBBLIZE & OVERLAY MAIN LANE RT	4500.18			24.00	12000.48			
231+73.40	256+91.81	FULL DEPTH MAIN LANE LT & SHOULDERS	2518.41	24.00	6715.76			38.00	1772.21	443.24
231+14.91	256+33.30	FULL DEPTH MAIN LANE RT & SHOULDERS	2518.39	24.00	6715.71			38.00	1772.20	443.24
256+91.81	333+87.14	RUBBLIZE & OVERLAY MAIN LANE LT	7695.33			24.00	20520.88			
256+33.30	333+48.36	RUBBLIZE & OVERLAY MAIN LANE RT	7715.06			24.00	20573.49			
333+87.14	358+41.62	FULL DEPTH MAIN LANE LT & SHOULDERS	2454.48	24.00	6545.28			38.00	1727.23	431.99
333+48.36	358+02.81	FULL DEPTH MAIN LANE RT & SHOULDERS	2454.45	24.00	6545.20			38.00	1727.21	431.98
358+41.62	437+40.77	RUBBLIZE & OVERLAY MAIN LANE LT	7899.15			24.00	21064.40			
358+02.81	438+24.82	RUBBLIZE & OVERLAY MAIN LANE RT	8022.01			24.00	21392.03			
437+40.77	447+40.77	FULL DEPTH MAIN LANE LT & SHOULDERS	1000.00	24.00	2666.67			38.00	703.70	176.00
438+24.82	448+24.82	FULL DEPTH MAIN LANE RT & SHOULDERS	1000.00	24.00	2666.67			38.00	703.70	176.00
178+14.81	184+80.04	LT ENTRANCE LANE TAPER & RETURN - FULL DEPTH	630.50	11.43	800.74			11.43	133.46	110.97
175+78.49	177+78.97	RT ENTRANCE LANE TAPER TO ACCEL LANE - FULL DEPTH	154.80	14.26	245.27			14.26	40.88	27.24
177+78.97	182+78.49	RT LANE ACCELERATION LANE - FULL DEPTH	695.20	12.00	926.93			12.00	154.49	122.36
182+78.49	185+78.49	RT LANE ACCELERATION LANE TAPER - FULL DEPTH	624.70	6.00	416.47			6.00	69.41	109.95
227+54.79	231+14.91	RT EXIT LANE TAPER & RETURN - OVERLAY	756.10			10.33	867.83			
231+14.91	234+23.79	RT EXIT LANE TAPER & RETURN - FULL DEPTH	93.90	12.68	132.29			12.68	22.05	16.53
222+54.01	225+54.01	LT LANE ACCELERATION LANE TAPER - OVERLAY	98.70			6.00	65.80			
225+54.01	231+12.10	LT LANE ACCELERATION LANE - OVERLAY	751.30			12.00	1001.73			
231+12.10	231+73.40	LT ENTRANCE LANE TAPER - OVERLAY	667.10			12.44	922.08			
231+73.40	232+54.01	LT ENTRANCE LANE TAPER - FULL DEPTH	667.10	15.57	1154.08			15.57	192.35	117.41
256+08.85	256+33.30	RT ENTRANCE LANE TAPER - FULL DEPTH	686.20	17.95	1368.59			17.95	228.10	120.77
256+33.30	258+07.00	RT ENTRANCE LANE TAPER - OVERLAY	692.57			14.10	1085.02			
258+07.00	263+08.98	RT LANE ACCELERATION LANE - OVERLAY	702.12			12.00	936.16			
263+08.98	266+08.98	RT LANE ACCELERATION LANE TAPER - OVERLAY	711.67			6.00	474.44			
253+27.19	256+91.81	LT EXIT LANE TAPER & RETURN - FULL DEPTH	721.22	8.46	677.94			8.46	112.99	126.93
256+91.81	263+35.00	LT EXIT LANE TAPER & RETURN - OVERLAY	730.77			12.42	1008.46			
331+03.06	333+48.36	RT ENTRANCE LANE TAPER & RETURN - FULL DEPTH	740.32	4.34	357.00			4.34	59.50	130.30
333+48.36	337+38.32	RT ENTRANCE LANE TAPER & RETURN - OVERLAY	749.87			12.43	1035.65			
322+53.90	325+53.90	LT LANE ACCELERATION LANE TAPER - OVERLAY	759.42			6.00	506.28			
325+53.90	331+03.08	LT LANE ACCELERATION LANE - OVERLAY	768.97			12.00	1025.29			
331+03.08	332+54.09	LT ENTRANCE LANE TAPER - OVERLAY	778.52			14.31	1237.84			
359+12.69	360+54.59	RT ENTRANCE LANE TAPER - OVERLAY	788.07			15.22	1332.71			
360+54.59	366+12.80	RT LANE ACCELERATION LANE - OVERLAY	797.62			12.00	1063.49			
366+12.80	369+12.80	RT LANE ACCELERATION LANE TAPER - OVERLAY	807.17			6.00	538.11			
356+67.13	358+41.62	LT EXIT LANE TAPER & RETURN - FULL DEPTH	816.72	3.21	291.30			3.21	48.55	143.74
358+41.62	363+51.03	LT EXIT LANE TAPER & RETURN - OVERLAY	826.27			10.75	986.93			
435+06.22	438+24.82	RT EXIT LANE TAPER & RETURN - OVERLAY	835.82			8.42	781.95			
438+24.82	441+70.75	RT EXIT LANE TAPER & RETURN - FULL DEPTH	845.37	14.27	1340.38			14.27	223.40	148.78
425+76.51	428+76.51	LT LANE ACCELERATION LANE TAPER - OVERLAY	854.92			6.00	569.94			
428+76.51	434+49.54	LT LANE ACCELERATION LANE - OVERLAY	864.47			12.00	1152.62			
434+49.54	435+76.51	LT ENTRANCE LANE TAPER - OVERLAY	163.80			14.19	258.26			
TOTALS:					45432.94		124558.32		11239.57	3664.63

BASE AND SURFACING - GUARDRAIL WIDENING

STATION	STATION	LOCATION	LENGTH FEET	ACHM SURFACE COURSE (1/2")				AGGREGATE BASE COURSE (CLASS 7)	
				AVG WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 64-22 TON	TON / STATION	TON
185+14.76	185+67.93	LT - R.M.L.	53.17	4.00	23.63	220.00	2.60	20.74	11.03
185+67.93	186+38.47	LT - R.M.L.	70.54	8.00	62.70	220.00	6.90	82.96	58.52
186+38.47	186+53.86	LT - R.M.L.	15.39	6.75	11.54	220.00	1.27	59.04	9.09
186+53.86	190+04.68	LT - R.M.L.	350.82	5.50	214.39	220.00	23.58	39.21	137.56
188+34.13	188+68.25	LT - L.M.L.	34.12	2.75	10.43	220.00	1.15	9.81	3.35
188+37.21	188+68.08	RT - L.M.L.	30.87	2.75	9.43	220.00	1.04	9.80	3.03
188+68.08	193+86.83	RT - L.M.L.	518.75	5.50	317.01	220.00	34.87	39.21	203.40
188+68.25	191+37.71	LT - L.M.L.	269.46	5.50	164.67	220.00	18.11	39.21	105.66
190+04.68	190+17.53	LT - R.M.L.	12.85	6.50	9.28	220.00	1.02	54.76	7.04
190+17.53	190+88.07	LT - R.M.L.	70.54	7.50	58.78	220.00	6.47	72.91	51.43
190+88.07	191+36.21	LT - R.M.L.	48.14	3.75	20.06	220.00	2.21	18.23	8.78
191+36.21	191+89.54	LT - L.M.L.	51.83	2.75	15.84	220.00	1.74	9.81	5.08
193+86.83	194+18.04	RT - L.M.L.	31.21	2.75	9.54	220.00	1.05	9.81	3.06
210+76.97	211+10.00	LT - L.M.L.	33.03	2.75	10.09	220.00	1.11	9.80	3.24
210+77.03	211+10.00	RT - L.M.L.	32.97	2.75	10.07	220.00	1.11	9.80	3.23
211+10.00	214+30.00	RT - L.M.L.	320.00	5.50	195.56	220.00	21.51	39.21	125.47
211+10.00	214+30.14	LT - L.M.L.	320.14	5.50	195.64	220.00	21.52	39.21	125.53
214+30.00	214+62.97	RT - L.M.L.	32.97	2.75	10.07	220.00	1.11	9.80	3.23
214+30.14	214+63.19	LT - L.M.L.	33.05	2.75	10.10	220.00	1.11	9.81	3.24
239+74.09	242+44.38	RT - R.M.L. (HWY. 270 OVERPASS)	270.29	VAR.	101.27	220.00	11.14	14.74	39.84
240+01.89	242+72.30	LT - R.M.L. (HWY. 270 OVERPASS)	270.41	VAR.	101.34	220.00	11.15	14.75	39.89
241+97.25	243+33.58	LT - L.M.L. (HWY. 270 OVERPASS)	136.33	VAR.	55.62	220.00	6.12	17.48	23.83
244+73.13	246+11.48	RT - R.M.L. (HWY. 270 OVERPASS)	138.35	VAR.	40.46	220.00	4.45	8.98	12.42
245+34.42	246+04.82	RT - L.M.L. (HWY. 270 OVERPASS)	270.40	VAR.	101.34	220.00	11.15	14.75	39.88
245+62.27	248+32.89	LT - L.M.L. (HWY. 270 OVERPASS)	270.62	VAR.	102.36	220.00	11.26	15.02	40.65
342+09.87	344+29.01	RT - R.M.L. (HOLLAND AVE. OVERPASS)	219.14	VAR.	101.31	220.00	11.14	22.44	49.18
342+28.36	344+98.72	LT - R.M.L. (HOLLAND AVE. OVERPASS)	270.36	VAR.	101.31	220.00	11.14	14.74	39.85
344+01.83	344+88.17	LT - L.M.L. (HOLLAND AVE. OVERPASS)	86.34	VAR.	39.14	220.00	4.31	21.58	18.63
346+50.60	347+88.15	RT - R.M.L. (HOLLAND AVE. OVERPASS)	137.55	VAR.	39.14	220.00	4.31	8.50	11.69
347+42.49	349+61.67	RT - L.M.L. (HOLLAND AVE. OVERPASS)	219.18	VAR.	101.34	220.00	11.15	22.45	49.21
347+09.74	349+80.15	LT - L.M.L. (HOLLAND AVE. OVERPASS)	270.41	VAR.	101.34	220.00	11.15	14.75	39.89
446+27.77	448+46.98	RT - R.M.L. (HWY. 104 OVERPASS)	219.21	VAR.	92.97	220.00	10.23	18.89	41.41
445+85.88	448+21.11	LT - R.M.L. (HWY. 104 OVERPASS)	235.23	VAR.	96.74	220.00	10.64	17.76	41.78
446+33.73	447+12.87	LT - L.M.L. (HWY. 104 OVERPASS)	79.14	VAR.	24.79	220.00	2.73	10.30	8.15
TOTALS:					2559.30		281.55		1367.27


BASIS OF ESTIMATE:
ACHM SURFACE COURSE (1/2").....94.8% MIN. AGGR.....5.2% ASPHALT BINDER
MAXIMUM NUMBER OF GYRATIONS = 115 FOR PG 64-22

NOTE: PAYMENT MADE FOR REMOVAL OF PLOWABLE PAVEMENT MARKERS WILL BE CONSIDERED SUBSIDIARY TO PRICE BID FOR 'RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT.'
* REMOVAL & DISPOSAL OF P.C. STABILIZED BASE (6" U.T.) WILL BE PAID FOR AS UNCLASSIFIED EXCAVATION.
** ACCELERATION LANE & TAPER LENGTH CALCULATION REMOVES 150' FROM THE STATION DIFFERENCE TO ACCOUNT FOR HALF THE 300' TAPER WIDTH.
*** ESTIMATED ON A LIME APPLICATION RATE OF 8% BY WEIGHT (PER AHTD SPECIFICATION SECTION 301.02) AND A 100 PCF DRY UNIT WEIGHT OF TREATED SUBGRADE.

CULVERT CLEAN OUT

STATION	LOCATION	EACH
ENTIRE PROJECT	TO BE USED IF AND WHERE DIRECTED BY THE ENGINEER	39
TOTAL:		39

QUANTITIES



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BBO202
								178
							QUANTITIES	


BASE AND SURFACING - SHOULDERS

STATION	STATION	LOCATION	LENGTH FEET	BORROW		AGGREGATE BASE COURSE (CLASS 1)		AGGREGATE BASE COURSE (CLASS 7)		TACK COAT				ACHM BASE COURSE (1 1/2")				ACHM BINDER COURSE (1")				ACHM SURFACE COURSE (1/2")				TOTAL PG 76-22 TON
				CU. YD. / LIN. FT.	CU. YD.	TON / STATION	TON	TON / STATION	TON	AVG. WID. FEET	SQ. YD.	GALLONS / SQ. YD.	GALLON	AVG. WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 76-22 TON	AVG. WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 76-22 TON	AVG. WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 76-22 TON	
				<p>OUTSIDE SHOULDERS - MAIN LANES</p> <p>175+90.50 181+80.04 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - LT. 589.54 0.19 112.01 47.00 277.08 41.75 246.13 30.74 2013.61 0.05 100.68 10.38 679.94 440.00 149.59 10.23 670.11 330.00 110.57 10.13 663.56 220.00 72.99 10.00 655.04 220.00 72.05 145.04</p> <p>231+73.40 242+73.40 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - LT. 1100.00 0.19 209.00 47.00 517.00 41.75 459.25 30.74 3757.11 0.05 187.86 10.38 1268.67 440.00 278.11 10.23 1250.33 330.00 206.30 10.13 1238.11 220.00 136.19 10.00 1222.22 220.00 134.44 270.63</p> <p>245+91.81 250+73.89 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - LT. 482.08 0.19 91.60 47.00 226.58 41.75 201.27 30.74 1646.57 0.05 82.33 10.38 556.00 440.00 122.32 10.23 547.96 330.00 90.41 10.13 542.61 220.00 59.69 10.00 535.24 220.00 58.92 118.61</p> <p>333+87.17 344+87.17 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - LT. 1100.00 0.19 209.00 47.00 517.00 41.75 459.25 30.74 3757.11 0.05 187.86 10.38 1268.67 440.00 278.11 10.23 1250.33 330.00 206.30 10.13 1238.11 220.00 136.19 10.00 1222.22 220.00 134.44 270.63</p> <p>347+14.62 358+14.62 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - LT. 1100.00 0.19 209.00 47.00 517.00 41.75 459.25 30.74 3757.11 0.05 187.86 10.38 1268.67 440.00 278.11 10.23 1250.33 330.00 206.30 10.13 1238.11 220.00 136.19 10.00 1222.22 220.00 134.44 270.63</p> <p>437+40.77 447+40.77 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - LT. 1000.00 0.19 190.00 47.00 470.00 41.75 417.50 30.74 3415.56 0.05 170.78 10.38 1153.33 440.00 149.59 10.23 670.11 330.00 110.57 10.13 663.56 220.00 72.99 10.00 655.04 220.00 72.05 145.04</p> <p>175+90.50 181+80.04 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - RT. 589.54 0.19 112.01 47.00 277.08 41.75 246.13 30.74 2013.61 0.05 100.68 10.38 679.94 440.00 149.59 10.23 670.11 330.00 110.57 10.13 663.56 220.00 72.99 10.00 655.04 220.00 72.05 145.04</p> <p>231+14.91 242+14.91 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - RT. 1100.00 0.19 209.00 47.00 517.00 41.75 459.25 30.74 3757.11 0.05 187.86 10.38 1268.67 440.00 278.11 10.23 1250.33 330.00 206.30 10.13 1238.11 220.00 136.19 10.00 1222.22 220.00 134.44 270.63</p> <p>245+33.30 250+73.89 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - RT. 540.59 0.19 102.71 47.00 254.08 41.75 225.70 30.74 1846.42 0.05 92.32 10.38 623.46 440.00 137.17 10.23 614.47 330.00 101.39 10.13 608.46 220.00 66.93 10.00 600.66 220.00 66.07 133.00</p> <p>333+48.36 344+48.36 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - RT. 1100.00 0.19 209.00 47.00 517.00 41.75 459.25 30.74 3757.11 0.05 187.86 10.38 1268.67 440.00 278.11 10.23 1250.33 330.00 206.30 10.13 1238.11 220.00 136.19 10.00 1222.22 220.00 134.44 270.63</p> <p>347+08.81 358+08.81 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - RT. 1100.00 0.19 209.00 47.00 517.00 41.75 459.25 30.74 3757.11 0.05 187.86 10.38 1268.67 440.00 278.11 10.23 1250.33 330.00 206.30 10.13 1238.11 220.00 136.19 10.00 1222.22 220.00 134.44 270.63</p> <p>438+24.82 448+24.82 OUTSIDE SHOULDER - FULL DEPTH NORMAL CROWN - RT. 1000.00 0.19 190.00 47.00 470.00 41.75 417.50 30.74 3415.56 0.05 170.78 10.38 1153.33 440.00 253.73 10.23 1136.67 330.00 187.55 10.13 1125.56 220.00 123.81 10.00 1111.11 220.00 122.22 246.03</p>																						

TOTALS: 11526.78 58819.53 8568.43 254842.18 12742.13 87659.48 21948.03 85785.29 14154.61 84594.12 9305.37 83051.76 9135.63 18441.00

BASIS OF ESTIMATE:
 ACHM SURFACE COURSE (1/2").....94.8% MIN. AGGR.....5.2% ASPHALT BINDER
 ACHM BINDER COURSE (1").....95.5% MIN. AGGR.....4.5% ASPHALT BINDER
 ACHM BASE COURSE (1 1/2").....96.1% MIN. AGGR.....3.9% ASPHALT BINDER
 MAXIMUM NUMBER OF GYRATIONS = 205 FOR PG 76-22

6/21/2016 10:22:48 AM
 Leonard.Speed
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_13825_L-530_Hwy104-Hwy65B-Deliverables\RD\DWG\Dr\cwg\ngs\BBO202_06_OUT_MAIN_06.dgn




QUANTITIES

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	180
						QUANTITIES		

BASE AND SURFACING - MAIN LANES MISC.

STATION	STATION	LOCATION	LENGTH FEET	AGGREGATE BASE COURSE (CLASS 1)		AGGREGATE BASE COURSE (CLASS 7)		TACK COAT				ACHM BASE COURSE (1 1/2")			
				TON / STATION	TON	TON / STATION	TON	AVG. WID. FEET	SQ. YD.	GALLONS / SQ. YD.	GALLON	AVG. WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 76-22 TON
ADDITIONAL FOR LEVELING & SUPERELEVATION CORRECTION															
175+14.73	186+14.73	MAIN LANES - FULL DEPTH - LT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
231+73.40	242+73.40	MAIN LANES - FULL DEPTH - LT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
245+91.81	256+91.81	MAIN LANES - FULL DEPTH - LT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
333+87.17	344+87.17	MAIN LANES - FULL DEPTH - LT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
347+41.62	358+41.62	MAIN LANES - FULL DEPTH - LT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
437+40.77	447+40.77	MAIN LANES - FULL DEPTH - LT.	1000.00	42.41	424.10	63.52	635.20					24.00	2666.67	110.00	146.67
175+14.73	186+14.73	MAIN LANES - FULL DEPTH - RT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
231+14.91	242+14.91	MAIN LANES - FULL DEPTH - RT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
245+33.30	256+33.30	MAIN LANES - FULL DEPTH - RT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
333+48.36	344+48.36	MAIN LANES - FULL DEPTH - RT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
347+08.81	358+08.81	MAIN LANES - FULL DEPTH - RT.	1100.00	38.55	424.05	57.74	635.14					24.00	2933.33	110.00	161.33
438+24.82	448+24.82	MAIN LANES - FULL DEPTH - RT.	1000.00	42.41	424.10	63.52	635.20					24.00	2666.67	110.00	146.67
211+49.38	231+73.40	MAIN LANES - RUBBLIZE & OVERLAY - NC - LT.	2024.02					38.00	8545.86	0.17	1452.80	24.00	5397.39	110.00	296.86
267+25.57	333+87.14	MAIN LANES - RUBBLIZE & OVERLAY - NC - LT.	6661.57					38.00	28126.63	0.17	4781.53	24.00	17764.19	110.00	977.03
358+41.62	358+48.43	MAIN LANES - RUBBLIZE & OVERLAY - NC - LT.	6.81					38.00	28.75	0.17	4.89	24.00	18.16	110.00	1.00
377+60.20	437+40.77	MAIN LANES - RUBBLIZE & OVERLAY - NC - LT.	5980.57					38.00	25251.30	0.17	4292.72	24.00	15948.19	110.00	877.15
211+49.38	231+14.91	MAIN LANES - RUBBLIZE & OVERLAY - NC - RT.	1965.53					38.00	8298.90	0.17	1410.81	24.00	5241.41	110.00	288.28
267+25.57	333+48.36	MAIN LANES - RUBBLIZE & OVERLAY - NC - RT.	6622.79					38.00	27962.89	0.17	4753.69	24.00	17660.77	110.00	971.34
358+02.81	358+48.43	MAIN LANES - RUBBLIZE & OVERLAY - NC - RT.	45.62					38.00	192.62	0.17	32.75	24.00	121.65	110.00	6.69
377+60.20	438+24.82	MAIN LANES - RUBBLIZE & OVERLAY - NC - RT.	6064.62					38.00	25606.17	0.17	4353.05	24.00	16172.32	110.00	889.48
186+14.73	211+49.38	MAIN LANES - RUBBLIZE & OVERLAY - SUPER E - LT.	2534.65					38.00	10701.86	0.17	1819.32	24.00	6759.07	110.00	371.75
256+91.81	267+25.57	MAIN LANES - RUBBLIZE & OVERLAY - SUPER E - LT.	1033.76					38.00	4364.76	0.17	742.01	24.00	2756.69	110.00	151.62
358+48.43	377+60.20	MAIN LANES - RUBBLIZE & OVERLAY - SUPER E - LT.	1911.77					38.00	8071.92	0.17	1372.23	24.00	5098.05	110.00	280.39
186+14.73	211+49.38	MAIN LANES - RUBBLIZE & OVERLAY - SUPER E - RT.	2534.65					38.00	10701.86	0.17	1819.32	24.00	6759.07	110.00	371.75
256+33.30	267+25.57	MAIN LANES - RUBBLIZE & OVERLAY - SUPER E - RT.	1092.27					38.00	4611.81	0.17	784.01	24.00	2912.72	110.00	160.20
358+48.43	377+60.20	MAIN LANES - RUBBLIZE & OVERLAY - SUPER E - RT.	1911.77					38.00	8071.92	0.17	1372.23	24.00	5098.05	110.00	280.39
OUTSIDE SHOULDERS - MAIN LANES															
211+49.38	231+73.40	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	2024.02									10.39	2336.62	110.00	128.51
267+25.57	333+87.14	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	6661.57									10.39	7690.41	110.00	422.97
358+41.62	358+48.43	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	6.81									10.39	7.86	110.00	0.43
377+60.20	437+40.77	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	5980.57									10.39	6904.24	110.00	379.73
211+49.38	231+14.91	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	1965.53									10.39	2269.10	110.00	124.80
267+25.57	333+48.36	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	6622.79									10.39	7645.64	110.00	420.51
358+02.81	358+48.43	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	45.62									10.39	52.67	110.00	2.90
377+60.20	438+24.82	OUTSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	6064.62									10.39	7001.27	110.00	385.07
186+14.73	211+49.38	OUTSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - LT.	2534.65									10.39	2926.11	110.00	160.94
256+91.81	267+25.57	OUTSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - LT.	1033.76									10.39	1193.42	110.00	65.64
358+48.43	377+60.20	OUTSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - LT.	1911.77									10.39	2207.03	110.00	121.39
186+14.73	211+49.38	OUTSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - RT.	2534.65									10.39	2926.11	110.00	160.94
256+33.30	267+25.57	OUTSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - RT.	1092.27									10.39	1260.97	110.00	69.35
358+48.43	377+60.20	OUTSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - RT.	1911.77									10.39	2207.03	110.00	121.39
INSIDE SHOULDERS - MAIN LANES															
211+49.38	231+73.40	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	2024.02									4.39	987.27	110.00	54.30
267+25.57	333+87.14	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	6661.57									4.39	3249.37	110.00	178.72
358+41.62	358+48.43	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	6.81									4.39	3.32	110.00	0.18
377+60.20	437+40.77	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - LT.	5980.57									4.39	2917.19	110.00	160.45
211+49.38	231+14.91	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	1965.53									4.39	958.74	110.00	52.73
267+25.57	333+48.36	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	6622.79									4.39	3230.45	110.00	177.67
358+02.81	358+48.43	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	45.62									4.39	22.25	110.00	1.22
377+60.20	438+24.82	INSIDE SHOULDER-RUBBLIZE & OVERLAY - NC - RT.	6064.62									4.39	2958.19	110.00	162.70
186+14.73	211+49.38	INSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - LT.	2534.65									4.39	1236.35	110.00	68.00
256+91.81	267+25.57	INSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - LT.	1033.76									4.39	504.25	110.00	27.73
358+48.43	377+60.20	INSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - LT.	1911.77									4.39	932.52	110.00	51.29
186+14.73	211+49.38	INSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - RT.	2534.65									4.39	1236.35	110.00	68.00
256+33.30	267+25.57	INSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - RT.	1092.27									4.39	532.79	110.00	29.30
358+48.43	377+60.20	INSIDE SHOULDER - RUBBLIZE & OVERLAY - SUPER E - RT.	1911.77									4.39	932.52	110.00	51.29
TOTALS:					5088.70		7621.80		170537.25		28991.36		208704.41		11478.72

BASIS OF ESTIMATE:
 ACHM SURFACE COURSE (1/2").....94.8% MIN. AGGR.....5.2% ASPHALT BINDER
 ACHM BINDER COURSE (1").....95.5% MIN. AGGR.....4.5% ASPHALT BINDER
 ACHM BASE COURSE (1 1/2").....96.1% MIN. AGGR.....3.9% ASPHALT BINDER
 MAXIMUM NUMBER OF GYRATIONS = 205 FOR PG 76-22



BASE AND SURFACING - SHOULDER RECONSTRUCTION

STATION	STATION	LOCATION	LENGTH	TRENCHING AND SHOULDER PREP		*** SOIL STABILIZATION	ACHM BASE COURSE (1-1/2")				ACHM BINDER COURSE (1")				ACHM SURFACE COURSE (1/2")				TACK COAT			
				FEET	STA.		TON	AVG. WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 76-22 TON	AVG. WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 76-22 TON	AVG. WID. FEET	SQ. YD.	POUND / SQ. YD.	PG 76-22 TON	0.05 GAL. PER SQ. YD.		
																				AVG. WID. FEET	SQ. YD.	GALLONS
172+60.00	242+69.57	RT. - L.M.L. (FOR MOT)	7009.57	70.10	168.23	6.00	4673.05	990.00	2313.16	6.00	4673.05	330.00	771.05	6.00	4673.05	220.00	514.04	12.00	9346.09	467.30		
245+71.26	344+84.63	RT. - L.M.L. (FOR MOT)	9913.37	99.13	237.92	6.00	6608.91	990.00	3271.41	6.00	6608.91	330.00	1090.47	6.00	6608.91	220.00	726.98	12.00	13217.83	660.89		
347+27.99	447+69.33	RT. - L.M.L. (FOR MOT)	10041.34	100.41	240.99	6.00	6694.23	990.00	3313.64	6.00	6694.23	330.00	1104.55	6.00	6694.23	220.00	736.37	12.00	13388.45	669.42		
166+96.25	175+78.99	RAMP D65 LT.	882.74	8.83	21.19									4.00	392.33	220.00	43.16					
175+15.42	175+78.99	RAMP D65 RT.	63.57	0.64	2.54									6.00	42.38	220.00	4.66					
173+61.98	180+24.29	RAMP A65 RT.	662.31	6.62	15.90									4.00	294.36	220.00	32.38					
177+44.16	180+24.29	RAMP A65 LT.	280.13	2.80	11.21									6.00	186.75	220.00	20.54					
232+09.90	237+38.56	HWY. 270 RAMP 1 LT.	528.66	5.29	12.69									4.00	234.96	220.00	25.85					
232+09.90	240+38.56	HWY. 270 RAMP 1 RT.	828.66	8.29	33.15									6.00	552.44	220.00	60.77					
232+53.30	238+14.97	HWY. 270 RAMP 4 RT.	561.67	5.62	13.48									4.00	249.63	220.00	27.46					
232+53.30	241+14.97	HWY. 270 RAMP 4 LT.	861.67	8.62	34.47									6.00	574.45	220.00	63.19					
246+95.37	256+04.89	HWY. 270 RAMP 2 LT.	909.52	9.10	21.83									4.00	404.23	220.00	44.47					
249+95.27	256+04.89	HWY. 270 RAMP 2 RT.	609.62	6.10	24.38									6.00	406.41	220.00	44.71					
248+01.77	256+49.50	HWY. 270 RAMP 3 RT.	847.73	8.48	20.35									4.00	376.77	220.00	41.44					
251+01.77	256+49.50	HWY. 270 RAMP 3 LT.	547.73	5.48	21.91									6.00	365.15	220.00	40.17					
335+08.82	339+96.82	HOLLAND AVE. RAMP 1 LT.	488.00	4.88	11.71									4.00	216.89	220.00	23.86					
335+08.82	342+96.78	HOLLAND AVE. RAMP 1 RT.	787.96	7.88	31.52									6.00	525.31	220.00	57.78					
332+54.25	338+04.25	HOLLAND AVE. RAMP 4 RT.	550.00	5.50	13.20									4.00	244.44	220.00	26.89					
332+54.25	341+04.25	HOLLAND AVE. RAMP 4 LT.	850.00	8.50	34.00									6.00	566.67	220.00	62.33					
350+63.40	359+13.40	HOLLAND AVE. RAMP 2 LT.	850.00	8.50	20.40									4.00	377.78	220.00	41.56					
353+63.40	359+13.40	HOLLAND AVE. RAMP 2 RT.	550.00	5.50	22.00									6.00	366.67	220.00	40.33					
350+30.27	358+80.27	HOLLAND AVE. RAMP 3 RT.	850.00	8.50	20.40									4.00	377.78	220.00	41.56					
353+30.27	358+80.27	HOLLAND AVE. RAMP 3 LT.	550.00	5.50	22.00									6.00	366.67	220.00	40.33					
440+12.09	444+68.94	HWY. 104 RAMP 1 LT.	456.85	4.57	10.96									4.00	203.04	220.00	22.33					
440+12.09	447+68.94	HWY. 104 RAMP 1 RT.	756.85	7.57	30.27									6.00	504.57	220.00	55.50					
435+75.68	441+25.68	HWY. 104 RAMP 4 RT.	550.00	5.50	13.20									4.00	244.44	220.00	26.89					
435+75.68	444+25.68	HWY. 104 RAMP 4 LT.	850.00	8.50	34.00									6.00	566.67	220.00	62.33					
TOTALS:					426.41	1143.90		17976.19		8898.21		17976.19		2966.07	26616.98	2927.88		35952.37	1797.61			


BASIS OF ESTIMATE:
 ACHM SURFACE COURSE (1/2").....94.8% MIN. AGGR.....5.2% ASPHALT BINDER
 ACHM BINDER COURSE (1").....95.5% MIN. AGGR.....4.5% ASPHALT BINDER
 ACHM BASE COURSE (1 1/2").....96.1% MIN. AGGR.....3.9% ASPHALT BINDER
 MAXIMUM NUMBER OF GYRATIONS = 205 FOR PG 76-22
 *** ESTIMATED ON A LIME APPLICATION RATE OF 8% BY WEIGHT (PER AHTD SPECIFICATION SECTION 301.02) AND A 100 PCF DRY UNIT WEIGHT OF TREATED SUBGRADE

BASE AND SURFACING - SUMMARY (PG 76-22)

DESCRIPTION	BORROW	AGGREGATE BASE COURSE (CLASS 1)		AGGREGATE BASE COURSE (CLASS 7)		TACK COAT		ACHM BASE COURSE (1 1/2")		ACHM BINDER COURSE (1")		ACHM SURFACE COURSE (1/2")				
		CU. YD.	TON	TON	SQ. YD.	GALLON	SQ. YD.	PG 76-22 TON	SQ. YD.	PG 76-22 TON	SQ. YD.	PG 76-22 TON	SQ. YD.	PG 76-22 TON	TOTAL PG 76-22 TON	
																TOTAL
BASE AND SURFACING - MAIN LANES	349.26	3627.82	19727.50	443787.46	23303.13	142707.70	35694.82	146082.53	24296.92	149716.05	16465.59	151655.40	16682.12	33147.71		
BASE AND SURFACING - SHOULDERS	11526.78	58819.53	8568.43	254842.18	12742.13	87659.48	21948.03	85785.29	14154.61	84594.12	9305.37	83051.76	9135.63	18441.00		
BASE AND SURFACING - ACCELERATION LANES AND RAMPS			5372.15	44499.38	3187.01	20177.72	3116.31	12160.84	2006.55	12160.84	1337.67	12160.84	1337.67	2675.34		
BASE AND SURFACING - MAIN LANES MISC.		5088.70	7621.80	170537.25	28991.36	208704.41	11478.72									
BASE AND SURFACING - SHOULDER RECONSTRUCTION				35952.37	1797.61	17976.19	8898.21	17976.19	2966.07	26616.98	2927.88			2927.88		
CROSSOVER & TEMP. ACCEL. LANE - BASE & SURFACING				43237.04	2161.86	39910.89	17740.52	3746.31	796.99	38286.57	4211.52			4211.52		
TOTALS	11876.04	67536.05	41289.88	992855.68	72183.10	517136.39	98876.61	265751.16	44221.14	311374.56	34248.03	246868.00	27155.42	61403.45		

BASIS OF ESTIMATE:
 ACHM SURFACE COURSE (1/2").....94.8% MIN. AGGR.....5.2% ASPHALT BINDER
 ACHM BINDER COURSE (1").....95.5% MIN. AGGR.....4.5% ASPHALT BINDER
 ACHM BASE COURSE (1 1/2").....96.1% MIN. AGGR.....3.9% ASPHALT BINDER
 MAXIMUM NUMBER OF GYRATIONS = 205 FOR PG 76-22

Scott.Thornberry/24/2016 11:07:57 AM
 WORKSPACE: scott.thornberry
 Y:\Projects\AHTD\38215.I-530_Hwy04-Hwy65A\Deliverables\ROADWAY\Drawings\RBBO202_06_OUT_MAIN_I.DGN




SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	QUANTITY BIM-HSP-B530(202)	QUANTITY BIM-B530(202)	TOTALS	UNIT
201	CLEARING		341	341	STATION
201	GRUBBING		341	341	STATION
202	REMOVAL AND DISPOSAL OF APPROACH SLAB AND GUTTERS		8	8	EACH
SP & 202	REMOVAL AND DISPOSAL OF CONCRETE DITCH PAVING		12553	12553	SQ. YD.
SP & 202	REMOVAL AND DISPOSAL OF WIRE ROPE SAFETY FENCE		28246	28246	LIN. FT.
SP & 202	REMOVAL AND DISPOSAL OF GUARDRAIL		4150	4150	LIN. FT.
202	REMOVAL AND DISPOSAL OF PIPE UNDERDRAINS		2000	2000	LIN. FT.
SP & 202	REMOVAL AND DISPOSAL OF UNDERDRAIN OUTLET PROTECTORS		8	8	EACH
SP & 210	REMOVAL OF EXISTING PORTLAND CEMENT CONCRETE PAVEMENT		45433	45433	SQ. YD.
SP & 210	UNCLASSIFIED EXCAVATION		53564	53564	CU. YD.
210	BORROW		11876	11876	CU. YD.
SP & 210	COMPACTED EMBANKMENT		21021	21021	CU. YD.
SP & 210	SOIL STABILIZATION		6162	6162	TON
SP & 215	TRENCHING AND SHOULDER PREPARATION		426	426	STATION
SS & 303	AGGREGATE BASE COURSE (CLASS 1)		67536	67536	TON
SS & 303	AGGREGATE BASE COURSE (CLASS 7)		43109	43109	TON
SS & 401	TACK COAT		72443	72443	GAL.
SP & 405	MINERAL AGGREGATE IN ACHM BASE COURSE (1 1/2")		95021	95021	TON
SP & 405	ASPHALT BINDER (PG 76-22) IN ACHM BASE COURSE (1 1/2")		3856	3856	TON
SP, SS, & 406	MINERAL AGGREGATE IN ACHM BINDER COURSE (1")		42231	42231	TON
SP, SS, & 406	ASPHALT BINDER (PG 76-22) IN ACHM BINDER COURSE (1")		1990	1990	TON
SP, SS, & 407	MINERAL AGGREGATE IN ACHM SURFACE COURSE (1/2")		58477	58477	TON
SP, SS, & 407	ASPHALT BINDER (PG 64-22) IN ACHM SURFACE COURSE (1/2")		15	15	TON
SP, SS, & 407	ASPHALT BINDER (PG 76-22) IN ACHM SURFACE COURSE (1/2")		3193	3193	TON
SP & 414	ASPHALT CONCRETE PATCHING FOR MAINTENANCE OF TRAFFIC		130	130	TON
SP & 415	ACHM PATCHING OF EXISTING ROADWAY		130	130	TON
504	APPROACH SLABS		490.44	490.44	CU. YD.
504	APPROACH GUTTERS		246.72	246.72	CU. YD.
507	REMOVAL AND DISPOSAL OF CONCRETE PAVEMENT FOR PATCHING		152	152	SQ. YD.
507	REMOVAL AND DISPOSAL OF CONCRETE PAVEMENT PATCHING (10" UNIFORM THICKNESS)		152	152	SQ. YD.
513	PORTLAND CEMENT CONCRETE PAVEMENT PATCHING (10" UNIFORM THICKNESS)		124558	124558	SQ. YD.
601	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT		1.00	1.00	LUMP SUM
601	MOBILIZATION		1	1	EACH
SP & 602	FURNISHING FIELD OFFICE		1.00	1.00	LUMP SUM
SP & 603	MAINTENANCE OF TRAFFIC		1.00	1.00	LUMP SUM
SP & 603	TRAFFIC CONTROL SUPERVISOR		2664	2664	LIN. FT.
603	12" TEMPORARY CULVERT		3183	3183	LIN. FT.
603	18" TEMPORARY CULVERT		2482	2482	SQ. FT.
SS & 604	SIGNS		880	880	LIN. FT.
SS & 604	BARRICADES		1291	1291	EACH
SS & 604	TRAFFIC DRUMS		31200	31200	LIN. FT.
604	FURNISHING AND INSTALLING PRECAST CONCRETE BARRIER		35400	35400	LIN. FT.
604	RELOCATING PRECAST CONCRETE BARRIER		300240	300240	LIN. FT.
604	CONSTRUCTION PAVEMENT MARKINGS		168660	168660	LIN. FT.
604	REMOVAL OF CONSTRUCTION PAVEMENT MARKINGS		64680	64680	LIN. FT.
604	REMOVAL OF PERMANENT PAVEMENT MARKINGS		950	950	DAY
604	ADVANCE WARNING ARROW PANEL		294	294	EACH
SS & 604	VERTICAL PANELS		250	250	WEEK
SP & 604	PORTABLE CHANGEABLE MESSAGE SIGN		390	390	SQ. YD.
SP & 604	CONCRETE DITCH PAVING (TYPE B)		14	14	EACH
SP & 605	SELECTED PIPE BEDDING	12186		12186	CU. YD.
606	YARD DRAINS		241	241	EACH
609	UNDERDRAIN OUTLET PROTECTORS		55152	55152	LIN. FT.
611	4" PIPE UNDERDRAINS		40383	40383	LIN. FT.
611	UNDERDRAIN COVER		55152	55152	LIN. FT.
611	UNDERDRAIN VIDEO INSPECTION		2925	2925	LIN. FT.
617	GUARDRAIL (TYPE A)		10	10	EACH
617	TERMINAL ANCHOR POSTS (TYPE 1)		15	15	EACH
617	GUARDRAIL TERMINAL (TYPE 2)		15	15	EACH
617	THREE BEAM GUARDRAIL TERMINAL		148	148	TON
620	LIME		74.14	74.14	ACRE
620	SEEDING		196.07	196.07	ACRE
SS & 620	MULCH COVER		10205.7	10205.7	M.GAL.
620	WATER		121.93	121.93	ACRE
621	TEMPORARY SEEDING		3272	3272	LIN. FT.
621	SILT FENCE		3432	3432	BAG
621	SAND BAG DITCH CHECKS		760	760	LIN. FT.
621	DROP INLET SILT FENCE		2226	2226	CU. YD.
621	SEDIMENT BASIN		3437	3437	CU. YD.
621	OBLITERATION OF SEDIMENT BASIN		74.14	74.14	ACRE
621	SECOND REMOVAL AND DISPOSAL		197	197	SQ. YD.
623	SECOND SEEDING APPLICATION		1.00	1.00	LUMP SUM
624	SOLID SODDING		4	4	EACH
SP & 635	ROADWAY CONSTRUCTION CONTROL		123434	123434	LIN. FT.
SP & 640	MODIFYING DROP INLETS		57931	57931	LIN. FT.
642	RUMBLE STRIPS IN ASPHALT SHOULDERS		57931	57931	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING WHITE (4")		13348	13348	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE WHITE (4")		13348	13348	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING (SKIP LINE) WHITE (4")		3532	3532	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE (SKIP LINE) WHITE (4")		3532	3532	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING WHITE (8")		59011	59011	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE WHITE (8")		59011	59011	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC PAVEMENT MARKING YELLOW (4")		286	286	LIN. FT.
SP	HIGH PERFORMANCE MARKING TAPE YELLOW (4")		286	286	LIN. FT.
SP & 719	INVERTED PROFILE THERMOPLASTIC CONTRAST PAVEMENT MARKING WHITE (4")		1333	1333	EACH
721	RAISED PAVEMENT MARKERS (TYPE II)		448	448	SQ. FT.
725	GUIDE SIGN-OVERHEAD MOUNTED (DEMOUNTABLE LEGEND)		3662	3662	SQ. FT.
725	GUIDE SIGN-OVERHEAD MOUNTED (DEMOUNTABLE LEGEND)		574	574	SQ. FT.
726	STANDARD SIGN		260	260	SQ. FT.
727	EXIT NUMBER PANEL (TYPE A)		10	10	EACH
SP & 729	CHANNEL POST SIGN SUPPORT (TYPE U-1)		22889	22889	POUND
730	BREAKAWAY SIGN SUPPORT (TYPE G-2)		8	8	EACH
731	TEMPORARY IMPACT ATTENUATION BARRIER		8	8	EACH
731	TEMPORARY IMPACT ATTENUATION BARRIER (REPAIR)		16	16	EACH
731	TEMPORARY IMPACT ATTENUATION BARRIER (RELOCATION)		79548	79548	POUND
804	REINFORCING STEEL-ROADWAY (GRADE 60)		1	1	EACH
SP	REMOVAL AND DISPOSAL OF IMPACT ATTENUATION BARRIER		2	2	EACH
SP	MOBILE SPEED NOTIFICATION SYSTEM		400	400	LIN. FT.
SP	MODULAR GLARE SHIELD		800	800	DAY
SP	PORTABLE CONSTRUCTION LIGHTING		1376	1376	LIN. FT.
SP	REMOVAL OF RUMBLE STRIP		2000	2000	SQ. YD.
SP	SCARIFYING CONCRETE PAVEMENT		27418	27418	LIN. FT.
SP	WIRE ROPE SAFETY FENCE		50	50	EACH
SP	WIRE ROPE SAFETY FENCE (POST REPAIR)		2	2	EACH
SP	WIRE ROPE SAFETY FENCE (END TERMINAL)		16	16	EACH
SP	WIRE ROPE SAFETY FENCE (POST REPAIR)		4	4	EACH
SP	FURNISH AND INSTALL VEHICLE DETECTION SYSTEM		10	10	EACH
SP	FURNISH AND INSTALL CLOSED CIRCUIT TELEVISION SYSTEM		2	2	EACH
SP	FURNISH AND INSTALL VARIABLE MESSAGE SIGN		16	16	MNTH
SP	FURNISH AND INSTALL PUBLIC NOTIFICATION SYSTEM		1.00	1.00	LUMP SUM
SP	AWIS OPERATION		16	16	EACH
SP	AWIS MOBILIZATION		34	34	EACH
SP	DEVICE RELOCATION		16	16	EACH
SP	OMNI-DIRECTIONAL BREAKAWAY SIGN SUPPORTS (TYPE G-2)		39	39	EACH
SP	CULVERT CLEAN OUT				

* DENOTES ALTERNATE BID ITEMS.

DATE	REVISION	SHEET NUMBER
7/26/2016	REVISED "PORTABLE CONSTRUCTION LIGHTING" SP.	183
7/28/2016	REVISED MAINTENANCE OF TRAFFIC DETAILS. REVISED CONSTRUCTION PAVEMENT MARKINGS QUANTITY.	128, 173, 183
8/4/2016	ADDED WIRE ROPE SAFETY FENCE STA. 453+28 TO STA. 463+00.	128, 173, 183 183, 204



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	
							BB0202	
							184	
							235	
(2) PLAN SHEET								

APPROXIMATE 100 YR. FLOODPLAIN LIMITS


I-530 CROSSOVER IA
P.I. 14+63.60
Δ = 11°13'05" RT.
D = 8'00'00"
T = 70.34'
L = 140.22'
P.C. = 13+93.27
P.T. = 15+33.49
NO SUPER

RAMP A65
P.I. 171+56.10
Δ = 33°58'17" RT.
D = 8'00'00"
T = 218.77'
L = 424.64'
P.C. = 169+37.33
P.T. = 173+61.98
MATCH EXIST. SUPER

RAMP A65
P.I. 178+41.30
Δ = 11°57'33" LT.
D = 4'00'00"
T = 150.04'
L = 298.98'
P.C. = 176+91.27
P.T. = 179+90.25
MATCH EXIST. SUPER


TEMP. RAMP A65 A
P.I. 30+35.23
Δ = 5°37'59" RT.
D = 8'00'00"
T = 35.23'
L = 70.41'
P.C. = 30+00.00
P.T. = 30+70.41
NO SUPER

TEMP. RAMP A65 A
P.I. 37+20.35
Δ = 23°18'45" LT.
D = 6'00'00"
T = 197.00'
L = 388.54'
P.C. = 35+23.35
P.T. = 39+11.89
NO SUPER



LEGEND
FULL DEPTH PAVEMENT TRANSITION

MAIN LANES STA. 180+24.67, 70.00' LT. = RAMP A65 STA. 180+24.29, 12.50' RT.



STA. 156+19.23 BEGIN SUPERELEVATION
STA. 160+19.23 MAX. SUPERELEVATION (0.085 %)
STA. 171+90.50 MAX. SUPERELEVATION (0.085 %)
STA. 175+90.50 END SUPERELEVATION

C.L. RAMP D65 STA. 166+95.98 =
C.L. TEMP. RAMP D65 STA. 20+00.00

RAMP D65
STA. 169+60 IN PLACE
18" X 60' R.C. PIPE CULVERT
WITH FES LT. & RT.
RETAIN
REMOVE FES LT. AND INSTALL
18" X 12' TEMPORARY CULVERT
EXTENSION LT.

MAIN LANES STA. 170+39.48, 37.50' RT. =
C.L. 530 CROSSOVER IA STA. 10+00.00

STA. 175+14.73
BEGIN JOB BB0202
LOG MILE 34.99

MAIN LANES STA. 175+14.73 =
RAMP D65 STA. 175+15.42

MAIN LANES STA. 175+78.49, 56.00' RT. =
RAMP D65 STA. 175+78.99, 9.50' LT.
END RAMP OVERLAY TRANSITION
BEGIN FULL DEPTH TRANSITION

STA. 172+00 TO 177+59 INSTALL
TEMPORARY 18" X 559' CULVERT IN MEDIAN.


COVER EXIST. DROP INLETS AT STA. 173+80.04 &
STA. 176+19.95 AS DIRECTED BY THE ENGINEER
PRIOR TO CONSTRUCTION OF THE TEMPORARY
CROSSOVER. REMOVE COVER WHEN CROSSOVER
IS REMOVED. PAYMENT FOR THIS WORK SHALL
BE INCLUDED IN THE PRICE BID FOR
VARIOUS CONTRACT ITEMS.

APPROXIMATE 100 YR. FLOODPLAIN LIMITS

I-530 CROSSOVER IB
P.I. 4+56.71
Δ = 11°14'45" RT.
D = 5'00'00"
T = 120.52'
L = 224.92'
P.C. = 0+00.00
P.T. = 2+24.92
NO SUPER



I-530 CROSSOVER IB
P.I. 4+56.71
Δ = 12°00'29" LT.
D = 5'00'00"
T = 120.52'
L = 240.16'
P.C. = 3+36.19
P.T. = 5+76.35
NO SUPER

6/21/2016 10:25:56 AM
 Leonard.Speed
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_13825_I-530_Hwy104-Hwy65B\Deliverables\Roadway\Drawings\BB0202_12_PP_MAIN_01.dgn



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
							SHEET NO.	185
							TOTAL SHEETS	235

2 PLAN SHEET



STATION	DESCRIPTION	QUANTITY	UNIT
STA. 185 +78 TO STA. 190 +78	LT. OF R.M.L.	425	LIN. FT.
STA. 188 +78 TO STA. 193 +78	RT. OF L.M.L.	425	LIN. FT.

STATION	DESCRIPTION	QUANTITY	UNIT
STA. 185 +78 TO STA. 190 +78	LT. OF R.M.L.	425	LIN. FT.
STA. 189 +28 TO STA. 193 +78	RT. OF L.M.L.	375	LIN. FT.
STA. 189 +28 TO STA. 191 +28	LT. OF L.M.L.	125	LIN. FT.


NOTE: EXISTING VERTICAL CLEARANCE UNDER SIGN AT STA. 189+78 IS 19'-2". A MINIMUM 17'-0" VERTICAL CLEARANCE IS REQUIRED FOR FINISHED ROADWAY.

STA. 189+78.00 IN PLACE 19'-2" OVERHEAD SIGN STRUCTURE RETAIN

LEGEND
 FULL DEPTH PAVEMENT TRANSITION

STA. 181+80.04 BEGIN SUPERELEVATION
 STA. 185+80.04 MAX. SUPERELEVATION (0.085 '/')
 STA. 207+49.38 MAX. SUPERELEVATION (0.085 '/')
 STA. 211+49.38 END SUPERELEVATION

Leonard.Speed 6/21/2016 10:25:56 AM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD_138215_1-530_Hwy104-Hwy65B-Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN_02.dgn





PLAN SHEET

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS	
				2	ARK.				
				JOB NO.	BBO202	186	235		
②								PLAN SHEET	

C.L. I-530
 P.I. 197+82.87
 $\Delta = 59^{\circ}14'01''$ RT.
 $D = 2^{\circ}30'00''$
 $T = 1302.83'$
 $L = 2369.35'$
 $P.C. = 184+80.04$
 $P.T. = 208+49.38$
 $e = 0.085'/'$
 $Ls = 400'$

APPROXIMATE 100 YR.
 FLOODPLAIN LIMITS




STA. 181+80.04 BEGIN SUPERELEVATION
 STA. 185+80.04 MAX. SUPERELEVATION (0.085 '/'')
 STA. 207+49.38 MAX. SUPERELEVATION (0.085 '/'')
 STA. 211+49.38 END SUPERELEVATION

WIRE ROPE SAFETY FENCE
 10' LT. OF I-530 R.M.L. (P.G.)
 WITH CONCRETE DITCH PAVING
 TYPE B (4'-0")

STA. 197+20.00 IN PLACE
 TYPE R DROP INLET
 IN MEDIAN (4' X 3' X H=3'6")
 WITH 18"X72" R.C. PIPE OUTLET
 ON RT. WITH FES
 RETAIN

STA. 204+90.00 IN PLACE
 TRIP, 4'X3' X 227' R.C. BOX CULVERT
 WITH TYPE T DROP INLET
 IN MEDIAN (4' X 3' X H=6'-2")
 D.A.=87 ACRES 050=209 CFS
 RETAIN



Leonor G. Speed 6/21/2016 10:25:57 AM
 WORKSPACE: Leonor G. Speed
 I:\Projects\AR10_15825_I-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202.12.PP_MAIN.03.dgn



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
				JOB NO.	BBO202	187	235	
								PLAN SHEET

APPROXIMATE 100 YR. FLOODPLAIN LIMITS

STA. 213+00.00 IN PLACE TYPE R DROP INLET IN MEDIAN (4' X 3' X H=3'-0") WITH 18" X 76' R.C. PIPE OUTLET ON LT. WITH FES RETAIN



WIRE ROPE SAFETY FENCE 10' LT. OF I-530 R.M.L. (P.G.) WITH CONCRETE DITCH PAVING TYPE B (4'-0")


STA. 212+20 IN PLACE 18'-3" OVERHEAD SIGN STRUCTURE RETAIN

NOTE: EXISTING VERTICAL CLEARANCE OF OVERHEAD SIGN STRUCTURE AT STA. 212+20 IS 18'-3". A MINIMUM 17'-0" VERTICAL CLEARANCE IS REQUIRED FOR FINISHED ROADWAY.

REMOVAL AND DISPOSAL OF GUARDRAIL


	GUARDRAIL (TYPE A)	GUARDRAIL TERMINAL (TYPE 2)	TERMINAL ANCHOR POST (TYPE 1)
STA. 211 +90 TO STA. 214 +10 LT. OF L.M.L.	= 145 LIN. FT.	1 EACH	1 EACH
STA. 211 +90 TO STA. 214 +20 RT. OF L.M.L.	= 155 LIN. FT.	1 EACH	1 EACH
GUARDRAIL			
	GUARDRAIL (TYPE A)	GUARDRAIL TERMINAL (TYPE 2)	TERMINAL ANCHOR POST (TYPE 1)
STA. 211 +20 TO STA. 213 +20 LT. OF L.M.L.	= 125 LIN. FT.	1 EACH	1 EACH
STA. 211 +20 TO STA. 213 +20 RT. OF L.M.L.	= 125 LIN. FT.	1 EACH	1 EACH

EXISTING GAS TRANSMISSION LINE



Leonard Speed 6/21/2016 10:25:57 AM
 WORKSPACE: Leonard.Speed
 Y:\Projects\ARTD\15825_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202_12_PP_MAIN_04.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.	BBO202	188	235
							PLAN SHEET	



HWY. 270 TEMP. RAMP 4A
 P.I. 70+62.66
 $\Delta = 10^{\circ}00'00''$ LT.
 $D = 8^{\circ}00'00''$
 $T = 62.66'$
 $L = 125.00'$
 P.C. = 70+00.00
 P.T. = 71+25.00
 NO SUPER

HWY. 270 TEMP. RAMP 4A
 P.I. 74+54.20
 $\Delta = 4^{\circ}25'53''$ RT.
 $D = 8^{\circ}00'00''$
 $T = 27.71'$
 $L = 55.39'$
 P.C. = 74+26.49
 P.T. = 74+81.89
 NO SUPER

RAMP 4
 STA. 233+14 IN PLACE
 TYPE E DROP INLET IN GORE
 WITH 18"x40" R.C. PIPE OUTLET
 ON LT. WITH FES
 ADJUST TO GRADE



STA. 230+90 TO 234+09
 INSTALL 18"x 319' TEMPORARY CULVERT IN MEDIAN

COVER EXISTING DROP INLET AT STA. 232+00 AS DIRECTED BY THE ENGINEER PRIOR TO CONSTRUCTION OF THE TEMPORARY RAMP. REMOVE COVER WHEN THE TEMPORARY RAMP IS REMOVED. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR VARIOUS CONTRACT ITEMS.

STA. 232+00 IN PLACE TYPE R DROP INLET IN MEDIAN (4'-3" X 3'-0" X H=12'-6") WITH 42"x126" R.C. PIPE INLET & 42"x114" R.C. PIPE OUTLET WITH FES LT. AND RT. D.A.=32 ACRES 050=92 CFS RETAIN

HWY. 270 TEMP. RAMP IA
 P.I. 51+20.44
 $\Delta = 12^{\circ}00'00''$ RT.
 $D = 5^{\circ}00'00''$
 $T = 120.44'$
 $L = 240.00'$
 P.C. = 50+00.00
 P.T. = 52+40.00
 NO SUPER

HWY. 270 TEMP. RAMP IA
 P.I. 56+46.12
 $\Delta = 6^{\circ}18'44''$ LT.
 $D = 5^{\circ}00'00''$
 $T = 63.19'$
 $L = 126.25'$
 P.C. = 55+82.93
 P.T. = 57+09.18
 NO SUPER

HWY. 270 TEMP. RAMP IB
 P.I. = 61+82.51
 $\Delta = 18^{\circ}05'58''$ RT.
 $D = 5^{\circ}00'00''$
 $T = 182.51'$
 $L = 361.99'$
 P.C. = 60+00.00
 P.T. = 63+61.99
 NO SUPER


HWY. 270 TEMP. RAMP IB
 P.I. = 65+75.43
 $\Delta = 3^{\circ}14'58''$ LT.
 $D = 5^{\circ}00'00''$
 $T = 32.50'$
 $L = 64.99'$
 P.C. = 65+42.93
 P.T. = 66+07.92
 NO SUPER

RAMP 1
 STA. 234+02 IN PLACE
 TYPE R DROP INLET IN MEDIAN (4' X 3' X H=13'-0") WITH 18"x72" R.C. PIPE OUTLET ON RT. WITH FES RETAIN

HWY. 270 RAMP 1
 P.I. 228+48.54
 $\Delta = 5^{\circ}37'12''$ RT.
 $D = 3^{\circ}00'00''$
 $T = 93.74'$
 $L = 187.33'$
 P.C. = 227+54.80
 P.T. = 229+42.13
 MATCH EXIST. SUPER


HWY. 270 RAMP 1
 P.I. 235+68.33
 $\Delta = 9^{\circ}09'44''$ RT.
 $D = 2^{\circ}00'00''$
 $T = 229.52'$
 $L = 458.06'$
 P.C. = 233+38.81
 P.T. = 237+96.87
 MATCH EXIST. SUPER

RAMP 1
 STA. 238+00 IN PLACE
 24"x68" R.C. PIPE CULVERT WITH FES RT. AND LT. RETAIN



LeonardSpeed 6/21/2016 10:25:58 AM
 WORKSPACE: LeonardSpeed
 P:\Projects\NH101530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\RBB0202.12.PP_MAIN.05.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							189	235
PLAN SHEET								



LEGEND

REMOVE & RECONSTRUCT APPR. SLAB & GUTTERS

FULL DEPTH PAVEMENT TRANSITION

HWY. 270 RAMP 1
P.I. = 235+68.33
Δ = 9°09'44" RT.
D = 2°00'00"
T = 229.52'
L = 458.06'
P.C. = 233+38.81
P.T. = 237+96.87
MATCH EXIST. SUPER

HWY. 270 TEMP. RAMP 1B
P.I. = 65+75.43
Δ = 3°14'58" LT.
D = 5°00'00"
T = 32.50'
L = 64.99'
P.C. = 65+42.93
P.T. = 66+07.92
NO SUPER

RAMP 1
STA. 238+00 IN PLACE
24"x60' R.C. PIPE CULVERT
WITH FES LT. & RT.
RETAIN

REMOVAL AND DISPOSAL OF GUARDRAIL


STATION	GUARDRAIL (TYPE A)	TERMINAL ANCHOR POST (TYPE 1)
STA. 240 +44 TO STA. 242 +44 RT. OF R.M.L.	= 175 LIN. FT.	1 EACH
STA. 240 +72 TO STA. 242 +72 LT. OF R.M.L.	= 175 LIN. FT.	1 EACH
STA. 242 +31 TO STA. 243 +06 RT. OF L.M.L.	= 50 LIN. FT.	1 EACH
STA. 242 +59 TO STA. 243 +34 LT. OF L.M.L.	= 50 LIN. FT.	1 EACH
STA. 244 +73 TO STA. 245 +48 RT. OF R.M.L.	= 50 LIN. FT.	1 EACH
STA. 245 +01 TO STA. 245 +76 LT. OF R.M.L.	= 50 LIN. FT.	1 EACH
STA. 245 +34 TO STA. 247 +34 RT. OF L.M.L.	= 175 LIN. FT.	1 EACH
STA. 245 +62 TO STA. 247 +62 LT. OF L.M.L.	= 175 LIN. FT.	1 EACH

GUARDRAIL

STATION	GUARDRAIL (TYPE A)	GUARDRAIL TERMINAL (TYPE 2)	THRUE BEAM GUARDRAIL TERMINAL	TERMINAL ANCHOR POST (TYPE 1)
STA. 240 +18 TO STA. 242 +37 RT. OF R.M.L.	= 150 LIN. FT.	1 EACH	1 EACH	
STA. 240 +46 TO STA. 242 +65 LT. OF R.M.L.	= 150 LIN. FT.	1 EACH	1 EACH	
STA. 242 +32 TO STA. 243 +26 LT. OF L.M.L.	= 50 LIN. FT.		1 EACH	
STA. 244 +81 TO STA. 245 +74 RT. OF R.M.L.	= 50 LIN. FT.		1 EACH	
STA. 245 +42 TO STA. 247 +61 RT. OF L.M.L.	= 150 LIN. FT.	1 EACH	1 EACH	1 EACH
STA. 245 +70 TO STA. 247 +89 LT. OF L.M.L.	= 150 LIN. FT.	1 EACH	1 EACH	1 EACH

HWY. 270 RAMP 2A
P.I. = 90+85.85
Δ = 11°23'40" LT.
D = 7°00'00"
T = 81.66'
L = 162.78'
P.C. = 90+04.19
P.T. = 91+66.97
NO SUPER

HWY. 270 RAMP 2
P.I. = 246+58.14
Δ = 24°45'00" LT.
D = 4°00'00"
T = 314.30'
L = 618.80'
P.C. = 243+43.84
P.T. = 249+62.64
MATCH EXIST. SUPER



LeonardSpeed 6/21/2016 10:25:59 AM
WORKSPACE: LeonardSpeed
H:\Projects\AR\Hwy270\Drawings\BB0202\12_PP_MAIN_06.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO. BB0202	190
							PLAN SHEET	235

STA. 250+40 IN PLACE
TYPE R DROP INLET IN MEDIAN
(5'-6" X 3'-0" X H=23'8") WITH
36" X 200' R.C. PIPE INLET WITH
(45° SKEW) HDWL. ON LT. &
36" X 140' R.C. PIPE OUTLET TO
D.I. ON RT. STA. 251+00
D.A.=15.5 ACRES 050=56 CFS
RETAIN

STA. 251+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4'-6" X 3'-0" X H=8'-6") WITH
36" R.C. PIPE FROM D.I. AT STA. 250+40
WITH 42" X 126' R.C. PIPE OUTLET
ON RT. WITH FES
D.A.=15.5 ACRES 050=56 CFS
RETAIN

STA. 253+81 TO 258+00 INSTALL
18" X 419' TEMPORARY CULVERT
WITH TEMP. CONNECTION TO DROP
INLET AT STA. 258+00


STA. 258+00 IN PLACE
5' X 3' X 202.5' R.C. BOX CULVERT
WITH TYPE T DROP INLET
IN MEDIAN (5' X 3' X H=5'-0")
D.A.=37 ACRES 050=134 CFS
RETAIN

HWY. 270 TEMP. RAMP 3A STA. 112+89
54' LT. FWD. SKEW
INSTALL 12" X 195' TEMP. CULVERT

HWY. 270 RAMP 3
P.I. 257+78.60
Δ = 26°46'00" LT.
D = 4'00'00"
T = 340.80'
L = 669.16'
P.C. = 254+37.80
P.T. = 261+06.96
MATCH EXIST. SUPER


HWY. 270 TEMP. RAMP 3B
P.I. 125+01.88
Δ = 21°10'36" LT.
D = 8'00'00"
T = 133.88'
L = 264.71'
P.C. = 123+68.00
P.T. = 126+32.71
NO SUPER

HWY. 270 RAMP 3 EOP
Δ = 15°24'00" LT.
D = 5'00'00"
T = 154.90'
L = 307.93'
P.C. = HWY. 270 RAMP 3 STA. 256+45.30, 7.50' LT.
P.T. = HWY. 270 RAMP 3 STA. 259+55.30, 15.58' LT.



LEGEND

	REMOVE & RECONSTRUCT APPR. SLAB & GUTTERS
	FULL DEPTH PAVEMENT TRANSITION



HWY. 270 RAMP 2
P.I. 246+58.14
Δ = 24°45'00" LT.
D = 4'00'00"
T = 314.30'
L = 618.80'
P.C. = 243+43.84
P.T. = 249+62.64
MATCH EXIST. SUPER

HWY. 270 TEMP. RAMP 2A
P.I. 90+84.20
Δ = 13°24'37" LT.
D = 8'00'00"
T = 84.20'
L = 167.63'
P.C. = 90+00.00
P.T. = 91+67.63
NO SUPER

HWY. 270 TEMP. RAMP 2A
P.I. 95+14.27
Δ = 24°57'16" RT.
D = 5'00'00"
T = 253.57'
L = 499.09'
P.C. = 92+60.71
P.T. = 97+59.79
NO SUPER

HWY. 270 RAMP 2
P.I. 253+30.53
Δ = 10°29'00" RT.
D = 3'00'00"
T = 175.20'
L = 349.42'
P.C. = 251+55.33
P.T. = 255+04.76
MATCH EXIST. SUPER


HWY. 270 TEMP. RAMP 2B
P.I. 101+01.39
Δ = 16°06'52" LT.
D = 8'00'00"
T = 101.39'
L = 201.43'
P.C. = 100+00.00
P.T. = 102+01.43
NO SUPER

HWY. 270 TEMP. RAMP 2B
P.I. 104+10.06
Δ = 10°46'35" RT.
D = 8'00'00"
T = 67.55'
L = 134.71'
P.C. = 103+42.51
P.T. = 104+77.21
NO SUPER

C.L. I-530
P.I. 259+07.11
Δ = 22°32'01" LT.
D = 2'00'00"
T = 570.72'
L = 1126.68'
P.C. = 253+36.39
P.T. = 264+63.07
e = 0.070 '
Ls = 350'

STA. 250+73.89 BEGIN SUPERELEVATION
STA. 254+23.89 MAX. SUPERELEVATION (0.070 ' / ')
STA. 263+75.57 MAX. SUPERELEVATION (0.070 ' / ')
STA. 267+25.57 END SUPERELEVATION

APPROXIMATE 100 YR. FLOODPLAIN LIMITS



Leonard.Speed 6/21/2016 10:26:18 AM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD\158215_1-530_Hwy104-Hwy65B\Deliverables\104DWAY\Drawings\RB0202\12_PP_MAIN_07.dgn

STA. 264+40 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4'-3" X 3' X H=9'-6") WITH
 42" X 89' R.C. PIPE INLET &
 42" X 100' R.C. PIPE OUTLET
 WITH FES LT. & RT.
 D.A.=23 ACRES 050=98 CFS
 RETAIN



STA. 272+00 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=2'-6") WITH
 18" X 76' R.X. PIPE OUTLET
 ON RT. WITH FES
 RETAIN

Michael Baker
 INTERNATIONAL

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	235
							BB0202	191
							PLAN SHEET	


C.L. I-530
 P.I. 259+07.11
 $\Delta = 22^{\circ}32'01''$ LT.
 $D = 2^{\circ}00'00''$
 $T = 570.72'$
 $R = 1126.68'$
 $P.C. = 253+36.39$
 $P.T. = 264+63.07$
 $e = 0.070$ '/'
 $Ls = 350'$

STA. 250+73.89 BEGIN SUPERELEVATION
 STA. 254+23.89 MAX. SUPERELEVATION (0.070 '/'')
 STA. 263+75.57 MAX. SUPERELEVATION (0.070 '/'')
 STA. 267+25.57 END SUPERELEVATION



Leonard.Speed 6/21/2016 10:26:19 AM
 WORKSPACE: Leonard.Speed
 I:\Projects\118295_1-530_Hwy04-Hwy655\Deliverables\ROADWAY\Drawings\BB0202.PP_MAIN_08.dgn

APPROXIMATE 100 YR.
 FLOODPLAIN LIMITS



PLAN SHEET


STA. 279+00 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4'-3" X 3' X H=10'-5") WITH
 42"X90" R.C. PIPE INLET &
 42"X97" R.C. PIPE OUTLET
 WITH FES LT. & RT.
 D.A.=33 ACRES 050=113 CFS
 RETAIN

APPROXIMATE 100 YR.
 FLOODPLAIN LIMITS

STA. 283+45 IN PLACE
 DBL. 9'X5'X219' R.C. BOX CULVERT
 (15° RT. FWD. SKEW) WITH
 TYPE T DROP INLET IN MEDIAN
 (4' X 3' X H=9'-0")
 D.A.=509 ACRES 050=918 CFS
 RETAIN

Michael Baker
 INTERNATIONAL

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	TOTAL SHEETS
							BB0202	192
							2	235
PLAN SHEET								




WIRE ROPE SAFETY FENCE
 10' RT. OF I-530 L.M.L. (P.G.)
 WITH CONCRETE DITCH PAVING
 TYPE B (4'-0")

APPROXIMATE 100 YR.
 FLOODPLAIN LIMITS

STA. 296+75 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=2'-6") WITH
 18"X78" R.C. PIPE OUTLET
 ON RT. WITH FES
 RETAIN

Leonard.Speed 6/21/2016 10:26:20 AM
 WORKSPACE: Leonard.Speed
 Y:\Projects\AHTD\188215-I-530_Hwy04-Hwy658\Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN_03.dgn



PLAN SHEET


STA. 296+75 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=2'-6") WITH
 18" X 78" R.C. PIPE OUTLET
 ON RT. WITH FES

APPROXIMATE 100 YR.
 FLOODPLAIN LIMITS


STA. 303+24 IN PLACE
 8'X5'X202' R.C. BOX CULVERT
 WITH TYPE T DROP INLET
 IN MEDIAN (4' X 3' X H=8'-6")
 D.A.=213 ACRES 050=384 CFS
 RETAIN

Michael Baker
 INTERNATIONAL

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO.	BBO202	193
						PLAN SHEET		



LeonardSpeed 6/21/2016 10:26:20 AM
 WORKSPACE: LeonardSpeed
 Y:\Projects\AR10_138205_1-530_Hwy04-Hwy688\Deliverables\ROADWAY\Drawings\RB0202_12_PP_MAIN_10.dgn



PLAN SHEET

STA. 310+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=2'-6") WITH
18"X84' R.C. PIPE OUTLET
ON RT. WITH FES RETAIN



STA. 317+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=2'-6") WITH
18"X78' R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN

Michael Baker
INTERNATIONAL


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	235
							PROJ. NO.	BB0202
							SHEET NO.	194
							TOTAL SHEETS	235

2

PLAN SHEET



Leonrd.Speed 6/21/2016 10:26:21 AM
 W:\CS\Projects\138265\138265-1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN.dgn



PLAN SHEET

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
							195	235
							PLAN SHEET	

STA. 326+90 IN PLACE
4'X3'X226' R.C. BOX CULVERT
(15° LT. FWD. SKEW) WITH
TYPE T DROP INLET IN MEDIAN
(4' X 3' X H=6'-6")
D.A.=29 ACRES 050=99 CFS
RETAIN

HOLLAND AVE. TEMP. RAMP 4A
P.I. 150+89.96
Δ = 14°19'09" LT.
D = 8'00'00"
T = 89.96'
L = 178.99'
P.C. = 150+00.00
P.T. = 151+78.99
NO SUPER

HOLLAND AVE. TEMP. RAMP 4A
P.I. 153+96.70
Δ = 11°19'23" RT.
D = 8'00'00"
T = 71.00'
L = 141.54'
P.C. = 153+25.70
P.T. = 154+67.24
NO SUPER

HOLLAND AVE. TEMP. RAMP 4B
P.I. 162+91.11
Δ = 28°30'27" LT.
D = 6'00'00"
T = 242.59'
L = 475.13'
P.C. = 160+48.52
P.T. = 165+23.65
NO SUPER

HOLLAND AVE. TEMP. RAMP 4B
P.I. 166+22.52
Δ = 13°03'29" RT.
D = 8'00'00"
T = 81.97'
L = 163.23'
P.C. = 165+40.56
P.T. = 167+03.78
NO SUPER

STA. 328+00 TO 331+84 INSTALL
12"X 384' TEMP. CULVERT IN MEDIAN



HOLLAND AVE. RAMP 4
P.I. 333+60.92
Δ = 15°22'34" LT.
D = 3'00'00"
T = 257.82'
L = 512.54'
P.C. = 331+03.10
P.T. = 336+15.64
MATCH EXIST. SUPER

C.L. I-530
P.I. 331+85.57
Δ = 6°59'00" RT.
D = 0'30'00"
T = 699.20'
L = 1396.67'
P.C. = 324+86.37
P.T. = 338+83.03
e = N.C.
Ls = 350'

STA. 332+00 TO 334+50 INSTALL
12"X 250' TEMP. CULVERT IN MEDIAN

HOLLAND AVE. TEMP. RAMP 4B STA. 165+33
74° RT. FWD. SKEW.
INSTALL 12"X 230' TEMP. CULVERT

LEGEND
[Symbol] FULL DEPTH PAVEMENT TRANSITION




HOLLAND AVE. TEMP. RAMP IA
P.I. 130+84.08
Δ = 13°23'30" RT.
D = 8'00'00"
T = 84.08'
L = 167.39'
P.C. = 130+00.00
P.T. = 131+67.39
NO SUPER

HOLLAND AVE. TEMP. RAMP IB
P.I. 142+08.67
Δ = 32°29'18" RT.
D = 8'00'00"
T = 208.67'
L = 406.10'
P.C. = 140+00.00
P.T. = 144+06.10
NO SUPER

HOLLAND AVE. TEMP. RAMP IB
P.I. 145+36.35
Δ = 15°12'06" LT.
D = 8'00'00"
T = 95.57'
L = 190.02'
P.C. = 144+40.77
P.T. = 146+30.80
NO SUPER

HOLLAND AVE. RAMP I
P.I. 334+10.84
Δ = 18°18'25" RT.
D = 3'00'00"
T = 307.74'
L = 610.23'
P.C. = 331+03.10
P.T. = 337+13.33
MATCH EXIST. SUPER

HOLLAND AVE. TEMP. RAMP IB STA. 144+76
54° LT. FWD. SKEW.
INSTALL 12"X 185' TEMP. CULVERT



Leonard Speed 6/21/2016 10:26:23 AM
WORKSPACE: Leonard.Speed
F:\Projects\NH1015825_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN_12.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.	BBO202	196	235
				JOB NO.		PLAN SHEET		


STA. 342+55 IN PLACE
4'X4'X108' R.C. BOX CULVERT
(45° RT. FWD. SKEW)
D.A.=46 ACRES 050=96 CFS
RETAIN

HOLLAND AVE. RAMP 4
P.I. 344+45.72
Δ = 19'16'34" RT.
D = 4'00'00"
T = 243.25'
L = 481.90'
P.C. = 342+02.47
P.T. = 346+84.37
MATCH EXIST. SUPER


APPROXIMATE 100 YR.
FLOODPLAIN LIMITS

LEGEND

	REMOVE & RECONSTRUCT APPR. SLAB & GUTTERS
	FULL DEPTH PAVEMENT TRANSITION



Leonard-Speed 6/21/2016 10:26:24 AM WORKSPACE: Leonard-Speed Y:\Projects\VAH101_18255_1-530_Hwy104-Hwy658-Deliverables\ROADWAY\Drawings\BBO202_12_PP_MAIN_13.dgn



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
							197	235
							PLAN SHEET	

RAMP 3
 STA. 354+26.20 IN PLACE
 4'X4'X116' R.C. BOX CULVERT
 (30° LT. FWD. SKEW)
 D.A.=61 ACRS. 050=119 CFS
 RETAIN

STA. 356+32.50 IN PLACE
 DBL. 6'X5'X404' R.C. BOX CULVERT
 D.A.=602 ACRES 050=650 CFS
 RETAIN

HOLLAND AVE. TEMP RAMP 3A STA. 192+30.00
 66' LT. FWD. SKEW
 INSTALL 12"X 170' TEMP. CULVERT

STA. 363+00 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=2'6") WITH
 18"X82' R.C. PIPE OUTLET
 ON RT. WITH FES
 RETAIN


HOLLAND AVE. TEMP. RAMP 2A
 P.I. = 195+91.56
 $\Delta = 31^{\circ}53'32''$ LT.
 D = 8'00'00"
 T = 204.64'
 L = 398.65'
 P.C. = 193+86.92
 P.T. = 197+85.57
 NO SUPER

HOLLAND AVE. TEMP. RAMP 3A
 P.I. = 192+55.51
 $\Delta = 14^{\circ}39'06''$ RT.
 D = 8'00'00"
 T = 92.08'
 L = 183.15'
 P.C. = 191+63.43
 P.T. = 193+46.58
 NO SUPER

HOLLAND AVE. TEMP. RAMP 1A
 P.I. = 174+89.38
 $\Delta = 28^{\circ}48'41''$ RT.
 D = 8'00'00"
 T = 183.96'
 L = 360.14'
 P.C. = 173+05.41
 P.T. = 176+65.56
 NO SUPER

HOLLAND AVE. RAMP 3
 P.I. 360+07.53
 $\Delta = 20^{\circ}50'28''$ LT.
 D = 3'00'00"
 T = 351.23'
 L = 694.70'
 P.C. = 356+56.30
 P.T. = 363+51.00
 MATCH EXIST. SUPER

HOLLAND AVE. TEMP. RAMP 2B
 P.I. 183+81.97
 $\Delta = 11^{\circ}27'30''$ RT.
 D = 8'00'00"
 T = 71.85'
 L = 143.23'
 P.C. = 183+10.12
 P.T. = 184+53.35
 NO SUPER



HOLLAND AVE. TEMP. RAMP 2A
 STA. 172+19.00
 70° RT. FWD. SKEW
 INSTALL 12"X 185' TEMP. CULVERT

STA. 353+00 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=10'-0") WITH
 18"X140' R.C. PIPE OUTLET
 TO D.I. IN RT. MEDIAN
 RETAIN

RAMP 2
 STA. 353+00 IN PLACE
 TYPE R DROP INLET 66' LT.
 (4' X 3' X H=2'-9") WITH
 30"X14' R.C. PIPE OUTLET
 ON RT. WITH FES
 D.A.=6 ACRES 050=30 CFS
 RETAIN

APPROXIMATE 100 YR.
 FLOOD LIMITS

LEGEND
 FULL DEPTH PAVEMENT
 TRANSITION

STA. 357+51 TO 359+63
 INSTALL 18"X 212' TEMP. CULVERT
 IN MEDIAN

HOLLAND AVE. TEMP. RAMP 1A
 P.I. = 171+88.98
 $\Delta = 14^{\circ}38'41''$ LT.
 D = 8'00'00"
 T = 92.03'
 L = 183.06'
 P.C. = 170+96.95
 P.T. = 172+80.01
 NO SUPER

HOLLAND AVE. RAMP 2
 P.I. 358+78.42
 $\Delta = 14^{\circ}10'00''$ RT.
 D = 4'00'00"
 T = 177.99'
 L = 354.17'
 P.C. = 357+00.43
 P.T. = 360+54.60
 MATCH EXIST. SUPER


STA. 361+26 TO 364+18
 INSTALL 18"X 292' TEMP. CULVERT IN MEDIAN
 WITH TEMP. CONNECTION TO MEDIAN
 DROP INLET AT STA. 363+00

HOLLAND AVE. TEMP. RAMP 2B
 P.I. 180+59.55
 $\Delta = 9^{\circ}30'23''$ LT.
 D = 4'00'00"
 T = 59.55'
 L = 118.83'
 P.C. = 180+00.00
 P.T. = 181+18.83
 NO SUPER

HOLLAND AVE. TEMP. RAMP 3B
 P.I. 205+74.44
 $\Delta = 17^{\circ}04'02''$ LT.
 D = 8'00'00"
 T = 107.47'
 L = 213.34'
 P.C. = 204+66.97
 P.T. = 206+80.31
 NO SUPER

STA. 358+48.43 BEGIN SUPERELEVATION
 STA. 361+98.43 MAX. SUPERELEVATION (0.054 '"/')
 STA. 374+10.20 MAX. SUPERELEVATION (0.054 '"/')
 STA. 377+60.20 END SUPERELEVATION

C.I. I-530
 P.I. 368+12.03
 $\Delta = 20^{\circ}48'00''$ LT.
 D = 1'30'00"
 T = 701.0'
 L = 1386.77'
 P.C. = 361+10.93
 P.T. = 374+97.70
 e = 0.054 '"/'
 Ls = 350'




Leonard.Speed 6/21/2016 10:26:25 AM
 WORKSPACE: Leonard.Speed
 T:\Projects\AR\10887\1530_Hwy104-Hwy58B\Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN.LR.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							198	235
PLAN SHEET								

STA. 369+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=2'-6") WITH
18" X 84' R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN

STA. 374+50 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=2'-6") WITH
18" X 84' R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN

STA. 380+00 IN PLACE
5' X 3' X 174' R.C. BOX CULVERT
WITH TYPE T DROP INLET
IN MEDIAN (4' X 3' X H=3'-3")
D.A.=67 ACRES 050=131 CFS
RETAIN



C.L. I-530
P.I. 368+12.03
D = 20°48'00" LT.
D = 1°30'00"
T = 701.10'
L = 1386.77'
P.C. = 361+10.93
P.T. = 374+97.70
e = 0.054 ' / '
Ls = 350'

STA. 358+48.43 BEGIN SUPERELEVATION
STA. 361+98.43 MAX. SUPERELEVATION (0.054 ' / '
STA. 374+10.20 MAX. SUPERELEVATION (0.054 ' / '
STA. 377+60.20 END SUPERELEVATION

Leonard.Speed 6/21/2016 10:26:25 AM
WORKSPACE: Leonard.Speed
I:\Projects\AR\110115855_1530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN_15.dgn





STA. 386+00 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=2'-6") WITH
 18" X 78' R.C. PIPE OUTLET
 ON RT. WITH FES
 RETAIN


STA. 393+00 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=2'-6") WITH
 18" X 74' R.C. PIPE OUTLET
 ON RT. WITH FES
 RETAIN

Michael Baker
 INTERNATIONAL

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
							199	235
2								PLAN SHEET



Leonard Speed 6/21/2016 10:26:26 AM
 WORKSPACE
 Y:\Projects\AATD_138215_1-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN_16.dgn



PLAN SHEET

STA. 400+00 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=3'-9") WITH
 36"X82' R.C. PIPE INLET &
 36"X82' R.C. PIPE OUTLET
 WITH FES LT. AND RT.
 D.A.=24 ACRES 050=54 CFS
 RETAIN



APPROXIMATE 100 YR.
 FLOODPLAIN LIMITS

STA. 406+50 IN PLACE
 TYPE R DROP INLET IN MEDIAN
 (4' X 3' X H=3'-9") WITH
 18"X86' R.C. PIPE OUTLET
 ON RT. WITH FES
 RETAIN

Michael Baker
 INTERNATIONAL

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	
							BB0202	
							200	235
PLAN SHEET								

STA. 409+60 IN PLACE
 DBL. 6'X5'X204' R.C. BOX CULVERT
 D.A.=614 ACRES 050=664 CFS
 RETAIN



Leoncr1.Speed 6/21/2016 10:26:27 AM
 WORKSPACE: Leoncr1.Speed
 Y:\Projects\1111013625_1330_Hwy04-Hwy55B\Deliverables\ROADWAY\Drawings\RB0202_12_PP_MAIN.IT.dgn

APPROXIMATE 100 YR.
 FLOODPLAIN LIMITS



PLAN SHEET

STA. 413+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=5'-3") WITH
18" X 90' R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN



STA. 417+05 IN PLACE
TRIP, 8'X6'X25' R.C. BOX CULVERT
(45° LT. FWD. SKEW)
D.A.=3.6 SO. MI. 050=I245 CFS
SPAN = 37.71'
RETAIN

STA. 420+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=5'-0") WITH
18" X 92' R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN


Michael Baker
INTERNATIONAL

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
							JOB NO.	BB0202
								201
								235
PLAN SHEET								

STA. 427+50 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=2'-6") WITH
18" X 76' R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN



Leonard.Speed 6/21/2016 10:26:27 AM
WORKSPACE: Leonard.Speed
F:\Projects\AR1013825-I-530_Hwy04-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202.I.PP_MAIN_18.dgn



PLAN SHEET

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						BBO202	202	235

PLAN SHEET

STA. 427+50 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=2'-6") WITH
18" X 76" R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN

STA. 435+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
(4' X 3' X H=2'-6") WITH
18" X 76" R.C. PIPE OUTLET
ON RT. WITH FES
RETAIN

HWY. 104 RAMP 4
P.I. 436+51.56
 $\Delta = 20^{\circ}00'00"$ LT.
D = 5'00'00"
T = 202.06'
L = 400.00'
P.C. = 434+49.50
P.T. = 438+49.50
MATCH EXIST. SUPER

HWY. 104 TEMP. RAMP 4B
P.I. = 245+22.82
 $\Delta = 12^{\circ}18'05"$ RT.
D = 8'00'00"
T = 77.18'
L = 153.77'
P.C. = 244+45.64
P.T. = 245+99.40
NO SUPER

HWY. 104 RAMP 4
P.I. 443+08.14
 $\Delta = 19^{\circ}59'57"$ RT.
D = 5'00'00"
T = 202.05'
L = 399.99'
P.C. = 441+06.10
P.T. = 445+06.08
MATCH EXIST. SUPER


STA. 441+40 IN PLACE
8' X 5' X 306.5' R.C. BOX CULVERT
(23' LT. FWD. SKEW) WITH
TYPE T DROP INLET IN MEDIAN
(4' X 3' X H=16'-5")
D.A. = 578 ACRES 050=416 CFS
RETAIN

HWY. 104 TEMP. RAMP 1B
P.I. = 222+85.72
 $\Delta = 28^{\circ}00'05"$ RT.
D = 6'00'00"
T = 238.10'
L = 466.69'
P.C. = 220+47.62
P.T. = 225+14.31
NO SUPER

HWY. 104 TEMP. RAMP 4A
P.I. 234+15.82
 $\Delta = 8^{\circ}34'27"$ RT.
D = 8'00'00"
T = 53.69'
L = 107.18'
P.C. = 233+62.13
P.T. = 234+69.31
NO SUPER

HWY. 104 TEMP. RAMP 1A
P.I. 211+01.28
 $\Delta = 16^{\circ}05'51"$ RT.
D = 8'00'00"
T = 101.28'
L = 201.22'
P.C. = 210+00.00
P.T. = 212+01.22
NO SUPER

WIRE ROPE SAFETY FENCE
10' RT. OF I-530 L.M.L. (P.G.)
WITH CONCRETE DITCH PAVING
TYPE B (4'-0")




LEGEND
 FULL DEPTH PAVEMENT TRANSITION

HWY. 104 TEMP RAMP 4A
P.I. 230+93.53
 $\Delta = 14^{\circ}52'50"$ LT.
D = 8'00'00"
T = 93.53'
L = 186.01'
P.C. = 230+00.00
P.T. = 231+86.01
NO SUPER

HWY. 104 RAMP 1
P.I. 436+00.02
 $\Delta = 5^{\circ}42'30"$ RT.
D = 3'00'00"
T = 95.22'
L = 190.28'
P.C. = 435+04.80
P.T. = 436+95.08
MATCH EXIST. SUPER

HWY. 104 TEMP. RAMP 4B
P.I. = 242+07.41
 $\Delta = 32^{\circ}18'09"$ LT.
D = 8'00'00"
T = 207.41'
L = 403.78'
P.C. = 240+00.00
P.T. = 243+03.78
NO SUPER

HWY. 104 RAMP 1
P.I. 442+07.27
 $\Delta = 10^{\circ}29'50"$ RT.
D = 3'00'00"
T = 175.45'
L = 349.91'
P.C. = 440+31.83
P.T. = 443+81.74
MATCH EXIST. SUPER



PLAN SHEET

LeonardSpeed 6/21/2016 10:26:28 AM
 WORKSPACE: LeonardSpeed
 Y:\Projects\AHTD\B0202_1-530_Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BBO202_12_PP_MAIN_19.dgn


DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
JOB NO. BB0202							203	235
PLAN SHEET								

LEGEND
 FULL DEPTH PAVEMENT TRANSITION


HWY. I04 TEMP. RAMP 4B
P.I. = 245+22.82
Δ = 12°18'05" RT.
D = 8°00'00"
T = 77.18'
L = 153.77'
P.C. = 244+45.64
P.T. = 245+99.40
NO SUPER

RAMP 3 STA. 448+28 IN PLACE
6' X 5' X 46' R.C. BOX CULVERT
050 = 280 CFS D.A. = 559 ACRES
RETAIN

HWY. I04 RAMP 3
P.I. 450+34.28
Δ = 13°35'33" RT.
D = 3°00'00"
T = 227.61'
L = 453.08'
P.C. = 448+06.67
P.T. = 452+59.75
MATCH EXIST. SUPER



STA. 447+70.79
END JOB BB0202
LOG MILE 29.89



Leonard.Speed 6/21/2016 10:26:29 AM
WORKSPACE: Leonard.Speed
T:\Projects\NAR1015825-1-530_HwyI04-Hwy65B-Deliverables\ROADWAY\Drawings\BB0202_12_PP_MAIN_20.dgn

GUARDRAIL (TYPE A)	GUARDRAIL (TYPE A)	GUARDRAIL (TYPE A)	GUARDRAIL (TYPE A)	GUARDRAIL (TYPE A)	GUARDRAIL (TYPE A)	THRIE BEAM GUARDRAIL TERMINAL	THRIE BEAM GUARDRAIL TERMINAL	THRIE BEAM GUARDRAIL TERMINAL	THRIE BEAM GUARDRAIL TERMINAL
STA. 446 +30 TO STA. 448 +49 LT. OF R.M.L. = 150 LIN. FT.	STA. 446 +63 TO STA. 447 +57 LT. OF L.M.L. = 50 LIN. FT.	STA. 446 +72 TO STA. 448 +91 RT. OF L.M.L. = 150 LIN. FT.	STA. 446 +30 TO STA. 448 +49 LT. OF R.M.L. = 150 LIN. FT.	STA. 446 +63 TO STA. 447 +57 LT. OF L.M.L. = 50 LIN. FT.	STA. 446 +72 TO STA. 448 +91 RT. OF R.M.L. = 150 LIN. FT.	1 EACH	1 EACH	1 EACH	1 EACH



STA. 453+00 IN PLACE
24" X 264' R.C. PIPE CULVERT
WITH F.E.S. LT. & RT.
(30' RT. FWD. SKEW)

STA. 457+00 IN PLACE
TYPE R DROP INLET IN MEDIAN
18" X 92' R.C. PIPE OUTLET
TO RT. WITH F.E.S.


STA. 462+50 IN PLACE
TYPE R DROP INLET IN MEDIAN
18" X 118' R.C. PIPE OUTLET
TO LT. WITH F.E.S.

Michael Baker
INTERNATIONAL

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
8-04-16				2	ARK.			
JOB NO.						BB0202	204	235
PLAN SHEET								





Scott Thornberry 8/4/2016 11:31:08 AM
 C:\Users\scott\Documents\Projects\BB0202\Drawings\Roadway\Drawings\BB0202_12_Plan_Main_21.dgn



PLAN SHEET

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						JOB NO. BB0202	205	235
						A&B 5500 - LAYOUT - XXXXX		



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
9-18-73				6	ARK.	RF-025-2(3)		
						JOB NO. 2182	17	37
						5500A&B Layout 18075		

GENERAL NOTES

BENCH MARK - N.I.S. P. POLE 58' KT. STA. 243+92, ELEV. 298.12.

ALL PILING SHALL BE 16" PRECAST CONCRETE OR 16" CONCRETE FILLED METAL SHELL AND SHALL BE DRIVEN WITH AN APPROVED AIR, STEAM, OR DIESEL HAMMER TO A MINIMUM CAPACITY OF 44 TONS PER PILE AND TO A MINIMUM PENETRATION OF 20' BELOW THE GROUND LINE. LENGTHS OF PILING SHOWN ARE ASSUMED FOR ESTIMATING QUANTITIES ONLY. ACTUAL LENGTHS ARE TO BE DETERMINED IN THE FIELD. DRIVE ONE 40' TEST PILE IN BENT NO. 1 OF BRIDGE "B" AND ONE 26' TEST PILE IN BENT NO. 3 OF BRIDGE "A". PILES FOR END BENTS SHALL BE DRIVEN AFTER EMBANKMENT TO SUBGRADE IS IN PLACE.

ALL CONCRETE IN THE SUPERSTRUCTURE SHALL BE CLASS S(AE). ALL CONCRETE IN THE SUBSTRUCTURE SHALL BE CLASS S AND SHALL BE POURED IN THE DRY. ALL EXPOSED CORNERS SHALL BE CHAMFERED 3/4" UNLESS OTHERWISE NOTED.

FOR DETAILS OF END BENTS, SEE DWG. NO. 18076
 FOR DETAILS OF INTERMEDIATE BENTS, SEE DWG. NO. 18077
 FOR DETAILS OF SUPERSTRUCTURE, SEE DWG. NO. 18078, 18079 & 18080
 FOR DETAILS OF PRECAST CONCRETE PILING, SEE DWG. NO. 2382
 FOR DETAILS OF CONCRETE FILLED METAL SHELL PILING, SEE DWG. NO. 2391A

SPECIFICATIONS: ARKANSAS STATE HIGHWAY COMMISSION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EDITION OF 1972, AND APPLICABLE SPECIAL PROVISIONS.

DESIGN SPECIFICATIONS: AASHO 1969
 LIVE LOADING: HS20

UNIT STRESSES: CLASS S AND S(AE) CONCRETE (N=IC) 1,200 PSI
 REINFORCING STEEL 20,000 PSI
 STRUCTURAL STEEL (A36) 20,000 PSI
 STRUCTURAL STEEL (A572-50) 27,000 PSI


FOR INFORMATION ONLY

LAYOUT OF BRIDGES OVER HWY. 270
 HWY. 270 - HWY 104
 JEFFERSON COUNTY
 ROUTE 65 SEC. 14
 ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.

BRIDGE NO. 5500A&E DRAWING NO. 18075

Leonard Speed 6/21/2016 10:26:31AM
 W:\PROJECTS\AR\CONTRACTS\ROADWAY\Drawings\BB0202\13.MAN.OLD.dgn
 Y:\Projects\AR\TDL\138215\1-530.Hwy104-Hwy65B\Deliverables\ROADWAY\Drawings\BB0202\13.MAN.OLD.dgn

DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				2	ARK.			
						BB0202	206	235
							A&B 5501- LAYOUT - XXXXX	



DATE	DATE FILMED	DATE REVISED	DATE FILMED	FED. RD. DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
3-11-74		5-17-74		6	ARK.			
							A&B LAYOUT - 18081	

GENERAL NOTES

BENCH MARK - R.R. SPIKE IN CORNER, +0.12' RT. STA. 345+20.0, ELEV. 278.64.

IN GENERAL, ALL CONSTRUCTION JOINTS SHALL BE HORIZONTAL AND SHALL BE PROVIDED WITH KEYS NOT LESS THAN 1/2" HIGH COVERING THE MIDDLE THIRD OF BOTH MEMBERS.

ALL PILING SHALL BE 16" OCTAGONAL PRECAST CONCRETE OR 16" CONCRETE FILLED METAL SHELLS AND SHALL BE DRIVEN WITH AN APPROVED AIR, STEAM OR DIESEL HAMMER TO A MINIMUM BEARING CAPACITY OF 44 TONS PER PILE AND TO A MINIMUM PENETRATION OF 20' BELOW THE GROUND LINE. LENGTHS OF PILES SHOWN ARE ASSUMED FOR ESTIMATING QUANTITIES ONLY. ACTUAL LENGTHS TO BE DETERMINED IN THE FIELD. DRIVE ONE 40' TEST PILE IN EACH BENT, BRIDGE "B", AND ONE 26' TEST PILE IN INTERIOR BENT 3, BRIDGE "A". PILES IN END BENTS SHALL BE DRIVEN AFTER EMBANKMENT TO SUBGRADE IS IN PLACE.

ALL CONCRETE IN THE SUPERSTRUCTURE SHALL BE CLASS "S(AE)". ALL CONCRETE IN THE SUBSTRUCTURE SHALL BE CLASS "S" AND SHALL BE POURED IN THE DRY. ALL EXPOSED CORNERS SHALL BE CHAMFERED 3/4" UNLESS OTHERWISE NOTED.


FOR DETAILS OF END BENTS, SEE DWG. NO. 18082
 FOR DETAILS OF INTERMEDIATE BENTS, SEE DWG. NO. 18083
 FOR DETAILS OF SUPERSTRUCTURE, SEE DWG. NOS. 18084 THRU 18086
 FOR DETAILS OF PRECAST CONCRETE PILING, SEE DWG. NO. 2352.
 FOR DETAILS OF CONCRETE FILLED METAL SHELL PILING, SEE DWG. NO. 2381A.

SPECIFICATIONS: ARKANSAS STATE HIGHWAY COMMISSION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, EDITION OF 1972, AND APPLICABLE SPECIAL PROVISIONS.

DESIGN SPECIFICATIONS: AASHTO 1969
 LIVE LOADING: HS20
 UNIT STRESSES: CLASS "S" AND S(AE) CONCRETE (N=10) 1,200 PSI
 REINFORCING STEEL 20,000 PSI
 STRUCTURAL STEEL (A36) 20,000 PSI

NOTE: For Guard Fence, Approach Slabs and Gutters, See: Detail Plans.
 For Concrete Riprap see: Det. No. 4795A

- BORING LOGGING**
- 1A Firm Brown Sandy Clay
 - 1B Firm Brown Sandy Clay & Small Gravel
 - 1C Firm Brown Sandy Clay & Large Gravel
 - 1D Med. Firm Brown Sandy Clay
 - 1E Firm & Gray Sandy Clay
 - 1F Gray Sandy Clay
 - 1G Blue Clay
 - 1H Firm Fine Gray Sand, Wet
 - 1I Brown Clay
 - 1J Gray Clay
 - 1K Firm Brown Clay - Few Large Gravel



FOR INFORMATION ONLY

Revised - Changed Profile Grade Elev. - As Shown, 3-11-74 (DF)


LAYOUT OF BRIDGES
 OVER HOLLAND STREET
 HWY. 270 - HWY. 104
 JEFFERSON COUNTY

ROUTE 65 SEC. 14
 ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.
 2 November 72

DRAWN BY: KMG DATE: 2 November 72
 TRACED BY: GVA DATE: 5/17/74
 CHECKED BY: GVA DATE: 5/17/74


BRIDGE NO. 5501 A & B DRAWING NO. 18081

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
9/2/15				6	ARK.		301	
JOB NO.							TYPE AT GUTTERS 55036	




PLAN - SQUARE BRIDGES

$\frac{3}{8}'' = 1'-0''$
 "S" = Distance from gutterline to edge of approach slab.




PLAN - SKEWED BRIDGES

$\frac{3}{8}'' = 1'-0''$



Note: All longitudinal lines within the limits of horizontal curves shall be on curves concentric to C.L. Bridge. Adjustment to longitudinal bar lengths may be required. Transverse reinforcing shall be placed on radial lines to C.L. Bridge.

Slope top of transition rail to match top of existing end post when end post is greater than 2'-9" above gutterline.




LONGITUDINAL SECTION THRU GUTTER

$\frac{1}{2}'' = 1'-0''$

DOWELING NOTE


If new approach slab is used, place dowels into approach slab using 18" embedment.

If existing approach slab is retained, dowels shall be drilled and grouted 18" into existing slab. At the Contractor's option, existing dowels may be retained, cleaned and incorporated into new gutters. Work for drilling and grouting, or retaining and cleaning will not be paid for separately but will be considered subsidiary to "Approach Gutters".




SECTION A-A

$\frac{1}{2}'' = 1'-0''$




SECTION B-B

$\frac{1}{2}'' = 1'-0''$




SECTION C-C

At end of Transition Roll
 $\frac{1}{2}'' = 1'-0''$



DETAIL X


$\frac{3}{8}'' = 1'-0''$



ALTERNATE DETAILS


N.T.S.

This document was originally issued and sealed by Charles R. Ellis, PE No. 9235, on September 2, 2015. This copy is not a signed and sealed document.



QUANTITIES FOR ONE SQUARE APPROACH GUTTER (FOR INFORMATION ONLY)

"S"	Concrete	Reinforcing Steel
5'-6"	12.06 cu.yd.	1091 lb.
9'-6"	18.78 cu.yd.	1573 lb.



GENERAL NOTES

All concrete shall be Class S or (S/AE) or mixture used for Portland Cement Concrete Pavement and shall be poured in the dry.
 All reinforcing steel shall be Grade 60 (yield strength = 60,000 psi) conforming to AASHTO M 31 or M 322, Type A, with mill test reports. Fabricate bar lengths to provide 2" minimum cover at each end.
 Approach gutters will be measured and paid for in accordance with Section 504.

Added note for gutters within the limits of horizontal curves. By: AMS
 Checked By: KKY 9/2/15

STANDARD DETAILS FOR TYPE 'AT' APPROACH GUTTERS (BRIDGES WITH 6" CURB WIDTH & TYPE A RAILING)



ARKANSAS STATE HIGHWAY COMMISSION
 LITTLE ROCK, ARK.

DRAWN BY: KDH DATE: 2/27/2014 FILENAME: b55036.dgn
 CHECKED BY: KKY DATE: 2/27/2014 SCALE: AS SHOWN
 DESIGNED BY: STD. DATE:

DRAWING NO. 55036

DATE REVISED	DATE FILMED	DATE REVISED	DATE FILMED	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.	TOTAL SHEETS
				6	ARK.		205	
				JOB NO.	TYPE CI APPROACH SLAB 55040CI			

Notes:
The surface finish for Approach Slabs shall match that used on the bridge deck.
All longitudinal lines within the limits of horizontal curves shall be on curves concentric to C.L. Bridge. Adjustment to longitudinal bar lengths may be required. Transverse reinforcing shall be placed on radial lines to C.L. Bridge.



- ① S5XX = S511 for 15'-0" Width
= S517 for 24'-0" Width
= S525 for 36'-0" Width
- ② S7XX = S730 for 15'-0" Width
= S748 for 24'-0" Width
= S772 for 36'-0" Width


PLAN - SKEWED APPROACH SLAB WITH APPROACH GUTTERS
1/4" = 1'-0"

PLAN - SQUARE APPROACH SLAB
1/4" = 1'-0"

BAR LIST
(Square & Skewed Approach Slabs)


Slab Width	Square		Skewed		
	Mark	No. Req'd.	Length	No. Req'd.	Length
15'-0"	S401	33	14'-8"	37	14'-8"
	S402	30	2'-8"	45	2'-8"
	S403	50	3'-0"	*	3'-0"
	S501	37	14'-8"	37	14'-8"
	S502	10	36'-2"	—	—
	S502 - S511	—	—	1 Ea.	36.1' + 0.75' (tan skew angle) to 36.1' + 14.25' (tan skew angle)
24'-0"	S5...	—	—	2 Ea.	14.7' - 0.75' / (tan skew angle) to 2'-0" Min.
	S701 - S730	30	36'-2"	—	—
	S701 - S748	—	—	1 Ea.	36.1' + 0.25' (tan skew angle) to 36.1' + 14.75' (tan skew angle)
	S401	33	23'-8"	37	23'-8"
	S402	48	2'-8"	72	2'-8"
	S403	50	3'-0"	*	3'-0"
36'-0"	S501	37	23'-8"	37	23'-8"
	S502	16	36'-2"	—	—
	S502 - S517	—	—	1 Ea.	36.1' + 0.75' (tan skew angle) to 36.1' + 23.25' (tan skew angle)
	S5...	—	—	2 Ea.	23.7' - 0.75' / (tan skew angle) to 2'-0" Min.
	S701 - S748	48	36'-2"	—	—
	S701 - S772	—	—	1 Ea.	36.1' + 0.25' (tan skew angle) to 36.1' + 23.75' (tan skew angle)
36'-0"	S401	33	35'-8"	37	35'-8"
	S402	72	2'-8"	108	2'-8"
	S403	50	3'-0"	*	3'-0"
	S501	37	35'-8"	37	35'-8"
	S502	24	36'-2"	—	—
	S502 - S525	—	—	1 Ea.	36.1' + 0.75' (tan skew angle) to 36.1' + 35.25' (tan skew angle)
36'-0"	S5...	—	—	2 Ea.	35.7' - 0.75' / (tan skew angle) to 2'-0" Min.
	S701 - S772	72	36'-2"	—	—
	S701 - S772	—	—	1 Ea.	36.1' + 0.25' (tan skew angle) to 36.1' + 35.75' (tan skew angle)

* Varies with skew angle




DETAILS OF LONGITUDINAL CONSTRUCTION JOINT
3/4" = 1'-0"


1/2" x 1" Poured Jt. Sealer (Type 3 or 4) per Subsection 501.02(h)(2) Backer rod is not required.




SECTION A-A
N.T.S.




SECTION B-B
AT ASPHALT APPROACH PAVEMENT
N.T.S.



SECTION B-B
AT CONCRETE APPROACH PAVEMENT
N.T.S.



SECTION X-X
SQUARE APPROACH SLAB SHOWN
1/4" = 1'-0"



SECTION Y-Y
N.T.S.

TABLE OF QUANTITIES FOR ONE SQUARE APPROACH SLAB
(FOR INFORMATION ONLY)

Slab Width	Reinforcing Steel (Lbs.)	Concrete (Cu. Yds.)
15'-0"	3640	30.75
24'-0"	5775	49.15
36'-0"	8620	73.75

GENERAL NOTES


This drawing shall be used for Approach Slabs in Seismic Performance Zone 1 and for the maximum skew angles shown below:
15'-0" Slab Width: Maximum Skew Angle = 50°
24'-0" Slab Width: Maximum Skew Angle = 40°
36'-0" Slab Width: Maximum Skew Angle = 30°
All concrete shall be Class S (AE) with a minimum 28 day compressive strength $f'_c = 4,000$ psi and shall be poured in the dry.
All reinforcing steel shall be Grade 60 (yield strength = 60,000 psi) conforming to AASHTO M 31 or M 322, Type A, with mill test reports.
Approach Slabs will be measured and paid for in accordance with Section 504.

STANDARD DETAILS FOR TYPE CI APPROACH SLAB
ARKANSAS STATE HIGHWAY COMMISSION
LITTLE ROCK, ARK.

DRAWN BY: A.M.S. DATE: 2/27/2014 FILENAME: b55040cl.dgn
CHECKED BY: K.W.Y. DATE: 2/27/2014 SCALE: AS SHOWN
DESIGNED BY: STD. DATE:


DRAWING NO. 55040CI

REFER TO TABULATION OF QUANTITIES FOR 'W' & 'B' DIMENSIONS



TYPE A


REFER TO TABULATION OF QUANTITIES FOR 'W' DIMENSIONS




TYPE B

THE STEEL AND ADDITIONAL CONCRETE FOR THE WALLS SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID FOR 'CONCRETE DITCH PAVING.'

TOE WALL DEPTH MAY BE ALTERED TO 1'-0" WHEN DIRECTED BY THE ENGINEER IN ROCK EXCAVATION




TOE WALL DETAIL FOR CONCRETE DITCH PAVING



NUMBER OF ELEMENTS PER ROW VARIES WITH WIDTH OF PAVING SPECIFIED

ENERGY DISSIPATORS TO BE USED FOR THE ENTIRE LENGTH OF DITCH WHEN SLOPE OF DITCH PAVING EXCEEDS 7%. THE DISSIPATORS WILL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID FOR CONCRETE DITCH PAVING.



ENERGY DISSIPATORS (NO SCALE)

GENERAL NOTES:

THE FULL WIDTH OF EACH SECTION SHALL BE POURED MONOLITHICALLY.

TOE WALLS TO BE CONSTRUCTED FULL WIDTH AT EACH END OF DITCH PAVING, AND POURED MONOLITHICALLY.

SOLID SOD ALONG DITCH PAVING TO BE PLACED WITHIN 14 DAYS OF DITCH PAVING CONSTRUCTION.


1" WIDE TRANSVERSE EXPANSION JOINTS SHALL BE PLACED IN CONCRETE DITCH PAVING AT 45' INTERVALS. THE SPACE SHALL BE FILLED WITH APPROVED JOINT FILLER COMPLYING WITH AASHTO M213.

DATE	REVISION	DATE FILM'D
11-17-10	ADDED GENERAL NOTE	
6-2-94	ADDED GENERAL NOTE ABOUT SOLID SODDING	
11-30-88	ELIMINATED MIN. ROWS OF ELEMENTS	11-30-89
7-15-88	REVISED DISSIPATOR NOTE	653-7-15-88
4-3-87	REVISED ENERGY DISSIPATOR	671-4-3-87
1-9-87	MODIFIED NOTE ON ENERGY DISS.	532-1-9-87
11-3-86	ADDED NOTE TO ENERGY DISS.	599-12-1-86
11-1-84	ENERGY DISSIPATOR DETAILS	508-11-1-84
11-1-84	ADDED EXCAVATION DETAILS ADDED	
10-2-72	TYPED A & B REVISED AND REDRAWN	508-10-2-72

ARKANSAS STATE HIGHWAY COMMISSION


CONCRETE DITCH PAVING

STANDARD DRAWING CDP-1




LONGITUDINAL JOINT

NOTE: THE TIE BAR SUPPORT SHOWN ABOVE MAY BE ELIMINATED IF OTHER APPROVED METHODS FOR PLACING AND SUPPORTING THE TIE BARS ARE PROVIDED.
TIE BARS SHALL BE 15' FROM TRANSVERSE JOINTS.




NOTE: EACH DOWEL TO BE COATED ACCORDING TO SECTION 502 OF THE STANDARD SPECIFICATIONS.




ONE-HALF 24' PAVEMENT
12 DOWELS
PLAN

NOTE: FOR 20' PAVEMENT USE 20 DOWELS @ 12' CTRS. WITH 6' SPACING FROM C.L. AND EDGE OF SLAB TO FIRST BAR. FOR 15' PAVEMENT USE 15 DOWELS @ 12' CTRS. WITH 6' SPACING FROM C.L. AND EDGE OF SLAB TO FIRST BAR. FOR 26' PAVEMENT USE 26 DOWELS @ 12' CTRS. WITH 6' SPACING FROM C.L. AND EDGE OF SLAB TO FIRST BAR. FOR PAVEMENT WIDTHS OTHER THAN THOSE SHOWN ABOVE, USE DOWELS AT 12' CTRS. WITH 6' MAX. SPACING FROM C.L. TO FIRST BAR. DISTANCE FROM EDGE OF SLAB TO FIRST BAR SHALL BE ADJUSTED TO MAINTAIN 12' DOWEL BAR SPACING

CONTRACTION JOINT DETAILS



DETAIL OF SAWED CONTRACTION JOINT




DETAIL OF EXPANSION JOINT

JOINT CONFIGURATION FOR TYPE 3 OR 4 JOINT SEALANT


JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/4	3/8	1/2
3/8	1/4	1/2	1/2
1/2	1/4	5/8	1/2
3/4	3/8	3/4	3/4
1	3/8	7/8	3/4
1 1/2	3/4	2	1 1/4

JOINT CONFIGURATION FOR TYPE 5 JOINT SEALANT

JOINT WIDTH	SEALANT THICKNESS ①	BACKER ROD DIAMETER	BACKER ROD PLACEMENT DEPTH ②
INCHES			
1/4	1/2	3/8	3/4
3/8	3/4	1/2	1




PLAN SHOWING EXPANSION JOINTS AT BRIDGE APPROACH SLABS



NOTE: ALL DOWEL BARS SHALL CONFORM TO THE DETAILS FOR CONTRACTION JOINTS.


ELEVATION



DETAIL OF SAWED LONGITUDINAL JOINT AND LONGITUDINAL CONSTRUCTION JOINT



*NOTE: T/3 SAW CUT NOT REQUIRED FOR LONGITUDINAL CONSTRUCTION JOINT.

DATE	REVISION	DATE FILMED
5-25-06	ADDED GENERAL NOTE 7	
10-9-03	REMOVED TIE BAR COATING & REVISED GENERAL NOTES	
11-16-01	ADDED TOOL SEALANT AND NOTE 5; REVISED NOTE 3	
4-26-96	REVISED CONTRACTION JOINT NOTE	
11-3-94	ADDED NOTE RE: REINF. BARS	
4-1-93	REVISED DOWEL BARS & GEN. NOTES	4-1-93
10-1-92	REVISED DOWEL SPACING	10-1-92
8-15-91	ADDED SPAC FOR CONTR JTS & DEL KEYWAY	
05-24-90	REVISED TIE BAR, DOWEL & JOINT SIZE	
01-25-90	ADDED EXPANSION JOINT	01-25-90
11-30-89	CHANGED T/4+1 TO T/3+1	11-30-89
03-23-89	ALTERED SAWED JOINT & ADDED NOTE	512-03-23-89
07-15-88	REVISED AND REDRAWN	632-07-15-88



DETAIL OF JOINT SUPPORT FOR EXPANSION JOINTS


- GENERAL NOTES
1. 'T' DENOTES THICKNESS OF SLAB.
 2. DOWEL BARS SHALL BE PLACED IN ACCORDANCE WITH THE DIMENSIONS SHOWN. A TOLERANCE OF PLUS OR MINUS ONE INCH WILL BE ALLOWED FOR THE VERTICAL AND LATERAL PLACEMENT AND A TOLERANCE OF PLUS OR MINUS 1/4" WILL BE ALLOWED FOR THE TILT AND SKEW. DOWEL BARS SHALL BE FIELD COATED FOR A MINIMUM DISTANCE OF 2' GREATER THAN HALF THE LENGTH OF THE BAR WITH AN APPROVED GREASE AS A BOND BREAKER JUST PRIOR TO PLACEMENT OF CONCRETE.
 3. THE EXPANSION JOINT SUPPORT MAY BE CONSTRUCTED WITH CLASS 'A', 'S' OR PAVING CONCRETE. PAYMENT FOR THE JOINT SUPPORT SHALL BE FOR THE CONTRACT UNIT PRICE BID FOR THE CLASS OF CONCRETE SPECIFIED IN THE PLANS. PAYMENT FOR ALL OTHER WORK AND MATERIALS REQUIRED FOR THE CONSTRUCTION OF THE JOINT SUPPORT SHALL BE INCLUDED IN THE PRICE BID FOR THE ABOVE ITEMS.
 4. CONTRACTION JOINTS SHALL BE CONSTRUCTED ON 15' CENTERS.
 5. TOOLING NOT REQUIRED FOR SELF-LEVELING SILICONE.
 6. UNLESS OTHERWISE SPECIFIED IN THE PLANS, CONCRETE SHOULDERS SHALL BE CONSTRUCTED ACCORDING TO THE DETAILS SHOWN HEREON. CONTRACTION JOINTS SHALL MATCH CONTRACTION JOINTS IN THE LANES.
 7. TIE WIRES IN DOWEL BAR ASSEMBLIES SHALL NOT BE CUT PRIOR TO PLACEMENT OF PAVING CONCRETE.



5/8" Ø X 2'-6" DEFORMED BARS @ 2'-6" CTRS. FOR ENTIRE LENGTH OF SLAB


NOTE: TIE BARS SHALL BE 15' FROM TRANSVERSE JOINTS.

LONGITUDINAL CONSTRUCTION JOINT




SECTION


TRANSVERSE CONSTRUCTION JOINT




SECTION B-B



PLAN




SECTION A-A




SECTION B-B

METHOD OF CONSTRUCTING DROP INLET ON EXISTING R.C. BOX CULVERT




SECTION A-A




SECTION B-B

METHOD OF CONSTRUCTING DROP INLET ON NEW R.C. BOX CULVERT

NOTE: "C" DIMENSIONS AND REINFORCING BAR SIZES, SHALL CONFORM TO THOSE SHOWN ON STANDARD DRAWING FOR DROP INLET.




PLAN




SECTION A-A

DROP INLET (TYPE E)

NOTE: REINF. BARS TO BE #4 BARS ON 6" CTRS. WITH 1/2" MIN. COVER. THIS TYPE DROP INLET TO BE USED WHERE NOT SUBJECTED TO TRAFFIC.



SECTION B-B




APPROX. WEIGHT = 11 LBS. (CAST IRON)


PLAN

NOTE: THIS DETAIL IS TYPICAL, OTHERS MAY BE USED WITH PRIOR APPROVAL OF THE ENGINEER.


DETAIL OF STEP FOR DROP INLET



COVER FACE




RING SECTION




COVER SECTION

APPROXIMATE TOTAL WEIGHT = 333 LBS.

HEAVY DUTY RING & COVER




PLAN




SECTION A-A

JUNCTION BOX (TYPE E)


NOTE: REINF. BARS TO BE #4 BARS ON 6" CTRS. WITH 1/2" MIN. COVER. THIS TYPE JUNCTION BOX TO BE USED WHERE NOT SUBJECTED TO TRAFFIC.



SECTION B-B




SECTION A-A



SECTION B-B

APPROXIMATE MINIMUM WATERWAY OPENING = 260 SQ. IN.

GRATE FOR TYPE E DROP INLET



DETAIL OF YARD DRAIN







DATE	REV.	REVISION	DATE FILMED
11-16-01		ADDED NOTE 10	
1-12-00		REVISED HEAVY DUTY RING & COVER	
7-02-98		CHANGED GRATE DETAIL, DELETED DI (TYPE D), REPLACED RING & COVER W/HEAVY DUTY RING & COVER, ADDED JUNCTION BOX (TYPE E)	
6-26-97		ADDED DIMENSION TO TYPE IV-A	
10-18-96		ADDED DETAIL OF YARD DRAIN	
8-15-91		DELETE TYPE IV GRATE	
7-15-88		REVISED STEP DETAIL	
5-20-83		REVISED DETAILS OF GRATES (TYPE IV & IV-A)	
2-4-83		ADDED GENERAL NOTE NO. 4	
3-2-81		ADDED TYPE IV-A GRATE	
5-22-74		DELETED INLET (TYPE F) & GRATE (TYPE III)	
10-2-72		REVISED AND REDRAWN	

- GENERAL NOTES:
1. ALL EXPOSED CORNERS SHALL BE 3/4" CHAMFERED.
 2. STEPS SHALL BE INSTALLED ON 16" CENTERS ON ALL INLETS 4'-0" HIGH OR OVER, OR AS APPROVED BY THE ENGINEER.
 3. EXPANSION JOINT MATERIAL SHALL BE 3/4" PREFORMED FIBER.
 4. GRATE OR GRATE AND FRAME SHALL BE CONSTRUCTED OF CAST IRON AND SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR GRAY IRON CASTINGS AASHTO M 105 CLASS 35B. GRATE MAY BE USED WITHOUT FRAME.
 5. GRATE AND FRAME SHALL NOT BE PAINTED.
 6. GRATE SHALL BE BICYCLE SAFE.
 7. HEAVY DUTY RING SHALL ALWAYS BE INSTALLED WITH FLANGE ON TOP.
 8. HEAVY DUTY RING AND COVER SHALL BE CONSTRUCTED OF CAST IRON AND SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR GRAY IRON CASTINGS AASHTO M 105 CLASS 35B & AASHTO M 306.
 9. HEAVY DUTY RING AND COVER SHALL NOT BE PAINTED.
 10. DIMENSIONS SHOWN FOR RING AND COVER ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR CASTINGS WITH THE APPROVAL OF THE ENGINEER. REQUESTING APPROVAL FOR CASTING DESIGNS MAY BE MADE BY REFERRING TO PREVIOUSLY APPROVED DRAWINGS.

ARKANSAS STATE HIGHWAY COMMISSION

DETAILS OF DROP INLETS & JUNCTION BOXES

STANDARD DRAWING FPC-9






APPROX. WEIGHT = 11 LBS. (CAST IRON)
 PLAN
 NOTE: THIS DETAIL IS TYPICAL. OTHERS MAY BE USED WITH PRIOR APPROVAL OF THE ENGINEER.
 DETAIL OF STEP FOR DROP INLET

- GENERAL NOTES:
1. STEEL PIPE FOR GRATES AND BOLTS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 807. BOLTS SHALL CONFORM TO ONE OF THE FOLLOWING: ASTM A193, GRADE BB CLASS 10R 2, ASTM A307 OR AASHTO M 164.
 2. STEEL PIPE FOR GRATES SHALL BE "STANDARD WEIGHT" PIPE CONFORMING TO ASTM A53 NATIONAL STANDARD PIPE.
 3. BOLTS, NUTS, WASHERS SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M 232 OR AASHTO M 298, CLASS 40 OR 50.
 4. ALL EXPOSED CORNERS TO HAVE 3/4" CHAMFER.
 5. ALL #4 AND #5 REINFORCING BARS TO HAVE 1/2" COVER. LARGER SIZES TO HAVE 2" COVER.
 6. THE COMPLETE PIPE GRATE SHALL BE PAINTED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

TABLE OF "W" DIMENSIONS

I.D. PIPE	SKEW OF CROSS DRAIN		
	STRAIGHT	30°	45°
24"	4'-0"	4'-0"	4'-0"
30"	4'-0"	4'-0"	4'-5"
36"	4'-0"	4'-3"	5'-3"
42"	4'-3"	4'-11"	6'-1"
48"	4'-10"	5'-7"	6'-11"

NOTE: DIMENSIONS SHOWN ABOVE ARE FOR PIPES INTERSECTING DROP INLET ON ONE SIDE ONLY. FOR SKEWED PIPES INTERSECTING BOTH SIDES OF DROP INLET, "W" WILL NEED TO BE INCREASED OR AXIS OF INTERSECTING PIPES WILL NEED TO BE SHIFTED.




8-22-02	ADDED & REVISED DIMENSION TO SECTION A-A	
1-12-00	CORRECTED DIMENSION ON SECTION B-B	
11-06-97	ADDED DIMENSION TO SECTION A-A	
10-18-96	REVISED ASTM REF. TO AASHTO AND ADDED NOTE TO TABLE OF "W" DIMENSIONS	
10-1-92	ADDED DIRECTION OF TRAFFIC	10-1-92
8-15-91	ADDED NOTE ABOUT PAINTING OF GRATE	8-15-91
11-30-89	ALTERED DETAIL A	11-30-89
7-15-88	REVISED STEP DETAIL, TM & RM D.I. & GRATE DETAIL	7-15-88
10-2-72	REVISED AND REDRAWN	542-10-2-72
REVISED		DATE FILMED


NOTE: ADDT'L. REINF. STEEL TO BE INCLUDED IN UNIT PRICE BID PER TYPE "TM" D.I.
 DIMENSIONS & REINF. BARS FOR D.I. TO BE THE SAME AS THOSE SHOWN ON APPLICABLE STD. BARREL DRAWING FOR R.C. BOX CULVERTS.

DROP INLET TYPE "TM" FOR REINFORCED CONC. BOX CULVERTS


ARKANSAS STATE HIGHWAY COMMISSION
 DETAILS OF DROP INLETS
 STANDARD DRAWING FPC-9D



PLAN



FRONT ELEVATION



SIDE ELEVATION
CONCRETE SPILLWAY

DETAILS OF CONCRETE SPILLWAY (TYPE A)


BAR LIST
(CONCRETE SPILLWAY)

MARK	NO. REQ'D.	LENGTH	BENDING DIAGRAM
D404	3	2'-2"	
D405	2	3'-8"	
D406	1	3'-5"	
D407	1	3'-1"	
D408	1	2'-9"	
D409	1	2'-5"	
D410	2	2'-5"	
D411	2	2'-2"	
D412	2	1'-9"	
D413	2	5'-6"	
D414	2	1'-2"	
D415	3	6'-5"	

BAR LIST (DROP INLET)

MARK	TYPE N-1		TYPE N-2		TYPE N-3	
	NO. REQ'D.	LENGTH	NO. REQ'D.	LENGTH	NO. REQ'D.	LENGTH
D401	20	3'-0"	26	3'-0"	32	3'-0"
D402	19	2'-2"	19	3'-8"	19	5'-2"
D403	17	2'-11"	20	2'-11"	23	2'-11"


ALL BARS #4 @ 6" SPACING



DETAILS OF DROP INLET



GENERAL NOTES (GRATE & FRAME)

1. RIBBED VANE GRATE AND FRAME SHALL BE CONSTRUCTED OF CAST IRON AND SHALL CONFORM TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR GRAY IRON CASTINGS AASHTO M 105 CLASS 35B & AASHTO M 306.
2. GRATE AND FRAME SHALL NOT BE PAINTED.
3. GRATE AND FRAME SHALL BE INSTALLED IN DROP INLET IN ASSEMBLED POSITION.
4. APPROXIMATE WEIGHT OF GRATE SHALL BE 170 LBS.




DETAILS OF RIBBED VANE GRATE AND FRAME


DATE REVISED	DATE FILMED	DESCRIPTION	ARKANSAS STATE HIGHWAY COMMISSION
7-02-98	7-2-98	REVISED SECT. A-A DETAIL OF DROP INLET & ADDED AASHTO REF. TO NOTE 1, REVISED GRATE	DETAILS OF DROP INLETS AND SPILLWAY OUTLET
10-18-96		REVISED ASTM REF. TO AASHTO	
8-15-91		ISSUED	
DATE REVISED	DATE FILMED	DESCRIPTION	STANDARD DRAWING FPC-9N




DETAILS OF W-BEAM GUARD RAIL
RAIL SECTION OF CLOSELY SIMILAR DIMENSIONS AND COMPARABLE STRENGTH MAY BE SUBSTITUTED IF APPROVED BY THE ENGINEER.




**SPLICE BOLT
POST BOLT - SAME EXCEPT LENGTH**



CUT STEEL WASHER




NUT




WOOD BLOCKOUT (W-BEAM) PLASTIC BLOCKOUT (W-BEAM)


NOTES:
1. SIMILAR SHAPED PLASTIC BLOCKOUTS MAY BE USED AS LONG AS THEY MEET NCHRP-350 TEST LEVEL 3 SPECIFICATIONS OR REQUIREMENTS FOR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH).
2. DIMENSIONS ARE SUBJECT TO MANUFACTURERS TOLERANCES.



**WOOD BLOCKOUT CONNECTIONS PLASTIC BLOCKOUT CONNECTIONS
DETAILS OF STEEL LINE POST CONNECTIONS (W-BEAM)**




STEEL POST



TYPE "B" TYPE "A"

DETAILS OF STEEL LINE POST CONNECTIONS (W-BEAM)



**WOOD BLOCKOUT CONNECTIONS PLASTIC BLOCKOUT CONNECTIONS
DETAILS OF WOOD LINE POST CONNECTIONS (W-BEAM)**

-GENERAL NOTES-


ALL BOLTS SHALL BE SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND NO MORE THAN 1/4" BEYOND IT.
WHERE W-BEAM GUARD RAIL CONTINUES, THE INTERMEDIATE SECTIONS SHALL HAVE A POST SPACING OF 6'-3" UNLESS OTHERWISE NOTED.
W-BEAM GUARD RAIL REPRESENTING INTERMEDIATE SECTIONS WILL BE MEASURED ALONG THE ROADWAY FACE FROM CENTERLINE OF POST TO CENTERLINE OF POST.
USE W-BEAM GUARD RAIL COMPONENTS OF SAME MATERIAL FOR ENTIRE JOB. FOR EXTENSIONS OR MODIFICATION OF EXISTING GUARD RAIL, W-BEAM GUARD RAIL COMPONENTS OF THE SAME TYPE AS THOSE EXISTING SHALL BE USED.
ANY BACKFILLING UNDER OR AROUND POST SHALL BE DAMP SAND THOROUGHLY TAMPED IN PLACE.
WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER 9.7f (1400 f) OR NO. 1 1350 f SOUTHERN PINE.
CONTRACTOR SHALL HAVE THE OPTION OF USING WOOD BLOCKOUTS FOR W-BEAM GUARD RAIL OR PLASTIC BLOCKOUTS, AS LONG AS BLOCKOUT USED MEETS NCHRP-350 TEST LEVEL 3 SPECIFICATIONS OR REQUIREMENTS FOR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) FOR W-BEAM GUARD RAIL.

DATE	REVISION	DATE FILED
7-14-10	RAISED HEIGHT OF GUARD RAIL 1"	
10-5-09	ADDED REFERENCE TO MASH	
4-10-03	REVISED GENERAL NOTES	
8-22-02	REVISED DIMENSION ON WOOD & PLASTIC BLOCKOUT CONNECTIONS & ON STEEL POST	
11-16-01	REVISED WOOD BLOCKOUT & DETAILS OF WOOD LINE POST CONNECTIONS	
3-30-00	REMOVED GUARD RAIL AT BRIDGE ENDS	
1-12-00	ADDED PLASTIC BLOCKOUT	
8-12-98	REV. BLOCKOUTS TO WOOD, DELETED CONC. POST & REV. GENERAL NOTE, DELETED DET. OF GUARD RAIL REPLACE BEHIND CURB & DET. OF POST PLACE IN SOLID ROCK, & ADDED DETAILS OF STEEL LINE POST CONN. REMOVED BACK-UP PLATE, REVISED HOLES IN STEEL POLES	
4-3-97	REMOVED "LAP IN DIRECTION OF TRAFFIC" NOTE & PLACED ARROWS ON WASHERS	
10-18-96	REVISED WOOD POST NOTE	
6-2-94	ADDED ALT. STEEL POST SIZE	
8-5-93	REVISED STEEL POST SIZE	8-5-93
10-1-92	REDRAWN & REVISED	10-1-92
8-15-91	REVISED WASHER NOTE	8-15-91
8-2-90	REV. GEN. NOTE & DET. OF ANC. POST IN ROCK	8-2-90
7-15-88	REVISED SECTION 3 & GENERAL NOTES	
3-4-88	REV. ANCHOR POST, ELEV. NOTES & POST IN ROCK	780-3-4-88
10-30-87	REVISED WOOD LINE POST DETAIL	546-10-30-87
10-9-87	REDRAWN & REVISED	802-10-9-87


ARKANSAS STATE HIGHWAY COMMISSION

GUARD RAIL DETAILS

STANDARD DRAWING GR-8



Note: Bolts, nuts, washers and plates shall be galvanized in accordance with Section 807 of the Standard Specifications.




FOR DESIGN SPEEDS OF 50 MPH OR LESS
ALIGN FACE OF GUARD RAIL WITH FACE OF CURB.

FOR DESIGN SPEEDS OF 55 MPH OR MORE
PLACE GUARD RAIL POSTS AGAINST BACK OF CURB.


DETAIL OF GUARD RAIL PLACEMENT BEHIND CURB (W-BEAM)

FOR DESIGN SPEEDS OF 50 MPH OR LESS ALL CURB FACES, AS SHOWN ON STD. DRWG. CG-1, MAY BE USED. FOR DESIGN SPEEDS OF 55 MPH OR MORE TYPE "E" CURB FACE SHALL BE USED.




Plan View Steel Posts

Either hole configuration acceptable



Plan View Wood Posts

Either hole configuration acceptable



Notes: For overlying soil depths (A) ranging from 0 to 18", the depth of required drilling (B) is equal to 24".


Zone A: Backfill according to Section 617.03(a).

Zone B: Backfill hole in 6" lifts with material meeting the requirements of Section 802.02(c) - Alternate gradation. Compact to 95% maximum dry density per ASTM D-698.


Notes: For overlying soil depths (A) ranging from 18" to 44", the depth of required drilling (B) is equal to either 12" or 44" minus the depth of soil whichever is less.

Zone A & B: Backfill according to Section 617.03(a).


DETAIL OF POST PLACEMENT IN SOLID ROCK (W-BEAM)



SECTION A-A



DETAIL OF CONNECTION



PLAN LAYOUT OF TYPE A GUARD RAIL AT LOW-FILL CULVERTS



NOTE: THIS DETAIL IS TO BE USED ONLY WHEN THE COVER OVER THE CULVERT DOES NOT PERMIT FULL EMBEDMENT OF GUARD RAIL POSTS AS SHOWN ON STD. DRWG. GR-8.

7-14-10	RAISED HEIGHT OF GUARD RAIL 1"	
4-12-07	REVISED DETAIL OF GUARD RAIL PLACEMENT BEHIND CURB	
1-10-05	ADDED GUARD RAIL PLACEMENT BEHIND CURB; REVISED DETAIL OF CONNECTION	
1-18-04	REVISED POST PLACEMENT IN ROCK & CULVERT CONNECTION DETAILS. ADDED DETAIL FOR GUARD RAIL PLACEMENT AT LOW-FILL CULVERTS	
3-30-00	REMOVED CONCRETE INSERT ANCHOR	
8-12-98	CHANGED STEEL SPACER BLOCK TO WOOD BLOCKOUT, ADD DET. OF GUARD RAIL CONNECTION TO R.C. BOX CULVT. DELETED DET. OF STEEL LINE POST CONN. & ADDED DET. OF GUARD RAIL PLACE. BEHIND CURB & DET. OF POST PLACE. IN SOLID ROCK	
4-3-96	PLACED ARROWS AT CUT STEEL WASHERS	4-3-96
10-18-96	REV. ASTM REF. TO AASHTO	
11-22-95	ADDED OPTIONAL HOLES	
6-2-94	REVISED ALTERNATE POST SIZE	
8-5-93	REVISED STEEL POST SIZE	
10-1-92	REDRAWN & REVISED	10-1-92
8-2-90	DEL. WASHER ON ANCHOR ASSEMBLY	8-2-90
1-15-88	CONFORMED TO 1988 SPECS	
3-4-88	REVISED ANCHOR NOTE	
10-30-87	REVISED ANCHOR ASSEMBLY	10-30-87
10-30-87	REVISED PLACEMENT BEHIND CURB	5-10-30-87
10-9-87	REDRAWN & REVISED	803-10-9-87
DATE	REVISION	DATE FILED



ARKANSAS STATE HIGHWAY COMMISSION

GUARD RAIL DETAILS



STANDARD DRAWING GR-8A



METHODS OF INSTALLATION OF GUARD RAIL AT LESS THAN FULL SHOULDER WIDTH BRIDGES USING GUARD RAIL TERMINAL (TYPE 2)



METHOD OF INSTALLATION OF GUARD RAIL AT FULL SHOULDER WIDTH BRIDGES USING GUARD RAIL TERMINAL (TYPE 2)




LEGEND


- THRIE BEAM GUARD RAIL TERMINAL
- GUARD RAIL TERMINAL (TYPE 2)

METHOD OF INSTALLATION OF GUARD RAIL USING GUARD RAIL TERMINAL (TYPE I) (FULL SHOULDER WIDTH OR LESS BRIDGES)


			ARKANSAS STATE HIGHWAY COMMISSION
			GUARD RAIL DETAILS
			STANDARD DRAWING GR-9
4-17-08	REVISED LAYOUTS		
11-10-05	REMOVED GUARD RAIL NOTES AND DETAILS		
11-16-01	DELETED NOTE-METHOD OF INSTALLATION OF GUARD RAIL USING GUARD RAIL TERM. (TY. I)		
1-12-00	ADDED CONSTRUCTION NOTE	1-12-00	
6-26-97	REVISED LAYOUT		
10-1-92	REDRAWN & REVISED	10-1-92	
10-9-87	ADDED NOTE		
	REDRAWN & REVISED		
DATE	REVISION	DATE FILM	



NOTE: NORMAL SECTION TO BE WIDENED APPROX. 5'-6" EACH SIDE TO SUPPORT GUARD RAIL.




SECTION A-A




SECTION B-B

DETAILS OF WIDENING FOR GUARD RAIL




SECTION ON TANGENT




SECTION ON CURVE

DETAILS SHOWING POSITION OF GUARD RAIL ON HIGHWAY




METHOD OF INSTALLATION OF GUARD RAIL AT FIXED OBSTACLE


ARKANSAS STATE HIGHWAY COMMISSION			
GUARD RAIL DETAILS			
STANDARD DRAWING GR-9A			
4-17-08	MINOR REVISION		
11-10-05	DRAWN		
DATE	REVISION	DATE	FILM




SECTION THRU THRIE BEAM RAIL



SPECIAL END SHOE



ELEVATION




PLAN


PLAN

- (1) VERIFY BOLT SPACING FROM RAIL TRANSITION PRODUCER.
- (2) REFER TO APPROACH CUTTER DETAILS.
- (3) LENGTH OF BLOCKOUT ON POST 8 TO BE MODIFIED TO FIT RAIL WIDTH.

THRIE BEAM GUARD RAIL CONNECTION AT BRIDGE ENDS



STRUCTURAL STEEL TUBING BLOCKOUT DETAIL




HOLE PUNCHING DETAIL FOR STEEL POST & WOOD OR PLASTIC BLOCKOUTS

ATTACH BLOCKOUT TO POST USING 3/8\"/>


1\"/>

CONNECTOR PLATE SHALL BE AASHTO M270, GR. 36 AND SHALL BE GALVANIZED AFTER FABRICATION. GALVANIZING SHALL CONFORM TO SUBSECTION 807.9 OF THE STANDARD SPECIFICATIONS. CONNECTOR PLATE TO BE BOLTED TO SPECIAL END SHOE USING 7/8\"/>

CONNECTOR PLATE



THRIE BEAM RAIL SPLICE AT POST




TRANSITION SECTION

GENERAL NOTES:


- THE THRIE BEAM RAIL, SPECIAL END SHOE, AND THE TRANSITION SECTION SHALL BE MADE OF STEEL AND SHALL BE 12 GAGE. ZINC COATING SHALL BE TYPE I.
- RAIL POSTS SHALL BE SET PERPENDICULAR TO THE ROADWAY PROFILE GRADE AND VERTICALLY IN CROSS SECTION.
- ALL BOLTS SHALL BE SUFFICIENT LENGTH TO EXTEND THROUGH THE FULL THICKNESS OF THE NUT AND NO MORE THAN 3/4\"/>
- ALL LAP SPLICES, INCLUDING SPECIAL END SHOES, SHALL BE MADE IN THE DIRECTION SHOWN ON STANDARD DRAWINGS GR-9 & GR-11.
- WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER 9.7f (400 #) OR NO. 1 (350 #) SOUTHERN PINE.
- REFER TO STD. DRWG. GR-10A FOR POST DETAILS.
- USE THRIE BEAM GUARD RAIL COMPONENTS OF SAME MATERIAL FOR ENTIRE JOB.
- THRIE BEAM POSTS SHALL BE SAME MATERIAL AS W-BEAM POSTS FOR ENTIRE JOB.

DATE	REVISION	DATE FILM
7-14-00	RAISED HEIGHT OF W-BEAM 1"	
11-29-07	ADDED PLASTIC BLOCKOUTS	
11-10-05	ADDED NOTE FOR ATTACHING STEEL BLOCKOUT	
11-8-04	REVISED GENERAL NOTES	
10-9-03	REVISED GENERAL NOTES	
4-10-03	REVISED GENERAL NOTES	
8-22-02	REVISED NOTE (2)	
6-29-00	MOVED DIMENSION LINES	
5-18-00	ADDED NOTE	
3-30-00	DRAWN & ISSUED	

ARKANSAS STATE HIGHWAY COMMISSION		
GUARD RAIL DETAILS		
STANDARD DRAWING GR-10		




THRIE BEAM RAIL WITH STEEL TUBING BLOCKOUT AND STEEL POST
POSTS 1-7




W-BEAM TO THRIE BEAM TRANSITION RAIL WITH WOOD OR PLASTIC BLOCKOUT AND STEEL POST
POST 8


* NOTE:
THESE DIMENSIONS WILL NEED TO BE ADJUSTED IN THE FIELD TO MAKE THE TRANSITION FROM 21" MID POINT OF THRIE BEAM TO 22" MID POINT OF W-BEAM.



THRIE BEAM RAIL WITH WOOD OR PLASTIC BLOCKOUTS & WOOD POSTS
POSTS 1-6



THRIE BEAM RAIL WITH WOOD OR PLASTIC BLOCKOUT & WOOD POST
POST 7



W-BEAM TO THRIE BEAM TRANSITION RAIL WITH WOOD OR PLASTIC BLOCKOUT & WOOD POST
POST 8


GENERAL NOTES:
RAIL POSTS SHALL BE SET PERPENDICULAR TO THE ROADWAY PROFILE GRADE AND VERTICALLY IN CROSS SECTION.
WOOD POSTS & WOOD BLOCKS SHALL BE EITHER DENSE NO. 1 STRUCTURAL OR BETTER 9.7F 11400 #1 OR NO. 1 1350 # SOUTHERN PINE.

DATE	REVISION	DATE FILM
7-14-10	REVISED POST 8 DIMENSIONS	
11-29-07	ADDED PLASTIC BLOCKOUTS	
9-22-02	REVISED LIP CURB NOTE	
3-30-00	DRAWN & ISSUED	


ARKANSAS STATE HIGHWAY COMMISSION

GUARD RAIL DETAILS

STANDARD DRAWING GR-10A




PLAN - GUARD RAIL TERMINAL (TYPE I)




ELEVATION - GUARD RAIL TERMINAL (TYPE I)

NOTE:
SECTIONS 1 AND 2 OF GUARD RAIL TERMINAL SHALL BE PAID FOR AT THE PRICE BID PER LINEAR FOOT OF THE TYPE OF GUARD RAIL SPECIFIED.



SECTION 1

TERMINAL SECTION



NOTE: GALVANIZE UPPER 15" OF ANCHOR POST AND ANCHOR ASSEMBLY

ELEVATION

SECTION

NOTE: RAIL MEMBERS MAY BE BOLTED TO ANGLE AT TERMINAL ANCHOR AND THE TWO ASSEMBLIES POSITIONED TO PROPER ALIGNMENT PRIOR TO PLACING CONCRETE AROUND 8 WF 17 POST IF CONTRACTOR SO DESIRES.

DETAIL OF TERMINAL ANCHOR POST (TYPE I)

			ARKANSAS STATE HIGHWAY COMMISSION
			GUARD RAIL DETAILS
			STANDARD DRAWING GRT-1
7-14-10	RAISED HEIGHT OF GUARD RAIL 1"		
6-28-97	REVISED LAP NOTE		
10-18-96	REVISED ASTM REF. TO AASHTO		
11-3-94	DIMENSION TERMINAL DETAIL		
11-11-92	ADDED NOTE FOR PAYMENT	11-11-92	
10-1-92	DRAWN & ISSUED	10-1-92	
DATE	REVISION	DATE	FILM

CORRUGATED STEEL PIPE (ROUND)

Table with columns for Pipe Diameter (Inches), Minimum Cover Top of Pipe to Top of Ground "H" (Feet), and Max. Fill Height "H" Above Top of Pipe (Feet). Includes two sections for different corrugation types: 2 3/8 inch by 1/2 inch and 3 inch by 1 inch or 5 inch by 1 inch.

CONSTRUCTION SEQUENCE

- 1. PLACE STRUCTURAL BEDDING MATERIAL TO GRADE. DO NOT COMPACT.
2. INSTALL PIPE TO GRADE.
3. COMPACT STRUCTURAL BEDDING OUTSIDE THE MIDDLE THIRD OF THE PIPE.
4. COMPLETE STRUCTURAL BACKFILL OPERATION BY WORKING FROM SIDE TO SIDE OF THE PIPE...

NOTE: STRUCTURAL BACKFILL AND STRUCTURAL BEDDING WILL NOT BE PAID FOR SEPARATELY, BUT COMPENSATION WILL BE CONSIDERED TO BE INCLUDED IN THE PRICE BID PER LINEAR FOOT OF METAL PIPE.


Table mapping Installation Type to Material Requirements for Structural Backfill and Structural Bedding. Includes Type 1 (Aggregate Base Course) and Type 2 (Selected Materials).

SM-3 WILL NOT BE ALLOWED.

LEGEND

- Do = OUTSIDE DIAMETER OF PIPE
MAX. = MAXIMUM
MIN. = MINIMUM
Structural Backfill Material symbols
Undisturbed Soil symbol
Equivalent Diameter symbol
H = FILL COVER HEIGHT OVER PIPE (FEET)

IN SOIL - MIN. EQUALS TWICE CORRUGATION DEPTH
IN ROCK - MIN. EQUALS GREATER OF:
1/2" PER FOOT OF FILL OVER PIPE (24" MAX.)
TWICE CORRUGATION DEPTH



EMBANKMENT AND TRENCH INSTALLATIONS

- 1. STRUCTURAL BACKFILL, EMBANKMENT, AND OUTER STRUCTURAL BEDDING MATERIAL SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY...
2. INSTALLATION TYPE 1 OR 2 MAY BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE (ROUND).
3. INSTALLATION TYPE 1 SHALL BE USED FOR CORRUGATED STEEL OR ALUMINUM PIPE ARCHES WITH 2 3/8" x 1/2" CORRUGATION.

GENERAL NOTES

- 1. METAL PIPE CULVERT CONSTRUCTION SHALL CONFORM TO ARKANSAS STATE HIGHWAY AND TRANSPORTATION DEPARTMENT STANDARD SPECIFICATIONS...
2. METAL PIPE CULVERT DESIGN SHALL CONFORM TO AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS...
3. METAL PIPE CULVERT MATERIALS AND INSTALLATIONS SHALL CONFORM TO SECTION 606 AND JOB SPECIAL PROVISION "METAL PIPE".

CORRUGATED ALUMINUM PIPE (ROUND)

Table with columns for Pipe Diameter (Inches), Minimum Cover Top of Pipe to Top of Ground "H" (Feet), and Max. Fill Height "H" Above Top of Pipe (Feet). Includes two sections for different corrugation types.

EQUIVALENT METAL THICKNESSES AND GAUGES

Table mapping Metal Thickness in Inches (Steel and Aluminum) to Gauge Number.

CORRUGATED METAL PIPE ARCHES

Table with columns for Equiv. Dia., Pipe Dimension Span x Rise of Radius, Min. Thickness, Min. Height of Fill, and Max. Height of Fill. Includes sections for Steel and Aluminum.


FOR MINIMUM COVER VALUES, "H" SHALL INCLUDE A MINIMUM 12" OF PAVEMENT AND/OR BASE.

WHERE THE STANDARD 2 2/3 x 1/2" CORRUGATION AND GAUGE IS SPECIFIED FOR A GIVEN DIAMETER, A PIPE OF THE SAME DIAMETER WITH A 3" x 1" OR 5" x 1" CORRUGATION MAY BE SUBSTITUTED...


Revision table with columns for Date, Revision, and Date Filmed. Includes entries for general note revisions and issue dates.

ARKANSAS STATE HIGHWAY COMMISSION
METAL PIPE CULVERT
FILL HEIGHTS & BEDDING
STANDARD DRAWING PCM-1


- NOTES:
1. REFER TO THE STRIPING DETAILS FOR PAVEMENT MARKING LINE WIDTHS.
 2. THIS DRAWING SHALL BE USED IN CONJUNCTION WITH THE LATEST REVISED ADDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
 3. RAISED PAVEMENT MARKERS SHALL BE PLACED ON AN 80 FEET SPACING UNLESS OTHERWISE SHOWN IN THE PLANS.




BROKEN LINE STRIPING



SOLID LINE STRIPING ON CONCRETE PAVEMENT




SOLID LINE STRIPING ON ASPHALT PAVEMENT




ASPHALT PAVEMENT

CONCRETE PAVEMENT


STRIPING AT ADJACENT NO PASSING LANES



PAVEMENT EDGE LINE MARKING




NOTE:
THE RED LENS OF THE TYPE II R.P.M. SHALL FACE THE INCORRECT TRAFFIC MOVEMENT.



DETAIL OF STANDARD RAISED PAVEMENT MARKERS

NOTE:
DIMENSIONS SHOWN FOR RAISED PAVEMENT MARKERS ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR MARKERS WITH THE APPROVAL OF THE ENGINEER, REQUESTING APPROVAL FOR SIMILAR MARKERS MAY BE MADE BY REFERRING TO THE AHTD QUALIFIED PRODUCTS LIST.



CROSSWALK AND STOPBAR DETAILS

DATE	REVISION	FILED
5-12-16	REVISED LINE WIDTHS, SPACING, & NOTES	
9-12-13	REVISED DETAIL OF STANDARD RAISED PAVEMENT MARKERS	
11-17-10	REVISED GENERAL NOTES & REMOVED PLOWABLE PAVT MRKRS	
11-18-04	REVISED NOTE 2 & GENERAL NOTES	
8-22-02	ADDED CROSSWALK & STOPBAR DTLS.	
7-02-98	ADDED DETAILS OF STD. RAISED PAV'T. MARKERS	
4-26-96	REV. NOTES 3&4; ADDED R.P.M.	
9-30-80	DRAWN	1-9-30-80

ARKANSAS STATE HIGHWAY COMMISSION


PAVEMENT MARKING DETAILS

STANDARD DRAWING PM-1


PAVEMENT MARKING QUANTITIES
(BASED ON 700' ACCEL. LANE + 300' TAPER)

ENTRANCE RAMP
8" WHITE = 228 LIN. FT.
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 38 EACH


EXIT RAMP
4" WHITE = 280 LIN. FT.
8" WHITE = 655 LIN. FT.
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 38 EACH
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 48 EACH
RAISED PAVEMENT MARKERS TYPE II (WHITE/RED) = 38 EACH



ENTRANCE RAMP




EXIT RAMP



DETAIL OF STANDARD RAISED PAVEMENT MARKERS

NOTE:
THE RED LENS OF THE TYPE II R.P.M. SHALL FACE THE INCORRECT TRAFFIC MOVEMENT.



(19) STANDARD TYPE II R.P.M.

DIRECTIONAL ARROWS

GENERAL NOTES:
THIS DRAWING SHOULD BE CONSIDERED AS TYPICAL ONLY AND THE FINAL LOCATION OF THE STRIPING AND PAVEMENT MARKERS SHALL BE DETERMINED BY THE ENGINEER.


THIS DRAWING SHOULD BE USED IN CONJUNCTION WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", LATEST REVISION.

NOTE:
DIMENSIONS SHOWN FOR RAISED PAVEMENT MARKERS ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR MARKERS WITH THE APPROVAL OF THE ENGINEER. REQUESTING APPROVAL FOR SIMILAR MARKERS MAY BE MADE BY REFERRING TO THE AHTD QUALIFIED PRODUCTS LIST.


DATE	REVISION	FILMED
9-12-13	REVISED DETAIL OF STANDARD RAISED PAVEMENT MARKERS	
7-26-12	REVISED RPM NOTATION	
12-15-11	REVISED RPMs ACCORDING TO LATEST POLICY	
11-17-10	REMOVED PLOWABLE PAVEMENT MARKERS	
6-3-10	REVISED PER 2009 MUTCD	
11-18-04	REVISED NOTES	
8-22-02	ADDED & REVISED NOTES; REV. ENTRANCE & EXIT RAMP	
5-18-00	REMOVED HASHMARKS	
7-02-98	CHANGED TYPES TO ROMAN NUMERALS	
4-26-96	ADDED DIMENSIONS & QUANTITIES; REVISED LANE WIDTH ON EXIT RAMP	
2-2-95	PLACED IN USE	2-2-95

ARKANSAS STATE HIGHWAY COMMISSION
PERMANENT PAVEMENT MARKING
ON ACCESS CONTROLLED ROADWAYS


NOTE:
 1. GRANULAR BACKFILL TO BE SUBSIDIARY TO PIPE UNDERDRAIN.
 2. UNLESS OTHERWISE SPECIFIED ON THE PLANS, THE UNDERDRAIN COVER SHALL BE THOROUGHLY COMPACTED EARTH AND SHALL BE SUBSIDIARY TO PIPE UNDERDRAIN.
 3. GRANULAR MATERIAL SHALL BE WRAPPED WITH GEOTEXTILE FABRIC, LAP FABRIC 12" OR THE WIDTH OF THE TRENCH AT THE TOP.





PLAN VIEW




DETAIL OF HOLE FOR 4" PIPE




DETAIL OF RODENT SCREEN



SIDE VIEW




FRONT VIEW



DETAILS OF PIPE UNDERDRAIN

UNDERDRAIN OUTLET PROTECTORS
 FERNCO 1056-44 (4" CI/PLASTIC) OR FERNCO 1051-44 (4" AC/DIOR 4" CI/PLASTIC) COUPLING OR EQUAL WITH 2 CLAMPS (TYPICAL)



NOTE:
 LATERALS SHALL BE INSTALLED AT ALL SAGS AND AT 250' INTERVALS ON GRADES. THE 250' DISTANCE MAY BE EXCEEDED ONLY WHERE NECESSARY FOR AN ACCEPTABLE OUTLET.

DETAIL OF PIPE UNDERDRAIN LATERALS WHEN PLACED ALONG PAVEMENT EDGE
 NOTE: PVC PIPE FOR LATERALS SHALL MEET THE REQUIREMENTS OF ASTM D 1785 (LATEST REVISION) FOR SCHEDULE 40 PIPE.

DATE	REVISION	DATE FILMED
4-10-03	REVISED NOTE 3	
1-12-00	REVISED DETAIL OF UNDERDRAIN LATERALS	
11-18-98	REVISED NOTE	
10-18-96	REVISED MIN. DEPTH & GEOTEXTILE FABRIC	
4-26-96	ADDED LATERAL NOTE; 5/2" TO 5"	
11-22-95	REVISED LATERALS	
7-20-95	REVISED LATERALS & ADDED NOTE	
11-3-94	REVISED FOR DUAL LATERALS	11-3-94
10-1-92	SUBSTITUTED GEOTEXTILE	10-1-92
8-15-91	ADDED POLYETHYLENE PIPE	8-15-91
11-8-90	DELETED ALTERNATE NOTE	11-8-90
1-25-90	ADDED 4" SNAP ADAPTER	1-25-90
11-30-89	DEL. (SUBGRADE); ADDED (WHERE REQUIRED)	11-30-89
7-15-88	ISSUED P.L.M.	647-7-15-88
	REVISION	

ARKANSAS STATE HIGHWAY COMMISSION

DETAILS OF PIPE UNDERDRAIN

STANDARD DRAWING PU-1

SUPERELEVATION TABLE FOR ONE - WAY TRAFFIC

Table with columns for Degree of Curve (0° 15' to 24° 00'), Speed (30 MPH to 70 MPH), and Ls (FT) with sub-columns for Minimum and Desirable values. Includes D MAX values for each speed range.


GENERAL NOTES

- 1. ON PAVEMENT WITH ONE-WAY TRAFFIC, THE SUPERELEVATION SHALL BE REVOLVED ON THE PROFILE GRADE POINT.
2. SUPERELEVATION VALUES SHOWN ON THE CROSS SECTIONS ARE VALUES (+) OR (-) TO BE ADDED OR SUBTRACTED FROM THE POINT OF CONTROL.
3. LENGTHS FOR Ls MAY BE ROUNDED IN MULTIPLES OF 25 FT. OR 50 FT. TO PERMIT SIMPLER CALCULATIONS.
4. MINIMUM Ls VALUES MAY BE USED FOR RAMPS; DESIRABLE VALUES SHALL APPLY TO MAIN LANES.
5. DIVIDED PAVEMENTS WIDER THAN 4 LANES SHALL HAVE ADDITIONAL TRANSITION LENGTHS AS FOLLOWS:


6 LANE DIVIDED-----+20%
8 LANE DIVIDED-----+50%

ABBREVIATIONS

- NC - NORMAL CROWN
RC - REVERSE CROWN, SUPERELEVATION AT NORMAL CROWN SLOPE
S - SUPERELEVATION
L - DISTANCE FROM BEGINNING OF SUPERELEVATION TRANSITION TO ANY POINT (FT.)
d - WIDTH OF PAVEMENT
e - MAXIMUM RATE OF SUPERELEVATION (FT. PER FT.)
Ls - LENGTH OF SUPERELEVATION TRANSITION (FT.)
C - NORMAL CROWN (FT.)














































SUPERELEVATION FORMULA = S = - (L(d-e)-C) / Ls



SUPERELEVATION FORMULA = S = + (L(d+e)-C) / Ls

Table with columns for DATE, ISSUED, REVISION, and DATE FILMED. Includes entries for 01-09-87 and 578-1-15-87.

ARKANSAS STATE HIGHWAY COMMISSION
TABLES AND METHOD OF SUPERELEVATION FOR ONE-WAY TRAFFIC
STANDARD DRAWING SE-1


<p>RI-1</p>  <p>STANDARD 30"x30" EXPRESSWAY 36"x36" SPECIAL 48"x48"</p>	<p>RI-2</p>  <p>STD. 36"x36"x36" EXPWY. 48"x48"x48" FWY. 60"x60"x60"</p>	<p>R2-1</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>W3-5</p>  <p>STD. 36"x36" EXPWY. 48"x48" FWY. 48"x48"</p>	<p>W3-5a</p>  <p>STD. 36"x36" EXPWY. 48"x48" FWY. 48"x48"</p>	<p>R4-1</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>	<p>R4-2</p>  <p>STD. 24"x30" EXPWY. 36"x48" FWY. 48"x60"</p>
<p>R5-1</p>  <p>STD. 30"x30" EXPWY. 36"x36" SPECIAL 48"x48"</p>	<p>R11-2</p>  <p>48"x30"</p>	<p>R11-3A</p>  <p>60"x30"</p>	<p>R11-4</p>  <p>60"x30"</p>	<p>RSP-1</p>  <p>48"x30"</p>	<p>W1-1</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W1-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>
<p>W1-3</p>  <p>STD. 48"x48"</p>	<p>W1-4</p>  <p>STD. 48"x48"</p>	<p>W1-6</p>  <p>STD. 48"x24" SPECIAL 60"x30"</p>	<p>W1-8</p>  <p>STD. 18"x24" SPECIAL 24"x30" EXPWY. 30"x36" FWY. 36"x48"</p>	<p>W3-1</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W3-2</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W4-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>
<p>W5-1</p>  <p>STD. 36"x36" SPECIAL 48"x48"</p>	<p>W6-3</p>  <p>EXPWY. 36"x36" SPECIAL 48"x48"</p>	<p>W8-7</p>  <p>EXPWY. 36"x36" FWY. 48"x48"</p>	<p>W9-2</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W13-1</p>  <p>STD. 24"x24"</p>	<p>W20-1</p>  <p>STD. 48"x48"</p>	<p>W20-2</p>  <p>STD. 48"x48"</p>
<p>W20-4</p>  <p>STD. 48"x48"</p>	<p>W20-5</p>  <p>STD. 48"x48"</p>	<p>W20-7a</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W21-2</p>  <p>STD. 30"x30" SPECIAL 36"x36"</p>	<p>W21-5</p>  <p>STD. 30"x30" SPECIAL 36"x36"</p>	<p>W24-1</p>  <p>STD. 36"x36"</p>	<p>W1-4b</p>  <p>STD. 48"x48"</p>
<p>W8-11</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>W8-9</p>  <p>STD. 36"x36" FWY. 48"x48"</p>	<p>G20-1</p>  <p>60"x24"</p>	<p>G20-2</p>  <p>48"x24"</p>	<p>OM-3L OM-3R</p>  <p>12"x36"</p>	<p>M4-9</p>  <p>STD. 30"x24" SPECIAL 48"x36" SPECIAL 60"x48"</p>	<p>M4-10</p>  <p>48"x18"</p>
						<p>R55-1</p>  <p>36"x60"</p> <p>• USE 6" C LETTERS •• USE 4" D LETTERS</p>

ADVANCE DISTANCES (XXXX)


500 FT	1/2 MILE
1000 FT	3/4 MILE
1500 FT	1 MILE AHEAD

- GENERAL NOTES:
- ALL TRAFFIC CONTROL DEVICES USED ON ROAD CONSTRUCTION SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, LATEST EDITION, AND TO THE STANDARD HIGHWAY SIGNS, LATEST EDITION, OR AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION.
 - TRAFFIC CONTROL DEVICES SHALL BE SET UP JUST BEFORE THE START OF CONSTRUCTION OPERATIONS AND SHALL BE PROPERLY MAINTAINED DURING THE TIME SUCH CONDITIONS EXIST. THEY SHALL REMAIN IN PLACE ONLY AS LONG AS NEEDED AND REMOVED THEREAFTER.
 - EXISTING SIGNS AND CONSTRUCTION SIGNS SHALL BE KEPT IN PROPER POSITION, AND BE CLEAN AND LEGIBLE AT ALL TIMES. SIGNS THAT DO NOT APPLY TO EXISTING CONDITIONS SHALL BE REMOVED. SIGNS THAT ARE DAMAGED, DEFACED, OR THAT ACCUMULATE DIRT DURING CONSTRUCTION SHALL BE CLEANED, REPAIRED, OR REPLACED.
 - SIGNS ARE USUALLY MOUNTED ON A SINGLE POST, ALTHOUGH THOSE WIDER THAN 36" OR LARGER THAN 10 SQ. FT. SHALL BE MOUNTED ON TWO POSTS OR ABOVE A TYPE III BARRICADE.
 - SIGN POSTS DIRECT BURIED IN SOIL SHALL BE 2 LB. MINIMUM CHANNEL POST OR 4"x4" WOOD POSTS. CHANNEL POSTS SHALL BE PAINTED GREEN. WOOD POSTS SHALL BE PAINTED WHITE. ALL POSTS SHALL BE NEATLY CONSTRUCTED, AND SHALL BE REPLUMBED, CLEANED, OR REPAIRED AS NEEDED FOR THE DURATION OF THE JOB. THERE SHALL NOT BE MORE THAN 2 POSTS IN A 7' PATH FOR WOOD OR CHANNEL POSTS. ANY CHANNEL POST SPLICE SHALL BE IN ACCORDANCE WITH STANDARD DRAWING TC-3.
 - POST MOUNTED SIGNS IN RURAL AREAS SHALL BE CONSTRUCTED WITH THE NEAR EDGE OF THE SIGN FROM 6 TO 12 FEET FROM THE PAVEMENT EDGE. SIGNS IN URBAN AREAS AND BARRICADE MOUNTED SIGNS SHALL BE MOUNTED A MINIMUM OF 2 FEET FROM THE PAVEMENT EDGE.
 - ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN URBAN AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE. ALL POST AND BARRICADE MOUNTED SIGNS MOUNTED IN RURAL AREAS SHALL BE MOUNTED A MINIMUM DISTANCE OF 7' FROM THE BOTTOM OF THE SIGN TO THE ROADWAY SURFACE, EXCEPT A MINIMUM OF 6' SHALL BE USED WHEN MOUNTING AN ADVISORY SIGN BELOW A WARNING SIGN. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR INTERMEDIATE TERM STATIONARY WORK CONDITIONS. THE SIGNS MINIMUM MOUNTING HEIGHT SHALL BE 5'. RETROREFLECTIVE DEVICES SHALL BE USED. TEMPORARY SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS FOR SHORT-TERM, SHORT DURATION, AND MOBILE CONDITIONS. THEY SHALL BE NO LESS THAN ONE (1) FOOT ABOVE THE TRAVELED WAY. LONG-TERM STATIONARY SIGNS SHALL BE DIRECT BURIED IN SOIL, UNLESS CONDITIONS NECESSITATE THE USE OF PORTABLE SIGNS, OR AS APPROVED BY THE ENGINEER. CONCRETE PADS, CONCRETE OR ROCK BALLAST, OR OTHER SOLID MATERIALS SHALL NOT BE UTILIZED WITH PORTABLE SIGN SUPPORTS.
 - FLAGGERS SHALL USE REFLECTORIZED STOP-SLOW PADDLES. FLAGS MAY BE USED ONLY FOR EMERGENCY SITUATIONS.
 - MOST OF THE SIGNS SHOWN ARE ORIENTED TO THE RIGHT. HOWEVER, THIS DOES NOT PRECLUDE THE USE OF MIRROR IMAGES OF THESE SIGNS WHERE THE REVERSE ORIENTATION MIGHT BETTER CONVEY TO MOTORISTS THE PROPER DIRECTION OF MOVEMENT.
 - R55-1 SIGNS SHALL BE PLACED AT LEAST 1500' BUT NOT MORE THAN 1 MILE IN ADVANCE OF THE WORK ZONE. IF A SPEED LIMIT REDUCTION IS IN EFFECT, THE SIGN SHALL BE PLACED A MINIMUM OF 500' IN ADVANCE OF THE "REDUCED SPEED AHEAD" SIGN.
- NOTE: SUPPORTS FOR SIGNS, BARRICADES, AND VERTICAL PANELS THAT ARE DIFFERENT FROM THE REQUIREMENTS SHOWN IN NOTES 4 & 5, BUT MEET THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH), WILL BE ACCEPTED. COMPLIANCE WITH THE REQUIREMENTS OF NCHRP-350 OR MANUAL FOR ASSESSING SAFETY HARDWARE (MASH) IS REQUIRED FOR ALL PROJECTS.


9-2-15	REVISED REDUCED SPEED LIMIT AHEAD SIGNS	
	REVISED ROAD WORK NEXT XX MILES	
12-15-1	REVISED W24-1	
1-17-10	DELETED W8-9a & ADDED W8-9	
10-15-09	ADDED REFERENCE TO MASH & ADDED SIGN W24-1	
4-17-08	REVISED SIGN DESIGNATIONS	
11-18-04	REVISED NOTES	
10-9-03	REVISED NOTE 1	
1-16-01	REVISED NOTE 7	
9-28-00	REVISED NOTE	
1-18-98	ADDED NOTE	
6-26-97	REVISED NOTE 5	
4-03-97	REVISED NOTE 5	
10-18-96	ADDED CONTROLLED ACCESS HWY. SIGN & TO NOTE 7	
10-12-95	ADDED R55-1	
6-8-95	REVISED TO CORRECT SIGN ILLUSTRATIONS	6-8-95
2-2-95	REVISED PER PART VI, MUTCD SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	
DATE	REVISION	FILMED




(A) TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES ON A 2-LANE HIGHWAY WHERE THE ENTIRE ROADWAY IS CLOSED AND A BYPASS DETOUR IS PROVIDED.



(B) TYPICAL APPLICATION - 4-LANE DIVIDED ROADWAY WHERE ONE ROADWAY IS CLOSED.




(C) TYPICAL APPLICATION - 4-LANE UNDIVIDED ROADWAY WHERE HALF OF THE ROADWAY IS CLOSED.




TAPER FORMULAE:
 $L = SXW$ FOR SPEEDS OF 45MPH OR MORE.
 $L = \frac{WS^2}{60}$ FOR SPEEDS OF 40MPH OR LESS.
 WHERE:
 L = MINIMUM LENGTH OF TAPER.
 S = NUMERICAL VALUE OF POSTED SPEED LIMIT PRIOR TO WORK OR 85TH PERCENTILE SPEED.
 W = WIDTH OF OFFSET.

- GENERAL NOTES:**
- ADVISORY SPEED POSTED ON W1-3 OR W1-4 CURVE WARNING SIGNS TO BE DETERMINED AT SITE. USE W1-4 WHEN SPEED IS GREATER THAN 30MPH AND W1-3 WHEN 30MPH OR LESS.
 - WHEN THE EXISTING SPEED LIMIT IS 55MPH AND THE PLANS REQUIRE A SPEED LIMIT OF 45MPH, THE R2-1(55) SHALL BE OMITTED AND THE W3-5 SHALL BE INSTALLED AT THAT LOCATION. ADDITIONAL R2-1(45MPH) SPEED LIMIT SIGNS SHALL BE INSTALLED AT A MAXIMUM OF 1MILE INTERVALS. AT THE END OF THE WORK AREA A R2-1(XX) SHALL BE INSTALLED TO MATCH ORIGINAL SPEED LIMIT.
 - WHEN THE EXISTING SPEED LIMIT IS 65MPH AND THE PLANS REQUIRE A SPEED LIMIT OF 55MPH, THE R2-1(65) SHALL BE OMITTED. ADDITIONAL R2-1(55MPH) SPEED LIMIT SIGNS SHALL BE INSTALLED AT A MAXIMUM OF 1MILE INTERVALS. AT THE END OF THE WORK AREA A R2-1(XX) SHALL BE INSTALLED TO MATCH ORIGINAL SPEED LIMIT.
 - THE MAXIMUM SPACING BETWEEN CHANNELIZING DEVICES IN A TAPER SHOULD BE APPROXIMATELY EQUAL IN FEET TO THE SPEED LIMIT. BEYOND THE TAPER, MAXIMUM SPACING SHALL BE TWO TIMES THE SPEED LIMIT, OR AS DIRECTED BY THE ENGINEER.
 - WARNING LIGHTS AND/OR FLAGS MAY BE MOUNTED TO SIGNS OR CHANNELIZING DEVICES AT NIGHT AS NEEDED.
 - PAVEMENT MARKINGS NO LONGER APPLICABLE WHICH MIGHT CREATE CONFUSION IN THE MINDS OF VEHICLE OPERATORS SHALL BE REMOVED OR OBLITERATED AS SOON AS PRACTICABLE.
 - TRAILER MOUNTED DEVICES SUCH AS ARROW PANELS AND PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE DELINEATED BY AFFIXING CONSPICUOUS MATERIAL IN A CONTINUOUS LINE ON THE FACE OF THE TRAILER. WHEN PLACED ON OR ADJACENT TO THE SHOULDER AND NOT BEHIND A POSITIVE BARRIER, THESE DEVICES SHALL BE DELINEATED BY PLACING FIVE (5) TRAFFIC DRUMS, EQUALLY SPACED ALONG THE TRAFFIC SIDE OF THE DEVICE.
 - DIMENSIONS SHOWN FOR RAISED PAVEMENT MARKERS ARE TYPICAL. THE CONTRACTOR MAY SUBSTITUTE SIMILAR MARKERS WITH THE APPROVAL OF THE ENGINEER. REQUESTING APPROVAL FOR SIMILAR MARKERS MAY BE MADE BY REFERRING TO THE AHTD QUALIFIED PRODUCTS LIST.


9-2-15	REVISED NOTE 2, ADDED NOTE 8, REVISED DRAWING (A) & REPLACED R2-5A WITH W3-5	
9-12-13	REVISED DETAIL OF RAISED PAVEMENT MARKERS	
3-8-10	ADDED (AFAD)	
8-20-08	REVISED SIGN DESIGNATIONS	
8-18-04	ADDED GENERAL NOTE	
10-18-96	ADDED R55-1	
4-26-96	CORRECTED (G) BEHIND G20-2	
6-8-95	CORRECTED SIGN IDENT. ON W1-4A	6-8-95
2-2-95	REVISED PER PART V, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	
DATE	REVISION	FILMED



(D) TYPICAL APPLICATION - ROADWAY CLOSED BEYOND DETOUR POINT.




(E) TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES ON 2-LANE HIGHWAY WHERE ONE LANE IS CLOSED AND FLAGGING IS PROVIDED.



(F) TYPICAL APPLICATION - 4-LANE UNDIVIDED ROADWAY WITH INSIDE LANE CLOSED.

ARKANSAS STATE HIGHWAY COMMISSION
 STANDARD TRAFFIC CONTROLS
 FOR HIGHWAY CONSTRUCTION
 STANDARD DRAWING TC-2

Channelizing devices




TRAFFIC CONTROL DEVICES FOR VERTICAL PAVEMENT DIFFERENTIALS



VERTICAL DIFFERENTIAL	LOCATIONS	TRAFFIC CONTROL
1" to 3"	Centerline, lane lines	W8-II
1" to 3"	Edge of shoulder	W8-9
Greater than 3"	Lane lines	Standard lane closure required
Greater than 3"	Edge of traveled lane	*RSP-I and vertical panels, drums or concrete barrier
Greater than 3"	Edge of shoulder	*Vertical panels, drums or concrete barrier

* When shown on the plans concrete barrier will be used. When the shoulder area is used as part of the traveled lane and there is insufficient width to place drums on the remaining shoulder width, then vertical panels shall be used.

(A) Typical application - daytime maintenance operations of short duration on a 4-lane divided roadway where half of the roadway is closed.




(B) Typical application - 3-lane one-way roadway where center lane is closed.



(C) Typical application - construction operations of intermediate to long term duration on a 4-lane divided roadway where half of the roadway is closed.








- KEY:**
 ○○○ Arrow Panel (if Required)
 ■ Channelizing Device
 ● Traffic drum
- GENERAL NOTES:**
- A speed limit reduction may be implemented ONLY when designated in the plan or when recommended by the Roadway Design Division.
 - When the existing speed limit is 55mph and the plans require a speed limit of 45mph, the R2-1(55) shall be omitted and the W3-5 shall be installed at that location. Additional R2-1(45) speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
 - When the existing speed limit is 65mph and the plans require a speed limit of 55mph, the R2-1(65) shall be omitted. Additional R2-1(55) speed limit signs shall be installed at a maximum of 1/2 mile intervals. At the end of the work area a R2-1(XX) shall be installed to match original speed limit.
 - The maximum spacing between channelizing devices in a taper should be approximately equal in feet to the speed limit. Beyond the taper, maximum spacing shall be two times the speed limit or as directed by the Engineer.
 - Warning lights and/or flags may be mounted to signs or channelizing devices at night as needed.
 - Pavement markings no longer applicable which might create confusion in the minds of vehicle operators shall be removed or obliterated as soon as practicable.
 - The G20-1 sign will be required on jobs of over two miles in length. When the lane closure is not at the beginning of the project, the G20-1 sign shall be erected 125' in advance of the job limit. Additional W20-1(1/2 MILE) signs are not required in advance of lane closures that begin inside the project limits.
 - Flaggers shall use STOP/SLOW paddles for controlling traffic through work zones. Flags may be used only for emergency situations.
 - All plastic drums and cones shall meet the requirements of NCHRP-350 or Manual for Assessing Safety Hardware (MASH).
 - Trawler mounted devices such as arrow panels and portable changeable message signs shall be delineated by affixing conspicuity material in a continuous line on the face of the trawler. When placed on or adjacent to the shoulder and not behind a positive barrier, these devices shall be delineated by placing five (5) traffic drums, equally spaced along the traffic side of the device.





(D) Typical application - closing multiple lanes of a multi-lane highway.

DATE	REVISION	FILED
9-2-15	REVISED NOTE 2 & REPLACED R2-5A WITH W3-5	
10-15-09	ADDED REFERENCE TO MASH	
11-20-08	REVISED SIGN DESIGNATIONS	
11-18-04	ADDED NOTE	
10-1-98	ADDED NOTE	
4-03-97	ADDED (SP) TO W6-1 & REVISED TRAFFIC CONTROL DEVICES NOTE	
10-18-96	ADDED R55-1	
10-12-95	MOVED UPPER SPLICE	
6-8-95	REVISED SPLICE DETAIL, TEXT	6-8-95
2-2-95	REVISED PER PART VI, MUTCD, SEPT. 3, 1993	
8-15-91	DRAWN AND PLACED IN USE	

REINFORCING BAR TABLE PER BARRIER UNIT			
MARK	LOCATION	BAR SIZE (NO. BARS)	SKETCH
H-1	HORIZONTAL IN BARRIER TIED INSIDE V-1 BARS	*5 (6)	19'-3"
H-2	CENTERED ABOVE DRAIN SLOTS LONG. & TRANSVERSELY	*5 (6)	6'-6"
H-3	TIED ABOVE H-1 BARS TO SUPPORT H-2, TIED TO V-1	*4 (2)	1'-6"
S-1	OVER LIFT HOLES	*4 (2)	
S-2	HORIZ. AROUND SLOTS BETWEEN V-1'S & DRAIN SLOTS	*4 (2)	
V-1	VERTICAL IN BARRIER (3) EACH END & (2) AT EACH DRAIN SLOTS	*5 (16)	





BARRIER STABILIZATION DETAIL
ROADWAY SECTION
E 4" - Concrete Pavement
8" - Asphalt Pavement
12" - Shoulder Areas



NOTE: 3/4" Threaded inserts shall be cast in place for all new bridge decks and drilled and grouted for existing bridge decks. Inserts shall have a minimum ultimate load capacity of 8000 lbs. in tension. After removal of barrier, bolts, and angles, the inserts shall be filled with approved non-shrink epoxy.

BARRIER STABILIZATION DETAIL
BRIDGE DECKS



- General Notes**
- The contractor shall furnish the Precast Concrete Barrier Units and shall be responsible for the manufacture, shipment, storage, placement and removal. At the completion of the project, the precast units will remain the property of the contractor.
 - Materials shall meet the following minimum requirements: Concrete: 2500 psi compressive strength at 28 days. Reinforcing Steel: AASHTO M 31 or M 53, Grade 60. Structural Steel: AASHTO-M270 Grade 36 shall be used for the Connection Pin, Connection Loops, and Stabilization Pins. A One Piece Pin with a 3" rounded top may be used in place of the detailed Connection Pin. Delineators: Delineators shall be mounted at 10' spacing on top of precast barrier.

In applications where barrier walls within 6 feet of a traffic lane, additional delineators shall be placed on the barrier at 10' spacing approximately one (1) foot from the top of the barrier. Delineators shall be on the AHTD Qualified Products List for Construction Concrete Barrier Markers. Delineator color shall be in accordance with the Manual Uniform Traffic Control Devices. Payment for delineators shall be considered included in the price bid per Lin. Ft. for "Furnishing and Installing Precast Concrete Barrier". The contractor shall certify to the Engineer that the material and the design used in the precast barrier units meets the requirements as shown on this standard drawing.
 - Other Precast Concrete Barriers that have been crash tested and approved by the Federal Highway Administration to meet the requirements of NCHRP-350 test level 3 or Manual For Assessing Safety Hardware (MASH) will be accepted in lieu of the barrier shown. Drain slots shall be provided as needed or as directed by the Engineer. The Contractor shall furnish a certification of NCHRP Report 350 or Manual For Assessing Safety Hardware (MASH) compliance for any other types of precast barrier to be used. The certification shall state that the precast concrete barrier meets the requirements of NCHRP Report 350 or Manual For Assessing Safety Hardware (MASH) and include a copy of the Federal Highway Administration's (FHWA) approval letter with all attachments. Precast concrete barrier units shall be fabricated and installed in accordance with crash testing and documentation provided in the FHWA approval letter. Mixing of shapes will not be allowed in a continuous line of units.
 - Dowel holes in pavement or bridge slabs that are to remain in place shall be filled. Holes in concrete pavement and bridge slabs shall be filled with an approved non-shrink epoxy grout. Holes in asphalt pavement shall be filled with an approved asphalt joint filler. Payment for drilling and filling holes to be included in the price for various barrier items.
 - Attach Units To Roadway Surface with Stabilization Pins and to Deck Slabs using bolts when required.
 - A 4" White PVC Sleeve may be used to form the Lifting Hole and if used the Sleeve is to be left in place.


2-27-14	REVISED BARRIER STABILIZATION DETAIL	
10-15-09	ADDED REFERENCE TO MASH	
8-5-09	REV. NOTE 3 CONCERNING DRAIN SLOTS	
11-29-07	REVISED NOTE 3	
5-25-06	DELETED GENERAL NOTE 7	
11-18-04	REVISED BARRIER STABILIZATION DETAIL BRIDGE DECKS	
4-10-03	REVISED GENERAL NOTE 2	
8-22-02	ISSUED NEW DRAWING	
D, TE	REVISION	FILMED

ARKANSAS STATE HIGHWAY COMMISSION

STANDARD TRAFFIC CONTROLS
FOR HIGHWAY CONSTRUCTION -
TEMPORARY PRECAST BARRIER


STANDARD DRAWING TC-4

(A) 4 feet or greater preferred. If less than 4 feet, Precast Units shall be connected to slab (SEE BARRIER STABILIZATION DETAIL-BRIDGE DECKS STD. DRWG. TC-4)



BARRIER PLACEMENT ALONG BRIDGE WITH OFFSET


No Scale



SECTION J-J

No Scale

** Offset Distance for Two Way Traffic Only



BARRIER PLACEMENT ALONG ROADWAY WITH OFFSET

No Scale


** Offset Distance for Two Way Traffic Only

* Offset Distance (See Table)

Offset Distance Table

Speed (MPH)	Offset Distance (FT.)
≤ 45	12
> 45	18

If offset distance is not attainable, then see 'Barrier Placement With Attenuator' Detail shown below.




SPECIAL END UNIT

No Scale

General Notes

When shown on the Plans, the ends of the Temporary Precast Concrete Barrier shall be protected with an NCHRP-350 or Manual For Assessing Safety Hardware (MASH) approved Crash Cushion. Payment for Crash Cushions shall be made under the item of "Temporary Impact Attenuation Barrier."



BARRIER PLACEMENT WITH ATTENUATOR


No Scale

** Offset Distance for Two Way Traffic Only


*** Min. 3'-0" From Edge of Travel Lane to Nearest Edge of Attenuator

			ARKANSAS STATE HIGHWAY COMMISSION	
			STANDARD TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION - TEMPORARY PRECAST BARRIER	
			STANDARD DRAWING TC-5	
10-15-09	ADDED REFERENCE TO MASH			
5-25-06	REVISED BARRIER PLACEMENT			
8-22-02	ISSUED NEW DRAWING			
DATE	REVISION		FILMED	


GENERAL NOTES
 INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.



WATTLE DITCH CHECK (E-1)




DROP INLET SILT FENCE (E-7)




SILT FENCE ON R/W FENCE (E-4)

GENERAL NOTES
 GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST, OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.


GENERAL NOTES
 1. STRAW BALES SHALL BE INSTALLED SO THAT THE BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES. THE BALES SHALL BE A MINIMUM OF 30 INCHES IN LENGTH.
 2. NO GAPS SHALL BE LEFT BETWEEN BALES.
 3. BALED STRAW FILTER BARRIERS COMPLETED AND ACCEPTED WILL BE MEASURED BY THE BALE IN PLACE AS AUTHORIZED BY THE ENGINEER AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE BID PER BALE FOR BALED STRAW DITCH CHECKS.



BALED STRAW FILTER BARRIER (E-2)




SAND BAG DITCH CHECK (E-5)



SILT FENCE (E-11)


GENERAL NOTES
 GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.




ROCK DITCH CHECK (E-6)

12-15-11	DELETED BALED STRAW DITCH CHECK & ADDED WATTLE DITCH CHECK	
11-18-98	ADDED NOTES	
7-02-98	ADDED BALED STRAW FILTER BARRIER (E-2)	
7-20-95	REVISED SILT FENCE E-4 AND E-11	7-20-95
7-15-94	REV. E-4 & E-11 MIN. 13\"/>	
6-2-94	REVISED E-1,4,7 & 11; DELETED E-2 & 3	6-2-94
4-1-93	REDRAWN	
10-1-92	REDRAWN	
8-2-76	ISSUED R.D.M.	298-7-28-76
DATE	REVISION	FILMED


ARKANSAS STATE HIGHWAY COMMISSION
 TEMPORARY EROSION CONTROL DEVICES
 STANDARD DRAWING TEC-1




NOTE:
SIZE OF BASIN TO BE DETERMINED
BY VOLUME REQUIRED; HOWEVER
A MINIMUM LENGTH-TO-WIDTH
RATIO OF 2:1 SHALL BE USED.




SEDIMENT BASIN WITH RIPRAP OUTLET (E-9)



NOTE:
SIZE OF BASIN TO BE DETERMINED
BY VOLUME REQUIRED; HOWEVER
A MINIMUM LENGTH-TO-WIDTH
RATIO OF 2:1 SHALL BE USED.





SEDIMENT BASIN WITH PIPE OUTLET (E-10)





DIVERSION DITCH (E-8)

NOTE:
A T-SECTION SHALL BE USED AT THE INLET
FOR TWO-DIRECTIONAL FLOW.
AN ELBOW SHALL BE USED FOR
ONE-DIRECTIONAL FLOW.



SLOPE DRAIN (E-12)



SEDIMENT BASIN (E-14)

6-2-94	Revised E-8 & E-12; Added E-14 & Deleted E-13		
4-1-93	ISSUED		
DATE	REVISION		FILMED


ARKANSAS STATE HIGHWAY COMMISSION
 TEMPORARY EROSION
 CONTROL DEVICES
 STANDARD DRAWING TEC-2

CLEARING AND GRUBBING

CONSTRUCTION SEQUENCE

1. PLACE PERIMETER CONTROLS (I.E. SILT FENCES, DIVERSION DITCHES, SEDIMENT BASINS, ETC.)
2. PERFORM CLEARING AND GRUBBING OPERATION.

EXCAVATION



NOTE:
NUMBER OF PHASES WILL VARY.
THREE PHASES SHOWN FOR
ILLUSTRATION.


GENERAL NOTE

ALL CUT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE EXCAVATED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.

CONSTRUCTION SEQUENCE

1. EXCAVATE AND STABILIZE INTERCEPTOR AND/OR DIVERSION DITCHES.
2. PERFORM PHASE 1 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
3. PERFORM PHASE 2 EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING.
4. PERFORM FINAL PHASE OF EXCAVATION. PLACE PERMANENT OR TEMPORARY SEEDING. STABILIZE DITCHES. CONSTRUCT DITCH CHECKS, DIVERSION DITCHES, SEDIMENT BASINS, OR OTHER EROSION CONTROL DEVICES AS REQUIRED.

EMBANKMENT



NOTE:
NUMBER OF PHASES WILL VARY.
THREE PHASES SHOWN FOR
ILLUSTRATION.

GENERAL NOTE



ALL EMBANKMENT SLOPES SHALL BE DRESSED, PREPARED, SEEDED, AND MULCHED AS THE WORK PROGRESSES. SLOPES SHALL BE CONSTRUCTED AND STABILIZED IN EQUAL INCREMENTS NOT TO EXCEED 25 FEET, MEASURED VERTICALLY.

CONSTRUCTION SEQUENCE



1. CONSTRUCT DIVERSION DITCHES, DITCH CHECKS, SEDIMENT BASINS, SILT FENCES, OR OTHER EROSION CONTROL DEVICES AS SPECIFIED.
2. PLACE PHASE 1 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
3. PLACE PHASE 2 EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PROVIDE DIVERSION DITCHES AND SLOPE DRAINS IF EMBANKMENT CONSTRUCTION IS TO BE TEMPORARILY ABANDONED FOR A PERIOD OF GREATER THAN 21 DAYS.
4. PLACE FINAL PHASE OF EMBANKMENT WITH PERMANENT OR TEMPORARY SEEDING. PLACE DIVERSION DITCHES AND SLOPE DRAINS AND MAINTAIN UNTIL ENTIRE SLOPE IS STABILIZED.

233

ARKANSAS STATE HIGHWAY COMMISSION		
TEMPORARY EROSION CONTROL DEVICES		
11-23-94	CORRECTED SPELLING	6-2-94
6-2-94	Drawn & Issued	FILMED
DATE	REVISION	
STANDARD DRAWING TEC-3		




TRIANGULAR SILT DIKE INSTALLATION FOR DIVERSION DITCH AND/OR DITCH LINER




TRIANGULAR SILT DIKE INSTALLATION FOR ROADWAY DITCH OR DRAINAGE DITCH


○ POINT "1" MUST BE HIGHER THAN POINT "2" TO ENSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS.
 ⊕ STAPLES SHALL BE PLACED WHERE THE UNITS OVERLAP AND IN THE CENTER OF THE UNIT AS SHOWN ON THE DIAGRAM.



TRIANGULAR SILT DIKE INSTALLATION FOR CONTINUOUS BARRIER




TRIANGULAR SILT DIKE INSTALLATION FOR DROP INLETS



TRIANGULAR SILT DIKE INSTALLATION FOR TEMPORARY DITCH LINER


GENERAL NOTES

1. THIS WORK SHALL CONSIST OF FURNISHING, INSTALLING, AND MAINTAINING THE TRIANGULAR SILT DIKE. THE DIKES SHALL BE USED AS A CONTINUOUS LINE BARRIER AT THE TOE OF SLOPE OR ACROSS THE ROADWAY DITCH TO CONTAIN SEDIMENT AND MINIMIZE EROSION, OR AS DIRECTED BY THE ENGINEER. THESE DIKES SHALL BE INSTALLED AND LOCATED AS SOON AS CONSTRUCTION WILL ALLOW OR AS DIRECTED BY THE ENGINEER.
2. TRIANGULAR SILT DIKE SHALL BE TRIANGULAR SHAPED HAVING A HEIGHT OF AT LEAST 8" TO 10" IN THE CENTER WITH EQUAL SIDES AND A 16" TO 20" BASE. THE TRIANGULAR SHAPED INNER MATERIAL SHALL BE URETHANE FOAM. THE OUTER COVER SHALL BE A WOVEN GEOTEXTILE FABRIC PLACED AROUND THE INNER MATERIAL & ALLOWED TO EXTEND BEYOND BOTH SIDES OF THE TRIANGLE 24" TO 36". THIS FABRIC SHOULD BE MILDEW RESISTANT, ROT-PROOF AND RESISTANT TO HEAT AND ULTRAVIOLET RADIATION MEETING REQUIREMENTS FOR SEDIMENT CONTROL IN AASHTO M288. THE DIKES SHALL BE ATTACHED TO THE GROUND WITH WIRE STAPLES. THE STAPLES SHALL BE NO. 11 GAUGE WIRE AND BE AT LEAST 6" TO 8" LONG. STAPLES SHALL BE PLACED AS SHOWN ON THESE DETAILS.
3. THE CONTRACTOR SHALL INSPECT ALL DIKES AFTER EACH RAINFALL EVENT OF AT LEAST 0.5" OR GREATER. ANY DEFICIENCIES OR DAMAGE SHALL BE REPAIRED BY THE CONTRACTOR. ACCUMULATED SILT OR DEBRIS SHALL BE REMOVED AND RELOCATED AS DIRECTED BY THE ENGINEER. IF THE DIKES ARE DAMAGED OR INADVERTENTLY MOVED DURING THE SILT REMOVAL PROCESS, THE CONTRACTOR SHALL IMMEDIATELY REPLACE AFTER DAMAGE OCCURS.




NOTE: SILT DIKE SHOULD ONLY BE USED FOR DROP INLETS IN SUMP LOCATIONS.

			ARKANSAS STATE HIGHWAY COMMISSION
			TEMPORARY EROSION CONTROL DEVICES
7-26-12	REVISED GENERAL NOTE 2.		
12-15-11	ISSUED		
DATE	REVISION		FILMED
			STANDARD DRAWING TEC-4



ENTRANCE RAMP


NOTE: JOINT SPACING ON THE MAIN LANES SHALL BE ADJUSTED AS NECESSARY TO CONFORM TO THESE JOINT LAYOUTS. THE MAIN LANE JOINT SPACING MAY BE REDUCED TO A 12' MINIMUM.




EXIT RAMP

EXIT RAMP

DESIGN SPEED V	Y	NOSE OFFSET C	LENGTH NOSE TAPER Z	RETURN RADIUS R	ADDITIONAL SURFACING SQ. YDS.
40	300.0	8.0	96.0	580.0	602.43
50	320.0	10.0	120.0	725.0	687.29
60	340.0	12.0	168.0	1182.0	790.55
70	360.0	14.0	210.0	1582.0	902.27



DETAIL "A"



DETAIL OF EXPANSION JOINT & JOINT SUPPORT

NOTE: THE EXPANSION JOINTS SHALL BE MEASURED AND PAID FOR AS P.C.C. PAVEMENT (RAMP THICKNESS). WHEN RAMP PAVING IS ASPHALT, EXPANSION JOINT IS NOT REQUIRED. THE JOINT SUPPORT MAY BE CONSTRUCTED WITH CLASS "A", "S", OR PAVING CONCRETE. PAYMENT FOR THE JOINT SUPPORT SHALL BE FOR THE CONTRACT UNIT PRICE BID FOR THE CLASS OF CONCRETE USED. ALL OTHER WORK AND MATERIALS REQUIRED FOR THE CONSTRUCTION OF THE JOINT SUPPORT SHALL BE INCLUDED IN THE PRICE BID FOR THE ABOVE ITEMS.

DATE	REVISION	DATE FILE'D
8-22-02	DELETED NOTE	
11-16-01	CORRECTED SPELLING ON ENTRANCE RAMP NOTE	
5-13-99	ADDED, EDITED AND DELETED NOTES	
11-03-94	ADDED NOTE RE: REINF. BARS	
10-1-92	ADDED DETAIL 'A' & OTHER MINOR CHANGES	10-1-92
1-25-90	REVISED EXPANSION JOINT	1-25-90
7-15-88	CONFORM'D TO 1988 SPECIFICATIONS	85C-7-15-88
3-2-81	ISSUED	811-18-2-72

ARKANSAS STATE HIGHWAY COMMISSION

DETAILS OF STANDARD TURNOUT

FOR

ENTRANCE & EXIT RAMPS (NON-REINFORCED)

STANDARD DRAWING TR-1A