INTEROFFICE MEMORANDUM

DATE: September 2, 1987

TO: BRIDGE DIVISION

FROM: Veral Pinkerton, Bridge Engineer

SUBJECT: Temporary Bridge Structures

For uniformity, the length of temporary structure shown on the layout shall be the length required if the contractor uses a spill-through design with a $1\frac{1}{2}$ to 1 slope.

If the contractor uses a vertical wall abutment the above length will still be required.

If a skewed structure is required this should be shown on the layout.

VP:kah