

ANALYSIS OF BIDS
 JOB NO. BR5610 - BAYOU DEVIEW STR. & APPRS. NO. 2 (S)
 LETTING OF 09SEP2008

QUANTITY	UNIT	ITEM	CAMERON CONST. CO., CO., INC.	ROBERTSON CONTRACTORS, INC.	ROBERTSON, INC., BRIDGE & GRADING DIV.	AVG. OF LOW BIDS
1.00	L.S.	REMV.EXIST.BR.STR. (SITE 1)	25,000.00	18,000.00	9,000.00	17,333.33
39.70	CUYD	CLASS S CONCRETE - BRIDGE	600.00	800.00	590.00	663.33
197.00	CUYD	CLASS S(AE) CONCRETE - BRIDGE	650.00	850.00	680.00	726.67
7.70	GAL	CLASS 1 PROTECT.SURF.TREATMENT	100.00	50.00	58.00	69.33
40,210.00	LB	REINF.STEEL-BRIDGE (GR 60)	1.25	1.35	1.40	1.33
1,000.00	LF	STEEL SHELL PILING (18")	130.00	145.00	160.50	145.17
150.00	LF	PILE ENCASEMENT	100.00	98.00	110.00	102.67
1.00	EACH	BRIDGE NAME PLATE (TYPE C)	500.00	1,000.00	310.00	603.33
315.00	SQYD	FILTER BLANKET	5.00	4.00	2.85	3.95
200.00	CUYD	DUMPED RIPRAP	60.00	55.00	42.50	52.50
TOTAL AMOUNT BID FOR JOB			\$818,338.43	\$958,543.50	\$1,001,709.71	
TOTAL AMOUNT BID FOR BRIDGE			\$386,977.50	\$444,838.50	\$409,831.35	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
04904	105.00	27.17	2,852.51	1A	1B
		A =	2,852.51		

1A 105' - THREE 35' R.C. DECK GIRDER SPANS ON CONC FILLED STEEL SHELL PILE TRESTLE BENTS.

1B #16080 - 103'L X 16.1'W; CONSISTS OF TIMBER PLANKS ON STEEL AND TIMBER GIRDERS SUPPORTED BY TIMBER PILE BENTS.

OUT TO OUT COST (\$/SF)=	\$386,977.50	/A = \$135.67	* FHWA COST (\$/SF)=	\$348,402.50	/A = \$122.14
LESS REMOVAL / TEMP. BR. (\$/SF)		= 8.77	EXISTING BR. REMOVAL (\$/SF)	=	\$15.08
NET COST (\$/SF)		= \$126.90	* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS		

FUNCTION CLASS - LOCAL
 OFF (09)

DESIGN SECTION - AMS