

QUANTITY	UNIT	ITEM	EUTAW CONSTRUCTION CO., INC.	BLOOMSDALE EXCAV. CO., INC.	T.J. LAMBRECHT CONST., INC.	AVG. OF LOW BIDS
565.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	20.00	9.45	8.95	12.80
394.70	CUYD	CLASS S CONCRETE - BRIDGE	600.00	604.52	572.50	592.34
282.90	CUYD	CLASS S(AE) CONCRETE - BRIDGE	650.00	482.81	457.24	530.02
952.00	LF	PRESTESS CONC GIRDERS (TY BT-72)	250.00	258.25	244.57	250.94
40.10	GAL	CLASS 1 PROTECT.SURF.TREATMENT	58.75	67.59	64.01	63.45
110,900.00	LB	REINF.STEEL-BRIDGE (GR 60)	0.75	0.87	0.82	0.81
670.00	LB	EPOXY COAT.REINF.STEEL-GR 60	1.20	1.46	1.38	1.35
1,650.00	LF	CONC.PILING (16" SQUARE)	65.00	66.10	62.60	64.57
75.00	LF	TEST PILE (16" SQUARE)	90.00	111.98	106.05	102.68
1,140.00	LF	PREBORING	65.00	39.87	37.76	47.54
4,880.00	LB	STR.ST.BM.SPANS (M270-GR50W)	10.00	8.58	8.13	8.90
6,432.00	CUIN	ELASTOMERIC BEARINGS	2.50	3.96	3.75	3.40
60.00	LF	ARM. JT W/NEOPRENE STRIP SEAL	125.00	130.35	123.45	126.27
65.00	LF	6" PIPE UNDERDRAINS	94.00	35.98	34.07	54.69
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	1,500.00	1,841.81	1,744.25	1,695.35
TOTAL AMOUNT BID FOR JOB			\$8,176,615.52	\$8,313,780.30	\$8,667,357.39	
TOTAL AMOUNT BID FOR BRIDGE			\$1,024,429.88	\$968,813.73	\$917,086.09	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07123	242.17	31.17	7,547.54	1A	NA
		A =	7,547.54		

1A 240' - CONT PRESTRESSED CONC GIRDER UNIT (120'-120') ON TWO COL INT BENTS W/CONC FOUNDATION PILES & SEMI-VERTICAL ABUTMENTS W/CONC FOUNDATION PILES.

1B

OUT TO OUT COST (\$/SF)=	\$1,024,429.88	/A = \$135.73	* FHWA COST (\$/SF)=	\$1,024,429.88	/A = \$135.73
LESS REMOVAL / TEMP. BR.	(\$/SF)	= NA	EXISTING BR. REMOVAL (\$/SF)	=	NA
NET COST (\$/SF)	=	\$135.73	* DEDUCT REMOVAL, TEMP. BR., RIPRAP, & FILTER BLANKET COSTS		

FUNCTION CLASS - PRINCIPAL ARTERIAL - OTHER
 ON (02)

DESIGN SECTION - CJF