

QUANTITY	UNIT	ITEM	KOLB GRADING, LLC	SOUTHERN IND'L CONTRS., LLC	APAC-CENTRAL, INC.	AVG. OF LOW BIDS
139.00	CUYD	UNCLASS.EXCAV.FOR STRS-BR	47.00	300.00	48.18	131.73
194.60	CUYD	CLASS S CONCRETE-BRIDGE	625.00	350.00	640.63	538.54
313.90	CUYD	CLASS S(AE) CONCRETE-BRIDGE	430.00	401.00	440.75	423.92
519.50	SQYD	TEXTURED COATING FINISH	15.00	6.00	15.37	12.12
1,277.50	SQYD	CLASS 2 PROTECT.SURF.TREATMENT	6.00	6.00	6.15	6.05
23,530.00	LB	REINF.STEEL-BRIDGE (GR 60)	1.33	0.80	1.36	1.16
71,580.00	LB	EPOXY COAT.REINF.STEEL-GR 60	1.00	0.90	1.03	0.98
690.00	LF	STEEL PILING (HP 12X53)	98.00	65.00	100.45	87.82
100.00	LF	PREBORING	333.10	50.00	341.43	241.51
96.00	LF	EXPLORATORY HOLES	20.25	100.00	20.76	47.00
250,890.00	LB	STR.ST.PL.GRD.SPN(M270-GR50W)	1.50	1.75	1.54	1.60
11,377.00	CUIN	ELASTOMERIC BEARINGS	2.00	1.75	2.05	1.93
111.00	LF	SILICONE JOINT SEALANT	95.00	60.00	97.38	84.13
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	500.00	500.00	512.50	504.17
12.00	CUYD	CONCRETE RIPRAP	650.00	400.00	666.25	572.08
1.00	L.S.	SHORING	0.01	100,000.00	19,475.00	39,825.00
TOTAL AMOUNT BID FOR JOB			\$13,647,413.56	\$14,096,849.40	\$14,182,926.42	
TOTAL AMOUNT BID FOR BRIDGE			\$902,275.41	\$960,089.15	\$945,216.17	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
07220	192.13	55.17	10,598.90	1A	NA
		A =	10,598.90		

1A 190'- CONT COMP PLATE GIRDER UNIT (95'-95') ON A MULTI-COL INT BENT W/FOUNDATION PILING & TRESTLE STEEL H-PILE END BENTS.

1B NA

OUT TO OUT COST (\$/SF)=	\$902,275.41	/A =	\$85.13	FHWA COST (\$/SF)=	894,475.40	/A =	\$84.39
LESS REMOVAL / TEMP. BR.	(\$/SF)	=	NA	EXISTING BR. REMOVAL (\$/SF)	=	NA	
NET COST (\$/SF)	=	\$85.13		DEDUCT REMOVAL, TEMP. BR., RIPRAP, FLTR BLNKT, SHORING & TRANS APP RAIL COSTS FROM FHWA COST.			

FUNCTION CLASS - 01 PRINCIPAL ARETRIAL - INTERSTATE  
ON NHS

DESIGN SECTION - BEF