

ANALYSIS OF BIDS
 JOB NO. 040206 - LEE CREEK - EAST (S)
 LETTING OF APRIL 21, 2015

QUANTITY	UNIT	ITEM	NABHOLZ CONST. CORP.	MOBLEY CONTRS., INC.	FORSGREN, INC.	AVG OF LOW BIDS
182.00	CUYD	UNCLASS. EXCAV.FOR STRS-BR	701.00	201.83	729.00	543.94
159.80	CUYD	CLASS S CONCRETE - BRIDGE	987.00	1,160.69	1,026.00	1,057.90
190.60	CUYD	CLASS S(AE) CONCRETE - BRIDGE	883.00	861.53	918.00	887.51
15.70	GAL	CLASS 1 PROTECT. SURF.TREATMENT	111.00	155.54	115.00	127.18
64,870.00	LB	REINF.STEEL- BRIDGE (GR 60)	1.14	1.07	1.08	1.10
75.00	LF	STEEL PILING (HP 12X53)	156.00	162.84	162.00	160.28
146,930.00	LB	STR.ST.BM.SPANS (M270-GR50W)	1.87	1.78	2.08	1.91
9,462.00	CUIN	ELASTOMERIC BEARINGS	2.08	1.75	2.16	2.00
75.00	LF	SILICONE JOINT SEALANT	78.00	49.79	81.00	69.60
1.00	EACH	BRIDGE NAME PLATE (TYPE D)	520.00	574.44	540.00	544.81
372.00	SQYD	FILTER BLANKET	3.75	6.42	4.10	4.76
213.00	CUYD	DUMPED RIPRAP	78.00	92.40	91.00	87.13
TOTAL AMOUNT BID FOR JOB			\$4,541,667.81	\$5,894,222.03	\$6,624,968.76	
TOTAL AMOUNT BID FOR BRIDGE			\$859,817.96	\$774,956.85	\$909,194.22	

BRIDGE ID	LENGTH	WIDTH	AREA (OUT-OUT)	NEW BRIDGE DESCRIPTION	EXISTING BRIDGE DESCRIPTION
06725	197.65	31.17	6,159.97	1A	NA
		A =	6,159.97		

1A 195'- CONT COMP W-BEAM UNIT (60' - 75' - 60') HAMMERHEAD INT BENTS ON SPRD FTGS, ONE STEEL H-PILE END BENT AND ONE MULTI-COL END BENT ON SPRD FTGS.

1B NA LOW WATER CROSSING.

OUT TO OUT COST (\$/SF) = \$859,817.96 /A =	\$139.58	FHWA COST (\$/SF) = \$841,808.96 /A=	\$136.66
LESS REMOVAL / TEMP BR/ SHORING (\$/SF)	\$0.00	EXISTING BR. REMOVAL (\$/SF) =	NA

NET COST (\$/SF) **\$139.58** DEDUCT REMVL, TEMP BR, RIPRAP, FLTR BLNKT, SHORING & TRANS APPR RAIL COSTS FROM FHWA COST.

FUNCTION CLASS - 07 MAJOR COLLECTOR - RURAL
 OFF NHS

DESIGN SECTION - AMS